This is a digital copy of a book that was preserved for generations on library shelves before it was carefully scanned by Google as part of a project to make the world's books discoverable online.

It has survived long enough for the copyright to expire and the book to enter the public domain. A public domain book is one that was never subject to copyright or whose legal copyright term has expired. Whether a book is in the public domain may vary country to country. Public domain books are our gateways to the past, representing a wealth of history, culture and knowledge that's often difficult to discover.

Marks, notations and other marginalia present in the original volume will appear in this file - a reminder of this book's long journey from the publisher to a library and finally to you.

Usage guidelines

Google is proud to partner with libraries to digitize public domain materials and make them widely accessible. Public domain books belong to the public and we are merely their custodians. Nevertheless, this work is expensive, so in order to keep providing this resource, we have taken steps to prevent abuse by commercial parties, including placing technical restrictions on automated querying.

We also ask that you:

+ *Make non-commercial use of the files* We designed Google Book Search for use by individuals, and we request that you use these files for personal, non-commercial purposes.

+ *Refrain from automated querying* Do not send automated queries of any sort to Google's system: If you are conducting research on machine translation, optical character recognition or other areas where access to a large amount of text is helpful, please contact us. We encourage the use of public domain materials for these purposes and may be able to help.

+ *Maintain attribution* The Google "watermark" you see on each file is essential for informing people about this project and helping them find additional materials through Google Book Search. Please do not remove it.

+ *Keep it legal* Whatever your use, remember that you are responsible for ensuring that what you are doing is legal. Do not assume that just because we believe a book is in the public domain for users in the United States, that the work is also in the public domain for users in other countries. Whether a book is still in copyright varies from country to country, and we can't offer guidance on whether any specific use of any specific book is allowed. Please do not assume that a book's appearance in Google Book Search means it can be used in any manner anywhere in the world. Copyright infringement liability can be quite severe.

About Google Book Search

Google's mission is to organize the world's information and to make it universally accessible and useful. Google Book Search helps readers discover the world's books while helping authors and publishers reach new audiences. You can search through the full text of this book on the web at `http://books.google.com/`

a39015 00002658 6b

Digitized by Google



THE GIFT OF
Ottawa Bur. of Mines

Digitized by Google

Science Library
TN
27
.05
A2
1903
pt. 1

Digitized by Google

Digitized by Google

Ontario, Dept. of ...

REPORT OF

THE BUREAU OF MINES, 1904

PART I

CONTENTS

INTRODUCTION	p. ix-xiv
STATISTICAL REVIEW	1-45
MICHIPICOTON MINING DIVISION	46-49
PROVINCIAL ASSAY OFFICE	50-51
SUMMER MINING SCHOOLS	52-57
MINES OF WESTERN ONTARIO	58-87
MINES OF EASTERN ONTARIO	88-95
COBALT-NICKEL ARSENIDES AND SILVER	96-103
THE ABITIBI REGION	104-134
ECONOMIC RESOURCES OF MOOSE RIVER BASIN	135-191
THE NORTHERN NICKEL RANGE	192-224
THE IROQUOIS BEACH IN ONTARIO	225-244

PRINTED BY ORDER OF THE LEGISLATIVE ASSEMBLY OF ONTARIO.

Toronto:
Printed and Published by L. K. CAMERON,
Printer to the King's Most Excellent Majesty,
1904.

Digitized by Google

WARWICK BRO'S & RUTTER, LIMITED, PRINTERS,
TORONTO.

Digitized by Google

Science Library

CONTENTS

	Page.
LETTER OF TRANSMISSION ..	ix.
INTRODUCTORY LETTER	xi.-xiv.
STATISTICAL REVIEW	1-45
Summary of mineral production	2
Gold and silver	3
Gold mining, 1899-1903	5
Silver mining, 1899-1903	5
Nickel and copper	5
Nickel-copper mining, 1899-1903	6
Copper mines, 1902-1903.. ..	7
Iron and steel	7
Iron ores of Ontario	8
Pig iron and steel	10
Production iron and steel, 1896-1903	10
Bounty on iron ore, 1896-1903	11
Lead	11
Molybdenite	11
Zinc	11
Actinolite	11
Graphite	12
Mica	12
Exports of mica	13
Talc	13
Building materials	13
Output, 1899-1903	13
Stone	13
Lime	14
Brick	15
Other clay products	15
Portland cement	16
New cement plants	17
Natural rock cement	17
Production cement, 1891-1903	18
Arsenic	18
Calcium carbide	18
Corundum	19
An ore of aluminium	19
Feldspar	21
Gypsum	21
Salt	21
Production, 1899-1903	22
Iron pyrites	22
Natural gas	22
Petroleum	23
Petroleum products, 1902-1903	24
do., 1899-1903	24
New oil fields	25
Brant county	25
Romney township	26
Peat fuel	27
The open-tube press	27
The Whitewater press	28
New peat factories	28
Lignite as a fuel	29
Peat-making in Ontario	29
A demonstrating plant	29
Harrowing for air-drying ..	31
Other peat works	31
The Milne gatherer	32
The Milne press	32
The industry in Europe	33
The bogs of Norway	33
Swedish tests	34
Peat meal	34
Peat board and paper	35
Mining lands disposed of	36
Sales	36
Leases	36
Mining companies	36
Incorporated in 1903	37
Mining accidents	38
Canadian Copper Company..	38
Victoria Mines	39
Elizabeth mine	39
Helen mine	39
Big Master mine	39
Loon Lake mine	40
Belmont mine	40
Table of accidents, 1903	41
Government diamond drills....	42
The "C" drill	42
The "S" drill.....	43
Summary of operations	45
MICHIPICOTON MINING DIVISION	46-49
Helen iron mine	46
Mariposa gold mine	46
Manxman gold mine..	47
Kitchi-gammi gold mine....	47
Grace gold mine	47
Sunrise mine	47
Josephine iron mine	47
List of licensees	48
PROVINCIAL ASSAY OFFICE ..	50-51
Work for Bureau of Mines	50
Work for private parties	50
Laboratory determinations	50
Assays	51
Analyses	51
Laboratory methods	51
SUMMER MINING SCHOOLS ...	52-57
The season's itinerary	52
Black Donald mine	53
Olden zinc mine	54
Class at Cordova mine	54
Copper Cliff	54
Massey copper mine	55
Big Master mine	55
The Twentieth Century	55
Tip-Top mine....	55
The Helen mine	57
The Grace mine	57
Superior copper mine	57
General remarks	57
MINES OF WESTERN ONTARIO	58-87
Gold mines	59
Sultana	59
Burley	60
Mikado	60
The Golden Horn	61
Crown Point	61
Olympia	61
Mines Contract	61
Great Northwest	62
Indian Joe	62
Cameron Island	62
Gold Reefs	62
Combined	62
Flint Lake	63
Nino	64
Virginia	64
Eagle Lake area	64
Golden Eagle	64
Grace	64
Buffalo	65
Eldorado	65
Baden-Powell	65
Viking	65
S 500	66
Ideal	66
Redeemer	66
Gold Rock	66
Reliance	66
Twentieth Century	67
Giant	67
Gold Standard..	68
Big Master	68
Little Master	68
National	69
King Edward	69
St. Anthony Reef	70
Shakespeare	70
A L 282, or Sunbeam	71
A L 278 and 200	71
Walsh	72
West End silver mine	72

Digitized by Google

	Page.
MINES OF WESTERN ONT. (Con.)	
Iron mines	73
North Shore Reduction Coy.	73
Argenteuil Mining Company	74
Williams	74
Loon lake	75
Locations in Aberdeen	76
Copper mines	77
Tip-Top	77
Pattison prospect	78
Black Bay Mining Company	78
Massey Station	78
Hermina	79
Rising Sun	79
Copper Queen	80
Ranson	81
Bruce mines	81
Rock Lake	81
Taylor	82
Superior	82
Nickel-copper mines	82
Canadian Copper Company	83
Ontario Smelting Works	84
Copper Cliff mine	84
No. 2	84
No. 3	84
Creighton	85
Victoria	86
North Star	86
Gertrude	87
Lead mines	87
MINES OF EASTERN ONTARIO	88-95
Corundum mines	89
Canada Corundum Company	89
Ontario Corundum Company	90
Feldspar mines	90
Mica mines	90
General Electric Company	91
Kent Bros.' properties	92
Other Loughborough mines	92
North Burgess	92
Bedford	92
Actinolite and asbestos	93
Gold mines	93
Copper mines	93
Zinc and lead mines	94
Iron mines	94
Iron pyrites	94
Other mineral industries	95
COBALT-NICKEL ARSENIDES AND SILVER	96-103
The deposits described	96
Deposit No. 1	98
Deposit No. 2	99
Ore bodies 3 and 4	100
A unique occurrence	101
The slate-breccia	102
Cobalt ores elsewhere	103
THE ABITIBI REGION	104-134
Part I.: Physical features	105
Mattagami to Night Hawk	105
Delbert and Jarvis lakes	105
Whitney township	106
The Porcupine river	106
Night Hawk river	107
Frederick House lake	108
Frederick House to Abitibi	108
Township of German	108
Moose lake	109
Driftwood river	109
Up Black river	109
First Falls to Matachewan	110
Cherry and Grave lakes	110
Bethea lake	110
Davis lake	111
Wataybeeg lake	111
A lake on the divide	111
Separation lake	112
Optic, Bird and Turtle lakes	112
Baptiste lake	112
Route to Temiskaming	113
Wataybeeg Lake to Black river	113
Falls on the Wataybeeg	113
Upper Black river	114
Part II.: Topography and resources	115
A drift-covered area	115
Drainage systems	115
Evidences of glaciation	115
Resources of the region	115
Climate	116
Requirements	116
Part III.: Petrography	116
Classes of rocks	116
Dolerites	116
Syenites	117
Diorites	119
Porphyries	119
Volcanic tuff	120
Schists	120
Agricultural capabilities of Abitibi	121
Tisdale township	121
Porcupine lake district	122
Porcupine river	122
Night Hawk lake	122
Frederick House lake	123
Long Portage district	123
Moose lake	124
Black river	125
Timber of the region	125
Birds of the Abitibi	126
Wild animals	127
Fish	127
Flies of the Abitibi	127
Black flies	127
Sand flies	128
Injurious insects	128
Weather observations	130
Abitibi soils	130
Methods of analysis	130
Classification of soils	130
The samples examined	130
Conclusions	134
ECONOMIC RESOURCES OF MOOSE RIVER BASIN	135-179
The territory explored	135
The Opazatika river	135
The Wabiskagami	136
The Nettogami	137
Stratigraphy	138
Pre-Cambrian gneisses	138
Pre-Cambrian schists	140
Greenstone dikes and bosses	140
The Palaeozoic series	141
Pleistocene geology	142
Rocks of glacial age	143
Post-glacial rocks	143
Physiography	144
The height of land plateau	144
Lakes of Moose basin	144
The river systems	145
The coastal plain	146
River habits and effects	146
Lake Kesagami	148
Cliffs of peat	148
Economic geology	150
Iron carbonates	150
Limonite on Mattagami	152
Gypsum on the Moose	156
Extent of beds	156
Gypsum Mountain	158
Other gypsum deposits	158
Shales and clays	159
Kaolinic clay	160
Deposits of lignite	161
Beds on the Missanabie	161
On the Opazatika	162
The Soweska seams	164
Drilling at Ells' bend	166
On the Kwataboahegan	168
On the Abitibi	169
Blacksmith rapid	169
Quality of the lignite	170
West side Blacksmith rapid	170
Other deposits	174
Peat bogs of coastal plain	174
Climate	174
Soil	175
Forest trees	176
The ravages of fire	177
Northern scenery	178
Wild animals	178
Aboriginal inhabitants	178

Digitized by Google

Page.

DEVONIAN FAUNA OF KWATABOAHEGAN RIVER 180-191
Anthozoa..... 181
Favosites gibsoni 181
Stromatoporoidea 182
Syringostroma restigouchense. 182
Syringostroma aurora 182
Syringostroma densum 183
Clathrodictyon laxum 183
Actinostroma moosensis 183
Clathrodictyon problematicum.. 184
Stromatopora tubulifera 184
Echinodermata 185
Polyzoa 185
Brachiopoda..... 185
Gasteropoda..... 186
Loxonema robusta 186
Loxonema subattenuata 186
Collonema bellatula 186
Euomphalus decewi 186
Euomphalus 186
Euomphalus, sp. 187
Platyostoma lineata 187
Murchisonia desiderata 187
Strophostylus unicus 187
Holopea 187
Murchisonia 187
Pleuratomaria delicatula 187
Pleuratomaria adjutor 187
Bellerophon pelops 187
Scaphopoda 188
Coleolus tenuicinctum 188
Coleolus tenuistriatus 188
Coleolus, sp. 188
Lamellibranchiata 188
Conocardium cuneus 188
Goniophora 188
Modiomorpha 188
Megambonia 188
Cypricardinia..... 188
Mytilarca 188
Avicula textilis 188
Lyriopecten dardanus 188
Cephalopoda..... 188
Orthoceras thoas 189
Orthoceras pelops 189
Orthoceras luxum 189
Orthoceras 189
Orthoceras extremum 189
Orthoceras algomense 189
Orthoceras pulcher 189
Gomphoceras beta 190
Hercoceras auriculum 190
Trilobita 190
Calymene platys 190
Dalmanites anchiops 190
Dalamnites stemmatus..... 190
Phacops cristata 190
Proetus 191
Conclusions 191

THE NORTHERN NICKEL RANGE 192-224
Topography of the range 192
Stratigraphical relationships ... 193
The range in detail 194
The southwest corner 194
Sultana nickel mine 195

Page.
Windy lake region..... 196
The Levack ore deposits 197
Strathcona mine 198
Moose lake region 198
Morgan township 199
In Bowell township 200
Offset to Ross mine.. 200
South edge of eruptive 201
Wisner township 202
Norman and Capreol 202
Acid edge of south range 204
Basin of the eruptive 205
Nature of sediments 205
Tuffs 205
Slates 206
Sandstones 206
The river systems 207
Nickel-bearing eruptive 208
Sultana mine — Fairbank lake 209
Onaping—Windy lake 210
Sections to the northeast... 211
Character of the eruptive ... 212
Results of rock analyses 212
Effects of eruptive. 218
Other eruptive rocks 218
Drillings in Blezard 214
Micro-norite groups 214
Hutton township iron range....216-221
Moose mountain..... 216
Extension of the range 218
Geology of the region.. 219
Relationships of the ranges .. 220
Michipicoton mining division....221-222
Iron belt west of Hutton 222-224
Geneva and Roam lakes..... 222
McCrindle lake..... 223
Morin lake..... 224
Iron ranges in Rathbun 224

THE IROQUOIS BEACH IN ONTARIO 225-244
Theories of origin..... 225
Detailed account of Iroquois beach..... 227
The beach near Hamilton..... 228
Burlington Heights to Toronto 229
Scarboro' to Colborne 230
Colborne to Trenton 231
Islands to north and east 231
North of Trent river... 232
Lake Peterborough 233
The beach in New York 233
Tilting of the beach 234
The Mohawk Valley outlet 235
Conditions of Iroquois time .. 236
Duration and age of beach.. 237
Economic geology 237
Lower water levels 238
Port Granby to Trenton 238
Near Trenton 239
Prince Edward county 240
Belleville to Gananoque 241
East of Gananoque 241
Old beaches in New York .. 242
Thousand Island Straits 242
Summary 243

ILLUSTRATIONS.

Page

Flint Lake gold mine and mill..... 48
Milne Peat Press, showing die or sprocket wheels in which briquettes are compressed..... 48
Twentieth Century gold mine, 1903..... 48
Gold Standard mine; shaft buildings and rock dump..... 48
Flint Lake gold mine, showing open cut..... 48
Vein in Little Master gold mine, showing lenticular form characteristic of veins in Manitou region..... 48
Combined gold mine, showing flat quartz vein overlain by trap..... 64
Manxman gold mine, Michipicoton mining division, 1903..... 64
Manxman mine; quarrying auriferous dike..... 64
Eldorado gold mine and mill, Eagle lake, 1903..... 64
Iron sand concentrating plant of North Shore Reduction Company at outlet of Nipigon river..... 64
Shakespeare gold mine; auriferous body of quartz and chloritic schist..... 64
Shakespeare gold mine; showing vent or natural opening..... 64
Williams iron mine, near Wilde station, Algoma Central & Hudson Bay Railway..... 80

Digitized by Google

Page.

Tip-Top copper mine, 1903... 80
Tip-Top copper mine, 1903... 80
Tip-Top copper mine, showing shaft house and ore dumps. 80
Superior copper mine, 1903. 80
Copper Queen mine, shaft and hoist house. 96
Copper Queen mine, 1903. 96
Shaft house, Ranson copper mine. 96
Baden-Powell gold mine, showing open trench. 96
Massey station copper mine, 1903. 96
Helen iron mine from the north. 96
Mineral Range Iron Mining Company. No. 3 mine. 96
Mineral Range Iron Mining Company. No. 1 or Childs mine. 96
Mill at Ontario Corundum mine, erected in 1903. 112
Side hill quarry, Ontario corundum mine. 112
Pit at Radnor iron mine, Grattan township. 112
Cobbing ore, Olden zinc mine. 112
Radnor iron mine, Grattan township. 112
Castellated trap cliffs of Nipigon bay. 112
Radnor mine; banded magnetite and silicious material in low-grade portions of ore body. 112
Drift boulders, south shore Night Hawk lake. 128
Falls on Black river. 128
Canoeing in shallow waters, Pike river. 128
Indian hut and garden, Night Hawk lake. 128
Indian wigwam, Black river. 128
Contorted laminated clay, south shore Night Hawk lake. 128
Tomstown, on the Blanche river, a new centre in Northern Ontario. 128
Fort Mattagami. 128
Indian camping ground, Fort Mattagami. 128
Coal exploration party, Missanabie river. 144
The Upper Nettogami river, showing timber. 144
Couchiching falls, Abitibi river. 144
Brecciated limestone cliffs, Nettogami river. 144
Peat island, lake Kesagami. 144
Peat cliffs, lake Kesagami. 144
Pond Portage rapids, Missanabie river. 144
Falls near mouth of New Post brook. 144
Gypsum beds, Moose river. 160
Gypsum beds, Moose river, showing cavernous structure. 160
Gypsum cliffs, Moose river. 160
Devonian shales, etc., below Sextant portage, Abitibi river. 160
Near view lignite, Soweska river. 160
The Upper Soweska river. 160
Fourth lignite seam, Upper Soweska river. 160
Lignite on Soweska river, showing test pit in seam. 160
Drift in lignite, east side Abitibi river; lignite in foreground. 176
Opened lignite seam, west side Blacksmith rapid, Abitibi river. 176
Grand or Breakneck Falls, Opazatika river. 176
Thundering Water falls, Missanabie river. 176
Ojibway Indian, "en costume". 176
Indian villagers of lake Abitibi. 176
Black Donald graphite mine and works, 1903. 176
Plate I. 192
Fig. 1.—Favosites Gibsoni, sp. nov. Page 181. Vertical radial section, to show the tabulae and the manner in which the corallites spring from the axis of the corallum. Enlarged three times.
Fig. 2.—Horizontal section to illustrate the intermural pores and the walls of the corallites. Enlarged three times.
Fig. 3.—The same enlarged six times. Owing to the imperfection of the photograph this figure is repeated in a pen and ink sketch, Plate VII., Fig. 2.
Fig. 4.—Tangential section to show the polygonal shape of the corallites and the absence of septa. Enlarged twenty-five times.
Fig. 5.—Horizontal section showing the lines of growth in the walls of the corallites. Enlarged thirty times.
Plate II. 192
Fig. 1.—Cyclotrypa Borealis, sp. nov. Page 185. Tangential section, enlarged about twenty-five times.
Fig. 2.—Ditto. Vertical section, enlarged about twenty-five times.
Fig. 3.—Actinostroma Moosensis, sp. nov. Page 188. Photograph of surface. Natural size.
Fig. 4.—Syringostroma Aurora, sp. nov. Page 182. Photograph of surface to show the flat mamelons and the long, fine astrorhizal canals. Natural size.
Fig 5.—Favosites Gibsoni, sp. nov. Page 181. Photograph of weathered end. Natural size. See also pen and ink sketch, Plate VII., Fig. 1.
Plate III. 192
Fig. 1.—Syringostroma Aurora, sp. nov. Page 182. Tangential section.
Fig. 2.—Ditto. Vertical section.
Fig. 3.—Actinostroma Moosensis, sp. nov. Page 188. Tangential section.
Fig. 4.—Ditto. Vertical section.
Fig. 5.—Actinostroma Expansa, Hall. Page 184. Tangential section.
Fig. 6.—Ditto. Vertical section. All figures enlarged six times.
Plate IV. 192
Stromatopora Tubulifera, page 184.
Fig. 1.—Vertical section, enlarged thirty-three times.
Fig. 2.—Tangential section, enlarged thirty-three times.

Digitized by Google

Page.

Fig. 3.—Vertical section, enlarged six times.
Fig. 4.—Tangential section, enlarged six times.
Fig 5.—Clathrodictyon Problematicum, sp. nov. Page 184. Vertical section, enlarged six times.
Fig. 6.—Tangential section, enlarged six times.

Plate V..... 192
Fig. 1.—Holopea, sp. Page 187. Front, apical and umbilical views of different specimens.
Fig. 2.—Loxonema Robusta, Hall. Page 186. View of internal cast of a large specimen and of the gutta percha impression of the exterior of a smaller one.
Fig. 3.—Goniophora, sp. Page 188. Photograph of internal cast, showing the great angularity of the shell.
Fig. 4.—Modiomorpha, sp. Page 188. Photograph of the cast of the exterior. All figures of the natural size.

Plate VI..... 192
Fig. 1.—Orthoceras Algomense, sp. nov. Page 189. View of chamber of habitation and the upper septa of the type specimen.
Fig. 3.—Ditto. Fifth septum, showing the outline and position of the siphuncle.
Fig. 2.—Orthoceras Pulcher, sp. nov. Page 189. Front view of the type specimen.
Fig. 5.—Hercoceras Auriculum, sp. nov. Page 190. Chamber of habitation of the smaller specimen.
Fig. 6.—Ditto. Side-view of the larger specimen showing the nodes and the degree of curvature. The dotted line indicates the probable outline of the ventral side.
Fig. 4.—Orthoceras, sp. Page 189. Portion of the septate region and outline of septum, with siphuncle.
Fig. 7.—Orthoceras Extremum, sp. nov. Page 189. Front view of type specimen and outline of septum.
Fig. 8.—Coleolus Tenuistratus, sp. nov. Page, 188. Large coarsely striated example.
Fig. 9.—Ditto. Apical portion of smaller form.

Plate VII..... 192
Fig. 1.—Favosites Gibsoni, sp. nov. Page 181. Pen and ink sketch of the weathered cross fracture, enlarged twice.
Fig. 2.—Ditto. Sketch of a portion of a horizontal section, showing the tabulae, intermural pores and lines of growth. The intermittent activity of the organism is well shown in the continuity of the light and dark portions across several corallites. Enlarged about twenty times.
Fig. 3.—Pleurotomaria Delicatula, var. Camera, var. nov. Page 187. Sketch of the best preserved specimen, enlarged six times.

Plate VIII..... 192
Fig. 1.—Proetus, sp. Page 191. Pygidium enlarged five times. (The photograph does not show the thickened margin).
Fig. 2.—Yellow Limestone from Kwataboahegan river. Page 180. Photograph of a fragment reduced one-half, to show the highly fossiliferous nature of the rock. The surface of this specimen shows: Orthoceras luxum, Orthoceras procerus (?), Coleolus tenuistriatus, C. tenuicinctum, Pleurotomaria adjutor, Modiomorpha sp., Platyostoma lineata, Bellerophon sp., Euompholus sp., Athyris spiriferoides, Cypricardinia indenta (?), Atrypa reticularis.

Nickel eruptive, Windy lake..... 208
Weathering of nickel eruptive, mouth of Moose creek..... 208
Strathcona nickel mine..... 208
Big Levack nickel mine..... 208
North Star nickel mine, October, 1908..... 208
No. 3 or new roast yard, Canadian Copper Company..... 208
Log jam, Onaping river..... 224
Log chute, Onaping river..... 224
Nickel ore deposit, five miles north of Onaping..... 224
Richardson feldspar mine, Bedford, Ont..... 224
Perched boulder near Nelson river..... 224
Missanabie river at Hell or Long rapids..... 224
Mineral Range Iron Mining Company, No. 1 or Childs mine..... 224

MAPS.

Map of Northern Nickel Range. By A. P. Coleman. Scale 2 miles to 1 inch.
Map of Northern Parts of the Districts of Algoma and Nipissing, to accompany report of J. M. Bell. Scale, 8 miles to 1 inch.
Map of Lake Iroquois. By A. P. Coleman; parts in New York after H. L. Fairchild.

Digitized by Google

Digitized by Google

To His Honor

William Mortimer Clark, etc., etc., etc.,

Lieutenant-Governor of the Province of Ontario.

Sir:

I have the honor to transmit herewith, for presentation to the Legislative Assembly, the Thirteenth Report of the Bureau of Mines.

I have the honor to be, Sir,
Your obedient servant,

E. J. DAVIS,
Commissioner of Crown Lands.

Department of Crown Lands,
Toronto, 17th March, 1904.

Digitized by Google

INTRODUCTORY LETTER

To the Honorable E. J. Davis,
Commissioner of Crown Lands.

Sir:—

I beg to submit to you herewith, to be presented to His Honor the Lieutenant-Governor, the Thirteenth Report of the Bureau of Mines.

The Report is in two parts; Part I, containing statistical and other information concerning the mineral industry of Ontario and a variety of papers dealing with important subjects connected with the industry or with the mineral resources of the Province; and Part II, to be published separately, consisting of a monograph by Prof. W. G. Miller, Provincial Geologist, on the Limestones of Ontario. The need for a work of the latter kind has been apparent for some years, or ever since the uses of limestone began to multiply and the demand for material suited for specific purposes revealed the dearth of information, or at any rate of classified information, respecting the limestones which abound in Ontario of varying composition and geological age. Previous investigators have described many outcroppings and occurrences of limestone found in the Archaean rocks and constituting also a large proportion of the Silurian and Devonian formations of the Province; and references to these, with numerous analyses, may be found in the reports of the Geological Survey of Canada and the Bureau of Mines, as well as elsewhere. Many of these reports, however, are out of print and are no longer accessible to the public; and even if they were available, the difficulty of locating and collecting these references and analyses is so great as to render the information of comparatively little practical value. In addition to massing the data previously on record, Prof. Miller has made many independent investigations, the results of which are set out in his paper, and it is confidently hoped that his treatment of the subject, while not wholly complete, is such as to present to the numerous users of limestone a body of facts and particulars which will be of service to them.

Part I, or the Report proper, contains a report on the Mines of Western Ontario and one on the Mines of Eastern Ontario, the former by Mr. W. E. H. Carter, the efficient secretary of the Bureau, who also performs the duties of Inspector of Mines, and the latter by Prof. Miller, who combines the functions of an Inspector with those of Provincial Geologist. These reports give many useful details of the mines and prospects at which operations were carried on during 1903, and exhibit the condition of the mining industry in the two divisions into which the Province naturally falls for inspection purposes.

Other methods pursued by the Bureau in its endeavors to promote the welfare of the mining industry are represented by the Provincial Assay Office at Belleville, where assays and analyses of mineral samples are made at low rates for the benefit of prospectors and others, the assayer in charge being Mr. A. G. Burrows, who reports upon the work of the office for the year; the Summer Mining Schools, which have been carried on under the auspices of the Bureau for a number of years and which have for their object the instruction of working miners, prospectors and others, in the identification of minerals and the rudiments of mineralogy, geology and chemistry, of which classes for 1903 Dr. W. L. Goodwin, Director of the School of Mining at Kingston, with whom was associated as instructor Mr. J. G. McMillan, of the School of Practical Science, Toronto, gives an interesting account; and the diamond drills, two of which are owned and operated by the Bureau for the benefit of owners of mineral lands wishing to explore them by means of bore holes, a summary statement with tables of cost being given, showing the work done with the drills during the year.

Digitized by Google

Mr. D. G. Boyd, Inspector of the Michipicoton Mining Division, gives a brief report on affairs in the Division during 1903, where mining received a serious setback through the collapse of the Clergue companies, which formerly were actively engaged in raising iron and extracting gold in that locality. It is hoped the contemplated resuscitation of these concerns will be followed by a revival of their mining operations, especially in iron ore, the Michipicoton deposits really owing their development, if not their discovery, to the energy displayed by these companies.

Remarkable finds of the arsenical ores of cobalt and nickel, some of the veins carrying a profusion of native silver, were made during the construction of the Temiskaming and Northern Ontario Railway—the Ontario Government line—through the unsurveyed territory south of the township of Bucke, and notwithstanding the lateness of the season when the discoveries became known, it was deemed advisable that Prof. Miller should visit the spot and make an examination of the deposits. This he was able to do before the snow fell, and the account which was published of these valuable ores aroused much interest. It is reprinted with considerable additions in the present volume under the title "Cobalt-Nickel Arsenides and Silver." As soon as spring opens it is proposed by the Department of Crown Lands to survey the area in which these mineral deposits are found, and to subdivide it into concessions and lots. This will much assist in making a more detailed examination of the geology of the region than was possible during the closing days of last autumn, as well as in ascertaining, if possible, the extent of the mineral-bearing tract and the relations which the deposits sustain to the enclosing rocks, which appear to be in the main the slate-breccia or conglomerate of the type characteristic of the Temagami region.*

The prospect of the early construction of a transcontinental line, traversing the agricultural belt of Ontario lying north of the Height of Land and the connection which the Government of this Province has undertaken to make therewith by extending the Temiskaming and Northern Ontario Railway a sufficient distance to effect a junction, render it a pressing necessity to ascertain in as much detail as possible the nature of the country which will thus be opened up for settlement. It is known that a wide zone of arable clay land stretches almost across the entire width of the Province in a northwesterly direction from the latitude of lake Abitibi, but previous investigations have necessarily been general in their nature, covering, as they did, extensive tracts of territory. Advantage was taken of the sending by the Department of Crown Lands of a number of surveying parties into the country south and west of lake Abitibi for the purpose of sub-dividing it into farm lots, to despatch an expedition into the same area with the view of ascertaining the character of the prevailing rock formations and the likelihood of minerals being found of economic value. Mr. Geo. F. Kay, fellow in Geology at the University of Chicago and a graduate of the University of Toronto, who had already performed field work for the Bureau and had carried on explorations for the Clergue companies, was placed in charge of the party as geologist, and it was deemed advisable to associate with him an agricultural expert in the person of Mr. Tennyson D. Jarvis, demonstrator in the department of Biology at the Ontario Agricultural College, Guelph, who might report on the quality of the soil, the flora

*Prof. Miller has since re-entered the field, and in a letter to the Bureau dated 26th June 1904, enumerates the principal minerals so far recognized in these unique deposits. "The chief ores are: nicolite, smaltite, chloanthite, native silver, erythrite. annabergite, dyscrasite, pyrargyrite, argentite. Native bismuth is found in all the deposits. Millerite and morenosite occur sparingly. Tetrahedrite and copper pyrites are also found, as also is graphite. Galena, zinc blende and iron pyrites occur in the disseminated form in the adjoining rock masses. Secondary products resembling asbolite and other minerals are common. The oxides of manganese appear to be present. Sulph-arsenides and sulph-antimonides of silver, which have as yet not been analyzed, are also probably associated with these ores, as are the arsenides of iron and various bismuth compounds. No large crystals are found, thus making it difficult to recognize some of the rarer minerals in the field. Microscopic or semi-microscopic crystals of smaltite and one or two other minerals are abundant."

Digitized by Google

and fauna, and generally the adaptability of the region examined for permanent settlement. The report of Messrs. Kay and Jarvis on the Abitibi region and its agricultural capabilities will be read with interest, and on the whole bears testimony to the general accuracy of preceding explorers, who have reported in favorable terms on the northern heritage of Ontario.

A special appropriation of $3,000 was made by the Legislature in the session of 1903 to defray the expenses of an expedition into the country north of the Height of Land for the purpose of procuring more definite information respecting the deposits of lignite which were known to exist in the valleys of a number of the rivers tributary to James Bay. Other minerals of importance have also been reported from a number of localities in that region, and it was thought possible to combine the work of examining some of these deposits with the main object of the expedition. The party was placed in charge of Mr. J. M. Bell, lecturer in Geology at Harvard University, and a graduate of Queen's University, Kingston, who, while in the employ of the allied companies of Sault Ste. Marie, had spent some time in exploring northern Ontario for economic minerals, including coal. Associated with Mr. Bell was Dr. W. A. Parks, lecturer in Mineralogy and Geology at the University of Toronto, who had also a good acquaintance with the geology of the northern portions of the Province acquired while exploring for the Bureau of Mines, and whose attainments as a palaeontologist qualified him to deal with questions of stratigraphy arising in the field. The difficulties of transporting heavy machinery, such as drilling apparatus, in a region where everything must be taken in in canoes and packed across portages on the backs of voyageurs, restricted the party to such tools as could be carried in this way, and in the case of some of the lignite occurrences the appliances proved inadequate to determine the extent and value of the beds. Nevertheless, the results of the expedition were such as to make it evident that in these lignite seams, as well as in the iron-bearing formations on the Mattagami and Opazatika, the gypsum beds of Moose river, Gypsum mountain and elsewhere, the kaolinic clays of the Abitibi, Soweska, Moose and Wabiskagami, and, lastly, the great peat bogs of the coastal plain surrounding James Bay on the south, the Province possesses resources of great potential value, much of which will be rendered available by the construction of the Government railways already mentioned. The expedition opened up a hitherto unknown portion of the Province by examining and charting lake Kesagami, whose remarkable cliffs and islands of peat are described by Mr. Bell.

Dr. Parks supplies an account of the Devonian fossils collected by him while exploring the Kwataboahegan river, a tributary of the Moose river entering that stream not far from its mouth, thus adding material to the data necessary for a better classification of the rocks in that region than it has hitherto been possible to make. The formations of the most southern part of the Province are proving to have their counterpart in the extreme north, and it is not unreasonable to suppose that these may be found to contain similar deposits of economic minerals, such as petroleum, natural gas and salt. The presence of gypsum—also found in southern Ontario—has already been abundantly established.

One of the most firmly established mining industries of the Province is that which is engaged in raising and treating the nickel-copper ores of the Sudbury region. The mineral-bearing ranges have usually been described as two in number, the southern and the northern. The working mines are all so far situated on the southern range, to which existing railway communication is confined. Dr. A. P. Coleman, Professor of Geology in the University of Toronto, and Mineralogist of the Bureau of Mines, has spent two consecutive seasons in the Sudbury nickel area, and his paper in the present report entitled, "The Northern Nickel Range," presents a continuation of the work begun in 1902, the results of which were given in the Twelfth Report under the heading "The Sudbury Nickel Deposits." Dr. Coleman has arrived at the conclusion that the nickel- bearing area is really comprised in a continuous band of eruptive rock, entirely enclosing a roughly elliptical or boat-shaped area composed in the main of tuffs, slates and sandstones, about 35 miles long and 8 miles wide. This nickel-bearing band on its inner edge is acid in composition and tends to phases of granite or syenite,

Digitized by Google

but becomes more basic and passes into gabbro or norite as it approaches the outer rim, where the ore bodies are found. Dr. Coleman regards the belt of eruptive as probably synclinal in form and as really constituting a gigantic laccolithic sheet, whose up-turned edges rest on rocks of Archaean age both on the north and the south. He will probably complete his examination of the nickel field during the season of 1904, and it is intended to issue a full account of the region and industry, with maps, in the Fourteenth Annual Report of the Bureau, and perhaps also in the form of a monograph.

Dr. Coleman has given much attention to the glacial geology of Ontario, and has for some years past been devoting considerable time to delimiting the boundaries of the ancient, ice-dammed lake which once occupied on a larger scale the basin of what is now Lake Ontario. In his paper on the Iroquois Beach in Ontario he traces the northern shore of this lake from Niagara around by Hamilton, Toronto, Port Hope, Trenton and Peterborough until it disappears from view, and discusses the interesting questions of differential elevation, former and present systems of drainage, etc., arising out of or connected with these phenomena of glacial times.

The yearly Reports of the Bureau continue to be in much demand among persons interested in the mineral resources of the Province, so much so that the only Report of which any considerable number of copies now remains on hand is the Tenth, or that published in the year 1901. Of this an extra edition was printed for distribution at the Pan-American Exposition held at Buffalo, N.Y., in that year, the whole of which was not then given away. The entire issue of Bulletin, No. 5, entitled, "Peat Fuel: Its Manufacture and Use," was exhausted some months ago, necessitating its re-publication in the Twelfth Report, of which only a few copies are now left. It is thought that by adopting the system of publishing bulletins or monographs dealing with subjects of importance, of which a considerable number can be struck off, the demand information on special subjects may be met without requiring a larger edition of the annual for Report to be printed than at present. It is, accordingly, proposed to publish a series of such bulletins on important minerals in Ontario, giving all the information which may be available on the subjects of which they will treat. A beginning in this work has already been made, Bulletin No. 5, already mentioned, having dealt with the subject of Peat Fuel, and Part II of the present Report with the Limestones of the Province.

The announcement made in the introduction to the Twelfth Report may be repeated here, namely, that on payment of a reasonable charge the services of Prof. W. G. Miller, Provincial Geologist, may be obtained during a limited portion of the year by persons wishing to have their mineral properties examined and reported upon. Correspondence to this end should be addressed to the undersigned.

I have the honor to be, Sir,

Your obedient servant,

THOS. W. GIBSON,
Director.

Office of the Bureau of Mines,
Toronto, 17th March, 1904.

Digitized by Google

Digitized by Google

REPORT OF THE BUREAU OF MINES 1904

Vol XIII Part I

By Thos. W. Gibson, Director

Statistical Review

The value of the mineral products of Ontario for the year 1903 was slightly under that for 1902, the decrease being wholly in the output of metallic substances, non-metallic products showing a material gain. Values were well maintained in the non-metallic class, in some instances even advanced, but in the metallic list a decided downward tendency was exhibited; hence the aggregate value of the one class of products was greater and of the other smaller than it would have been were the comparison made on the basis of prices prevailing in 1902.

The total output footed up to a value of $12,870,593, the reduction as compared with the previous year being about 4 per cent. The chief decreases in the metallic production were in iron ore and steel, the greater part of the shrinkage being accounted for by the paralysis that fell on the Sault Ste. Marie industries, involving as it did the closing of the Helen iron mine, from which the great bulk of the iron ore raised during the last four years in Ontario has come, as well as the stoppage of the Algoma Steel Works. A diminution in the yield of the precious metals and a smaller output of pig iron, also contributed to the result. On the other hand, 1903 was the record year in nickel and copper, the production of which, both in quantity and value, considerably exceeded that for 1902, or any previous twelvemonth. When the increased facilities for mining and treating the nickel-copper ores of the Sudbury district now being provided come into full operation, the output from this field will doubtless show still further advance.

The most notable increase among non-metallic substances was exhibited by petroleum, where, owing to higher prices, a considerably smaller yield brought a much larger return. Slight fluctuations were shown by some of the other articles of staple production, such as salt, lime, stone and brick, but on the whole the important industries concerned with these materials have improved their position during the year in the matter of prices, and have held their ground in point of production. Portland cement also took a long stride forward during the year; indeed, few products can show so consistent and rapid a rate of increase from the time of its first appearance in the list. Among the other branches of the mineral industry represented in the non-metallic class, there are a number which present unmistakable signs of growth, and which bid fair to rise to a much higher place in the extent and value of their products. Corundum, feldspar, iron pyrites, and calcium carbide are all undergoing favorable development. Mica has stepped well forward, and Ontario, along with her sister Province of Quebec, now ranks as the principal producer of the phlogopite or "amber" mica, so desirable in the manufacture of electrical apparatus.

Just before the snow fell in November last, some remarkable discoveries of nickel, cobalt, arsenic and silver ores were announced from a point in the unsurveyed territory along the line of the Temiskaming and Northern Ontario railway, south of the township of Bucke, and Prof. Miller, Provincial Geologist, was at once instructed to make an examination of the deposits.

Digitized by Google

In the few days at his disposal before the coming of winter, which put an end to exploration, Mr. Miller ascertained beyond doubt that the discoveries were very rich as well as unique in character. In a slate or slate-breccia formation, and within a short distance of one another, some four veins were found, carrying compounds of arsenic, cobalt and nickel in the form of smaltite and niccolite, and in some of the veins abundance of native silver. Time did not permit of extensive examinations being made, so that it is yet uncertain whether the deposits are isolated in occurrence, or whether others of similar character are likely to be found. The areas occupied by the slate or slate-breccia are, however, widespread and numerous, and there appears to be no reason why the ore bodies should be confined to one small corner. The discoveries were made by men engaged in constructing the line of the Government railway, the railway, indeed, being located almost directly over one of the deposits, and they well illustrate the possibilities of the northern regions of the Province, where so much wealth doubtless yet lies concealed, as well as the propriety of prospecting every square mile of the so-called Huronian formations. A fuller account of these discoveries, with analyses of the ores, is given in this volume by Mr. Miller. The richness of the finds and the possibility of the occurrence of another nickel field within the boundaries of the Province led to the withdrawal of a belt or tract of land ten miles in width on either side of the railway from the northern boundary of the township of Widdifield to the town of New Liskeard, by Order in Council dated 11th November 1903, to the end that such steps might be taken as were required by the public interest. On 6th April 1904 the Order in Council was rescinded, and it was provided that mining locations within the above belt should not exceed 40 acres in area, and that no applicant should be entitled to more than three such locations in any one calendar year. Part of the belt lies within the Temagami Forest Reserve, and to this portion the Forest Reserve regulations will also apply. Among other things, these regulations require any one wishing to prospect for minerals in a Forest Reserve to take out a license costing $10 per annum, and they also make provision for the careful protection of the pine and other timber.

Prospecting for minerals, especially for iron ores, was active during the exploring season of 1903. Much work was done on the various iron "ranges" of the north, and the extension of railway facilities into the Temagami region is likely to lead to the systematic testing of some of the enormous outcroppings of banded ore in that region as soon as drilling plants and other necessary appliances can be taken in.

In the following schedule are given the output and value of the various minerals and mineral products in the Province for 1903, as well as the number of workmen and amount of wages paid in the mining or treatment of each product :

Summary of Mineral Production

Product.		Quantity.	Value. $	Employees.	Wages. $
METALLIC :					
Gold	oz.	10,383	188,036	493	245,490
Silver	"	16,688	8,949	32	8,000
Copper	tons.	5,331	716,726	1,437	872,802
Nickel	"	6,998	2,499,068		
Iron Ore	"	208,154	450,099	324	166,457
Pig Iron	"	87,004	1,491,696	622	283,928
Steel	"	15,229	304,580		
Pig Lead	"	25	1,500	20	5,189
Molybdenite	"	85	1,275	5	450
Zinc Ore	"	1,150	17,000	28	7,184
			5,678,929		
Less value Ontario ore smelted into pig iron, and pig iron converted into steel			436,354		
Net metallic production			5,242,575	2,961	1,589,000
NON-METALLIC :					
Actinolite	tons.	550	1,650	8	907
Arsenic	"	257	15,420	24	
Tile, drain	No.	18,200,000	227,000		
Brick, common	"	230,000,000	1,561,700	3,113	771,163
" paving	"	3,788,800	45,288		
" pressed and terra cotta	"	23,702,610	218,550	207	94,182
Building and crushed stone			845,000	1,270	500,000
Carbide of calcium	tons.	2,507	144,000	66	33,934

Digitized by Google

Summary of Mineral Production—Continued

Product.		Quantity.	Value. $	Employees.	Wages. $
NON-METALLIC—Continued					
Cement, natural rock	bbl.	89,549	69,319	74	20,750
" Portland	"	695,260	1,182,799	780	368,504
Corundum, grain	tons.	849	84,900	186	106,382
" cobbed	"	270	2,700		
Feldspar	"	15,296	20,046	51	14,089
Graphite	"	4,400	20,636	63	21,578
Gypsum	"	4,520	7,910	19	4,825
Iron pyrites	"	7,469	21,693	39	16,327
Lime	bush.	3,400,000	520,000	725	193,500
Mica	tons.	948	102,205	164	45,394
Natural gas			196,535	138	79,945
Peat fuel	tons.	1,100	3,300	12	4,000
Petroleum	imp. gals.	16,640,338			
Illuminating oil	"	7,096,073			
Lubricating oil	"	2,614,313			
Benzine and naphtha	"	832,153	1,586,674(1)	291	165,700
Gas and fuel oils and tar	"	1,968,172			
Paraffin wax and candles	lbs.	2,673,806			
Pottery			160,000	150	57,000
Salt	tons.	58,274	388,097	208	87,995
Sewer pipe			199,971	101	46,486
Talc	tons.	920	2,625	8	1,275
Total non-metallic production			$7,628,018	7,697	2,633,386
Add metallic production			5,242,575	2,961	1,589,000
Total production			$12,870,593	10,658	4,222,386

(1) Value of refined products and of crude oil (2,176,090 imp. gals.) used for fuel and gas-making, etc.

A comparison of the foregoing table with the one for 1893, ten years ago, reveals not only a large gain in the total value of production, amounting to $6,749,840, or upwards of 100 per cent., but also a decided increase in the number and range of the minerals and mineral substances produced. The following articles not appearing at all on the list for 1893 figure, for the values given, in 1903: Iron ore $450,099, pig iron $1,491,696, steel $304,580, molybdenite $1,275, lead $1,500, zinc ore $17,000, actinolite $1,650, arsenic $15,420, carbide of calcium $144,000, corundum $87,600, feldspar $20,046, graphite $20,636, iron pyrites $21,693, talc $2,625, peat fuel $3,300, and paving brick $45,288. The only minerals which disappeared from production during the same period were phosphate of lime and cobalt, of which $200 worth and $9,400 worth respectively were produced in 1893. The former of these two substances was driven out by the competition of the lower grade but more cheaply mined phosphate of the southern States, but the recent finds along the Temiskaming and Northern Ontario railway are likely to restore cobalt ores to the list of products, probably in increased quantity and value. The yield in 1893 was from the nickel-copper ores of the Dominion Mineral Company's mines.

The progress of the mineral industry during the last five years may be traced by means of the table on page 4, from which it will be seen that the value of the metallic output rose from $2,055,592 in 1899 to $5,242,575 in 1903, of non-metallic materials from $6,361,081 to $7,628,018, and of the total from $8,416,673 to $12,870,593, the aggregate gain during the five-year period being 53 per cent.

Gold and Silver

The output of gold for 1903, as returned to the Bureau of Mines, was 10,383 ounces of bullion worth $188,036, a considerable decrease from the yield for 1902, when it was 13,625 ounces valued at $229,828. The product of the gold mines of the Province has, in fact, been growing less year by year since 1899, when at the sum of $424,568 it reached the highest point yet recorded.

The causes for this continued decline are various, and allusion has been made to them in previous reports. The gold ores of Ontario are in the main, so far as yet proven, low-grade in character, and to be made to yield a profit must be worked on a considerable scale, and by companies with sufficient capital and confidence to expend large sums of money in thoroughly proving and developing their properties before looking for large returns. The bane of gold-mining in the Province has been the excessive haste of

Digitized by Google

Mineral Production 1899 to 1903

Product.	1899	1900	1901	1902	1903
METALLIC:	$	$	$	$	$
Gold	424,568	297,861	244,448	229,828	188,036
Silver	65,575	96,367	84,830	58,000	8,949
Copper	176,237	319,681	589,080	680,283	716,726
Nickel	526,104	756,626	1,859,970	2,210,961	2,499,068
Iron Ore	30,951	111,805	174,428	518,445	450,099
Pig Iron	808,157	936,066	1,701,708	1,683,051	1,491,696
Steel	.....	46,380	347,280	1,610,081	304,580
Pig Lead	.....	.....	.....	.....	1,500
Molybdenite	.....	.....	.....	400	1,275
Zinc Ore	24,000	500	15,000	11,500	17,000
	2,055,592	2,565,286	5,016,734	7,002,499	5,678,929
Less value Ontario ore smelted into pig iron, and pig iron converted into steel	.....	.....	.....	745,000	436,354
Total metallic production	2,055,592	2,565,286	5,016,734	6,257,499	5,242,575
NON-METALLIC:					
Actinolite	.....	.....	3,126	6,150	1,650
Arsenic	4,842	22,725	41,677	48,000	15,420
Brick, common	1,313,750	1,379,590	1,530,460	1,411,000	1,561,700
" paving	42,550	26,950	37,000	42,000	45,288
" pressed and terra cotta	105,000	114,419	104,394	144,171	218,550
Building and crushed stone	667,582	650,342	850,000	1,020,000	845,000
Carbide of calcium	74,680	60,300	168,792	89,420	144,000
Cement, natural rock	117,089	99,994	107,625	50,795	69,319
" Portland	444,227	598,021	563,255	916,221	1,182,799
Corundum	.....	6,000	53,115	83,871	87,600
Feldspar	.....	5,000	6,375	12,875	20,046
Graphite	16,179	27,030	20,000	17,868	20,636
Gypsum	16,512	18,050	13,400	19,149	7,910
Iron pyrites	.....	.....	17,500	14,993	21,693
Lime	535,000	544,000	550,000	617,000	520,000
Mica	38,000	91,750	39,780	102,500	102,205
Natural gas	440,904	392,823	342,183	199,238	196,535
Peat fuel	.....	.....	.....	.....	3,300
Petroleum products	1,747,352	1,869,045	1,467,940	1,431,054	1,586,674
Pottery	101,000	157,449	193,950	171,315	160,000
Salt	317,412	324,477	323,058	344,620	388,097
Sewer pipe	138,356	130,635	147,948	191,965	199,971
Talc	500	5,000	1,400	930	2,625
Tile, drain	240,246	209,738	231,374	199,000	227,000
Total non-metallic production	6,361,081	6,733,338	6,814,352	7,134,135	7,628,018
Add metallic production	2,055,592	2,565,286	5,016,734	6,257,499	5,242,575
Total production	8,416,673	9,298,624	11,831,086	13,391,634	12,870,593

many engaged in it to produce bullion, the effort to do so leading them to lay out their capital upon stamp mills and works above ground before sinking on their veins and demonstrating by drifts and levels that the values contained in the lode warranted the erection of a surface plant. Time and again funds have been exhausted before the existence of payable ore bodies was either proven or disproven, and discouraged shareholders have refused to make further contributions towards what appeared to be a doubtful or hopeless cause. Had the natural and legitimate course been adopted of blocking out ore reserves before putting up expensive surface plants, not so many decaying stamp mills would now be disfiguring the gold districts of western Ontario, and those districts would be in better repute.

Want of judgment, and, in some cases, want of honesty, on the part of promoters and directors, as well as lack of competent and experienced management, have also contributed to the failure. There is good ground for believing that the free-milling ores of this Province, offering as they do no special difficulties of treatment, will yet be mined and crushed at a profit by companies whose operations are superintended by men of skill, experience and technical training.

The producing mines of last year were the Grace, Michipicoton district, owned by the Algoma Commercial Company; the Big Master and the Twentieth Century, both in the Manitou district, the former the property of the Interstate Consolidated Mineral Company, and the latter of the Twentieth Century Mining Company; and the Atlas and Belmont

Digitized by Google

mines in the Hastings county gold field of eastern Ontario. Other properties were worked on a small scale, but with the exception of the Northern Light Mines Company, on Eagle lake, none turned out any bullion, the operations being confined to preliminary prospecting.

Following are statistics of the gold-mining industry from 1899 to 1903, inclusive:

Gold Mining 1899 to 1903

Schedule.	1899	1900	1901	1902	1903
Mines worked..... No.	15	18	11	20	19
Ore treated.....tons.	59,615	46,618	54,336	48,544	32,347
Gold product..... oz.	27,594	18,767	14,293	13,625	10,383
Gold value..... $	424,568	297,861	244,443	229,828	188,036
Men above ground..... No.	307	412	305	341	243
" under ground..... "	356	338	288	385	250
Wages paid..... $	324,024	350,694	287,409	343,984	245,490

The St. Anthony Reef mine, on Sturgeon lake, north of Ignace station on the Canadian Pacific railway, is being equipped with a 10-stamp mill, formerly on the Golden Star, which was taken in over the ice during the past winter, and is expected to be in operation early in the summer of 1904. On A L 282 or the Sunbeam mine, a mill is also to be erected, careful development work carried on for some time having, in the opinion of those interested, shown that the mine will be a paying one.

A find of free gold on lot 5 in the first concession of the township of Shakespeare, not far from Webbwood station on the Sault branch of the Canadian Pacific railway, caused much local excitement on account of the rich and handsome specimens obtained. Development work was at once undertaken and has been continued ever since. The prospects are encouraging, and the property is believed to be valuable.

All the silver produced in Ontario so far has come—with the exception of the trifling quantity found associated with the gold in ores worked for that metal—from the Animikie formation of the northwestern shore of Lake Superior. Here was situated the famous Silver Islet mine, where from a tiny rock projecting above the waters of that lake was raised silver ore aggregating in value some $3,500,000, and on the main land were worked the rich deposits of Rabbit Mountain, the Badger, Beaver, Silver Mountain and other mines. When silver fell from its high estate to 50 or 55 cents an ounce, these mines for the most part went out of commission, but one or two were sufficiently high in grade to warrant their operation, even at the reduced value of their product. For several years, West End Silver Mountain mine has been producing annually about $70,000 worth of silver, but early in 1903 a serious fire occurred, which burned down the shaft and power houses and otherwise injured the property, bringing operations to a close. The production of silver in 1903 consequently fell to the lowest point reached since 1897.

The statistics of silver mining from 1899 to 1903 are as follows:

Silver Mining 1899 to 1903

Schedule.	1899	1900	1901	1902	1903
Ore raised.....tons.	8,000	12,500	11,000	6,250	3,400
Ore stamped..... "	8,000	8,000	7,560	6,250	3,360
Bullion product..... oz.	105,467	160,612	151,400	96,666	16,688
Value of bullion..... $	65,575	96,367	84,880	58,000	8,949
Men above ground.....No.	23	20	30	25	12
" below ground..... "	17	30	35	25	20
Wages paid..... $	29,000	24,000	29,500	36,000	8,000

Nickel and Copper

In nickel, which may be called the distinctive metal of Ontario, the production of the past year reached the highest point yet recorded. The output for several years past has been in-

Digitized by Google

creasing at an accelerated rate, the quantity produced in 1903 being nearly double that for 1900. In value the advance has been even more decided, the product in 1903 being worth more than three times the product in 1900. To the superior richness of the ores now raised by the Canadian Copper Company, which come chiefly from the Creighton mine, as compared with the lower grade ores of the Evans, Stobie and other deposits formerly worked, the marked increase in the amount of nickel raised is probably in large part due; while the enhanced value arises from the fact that the nickel-copper mattes are now and for the past three years have been brought to a much higher metallic content than formerly, thus conferring a greater value per pound upon the metals contained. The mines of the Sudbury district are now disputing with the deposits of New Caledonia the position of pre-eminence as a source of nickel, and although there is much variety in the statistics given of the New Caledonian production (2) it is evident that the present rate of growth in the output of Ontario will soon give this Province the supremacy, if it has not already attained it.

The nickel contents of the mattes produced by the operating companies in 1903, namely, the Canadian Copper Company, the Mond Nickel Company, and the Lake Superior Power Company, aggregated 6,998 tons in weight and $2,499,068 in value, being in excess of the production of 1902 by 1,053 tons in weight and $288,107 in value. The quantity of ore raised from the mines was much less than in 1902, being 152,940 tons, as compared with 269,538 tons, but the quantity smelted showed comparatively little reduction, since there was put through the furnaces 214,368 tons, as against 233,388 tons last year.

Both the Canadian Copper Company and the Mond Nickel Company smelted considerably more ore than they raised, drawing on their reserves in the roast heaps, where ore may rest for several months during and subsequent to the process of desulphurization, before being sent to the smelters. The Mond Company confined its mining operations to the taking of some ore from a property held under option, and having run all the roasted ore on hand through the smelter, it ceased operations for the time being. Neither was the raising of ore pushed last year by the Canadian Copper Company, whose energies and labor were largely occupied with the extensive overhauling and re-modelling of the smelting plant, which has been going on for upwards of a year. It is expected that the new works, which will produce bessemer matte, will be ready for operation by May or June, 1904. Early in March of the present year (1904) the Ontario Smelting Works, in which the Canadian Copper Company's low grade mattes were retreated and enriched, were consumed by fire, and the company leased the converting plant at Victoria Mines in which to bessemerize its mattes. The mines and smelter of the Lake Superior Power Company were closed down early in 1903, as a result of the financial difficulties in which this and the other Clergue companies became involved. It is understood that there is a considerable stock of ordinary or low-grade matte in stock at the Gertrude smelter.

The schedule which follows shows the progress of the nickel-copper mining and smelting industry during the last five years :

(2) For instance, the amount of nickel refined from New Caledonia ores in 1901 is given by Annales des Mines (whose figures are adopted by The Mineral Industry) as 6,202 metric tons, while Metallurgische Gesellschaft, A. G., places it at 5,210 metric tons. The last-mentioned authority credits New Caledonia with an output of 3,620 metric tons in 1902, and Canada with 4,715 tons. Apparently, however, this authority takes no account of the product of Canadian matte refined in England. The nickel contents of the ore exported from New Caledonia in 1902 is given by Annales des Mines as 7,045 metric tons. As its own tables show, the latter quantity for a succession of years is invariably much in excess of the quantity of nickel actually recovered.

Nickel-Copper Mining 1899 to 1903

Schedule.	1899	1900	1901	1902	1903
Ore raised.....tons	203,118	216,695	326,945	269,538	152,940
Ore smelted..... "	171,230	211,960	270,380	233,388	220,937
Ordinary matte produced..... "	19,109	23,336	29,588	24,691	30,416
High-grade matte produced..... "	106	112	15,546	13,332	14,419
Nickel contents ..... "	2,872	3,540	4,441	5,945	6,998
Copper contents..... "	2,834	3,364	4,197	4,066	4,005
Value of nickel ..... $	526,104	756,626	1,859,970	2,210,961	2,499,068
Value of copper..... "	176,236	319,681	589,080	616,763	583,646
Wages paid..... "	443,879	728,946	1,045,889	835,050	746,147
Men employed ..... No.	839	1,444	2,284	1,445	1,277

Digitized by Google

Judging from the above figures, the percentage of nickel in the ore smelted, or at any rate the proportion of nickel recovered therefrom, has increased materially during the last two years. In 1899 and 1900 the contents of nickel in the matte product was 1.67 per cent. of the ore smelted, and in 1901 1.64 per cent., while in 1902 it rose to 2.54 per cent., and in 1903 to 3.16 per cent., or nearly twice as high as in 1901. As mentioned already, this enhanced value must largely be set down to the credit of the Creighton mine, an extensive body of high-grade ore, which, being easily worked by quarrying methods, is now drawn upon by the Canadian Copper Company for the bulk of its supplies, other mines, though far from exhausted but more expensive to work and yielding leaner ore, being held in reserve.

The greater part of the copper produced in Ontario is the product of the nickel-copper mines of the Sudbury district, but there are also a number of non-nickeliferous copper properties, some of which are now giving excellent promise of becoming large producers. Perhaps the foremost among these is the Massey Station mine, in the township of Salter, where the main shaft is now down to a depth of nearly 600 feet, and in the neighborhood of which are other copper ore bodies undergoing exploitation. Other mines on the north shore of Lake Huron are the Rook Lake and Superior, and west of Lake Superior the Tip-top mine is being developed with promise of proving a valuable property.

Following are statistics covering the operation of these purely copper properties during 1903, with the figures for 1902 given for purposes of comparison:

Copper Mines 1902-3

Schedule.	1902	1903
Ore raised.....tons.	21,800	23,030
Copper in ore, estimated "	794	1,326
Value copper in ore " $	63,520	133,080
Concentrates produced.tons	720	2,500
Value concentrates..... $	28,082	75,000
Workmen employed.... No.	287	250
Wages paid .... $	137,859	171,155

Adding the copper product from the above mines to that from the copper-nickel mines, a total output is obtained of 5,331 tons, valued at $716,726.

Iron and Steel

Compared with 1902, the output of iron ore fell off considerably both in quantity and value, 208,154 tons worth $450,009 being raised, as against 359,288 tons worth $518,445, the previous year. Of the quantity raised, 195,504 tons were hematite and 12,650 tons magnetite. The Helen mine in Michipicoton being now the main source from which Ontario ore is drawn, the business of iron mining in the Province practically came to an end with the stoppage of work at that mine, before the end of the shipping season last year. Apart from a small quantity of ore raised from a hematite property in Hastings county, the only other mine in operation during the year was the Radnor, in the township of Grattan, Renfrew county, where the Canada Iron Furnace Company has for two or three years past been developing a fair-sized body of good magnetic ore. The output is taken by rail to the company's blast furnaces in Quebec, where it is used with a mixture of bog ore.

The fundamental place occupied by iron and steel in the industrial fabric of civilization has given rise to an immense amount of exploration for fresh supplies of workable ore in all regions of the world which are sufficiently accessible to the centres of iron and steel production. The anxiety to uncover new sources of supply has its root in the fact that present reserves, though undoubtedly large, are being steadily invaded, while each succeeding decade, almost each succeeding year, sees a tremendous increase in the consumption of iron and steel. The demand for these products is rising indeed almost in geometrical ratio, more and more being required per capita as civilization advances and brings nation after nation under its sway, as well as in the general progress of the industrial arts. The necessity for new and larger sources of ore supply is therefore a pressing one, and as it is difficult to see how any other material can be substituted for iron and steel, or, indeed, how these can be diverted from many uses in which they are not at present employed, but for which they are well suited, this necessity may almost be considered bound up with the prosperity of mankind in general.

The command of vast supplies of easily worked, conveniently situated, and high-class iron ores, together with similar facilities in the matter of coal and coke, has placed the ironmasters of the United States in a position to produce iron and steel more cheaply than those of most other countries, and in consequence the development of the iron industry on this continent has been more rapid than in any other part of the world. The discovery, particularly in the States of Michigan and Minnesota in the north,

Digitized by Google

and the State of Alabama in the south, of good ores in unprecedented quantity, was what made this development possible, and indeed brought it about. But the iron mines of the Mesabi, Gogebic and Vermilion ranges, and of the Birmingham district, will not for many years continue to withstand the increasing and ever-increasing demands being made upon them, and far-sighted men are beginning to apprehend that serious consequences may follow upon their depletion. Especially are there grave elements in the situation when it is realized that of the known deposits in the principal ranges of Minnesota and Michigan, about 90 per cent. of the tonnage is owned or controlled by one company, the United States Steel Corporation, thus practically making competition impossible and cutting off independent producers from fresh ore when their present supplies are exhausted. Two things will prolong, perhaps indefinitely, at any rate for generations to come, the life of the iron business, and ward off the evil day when pig iron will become scarce and consequently dear. One is the resort by blast furnacemen to ores of lower metallic contents or of inferior quality, and the other is the discovery of new and plentiful sources of high-grade ore.

Of these, the latter remedy is the one which will probably be sought for first, and its pursuit will be assiduous. Present methods of producing iron and steel in America are in the main based upon and suited to ores of good quality, easily smelted, and containing as much as 60 per cent. and upward of metallic iron. Since the opening of the mines on the iron ranges of the Lake Superior States ores of this description have been on the market in abundance, and ores of lower grade, either as regards their percentage of metallic iron or their proportion of deleterious ingredients, have been in little demand, coming into play only in seasons of great activity and high prices, when the margin of profit was sufficiently large to permit of their being used.

In order to retain the advantage of employing ores high in iron, and offering few difficulties of treatment, the strong tendency is to search for new supplies of like quality to take the place of those now being used when the point of exhaustion is reached. The States of Michigan, Minnesota and Wisconsin have been and are now being examined with the utmost diligence and skill to see whether it is possible that nature has repeated the operations which resulted in the formation of those great ranges that have supplied, and will yet supply, so many millions of tons of high-class ore. The opinion of experts is against the probability of similar ranges being found, and the conclusion has been expressed that although many bodies of ore yet undiscovered may be brought to light within the limits already defined, it is not at all probable that extensive ranges like the Mesabi, Vermilion or Gogebic will again be found.

Iron Ores of Ontario

But the forces which produced the Minnesota iron ranges were also at work in what is now Ontario territory. The Mesabi rocks have been traced northward from Minnesota, and at various points give promise of containing valuable bodies of ore. On Hunter's Island, a short distance north of the international boundary line, recent explorations carried on by Duluth parties have, it is said, resulted in locating a large deposit of first-class ore, while at Loon lake, on the Canadian Pacific railway, the diamond drill has penetrated a flat-lying body of first-class hematite of considerable dimensions, also enclosed in rocks typically Mesabi in their character. There is a large extension of Animikie rocks, considered to be the equivalent of those of the Mesabi range, stretching from Gunflint lake on the boundary between Minnesota and Ontario, in a northeasterly direction to a point on Lake Superior east of Port Arthur, and in this area it is probable that other important deposits will be found. The iron range which has within the last two or three years been located in and west of the township of Hutton, northwest of lake Wahnapitae, and in which at least one large body of magnetic ore has been discovered, differs in some of its characteristics from the Vermilion iron-bearing series of Minnesota, its nearest prototype south of the line, and its geology has not yet been fully worked out. Its importance, however, is great, since the deposit referred to is believed to be of large size and to contain much ore of good quality. The iron formation showing banded magnetite in huge outcroppings on the northeast arm of lake Temagami and elsewhere in the neighborhood of that lake appears to be also of the Vermilion type, resembling the latter more nearly than does the Hutton or Moose Mountain range, though differing also in being, like the latter, associated with parellel bands of pyritiferous rock. Magnetic surveys of certain of the locations on the northeast arm have been made, and if this method of examination can be depended upon, there is an immense amount of ore in the deposit, the only point remaining to be

Digitized by Google

proven being whether there is concentration of ore in depth, so as to get rid of the intermixture of silica or jasper so prominent on the surface. It is the intention of the owners to further prospect the locations during the present season, preliminary to putting on a diamond drill when the same can be taken in on the Government railway now being built past the eastern end of the range.

There are many other districts of Ontario, which need not here be enumerated, highly promising to the searcher for iron ore (3), not the least hopeful being some regions lying near the Hudson Bay watershed now almost inaccessible, but which will be brought within reach by the building of the Grand Trunk Pacific railway, and the projected extension of the Temiskaming and Northern Ontario railway. The large deposit of carbonate of iron, or spathic ore, at Grand Rapids, on the Mattagami river, referred to by Dr. Robert Bell in the Report of the Geological Survey for 1875-6, and described in greater detail in the present volume by Mr. J. M. Bell; the iron range near Round lake on the Blanche river, which has not yet been reported upon, but which from the specimens brought out appears to contain both specular ore and magnetite, and the banded hematite and magnetite ranges near Flying Post, on the Ground Hog river, are some of the localities which merit closer investigation, and no doubt will receive it when better means of communication and transportation are provided.

The potential resources of Ontario in iron ore have been greatly extended within the last five years by the discovery of the following iron ranges situated in widely separated portions of the Province: the Michipicoten range in the Michipicoten Mining Division, east shore of Lake Superior, containing the Helen, Josephine, Frances and Brant Lake hematite deposits; the Hutton or Moose Mountain range northwest of lake Wahnapitae, where the ore is magnetic; the lake Temagami ranges, including those on the northeast arm, Vermilion, Iron and Ko-ko-ko lakes, where the outcroppings are chiefly of magnetite banded with jasper, but which also show a little hematite; the Flying Post or Ground Hog river ranges of banded magnetite and hematite; the banded hematite belt of Black Sturgeon lake, southwest of lake Nipigon, and the extensive range of interbanded hematite and jasper stretching, with some interruptions, from the east shore of lake Nipigon to Little Long lake, a distance of some 70 miles, the western and eastern terminations of which on Nipigon and Little Long lakes respectively have long been known.

Of workable bodies of ore during the same period there have been discovered, in Michipicoten, the Helen, Josephine and Frances mines, the first of which has up to the end of 1903 produced about 900,000 tons of good ore; the Loon lake deposit, which though taken up many years ago was never actually proven to exist until 1902; the large, though lean, deposits of the Mattawin range; and the ore body on Hunter's island already referred to, all of which are of hematite; also the Hutton township deposit, which is magnetite. In addition to these, masses of excellent magnetic ore have been found at the Radnor mine, Renfrew county, and in the township of Mayo, in the county of Hastings. It is evident therefore that the work of proving the iron ore wealth of the Province is proceeding with considerable speed, and that there is yet not only favorable ground for very many more deposits, but good reason for believing that they exist.

When the time arrives for the utilization of iron ores which are now below the accepted standard on account of their containing sulphur or titanium in objectionable proportions, or because they are too low in iron, numerous deposits in eastern and western Ontario will be available which for one or other of these reasons cannot now be worked. It is not impossible that by reason of improved processes such ore bodies will ere long be drawn upon, since their lower cost as compared with better ores, offers inducements for their utilization. Besides, sulphur can now be controlled or got rid of without excessive cost, if not present in too great quantity, and titanium, it has been discovered, rather improves than depreciates pig iron, and can also in moderate proportion be run through the blast furnace without trouble, while for certain purposes phosphorus is actually desirable, and is sometimes, where absent, even added to the charge. In any event, the furnacemen of the second quarter, or at least the second half, of the twentieth century, are likely perforce to be less averse to handling impure or low-grade ores than their fellows of the present day, for the reason that high-class, pure ores will be scarcer then than they are now.

(3) For a fuller account see Iron Ranges of Northern Ontario, 12th Rep. Bur. Mines, p. 304, etc.

Digitized by Google

Pig Iron and Steel

The output of the three blast furnaces of the Province—Hamilton, Deseronto and Midland—for 1903 was 87,004 tons pig iron, the value of which was $1,491,696. Of this quantity, 9,979 tons was charcoal pig valued at $151,470, and 77,025 tons coke iron worth $1,340,226. The production of 1903 was less than that of 1902 by 25,683 tons in quantity and $191,355 in value. This reduction was due in part to the Hamilton furnace being out of blast for repairs during the month of February and part of March. The average value per ton of pig iron at the furnace in 1903 was considerably more than in 1902, being $17.14, as against $14.04. Charcoal iron in 1902 was worth $16.96 per ton, and last year $15.46 per ton, while the prices of coke iron were $14.93 and $17.40 per ton respectively. Contracts are usually made for some time in advance, and these changes in price do not necessarily reflect the state of the market for the period they cover. The demand for pig iron, both charcoal and coke, was perhaps less active than in the previous year, and the tendency of prices, especially towards the close of the year, was downwards.

The product of the Ontario furnaces is all sold in Canada, mostly in Ontario. The coke smelters produce principally foundry iron, also malleable pig and a quantity of basic iron. At Deseronto, where charcoal is the fuel employed, and the ore smelted comes mainly from the Lake Superior district, the product goes principally into malleable castings, and is also used in the manufacture of cast-iron car wheels. Operating expenses were considerably greater than in 1902, owing to the higher level of the three chief elements of cost, namely, iron ore, coke and labor.

The demand for iron and steel continues to be good, and the outlook for business in 1904 is fair, clouded however in the opinion of furnacemen, by the prospect of severer competition from outside sources, principally the United States, where conditions in the iron and steel business are not satisfactory. Canada is regarded as the natural "dumping" ground of American ironmakers, and low water freights and the preferential tariff enable the furnaces of England and Scotland to market their iron here when an outlet for surplus production is required. This, however, is offset in part at least by the bounty of $2.70 per ton on pig iron and an equal amount per ton on steel, paid by the Government of Canada on the home product, as well as the bounty contributed by the Government of Ontario on iron ore mined and smelted in the Province, and the duty of $2.50 per ton which imported pig iron must pay on entry into Canada.

To produce the quantity of pig iron made in 1903, 151,229 tons of iron ore were required, of which 48,092 tons, or 32 per cent., was the product of Ontario mines, and 103,137 tons were imported from the United States.

The steel product for the year—15,229 tons—was much less than in 1902, when 68,802 tons were made. The reason for this falling off was the fact that owing to the paralysis which fell on the great industries at Sault Ste. Marie, the steel plant which ran for several months in 1902, and turned out a large tonnage of steel rails, was idle during the whole of last season. The output for 1903 was wholly the product of the Hamilton Steel and Iron Company, and was made by the open-hearth process.

Following are statistics of the iron and steel making industry of the Province for last year :

Ontario ore smelted, tons.....	48,092
Foreign ore smelted, tons.....	103,137
Scale and mill cinder, tons....	12,188
Limestone for flux, tons.	49,426
Coke for fuel, tons.....	96,540
Value of coke for fuel.....	$ 561,614
Charcoal for fuel, bush.....	932,630
Value of charcoal for fuel....	$ 55,958
Pig iron product, tons.....	87,004
Value of pig iron product....	$1,491,696
Steel product, tons.....	15,229
Value of steel product.....	$ 304,580
Workmen employed, number...	622
Wages paid.....	$ 283,928

In the following table is given a bird's-eye view of the ironmaking business of Ontario since its revival in 1896 :

Production Iron and Steel 1896 to 1903

Schedule.	1896	1897	1898	1899	1900	1901	1902	1903
Ont. ore smelted ...tons.	15,270	2,770	20,968	24,494	22,887	109,109	92,883	48,092
Foreign " ... "	35,868	34,722	56,555	85,542	77,805	85,401	94,079	103,137
Limestone flux..... "	8,657	9,473	13,799	25,301	24,927	51,152	58,885	49,426
Coke ..... "	30,348	27,810	50,407	74,403	59,345	113,119	111,390	96,540
Charcoal .....bush	.....	.....	.....	.....	955,437	915,789	968,623	932,630
Pig iron .....tons.	28,302	24,011	48,253	64,749	62,386	116,370	112,687	87,004
Value pig iron..... $	353,780	288,128	530,789	808,157	936,066	1,701,703	1,683,051	1,491,696
Steel. .....tons.	.....	.....	.....	.....	2,819	14,471	68,802	15,229
Value .... $	.....	.....	.....	.....	46,380	347,280	1,610,031	304,580

Digitized by Google

Under the provisions of the Mines Act iron ore raised in Ontario and smelted into pig iron in the Province is entitled to be paid out of the Iron Mining Fund a bounty equal to $1 per ton of the metallic product of the ore, provided the amount called for does not exceed $25,000 in any one year. Where the claims on a basis of $1.00 per ton are in excess of this sum, the rate is reduced proportionately. The amount earned and paid out of this fund for the bounty year ending 31st October 1903 was $25,000. The details are as follows :

Name.	Tons Ont. ore smelted.	Tons Pig Iron produced.	Bounty. $
Hamilton Steel and Iron Coy	30,959	16,631	15,572 40
Canada Iron Furnace Coy.....	19,160	10,068	9,427 60
Total	50,119	26,699	$25,000 00

The quantity of ore eligible for bounty yielding more than 25,000 tons of pig iron, the rate per ton was lowered to $0.936. There has been paid out of the Iron Mining Fund up to the present time the sum of $109,741.01, as follows :

Bounty on Iron Ore 1896 to 1903

Year.	Pig iron product Ont. ore. tons.	Bounty paid. $
1896.....	4,000.00	4,000 00
1897.....	2,603.95	2,603 95
1898.....	8,647.19	8,647 19
1899.....	12,752.07	12,752 07
1900.....	6,737.80	6,737 80
1901.....	55,214.00	25,000 00
1902.....	53,868.22	25,000 00
1903.....	26,699.28	25,000 00
Totals ...	170,522.51	$109,741 01

The sum originally appropriated by the Legislature for the purposes of the Fund was $125,000, and by the terms of the Act it passes out of existence by effluxion of time on 1st January, 1906. The payments which have now been made leave a balance in the Fund of a little over $15,000, and the prospects are that the amount so remaining will be fully absorbed by the claims made during the current bounty year which ends 31st October 1904.

Lead

A generation ago the Frontenac lead mine in the township of Loughborough was opened up, and a small smelting plant was erected in the city of Kingston for treating the ore. The works were put up in 1879, and ran intermittently until 1881 or 1882. Since that time no pig lead has been produced in the Province until 1903, although more or less galena has been raised at several points, including the Victoria mine at Echo lake, and the Katherine mine in Hastings county. Last year the Ontario Mining and Smelting Company, a concern organized in the United States, with an authorized capital of $300,000, purchased the old Hollandia mine near Bannockburn, in the county of Hastings, cleaned out and extended the workings, and constructed a small furnace for reducing the ore. The runs so far have been mainly experimental, the quantity produced up to the close of the year being about 25 tons, having a value of $1,500.

Molybdenite

Some 85 tons of molybdenite ore was taken from a deposit on the east half of lot 5 in the fourteenth concession of the township of Sheffield in the county of Addington, and shipped to the United States and elsewhere. There were raised from the opening some 500 or 600 tons of rock carrying pyrite and pyrrhotite, with an average of perhaps 4 per cent. molybdenite, from which the quantity shipped was culled. Mr. A. M. Chisholm of Kingston had charge of the operations.

Zinc

Two zinc deposits were worked during the year, the Olden mine in the township of that name, operated by Messrs. J. Richardson and Sons of Kingston, and another in the township of Dorion, in the Port Arthur district, where the Dorion Mining Syndicate carried on development work and took out a considerable quantity of zinc-lead ore during the process.

Actinolite

For many years the mineral known as actinolite has been mined near Actinolite (formerly Bridgewater), Hastings county, in which neighborhood it occurs in considerable quantity. It is ground without destroying the fibre and is then used in the manufacture of fire-proof roofing material, paint, etc. It may also be employed as a "filler" along with the more

Digitized by Google

easily worked and silky asbestos of Quebec in making steam-pipe covering, packing material and such like articles. Mr. Joseph James of Actinolite, was the principal producer last year. As mined, the crude actinolite is valued at $3.00 per ton, and after being ground, at $5.00 per ton. It is for the most part exported to the United States in the latter condition.

Graphite

Three graphite mines last year produced 4,400 tons of crude graphite in all, valued at $20,636. These were the Black Donald mine, in the township of Brougham, owned by the Ontario Graphite Company, the McConnell mine, near Oliver's Ferry, on the Rideau canal, the property of Mr. Rinaldo McConnell of Ottawa, and the Allanhurst mine in the township of Denbigh, owned by Mr. J. G. Allan. There are plants for treating or refining the ore at the Black Donald mine, and was also at Port Elmsley for the material taken from the McConnell mine. There were produced at these plants 380 tons of refined graphite worth $21,000, and 575 tons of the material were shipped for use in the crude state, including the output of the Allanhurst property. Operations at the Black Donald have been interfered with by the unfortunate circumstance that in following the lead under the bed of Whitefish lake, the bottom of the lake was pierced, admitting the water into the workings, and compelling the workmen to make a hasty retreat.

Mica

There was produced from the mica mines of Ontario in 1903, according to returns made to the Bureau of Mines, 948 tons of mica, worth $102,205. A decided change has come over the business of mica mining in this Province. Formerly a large number of small openings, hardly to be designated "mines," were spasmodically worked by their owners, mostly the farmers on whose lands they were situated, during their spare time, or when a rise in prices made it an object to bring mica to the market. Recently, modern business methods have been applied to the production of mica, and the number of properties worked has become much smaller, while at the same time operations have been on a larger scale and more steadily carried on. The output of last year was practically all from three mines, two of them, the 'Lacey and the Hanlan, owned by the General Electric Company, and the third, the Bob's lake, by Messrs. Kent Bros., of Kingston. Mr. J. W. Trousdale of Sydenham, Mr. L. J. Gemmell of Perth, and Messrs. J. Richardson & Sons of Kingston, also produced smaller quantities, from the McClatchey, Donnelly and Freeman mines respectively.

The practice is now generally adopted of simply "rough-cobbing" the mica at the mine as it comes from the pits, and forwarding the product thus obtained to the trimming works, where it is graded, split and cut into marketable sizes and forms. The figures given above as to quantity and value of product represent the "rough-cobbed" mica, and not the output of the trimming works, which employ in the aggregate a large amount of labor.

Ontario and Quebec are perhaps the leading sources of mica supply on the continent, and furnish a very large share of the mica used in the manufacture of electrical apparatus. The variety yielded by both Provinces is almost entirely phlogopite or "amber" mica, the flexibility and resistance of which to the passage of the electric current render it most suitable for this purpose. It is exported principally to the United States, but, as is shown by the table given below, quantities have of late years also gone to Great Britain, whose supplies in the past have been drawn mainly from India. Muscovite or white mica also occurs in both Provinces, but it is usually stiffer in quality, and less amenable to the bending and shaping required in making the insulating parts of electrical machinery.

The disproportion which formerly existed between the value of the larger sizes of mica and the smaller sizes has to some extent been done away by the increasing manufacture of "micanite," in which pieces of mica of all shapes and sizes are built up by means of a shellac cement into any dimension and thickness required. These boards can be cut, planed and shaped with ease, and are almost, if not quite, as efficient in their insulating properties as the mica itself. In making "micanite," the quality, not the size, of the piece is the important consideration, and fragments down to 1 inch by 2 inches in area, which were formerly relegated to the scrap heap, are now made use of in this way.

The producing mica mines of Ontario are situated in the counties of Lanark and Frontenac, in eastern Ontario, but mica of what appears to be marketable quality has also been found in the districts of Nipissing and Parry Sound.

Exports of mica from Canada for the last three fiscal years were as follows. It all came from the mines of Ontario and Quebec :

Digitized by Google

Exports of Mica

Year.	To United States.		To Great Britain.	
	lb.	$	lb.	$
1901.....	761,991	121,310	211,833	26,959
1902.....	868,645	186,400	115,388	53,001
1903.....	729,489	183,198	658,081	143,736

Talc

The quantity of talc raised in the Province last year was 920 tons worth $2,625. It was produced from two deposits, near Madoc and Gananoque respectively. These are of diverse character, the output of the Madoc mine, which was operated by Mr. C. Henderson of that place being exported chiefly to Newark, New Jersey, where it is used in the manufacture of a popular cosmetic, or "face powder." It is also employed in making the so-called "foot elm" in Batavia, N. Y., and Bowmanville, Ont. The product of the Gananoque deposit, worked by Mr. George Jackson, is more fibrous in its nature, and is employed in the manufacture of fireproof roofing at works in Montreal. There is a demand for a variety of talc suitable for making the burner-tips used for acetylene gas. It must be of a specially compact character.

Building Materials

There is no lack of building material in Ontario. In the southern portion of the Province where brick, stone and lime are mainly in demand, not only the surface clays but the indurated shales of certain of the Silurian series afford inexhaustible supplies of raw material for the brickmaker, while for lime, limestone and sandstone, both the Silurian and Devonian rocks can be drawn upon in innumerable localities and at various points in the geological scale. For heavy construction work, such as railway building, and to some extent for lime-making, the still older rocks of Archaean age which characterize the northern districts are frequently called into use. As brick and stone are heavy articles, which cannot be transported from place to place without large expense for freight charges, this wide distribution of clay and stone is a fortunate circumstance, in that it brings within reach of the majority of people the possibility of obtaining substantial dwelling-houses and other buildings at a minimum of cost. In a northern climate like that of Canada this is no mean advantage, and contributes not a little to the general comfort and welfare.

The production of building materials, including in this term brick, both common and pressed, as well as terra cotta, lime and stone, but excluding cement, was in the aggregate about on the same level as in 1902, although the output of lime and stone was somewhat less and the output of brick somewhat greater than in that year. The figures for the last five years are given in the following table, from which it will be seen that there has been a considerable expansion in the output during the period covered :

Building Materials 1899 to 1903

Material.	1899 $	1900 $	1901 $	1902 $	1903 $
Building and crushed stone	667,582	650,342	850,000	1,020,000	845,000
Lime	585,000	544,000	550,000	617,000	520,000
Common brick	1,313,750	1,379,590	1,530,460	1,411,000	1,561,700
Pressed brick and terra cotta	105,000	114,419	104,394	144,371	218,550
Totals	2,621,282	2,688,351	3,034,854	3,192,371	3,145,250

Stone

Most of the stone quarried for building and construction purposes is limestone, the quantity of sandstone, or other kinds of rocks, such as granite, trap, etc., being comparatively small. In the figures for stone is concluded the production of crushed stone or rubble used mainly in the construction of road foundations and concrete masonry, and also as limestone flux in blast furnaces.

For substantial and permanent structures, stone is often preferred, and seems likely to retain its hold, particularly where a quarry product has proved its durability by the lapse of years. Some of the limestone quarries which have been in operation a long time are now able to point to specimens of their pro-

Digitized by Google

duct which have withstood the disintegrating effects of exposure to the weather for upwards of half a century. The Queenston Quarry Company, St. Davids, state that Queenston stone was used in the abutments on the Canadian side of the old bridge built across the Niagara river at that point 57 years ago. Four years ago, when the present bridge was built, the engineer took down the old abutments and used the stone in the new work, since it was still practically as good as freshly-quarried material, being without checks or defects of any kind.

The manifold usefulness of a good limestone is illustrated by the product of the Longford Quarry Company's quarries at Longford Mills. Blocks of first-class quality can be turned out in almost any size with natural face on top and bottom, which are used in the foundation of heavy walls and chimneys, also as course stone in buildings, and for bridge work. In the form of rubble it is shipped in large quantities, and as cut and dressed stone it is in demand for window sills, door steps, etc. In addition, it is used as flux for smelting iron ores, and for burning into lime.

Where smallness of cost is a prime requisite, however, and because of greater ease in handling, cement is proving a formidable competitor to stone for uses in which the latter was for long employed almost exclusively. Quarrymen look askance at the new material which is replacing their product in bridge work, foundations and construction work of various kinds, contending that it will prove less durable, and more liable to destruction by frost when exposed to the action of water. Time only will show whether these imputations are warranted, but in the meantime there is little doubt that cement for many uses is pressing hard upon stone.

The same process is observable in the quarrying of stone as in many other branches of the mineral industry in Ontario. The small quarry, worked by the farmer and his boys in a desultory way, and only when there are orders to fill, still survives, and probably will continue to do so for a long time to come in districts out of the freight-charge range of larger works, but year by year more and more of these small quarries are going out of business, their owners finding it not worth while to continue in operation, when their output cannot compete on equal terms with that of more systematically worked concerns, or when they can employ their labor more advantageously in some other field.

Lime

The quantity of lime turned out by the kilns of the Province was apparently about the same as in 1902. There is more or less difficulty in procuring accurate statistics regarding the production of lime, since much of the output is from small kilns, worked spasmodically, whose owners are for the most part engaged in other business, and do not keep accurate records of their production. But in lime, even more than in stone, the day of the small plant is passing away. The rise in the cost of labor, and still more, the growing scarcity and increased cost of wood for fuel, has shorn the small "set" kilns of the chief advantages they formerly enjoyed, and the principal one remaining, namely, lower transportation charges to their markets, does not count for so much in an article like lime as in heavy materials such as stone and brick. Probably the small kiln can still in many instances undersell the larger one, so long as it has lime on hand, but the large stocks and regular supplies which building operations in the cities and towns require can only be procured from works operating constantly, and on a large scale. Consequently, the number of small kilns is decreasing, and the business is more and more coming under the control of the larger, more centrally situated, and more systematically operated plants, which, moreover, being less numerous, are more amenable to the modern methods of eliminating unnecessary competition. The larger draw kilns, too, are more economical of fuel and less wasteful of product than the smaller plant of the "set" or "pot" type.

The demand for lime during the season of 1903 was good, and the outlook for 1904 is regarded as promising. Owing to the advance in the price of fuel and the cost of labor, operating expenses are much higher than a few years ago, perhaps 20 or 25 per cent. higher. The average price of lime has gone up nearly in proportion, being 15.3 cents per bushel last year, as compared with 14.3 cents in 1902, and 13.4 cents in 1901. The competition of cement is being felt to some extent, though this is partially offset by the greater use of lime in industrial works, as distinguished from building purposes.

Toronto offers a large market for lime on account of the extensive building operations which have been going on there for two or three years, and which seem likely to continue for some time to come. Kilns at Limehouse, Acton, Rockwood, Elora, Fergus, Hespeler, St. Mary's, Beachville, Galt, Milton, Kelso,

Digitized by Google

and many other of the numerous places where suitable limestone outcrops within convenient distance supply this market, and other cities and towns in older Ontario have as a rule equally easy access to lime supplies. The analysis of a lime made at Milton, and sold largely in the Toronto market is: Lime 60.08, magnesia 35.67, silica .20, oxide of iron 1.34, carbon dioxide 2.71. The northern portion of Ontario, as for instance, the towns and settlements along the main line of the Canadian Pacific Railway as far west as Fort William, is to a considerable extent supplied with lime from the kilns of Renfrew, Lanark and other counties in eastern Ontario, which also send their product to Valleyfield, Lachute and elsewhere in the Province of Quebec.

Brick

The brickmaking industry of the Province is an extensive one. Abundance of clay has led to a large production and free use of brick for building purposes, and in almost all the cities and larger places of the Province—with the exception of a few towns which, like Guelph, are situated in districts where building stone is abundant and good—brick is the prepondering material. A taste for brick has thus been fostered, and the substantial appearance of such cities as Toronto and Hamilton is in decided contrast to the flimsiness of many frame-built American towns. The number of common brick made last year was 230 millions as compared with 220 millions in 1902, the value being $1,561,700 as against $1,411,000. The higher cost of labor and fuel and the active demand for brick brought about an increase in the average price per thousand from $6.41 in 1902 to $6.78 in 1903. There are decided differences in the price of brick in various parts of the Province, the higher costs prevailing in the cities and the lower values in the country districts. For instance, in Toronto prices ranged from $7.00 to $8.00 per thousand, while in Casselman, in the county of Russell, at the eastern end of the Province, the price was $5.00, and at Sandwich, in the western end, it was $6.00 per thousand. At Waterloo, in the central part of the southwestern peninsula, the cost averaged $6.50 per thousand, and at Lindsay, in the mid-east section, it was the same. Housebuilders in northwestern Ontario had to pay higher prices, as at Fort William, where bricks were worth $9.50 per thousand, 20 per cent. more than in 1902. The demand for brick, as for other building materials, would have been greater throughout the Province generally, and the price been less, as much building has been postponed in the hope that lower prices will be restored.

Pressed brick is made at Toronto, Milton, Brampton and Beamsville. Demand and prices were about on a par with those of 1902.

Other Clay Products

Drain tile is made in many brickyards, especially in the southwestern portion of the Province, where there is much low-lying land, and where it is of prime importance to farmers to rid their lands quickly of the surplus rainfall. The value of the tile made last year was $227,000, an increase of $28,000 over 1902.

Paving brick has not met with that degree of general acceptance as material for street pavements, which was looked for when it was first introduced. Nevertheless, it continues to be in some demand in Toronto, where every year more or less brick pavement is laid down. The paving or vitrified brick made last year numbered 3,788,800 worth $45,288, an average of $11.95 per thousand. The principal makers of paving brick are the Ontario Paving Brick Company, Limited, of Toronto Junction.

The manufacture of sewer pipe is expanding, the value of the product of 1903 being $199,971, as compared with $191,965 in 1902, $147,948 in 1901, and $130,635 in 1900. The makers of clay sewer pipe are the Hamilton and Toronto Sewer Pipe Company of Hamilton, and the Ontario Sewer Pipe Company of Mimico. A small quantity of sewer and culvert pipe is also made from cement.

The following table gives the statistics of production of tile drain, paving brick, sewer pipe and pottery for the last five years:

Product.	1899 $	1900 $	1901 $	1902 $	1903 $
Drain tile	240,246	209,738	231,374	199,000	227,000
Paving brick	42,550	26,950	37,000	42,000	45,288
Sewer pipe	138,356	130,635	147,948	191,965	199,971
Pottery	101,000	157,449	193,950	171,315	160,000

Digitized by Google

The output of the potteries of Ontario in 1903 had a value of $160,000, as against $171,315 in 1902. The principal products from local clays are flower pots, jardinieres, hanging baskets and other common articles of earthenware. Higher-priced goods or stoneware, such as butter pots, churns, pitchers, filters, etc., are made from imported clay by firms in Brantford and Belleville.

Portland Cement

In the Report of the Bureau of Mines for last year (4), some account was given of the origin and development of the Portland cement industry, and of the rapid increase both in consumption and production since the business was established in the Province in 1891. The expansion in the manufacture of Ontario cement has been remarkable, each year, with a single exception (1894), showing a decided increase over the previous one. The rate of growth during the last five years, taking the number of barrels as a basis, has been as follows: 1899 over 1898, 45 per cent., 1900 over 1899, 38 per cent., 1901 over 1900, 14 per cent., 1902 over 1901, 49 per cent., 1903 over 1902, 33 per cent.

For construction purposes cement is constantly encroaching upon the domain of stone, lime, wood, and even iron and steel, and there is every indication that its use will continue to multiply and extend. Well made and well manipulated cement will withstand exposure to the weather for hundreds, even thousands of years, as the excellently preserved remains of ancient Roman buildings attest, and each recurring conflagration in modern cities shows that while limestone, granite and sandstone will disintegrate and crumble under the influence of intense heat, and steel-frames warp and destroy the structures which they support, such inert and homogenous materials as brick and cement will pass through the ordeal comparatively uninjured. The development of the country, especially by means of the great transcontinental and other railways in progress or projected, as well as the improvements constantly going on in roads and pavements, together with the growing employment of cement for building and other purposes, will undoubtedly sustain and increase the demand. Up to the present time the price has been fairly well kept up, but the tendency appears now to be to a lower level. The following table shows the price per barrel of Portland cement at the place of production since the beginning of the manufacture in the Province:

1891	$2.50
1892	2.34
1893	2.00
1894	2.00
1895	1.94
1896	1.77
1897	1.75
1898	1.97
1899	1.99
1900	1.94
1901	1.60
1902	1.75
1903	1.70

The demand for cement at Ontario factories was good early in 1903, and prices were higher than in 1902, but at the close of the season the demand was fully met at prices about 20 per cent. less than those of a year before. The cause of the reduction was the large importations, chiefly from the United States, where manufacturers have the advantage of cheaper plants and cheaper coal, the latter being a leading element of cost. The total production of Ontario, practically the only Province in the Dominion where cement is made, was last year 695,260 barrels, valued at $1,182,799; while the imports into Canada for the fiscal year ending 30th June 1903 were 2,572,088 cwt., or the equivalent of 734,882 barrels of 350 pounds each, valued at $1,172,067, including duty. These imports were from the following countries:

	Cwt.	Value.	Duty.
Great Britain.	701,775	$185,751	$ 45,993.02
Belgium	840,761	261,618	101,781.50
Germany	362,844	129,633	39,731.01
Holland	3,750	1,085	468.75
Japan	53,788	17,485	6,723 50
United States.	609,170	305,491	76,306.22
Total ...	2,572,088	$901,063	$271,004 03

For the seven months ending 31st January 1904 the imports of cement have amounted to 1,675,742 cwt. or 478,783 barrels, of which 555,896 cwt. came from the United States, 444,420 cwt. from Belgium, 321,519 cwt. from Great Britain, and 353,907 cwt. from other countries.

In view of the increasing importations of cement and the number of new plants under construction and likely to place their product on the market at an early date, the prospect before the cement industry is not free from uncertainty, since the capacity of the present plants if fully exercised, would seem to be nearly, if not quite, sufficient to fill the demand. Indeed, those interested in the companies now at work are not slow to express their belief that any increase in productive power is not warranted, and that there will shortly be an era of over-production in Ontario with attendant curtailment or extinction of profits. The duty on cement is

(4) 12th Rep. Bur. Mines, pp. 29 *et seq.*

Digitized by Google

12½ cents per 100 pounds, but even this substantial barrier is not, it is claimed, sufficient to prevent extensive "dumping" by U. S. manufacturers in the Canadian market.

There were nine factories producing Portland cement in Ontario last year. These were the plants of the Lakefield Portland Cement Company, Lakefield, the Owen Sound Portland Cement Company, the Imperial Cement Company, the Sun Portland Cement Company, and the Grey and Bruce Cement Company, all of Owen Sound, the Hanover Portland Cement Company, Hanover, the National Portland Cement Company, Durham, and the works of the Canadian Portland Cement Company at Marlbank and Strathcona.

New Cement Plants

Four other plants are in process of construction, namely, those owned by the Belleville Portland Cement Company, Belleville, the Raven Lake Portland Cement Company, Raven Lake, the Colonial Portland Cement Company of Wiarton, and the Ontario Portland Cement Company of Brantford.

Of these the Belleville Company, whose works are situated on the Bay of Quinte, within four miles of the city of Belleville, have completed the railway connecting the plant with the Grand Trunk, a spur of 3¼ miles long. They have also built their machine shop and storehouse, two structures 40 by 80 feet, with steel roof trusses and walls of stone. The machine shop has been equipped with tools and power. Foundations for the rotary kilns have been laid, and a coal dock is being built and coal unloading apparatus installed. The buildings of the factory proper are to be of steel, and are under contract to be finished by 1st July. They will be fitted with machinery of the latest design, and the company expects to be in a position to produce cement at low cost, claiming as exceptional advantages cheap water-carried coal and contiguity to the works of the raw materials—limestone and clay. This plant will differ from all the other factories now making cement in the Province in that instead of marl it will use limestone, large quantities of which of suitable composition are situated on the property.

The Raven Lake Company are completing their plant, and expect to be manufacturing cement in April, 1904. The buildings lie immediately between Raven Lake (354 acres in extent) and the Grand Trunk railway, about 1 1-4 miles from Victoria Road station. They are so situated as to permit of taking in the marl automatically and loading the cement direct from the factory into the car. Marl will be dredged from the lake bottom and deposited on a scow, whence it will be conveyed to large storage tanks in the factory by means of compressed air. The capacity of the works will be from 600 to 800 barrels per day. A full line of cement machinery of the best American make is being installed, and the process so far as possible will be automatic throughout. Power will be supplied from Elliott's Falls, 13 miles distant, where hydraulic machinery for the development of 1,000 horse power has been put in place.

The works of the Colonial Portland Cement Company are situated on part of lot 3, Jones range, Keppel township, the property having a frontage of 20 chains on Colpoy's bay, where a wharf is being constructed 800 feet in length. The following buildings have been erected: kiln building, 150 by 300 feet, engine house 50 by 120 feet, boiler house 45 by 105 feet, all with steel walls and concrete walls. The dry grinding building 52 by 106 feet, machine shop 40 by 128 feet, and blacksmith shop 24 by 30 feet are of frame, with metallic siding. The coal grinding building 40 by 120 feet, and stock house 75 by 300 feet, when erected, will be of the same material as the kiln building. A large portion of the machinery for the kiln building is in place, and the company expects to be turning out cement some time during the present year (1904). The plant is connected with the Grand Trunk railway at Wiarton by a switch over 7,000 feet long, and will have a capacity of 1,000 barrels per day, with building room to increase to 1,500 or 2,000 barrels per day.

The factory erected by the Ontario Portland Cement Company is at Blue lake, near Brantford, and will have a capacity of 500 barrels per day. It has been completed and will go into operation during the present spring.

Natural Rock Cement

The output of natural rock cement in 1903 was in excess of that for 1902 by 12,249 barrels and $18,524 in value. The demand for this variety of cement, which is cheaper than Portland cement and is used mainly in the foundations and lower stories of farm barns, silos, etc., was good throughout the year. The average selling price at the factories remained at the same figure as in 1902, namely, 77 cents per barrel, which was 11 cents in excess of the price during 1901. Portland cement appears to be preferred for large and important con-

Digitized by Google

struction works because of its greater regularity of composition, but for many minor uses, such as those mentioned above, natural rock cement is a perfectly satisfactory article, and can be obtained for much less money. When the price of Portland cement is high, the natural rock article is in better demand and goes up in price, and when Portland cement falls in value, the price of natural rock decreases.

The manufacturers of natural rock cement are Estate of John Battle, Thorold, Isaac Usher, Queenston, Toronto Lime Company, Limehouse, and F. W. Schwendiman, Hamilton.

Following are statistics of Portland and natural rock cement since 1891, when production of the former began in Ontario:

Production of Cement 1891 to 1903

Year.	Natural Rock.		Portland.		Total	
	bbl.	value. $	bbl.	value. $	bbl.	value. $
1891	46,178	39,419	2,033	5,082	48,211	44,501
1892	54,155	38,580	20,247	47,417	74,402	85,997
1893	74,353	68,567	31,924	63,848	106,277	127,415
1894	55,323	48,774	30,580	61,060	85,903	109,834
1895	55,219	45,145	58,699	114,332	113,918	159,477
1896	60,705	44,100	77,760	138,230	138,465	182,330
1897	84,670	76,128	96,825	170,302	181,495	246,425
1898	91,528	74,222	153,348	302,096	244,876	376,318
1899	139,487	117,039	222,550	444,227	362,037	561,266
1900	125,428	99,994	306,726	598,021	432,154	698,015
1901	138,628	107,625	350,660	563,255	489,288	670,880
1902	77,300	50,795	522,899	916,221	609,199	967,016
1903	89,549	69,319	695,260	1,182,799	784,809	1,522,118

Arsenic

The Canadian Goldfields Limited ceased in March 1902 to operate their gold recovering plant at the Deloro mine, Hastings county, from which all the arsenic hitherto obtained in Ontario has been produced, but continued to work the residues and tailing heaps for arsenic during part of 1903. The quantity of white arsenic produced was 257 tons, valued at $15,420, a reduction in quantity of 543 tons and in value of $32,580, as compared with the output for 1902.

Year.	Tons.	Value. $
1899	57	4,842
1900	303	22,725
1901	695	41,677
1902	800	48,000
1903	257	15,420

Calcium Carbide

The Willson Carbide Works Company of St. Catharines, and the Ottawa Carbide Company, of Ottawa, produced together 2,507 tons of calcium carbide in 1903, worth $144,000, as compared with 1,402 tons worth $89,420 in 1902. The demand was good during the year, and the prospects for business in 1904 are very favorable. The product finds a market exclusively in Canada, and is used almost entirely in the generation of acetylene gas for lighting purposes, and to a small extent only for heating and cooking. The employment of acetylene gas is extending, especially in small towns and villages, where a plant for the manufacture of ordinary illuminating gas would be too expensive. A slight departure in the method of installation has been adopted within the last two years, in that a central plant is now being put in capable of generating the total quantity of acetylene required, the gas being conveyed through pipes to consumers, who pay for it by meter measurement, as in the case of coal gas. By this means the difficulties occasioned by individual generators, many of them not properly cared for, are avoided. That under certain circumstances and with defective or neglected apparatus, there are dangers connected with the use of acetylene, is sufficiently attested by several explosions during the past year, one of them, at Ridgetown, being attended with loss of life and severe injuries.

Following are the statistics of the calcium carbide industry for the last five years:

Digitized by Google

Calcium Carbide 1899 to 1903

Schedule.	1899	1900	1901	1902	1903
Carbide produced.....tons.	1,064	1,005	2,771	1,402	2,507
Value of product..... $	74,680	60,300	168,792	89,420	144,000
Workmen employed..... No.	48	52	83	57	66
Wages paid..... $	23,828	72,584	40,788	28,965	33,934

Corundum

There was a small gain in the production of corundum in 1903, in comparison with 1902, the total output being 1,119 tons, valued at $87,600, of which 849 tons was grain corundum, and 270 tons rough-cobbed. The operating concerns were the Canada Corundum Company, whose works are at Craigmont in the township of Raglan, Renfrew county, and the Ontario Corundum Company, working a deposit at New Carlow, Carlow township, in the county of Hastings. The former of these was the first to engage in the industry, and under special arrangements with the Government of the Province, erected a mill for the production of grain corundum and was given control of a considerable area of corundum-bearing lands. Having worked out the problem of concentrating corundum and separating it from the feldspar in which it is chiefly found, as well as the accompanying impurities such as hornblende and magnetite, the company last year put up a much larger plant a short distance from their old one, which is now completed and running, with a capacity of treating 300 tons of corundum rock per day.

An Ore of Aluminium

One of the conditions of the Canada Corundum Company's agreement with the Government was that experiments should be undertaken with the view of producing aluminium and other useful substances from corundum and corundum-bearing rock. The percentage of aluminium in corundum is much greater than in bauxite, from which the metal is now chiefly obtained, and it was thought that if a practicable process could be devised for obtaining aluminium from corundum, the usefulness of the Ontario deposits would be greatly extended, since the leading, if not the only, purpose for which the mineral is at present employed is as an abrasive. The company has necessarily been obliged so far to confine its attention principally to ascertaining the best methods of treating corundum for the uses to which it is ordinarily put, which has been a task sufficiently troublesome, since the ground which had to be covered was practically new. With regard to the experiments for producing aluminium from corundum, Mr. B. A. C. Craig, president of the Canada Corundum Company, writes under date of 12th February 1904 as follows:

"When the Canada Corundum Company was first formed the writer had one of the staff of Columbia University conduct preliminary experiments in this matter. Pure corundum, as you know, is composed in almost equal parts of the metal aluminium and the element oxygen. The affinity between them is very strong, and the problem before the experimenter is to break down this affinity and drive off the oxygen. A certain degree of success was met with in this, but was far from being success of a practical kind.

"In producing aluminium it has been found that the presence of less than 1 per cent. of iron or less than 1 per cent. of silica will destroy the value of the aluminium, making it brittle, and therefore worthless. We were therefore confronted with the preliminary problem of getting our corundum absolutely pure.

"In ordinary concentration, 70 to 80 per cent. purity is all that is required. Using the latest type of concentrating tables, we found that we could achieve a purity of from 95 to 98 per cent. In fact this purity is required if our material is to be made into vitrified wheels. We found, however, that it was difficult and expensive, if not impossible to go much beyond this. In the case of corundum its specific gravity is only about 1.4 greater than that of its gangue. Another obstacle is found in the fact that even when the rock containing the corundum is crushed comparatively fine, the rock does not completely break away, and grains are often found that are composed partly of feldspar and partly of corundum. If the corundum predominates, the particle of feldspar will often be taken over into the corundum. In addition to this, magnetite, iron pyrites and copper pyrites are found to be disseminated throughout the rock. The specific gravity of a grain that is composed partly of feldspar and partly of one of these minerals is often

Digitized by Google

almost exactly the same as the specific gravity of corundum, and therefore comes down with the corundum.

"Another obstacle in producing a 99 or a 99.5 per cent. pure corundum is the presence of hornblende which occurs here and there in the corundum. It is chiefly found in separate dikes, but occasionally crystals of it are found in the same rock with the corundum. Its specific gravity differs from the specific gravity of corundum by less than one-half of one per cent., and this is the minimum difference necessary for separation by mechanical means. Mr. Overstrom, inventor of the Overstrom table, has lately conducted a number of experiments for us, and considers that the only method of separation is by cobbing.

"As it was impossible to get a perfectly pure corundum by mechanical means, the experimenter suggested that it would be necessary to leach out the iron and silica from the corundum by the same or by a method similar to that employed in leaching out the same materials from bauxite. But in bauxite both of these materials occur virtually as a powder, while in corundum they occur as hard distinct grains, and the leaching process would therefore be longer and more expensive. These together with the additional obstacle consisting of the greater cost of corundum than bauxtite, caused us to temporarily abandon the experiments. If you can get absolutely pure corundum by mechanical means, the corundum might be the cheaper ore, but if corundum has to be treated first mechanically and then chemically there is no doubt that bauxite is the cheaper.

"In separating our material on Overstrom and Willfley tables the crushed material, as you know, stretches out in a thin sheet, the heaviest materials being at the upper side and the lighter tailings at the other. In treating our ore we therefore get on the upper side, iron and iron pyrites, then corundum, then feldspar. The edges of these more or less overlap, but it would seem to the ordinary observer that the middle of the corundum band would be almost absolutely pure and that this could be easily drawn off for the purpose of making aluminium were it so desired. Apart from the presence of grains of feldspar and magnetite, or feldspar and pyrites, etc., a practical difficulty presents itself. It is found that the particles of iron, corundum and feldspar all arrange themselves according to their size. On the upper side of each band is found the smallest grains (apart from slimes that are so fine as to float off) and as you go across each band the grains gradually become larger, the largest grains of each material being at the lower edge. Were you to draw off the middle part of the corundum band you would draw off most of the medium sizes, and as these are the sizes that sell best for abrasive purposes, you would soon find yourself with a great accumulation of unsalable material.

"Another practical difficulty is that if there be any clogging of the screens, spouts, etc., or any inconvenience in the feed so that too heavy a feed comes upon the tables, their work will not be as perfect, and you would always be in danger of getting more than a maximum of one-half of one per cent. of impurities.

"A new method has been suggested for completely eliminating by a mechanical means the impurities that remain after ordinary concentration. The terms magnetic and non-magnetic as ordinarily used, are not scientifically speaking correct. At one end of the magnetic scale we have iron and at the other bismuth. The latter may be called zero. All materials between these are more or less susceptible.

"Taking advantage of this Mr. F. T. Snyder, metallurgical engineer, and Mr. H. H. Waite, chief electrical engineer of The Western Electric Company, have invented a very powerful magnetic separator which separates many substances not generally known to be magnetic. It differs, so far as I know, from all other machines in that the material being treated passes through the line of greatest magnetic density. By means of this machine I understand that they have been able to draw over such materials as zinc blende, and a number of them are in successful operation in Kansas, where they separate zinc blende from the iron pyrites.

"For the purpose of testing this machine on our material, I recently made a trip to Chicago. It successfully separated all the iron from the corundum, and also muscovite mica, but when a more intense current was put on for the purpose of seeing whether it could separate feldspar and hornblende from corundum, the machine in some way got out of balance, as it is termed, and the experiments had to be temporarily abandoned. During my visit there I was shown samples of a red hematite that had been separated from their sandstone gangue. The separation seemed to be a clean one, although when tested with an ordinary powerful magnet, the hematite did not appear to be at all magnetic.

"Apart from this machine, we know of no possible method of mechanical

Digitized by Google

separation. We have by no means given up the idea of experimenting, but until some perfect method of separation of corundum from all other minerals is worked out, there is no use going further.

"We have now installed a chemical laboratory and have secured the services of a Swedish chemist who has had considerable experience in original research work. It is our intention to have him continue experimenting, but we think that it would be better for us to have him give his first attention to other and different lines such as the producing of aluminate of soda and aluminate of potash and other similar minerals.

"The production of aluminium from corundum is something that will take not only money, but painstaking and long continued research. There is no corundum-bearing rock in the district that is pure enough to enable one to use the tailings in the manufacture of pottery."

During the year the Ontario Corundum Company which had been simply rough-cobbing their corundum rock and shipping the richest portions to the United States for treatment, put up a plant on the ground, and are now turning out a very good quality of grain corundum.

A third organization, composed principally of Buffalo capitalists, called Corundum Refiners, Limited, has been formed to engage in the production of corundum, the deposits which it proposes to open being situated mainly in the township of Raglan, east of Craigmont. Mr. P. Kirkegaard, formerly of the Deloro gold mine, is manager.

The subjoined figures show the progress of the corundum business since the first production of 1900:—

Schedule.	1900.	1901.	1902.	1903.
Corundum .....tons.	60	534	1,137	1,119
Value of product $	6,000	53,115	83,871	87,600
Workmen..... No.	35	68	95	186
Wages paid..... $	10,000	30,406	34,674	106,332

The considerable amount of construction work done during 1903 accounts for the apparent disproportion between the sum paid out as wages and the value of the corundum product in that year.

Feldspar

The potash feldspar which exists in large deposits in the township of Bedford and elsewhere along the line of the Kingston & Pembroke Railway, has come into demand during the last three or four years for export to American potteries, in which it is used for glazing tile, baths, enamelled ware, etc. Last year the production was largely in excess of that for 1902, being 15,296 tons, valued at $20,046. The chief producers were the Kingston Feldspar and Mining Company, of Kingston; the Pennsylvania Feldspar Company, Verona, and Charles Jenkins of Petrolea. At the beginning of the present season the outlook for business was not encouraging, trade being somewhat slack in the New Jersey and Ohio potteries, and there being severe competition from American feldspar, which is nearer the market and is consequently lower in price.

The quantity and value of feldspar produced in Ontario during the last four years were as follows:—

	Tons.	Value.
1900.....	4,000	$ 5,000
1901.....	5,100	6,375
1902.....	8,776	12,875
1903.....	15,296	20,046

Attempts have been made to introduce Ontario feldspar into England, but owing to the different methods of manipulation in vogue there and to competition from Scandinavian and other sources, they have so far not resulted successfully.

Gypsum

The output of crude gypsum last year was 4,520 tons, as against 1,917 tons in 1902. It comes from the deposits in the valley of the Grand river, near Paris, and is worked up into a variety of products, such as wall plaster, alabastine, etc., by the Alabastine Company of that place. A quantity is also used by the Imperial Plaster Company of Toronto in the manufacture of wall plaster, wood fibre, etc. The material known as "wall plaster" is calcined gypsum treated with an animal retarder, and is highly commended for use as a coating for walls in buildings, being when set, harder and more durable than ordinary plaster. Land plaster is ground gypsum intended for use as a fertilizer.

Salt

There is no rock salt produced in Ontario, the wells along the east shore of lakes Huron and St. Clair yielding a strong brine which is evaporated by artificial heat, leaving a product of great purity. The salt beds are found in the Onondaga formation, and were first discovered at Goderich about forty years ago.

Digitized by Google

The chief producer is the Canadian Salt Company of Windsor, but other plants in operation last year were those of R. & J. Ransford, at Brussels, Seaforth, Stapleton and Goderich; Ontario People's Salt and Soda Company, Kincardine; Carter and Kittermaster, Moore; Sarnia Salt Company, Sarnia; and Grey, Young and Sparling Company, Wingham.

The production of salt in the Province has remained nearly stationary during the last five years, as will be seen by the table given below:

Production of Salt 1899 to 1903

Schedule.	1899	1900	1901	1902	1903
Salt produced ..... tons.	56,375	66,588	60,327	62,011	58,274
Value of product ..... $	317,412	324,477	323,058	344,620	388,097
Workmen employed ..... No.	261	243	189	193	208
Wages paid ..... $	80,021	72,584	67,024	76,154	87,995

Iron Pyrites

Two deposits of iron pyrites were worked last year, the one producing most largely being that operated by the Madoc Mining Company near Bannockburn. A smaller quantity was raised at the Helen iron mine, Michipicoten. The product is exported to the United States, chiefly to Buffalo and Cleveland, and is used in the manufacture of sulphuric acid.

A peculiar feature in connection with the first-mentioned deposit is that it appeared at the surface as a bed of bog iron ore, and was worked as such. On sinking a short distance the bog ore was found to be succeeded by pyrite, strongly suggesting that the upper layer was due to alteration of the exposed portion of the main body.

The production of iron pyrites during the last three years has been as follows:

	Tons.	Value.
1901	7,000	$17,500
1902	4,371	14,993
1903	7,469	21,693

Natural Gas

The value of the natural gas produced in the Province was somewhat less than in 1902, being $196,535, as against $199,238, though these figures show a large reduction as compared with 1899, when the value of the production rose to the maximum amount, namely, $440,904.

For a number of years the Essex county gas field yielded large quantities of gas, but in 1900 and 1901 the production fell off very much, and in consequence there was great local complaint against exporting the gas to Detroit, the principal place of consumption. Accordingly, the Government of the Province by Order-in-Council dated 26th October 1901 revoked the license of occupation which authorized the exporting company to use the bed of the Detroit river for the purposes of its pipe line, and so brought the export to an end. This step, however, did not have the effect of materially increasing or prolonging the supply to Canadian consumers, and the field is now practically abandoned, the United Gas and Oil Company having notified its customers in Windsor and Walkerville that they would cease to supply them after 1st April 1904. The wells owned and operated by the corporations of the towns of Leamington and Kingsville are no longer adequate for the wants of the inhabitants of these places. Mr. W. A. Smith, town clerk of Kingsville, writes under date of 8th February 1904: "The corporation wells are practically exhausted, and are not producing any gas sufficient to be utilized. The yield has been noticeably declining for over a year, the crisis being reached last July, when the gas supply suddenly ceased. Since then a little gas has reached town and been utilized for domestic purposes, but now it is gone, and we think for good. There are no prospects for a future supply."

The field in Welland has been worked longer than the Essex one, and is still furnishing much gas. Pains are taken to keep the wells free from water, and new ones are constantly being put down. The bulk of the gas comes from the Medina formation, but large wells are also found in the Clinton. A pool in the neighborhood of Dunnville is being exploited, and considerable gas obtained for local use. Recently, gas has been struck in the Medina formation at Brantford, and the product is being utilized under a couple of furnaces in the Cockshutt plough works on the outskirts of that city. Some seven or eight wells have been put down, and gas obtained in several of them, but the total quantity is not great, and it is yet uncertain whether

Digitized by Google

there is a large reservoir. The rock pressure at first was 250 pounds, but has declined to 50.

Returns show that there are 210 wells producing gas in the Province, of which 157 are in the Welland field, and the majority of the remainder in the vicinity of Dunnville. Twenty producing and twelve non-producing wells were put down last year; there were 312 miles of pipe used for conveying the gas to consumers; the number of workmen was 138, and the amount of wages paid $79,945.

Petroleum

Petroleum, of which the Lambton county oil district remains the chief source, is steadily declining in yield. Compared with 1902, the production of crude in 1903 was 1,545,254 Imperial gallons less, and with 1901 4,793,162 Imperial gallons less. The progressive shrinkage is plainly evident from a glance at the statistics of production for the last ten years:

Year.	Imp. gals.
1894	34,912,360
1895	33,351,997
1896	27,380,588
1897	25,556,591
1898	26,978,977
1899	23,615,967
1900	23,381,783
1901	21,433,500
1902	18,185,592
1903	16,640,338

As compared with 1894, the yield has therefore fallen off over 52 per cent., yet the number of wells pumping oil in the Petrolea and Oil Springs fields is probably as great as it ever was. The reduction has been brought about, not by the sudden cessation of oil in any particular portion or portions of the territory, but by a gradual and apparently accelerating diminution in the yield of oil per well. In fact, the oil producing territory of Ontario is unique in the small individual production of its wells, and in the tenacity with which it is worked. Had it been situated in almost any other part of the world it would probably have been abandoned some years ago, but by the use of economical methods its life is prolonged; indeed, the very smallness of the flow and the gradual nature of the process of exhaustion guarantee its existence for a considerable time to come. Additional vitality was given the oil territory of the Province last year by the high prices prevailing for crude, the year closing with a market value of $2.32 per barrel. At this rate the total value of the crude product of the year was $1,103,016, while in 1899 when the closing price was $1.40 per barrel, the total value of crude produced, figured on this basis, was only $944,637, notwithstanding that the quantity was 6,975,629 gallons more. It is clear therefore that price is an important factor in preserving the oil territory of Ontario in production.

Formerly, practically the whole of the crude product of Ontario went to the refining works for distillation, but of late years a considerable and increasing proportion has been used for fuel purposes and in the manufacture of gas. Last year about 2,176,090 Imperial gallons is estimated to have been diverted from the refineries for uses of this sort, or over one-eighth of the total quantity. Even if the refineries had received the whole of the crude produced, there would still have been insufficient to supply the wants of the home market, if it can be held that all parts of the Dominion of Canada ought of right to constitute the market for the refined oils of Ontario. The trade tables show that there were imported into Canada during the fiscal year ending 30th June 1903 the following quantities of crude petroleum and products thereof:

	Gals.	Value.
Oil, coal and kerosene, distilled, purified or refined naphtha and petroleum N.E.S.	14,478,350	$1,965 429
Products of petroleum	554,668	95,225
Crude petroleum, fuel and gas oils (other than naphtha, benzine or gasoline) when imported by manufacturers (other than oil refiners) for use in their own factories, for fuel purposes, or for manufacture of gas	2,143,888	189,689
Lubricating oils, composed wholly or in part of petroleum, costing less than 30 cents per gal.	1,613,943	276,380
Total	18,790,849	$2,526,723

Practically the whole of the above came from the United States. These statistics are sufficient to show how far the Canadian consumption of oil and oil products is from being met by Ontario petroleum.

The refining facilities of the two plants in the Province, those of the Imperial Oil Company at Sarnia, and the Canadian Oil Refining Company at Petrolea, are more than adequate for the entire crude product, and under these circumstances it is not to be wondered at that a strong local agitation has sprung up in favor of reducing the import duty on crude petroleum from five cents per gallon to say two cents. This, it is contended, would enable the refin-

Digitized by Google

eries to supply themselves with the raw material to keep their plants employed, without injuring the producer of crude in Ontario, as the latter would have the advantage which the freight from Pennsylvania or Ohio would give him with the addition of two cents per gallon duty. Besides, it is argued, if the refineries are unable to obtain sufficient crude oil to warrant them in keeping their stills in profitable operation, and are obliged to close their doors, the market for Ontario crude will be gone, and the producer will not be able to sell at all. These views, it is needless to say, are not shared by all oil-well owners, some of whom fear a flood of crude petroleum from south of the line which would speedily put an end to their industry, and are reluctant to relinquish the benefits which are conferred upon them by the present tariff protection.

It is a legitimate subject of inquiry whether other oil horizons do not exist in southern Ontario below the Cornif-erous formation to which production has hitherto been confined. The Trenton limestone, so prolific a source both of oil and gas in Ohio and Indiana, underlies the whole of the southwestern peninsula. In the Lambton oil field it lies at considerable depth, and it is a matter involving some expense to reach it. It has been struck at several points, but so far without yielding oil in any quantity. The Imperial Oil Company have drilled to the Trenton at the following places :

Lot 5 in the fourth concession of Brooke township, Lambton county. Well completed 3rd March 1900; depth 3,380 feet.

Lot 5 in the third concession of Peel township, Wellington county. Well completed 22nd August 1900; depth 2,573 feet.

Lot 6 in the fifth concession of Pilkington township, Wellington county. Well completed October 31 1900; depth 2,390 feet.

Lot 4 in the sixth concession of Amabel township, Bruce county. Well completed 18th June, 1901; depth 1,678 feet.

Lot 6 in the eleventh concession of Amabel township. Well completed 16th January 1902; depth 1,470 feet.

Lot 38 in the second concession, north centre diagonal, Keppel township, Grey county. Well completed 3rd May 1902; depth 1,500 feet.

"Nothing," the company states, 'was found in any of the above wells to encourage further drilling to the Trenton rock."

Nothwithstanding the diminished yield of crude oil in 1903, the decidedly higher range of prices which prevailed during the year not only prevented the total value of the refined products from falling below that of 1902, but actually brought about a noticeable increase, as the following comparison of the statistics for the two years will show :

Petroleum Products 1902 and 1903

Schedule.		1902.		1903.	
		Quantity.	Value. $	Quantity.	Value. $
Illuminating oil	Imp. gals.	7,720,866	715,513	7,096,073	793,426
Lubricating oil	"	2,765,677	287,219	2,614,313	280,449
Benzine and naptha	"	902,847	104,696	832,153	126,052
Gas and fuel oils and tar	"	2,157,049	83,426	1,968 172	122,074
Paraffin wax and candles	lb.	2,433,127	108,107	2,673 806	129,755
Total			1,298,961		1,451,756

The production of crude petroleum and products of refinement for the last five years are given in the following table :

Petroleum and Petro'eum Products 1890 to 1903

Schedule.		1899	1900	1901	1902	1903
Crude produced	Imp. gals.	23,615,967	23,381,783	21,433 500	18,185,592	16,640,338
" distilled	"	23,615,967	23,381,783	17,745,182	15,630,592	14,464,248
Value of crude produced	$	1,747,352	1,839,045	1,335,540	1,298 931	1,024,597
" distilled products	$	1,021,528	1,126,777	980,222	940,104	1,451 756
Illuminating oil	Imp. gals.	11,697,910	11,783,755	9,463,262	7,720,866	7,096,073
Lubricating oil	"	2,087,475	1,980,128	764,861	2,765,677	2,614,313
Benzine and naphtha	"	1,394,530	1,463,599	1 075,909	902 847	832 153
Gas and fuel oils and tar	"	5,410,915	3,669,102	2,652,987	2,157,039	1,968 172
Paraffin wax and candles	lb.	2,792,766	4,599,683	3,189,492	2,433,127	2,673,806
Workmen employed	No.	491	347	351	323	291
Wages paid	$	214,171	163,077	161,042	169,398	165,700

Digitized by Google

New Oil Fields

During the past year oil has been found in promising quantities at two rock horizons which lie a considerable distance, in the geological scale below the productive horizon in the older fields. While in search for gas in the township of Romney oil was found in the Guelph limestone. Oil was discovered under similar circumstances in the city of Brantford. Very little has yet been done in the way of testing these Brantford wells, but considering the size of the area over which they have been found, they can be said to give considerable promise. The productive horizon here lies in still older rocks than those of Romney, namely the Medina.

The fact that oil has thus been discovered in promising quantities both in the Guelph and Medina, below the Corniferous which is the productive zone in the older fields, should induce the drilling of much deeper wells for oil than has been the custom in the southwestern peninsula of the Province. Last year, for instance, when there was great excitement over oil in the township of Raleigh, which adjoins Romney on the east, and many wells were drilled, no one seems to have thought it worth while to drill below the limestone bed of the Corniferous, which has been considered to be the oil-bearing horizon in the Province. There seems little doubt that oil is to be found at greater depths than it has heretofore been looked for in these fields. Before the oil refiners decide that Ontario is unable to furnish them with sufficient crude petroleum to keep their works in operation, it would be well for them to thoroughly test other formations than the Corniferous.

Brant County

In the latter part of 1903 drilling was begun for gas in the city of Brantford. From two or three wells put down at the Cockshutt plough works a strong flow of gas was obtained. This gas was used in the furnaces at the works for a short time, when the pressure began to lessen and the supply soon became too small to keep the furnaces going. It was then found, however, that two of these wells contained oil, which appears to have gradually oozed in as the gas disappeared. On account of unforeseen delays in getting machinery, these wells have not been systematically pumped, so that it is impossible to say what their daily output of oil is likely to be. With a hand pump, used for only a short time daily, three or four barrels of oil have been taken from one well from day to day. The oil is said to contain about fifty per cent. lubricating material, and is thus more valuable than ordinary petroleum. Six or seven wells have been drilled in the city, four of which are on the Cockshutt property, and only one of the seven is said to contain neither gas nor oil. Four wells have also been drilled on the Bow Park farm, which is distant about two miles southeast of the Cockshutt wells. Gas and oil have been found in these wells. In the last one drilled it is stated that oil began to come almost immediately, after the bottom of the well was reached, and kept rising in the pipe "until now it has come to the top and the gas pressure will force it out, the same as it did in the two wells on the Cockshutt property." None of these wells have been "shot."

The oil contents of the wells would appear to give more promise than the gas, which does not show a high pressure for any great length of time. There will doubtless be sufficient gas to supply Bow Park and other farms on which the wells are situated for years to come, if the use of the gas is confined to the farms.

The horizon, red shales of the Medina formation, appears to be practically the same as that in which gas is found in the Port Colborne and adjacent pools. This horizon is much lower in the geological scale than that of the old Petrolea field, which is in the Corniferous.

The following logs and notes on the first three wells put down on the Bow Park farm have been furnished by the driller. It will be noticed that the first limestone met with in the drill holes is classed as Niagara. The upper part of this really belongs to the Onondaga formation, which immediately underlies the glacial and loose deposits in this field. The Niagara has a total thickness here of about 250 feet, consisting of limestone and the underlying black shale. The strata below the Clinton all belong to the Medina formation.

Report of Well No. 2 on "Bow Park," Drilled December, 1903 :

	Feet.
Surface red clay and sand 6 ft., blue clay 55 ft.	61
Hard pan 25 ft., broken stone 2 ft.	27
Niagara Lime, 88 ft. to 340 ft.	252
Black Shale, 340 ft. to 390 ft.	50
Clinton, 390 ft. to 410 ft.	20
Red Medina, 410 ft. to 450 ft.	40
Grey Shale, 450 ft. to 490 ft.	40
White Medina, 490 ft. to 505 ft.	15
Red Shale and Rock, 505 ft. to 510 ft.	5
Red Shale, 510 ft. to 582 ft.	72
	582

Digitized by Google

Surface water shut off at 91 ft. with 6-inch casing. Deep water shut off at 344 ft. with 5-inch casing. Gas struck at 395 ft., 505 ft. and 508 ft. Pressure 265 lb.

After drawing heavily for about thirty days pressure was reduced to 180 lbs. When shut off altogether pressure ran up 220 lbs.

Report of Well No 1 on "Bow Park." Drilled February, 1904.

	Feet.
Surface clay and sand 18 ft., Blue clay 30 ft., Quicksand 10 ft.	58
Hard pan	10
Niagara Lime (Onondaga), from 68 ft. to 335 ft.	267
Black (Niagara) Shale, 335 ft. to 375 ft.	40
Clinton, 375 ft. to 390 ft.	15
Red Medina, 390 ft. to 430 ft.	40
Blue Shale, 430 ft. to 450 ft.	20
Sand Rock, 450 ft. to 470 ft.	20
White Medina, 470 ft. to 485 ft.	15
Rock and Shale, 485 ft. to 490 ft.	5
Red Shale, 490 ft. to 602 ft.	112
	602

Surface water shut off at 73 ft. with 6-inch casing. Deep water shut off at 338 ft. with 5-inch casing. Gas struck at 490 ft. Pressure 282 lb.

Report of Well No. 3 on "Bow Park." Drilled January, 1904.

	Feet.
Surface clay and sand 13 ft., Blue clay 30 ft.	43
Basket sand 15 ft., Hard pan 7 ft., Stone and broken rocks 5 ft.	27
Niagara Lime, 70 ft. to 330 ft.	260
Black Shale, 330 ft. to 375 ft.	45
Clinton, 375 ft. to 395 ft.	20
Red Medina, 395 ft. to 440 ft.	45
Blue Shale, 440 ft. to 460 ft.	20
Shale and sand rock, 460 ft. to 480 ft.	20
White Medina, 480 ft. to 500 ft.	20
Red Shale, 500 ft. to 611 ft.	111
	611

Surface water shut off at 72 ft. with 6-inch casing. Deep water shut off at 335 ft. with 5-inch casing. Gas struck at 498 ft. Pressure 235 lb. Same quantity of oil came in.

Romney Township

Under date of February 12th 1904 the United Gas and Oil Company of Ontario, Limited, furnish the following particulars concerning the oil wells recently drilled by them. They state, "As to the oil, we have now four producing wells on lot 11 in the second concession of the township of Romney, Kent county, yielding a total daily production of 40 barrels." Since that time, according to press notices, other wells, with a large oil production, have been drilled in the surrounding area. It is stated that one or two of these wells had the character of gushers or flowing wells.

A set of drillings from one of the wells in the above mentioned lot in Romney was sent to the Bureau, together with a statement as to the depths from which they were taken. The surface soil here has a thickness of 135 feet. The well was drilled to a depth of 1,305 feet. Between 1,285 and 1,290 feet the first showing of oil was obtained, and the productive horizon lies between 1,290 and 1,300 feet, in the Guelph formation.

The company asked that it be determined from the samples of drillings sent by them to the Bureau whether the oil from the Romney well comes from the same horizon as the gas in the townships of Mersea and Gosfield. For this purpose they sent a sample, No. 101, from a depth of 1,025 feet in an old gas well in the township of Mersea. Chemical analyses were made of this sample and of three others from the Romney well. The results obtained are given in the following table:

	No. 50.	N. 51.	No. 52.	No. 101.
Insoluble silicious residue	1.32	2.02	1.06	.58
Alumina and ferric oxide	1.56	2.24	1.28	1.56
Lime	29.18	29.38	28 80	29.70
Magnesia	21.61	21.22	20.66	21.53
Carbon dioxide	46.62	46.30	44.39	46.82
	100.29	100.16	96.69	100.19

Samples 50 and 51 show the character of the rock in the Romney well between the depths of 1,290 and 1,300 feet, the productive oil horizon. It will be noticed that there is a remarkably close agreement, in the lime and magnesia percentages, in the analyses of Nos. 50, 51 and 101. Sample No. 52, from 1,300 to 1,305 feet, is also close to these three in its percentage of the same two constituents. There is also a fairly close agreement as regards the percentages of carbon dioxide, and alumina and ferric oxide. In fact the four analyses agree so closely that they might easily represent samples from a single bed or stratum. There therefore seems little doubt that the gas of Mersea and the oil of Romney come from the same horizon in the Guelph formation. This formation lies, of course, a considerable distance below the horizon at which oil is found in the old Petrolea field and where it has been sought for in the township of Raleigh and other areas adjacent to Romney.

Digitized by Google

Peat Fuel

In the Twelfth Report of the Bureau of Mines a full account of the peat fuel industry, both in Ontario and in Europe, was given by Mr. W. E. H. Carter, Secretary of the Bureau (5), and in the following paragraphs Mr. Carter presents further information on the subject. The output of compressed peat fuel in the Province last year was 1,100 tons, valued at $3,300. It was produced mainly at the factory of Mr. Alexander Dobson, Beaverton, but a small tonnage was also made by Dominion Peat Products at Newington.

Operations during the season of 1903 were confined to the factories noted in the above-mentioned report. New methods and machines applicable to various parts of the process of manufacture have been tried at both the older works and the new plants during the year. New machines for field operations and for compressing peat briquettes have been invented, and others already known to the industry, though not as yet placed in commercial operation, have been modified or improved. Not all of these machines have yet been tried in actual practice, either experimental or commercial, so that no expression of opinion as to their economic value is yet possible.

The very general interest in the manufacture of peat fuel awakened during the past year or so both in Ontario and other parts of Canada, and in many parts of the United States, and even Mexico, has led to the formation of a large number of companies to undertake the business. There is a tendency amongst many of these companies to adopt newly invented or at least untried machines, and while this may of course mean the introduction into the industry of other efficient processes and apparatus, it would be much safer and more satisfactory if at the outset only those processes were employed which had stood the test of actual use.

The more peat is handled and worked the more apparent does it become that in its physical characteristics it is quite unlike any other substance. It requires methods of treatment for drying and compressing—the two fundamental operations in the manufacture of the fuel—which are applicable to peat alone. Accordingly machines and processes which work successfully on such substances as sawdust, coal slack or lignite, alone or mixed with other materials, are not necessarily suitable for peat. It will be time enough to strive for machinery to make cheaper and better peat when the fuel which has already been found commercially satisfactory is being turned out in quantity. Peat briquettes can be and are being made now in Ontario for about $1.50 per ton, and are sold for $3.50 per ton at the works. One plant has during the past year (the third year of its operation) manufactured 1,000 tons and sold the product in small lots from end to end of the Province. This is surely profit enough and proof of success enough to show the business to be a legitimate one.

Of equal importance with the adoption at the outset of only tried and proved machines is the employment of a superintendent or manager who is well acquainted with the machines and processes of the day and with the peculiarities of peat.

(5) Bulletin No. 5, Peat Fuel; its Manufacture and Use, reprinted in 12th Rep. Bur. Mines, pp. 191-234.

The Open-Tube Press

As described in Bulletin No. 5, only two types of briquetting press have been tried on a commercial scale so far. The principle of one is compression against a solid base without friction in the die or mould; the other, compression against the frictional resistance of the peat briquettes on the walls of the open-tube or bottomless die. Further investigation has exposed a serious weakness, probably the most important one in the latter variety of press, and as the failure strikes directly at the principle of its operation it appears insurmountable. The open-tube or bottomless die is largely used in Germany for compressing lignite and coal dust or fines into briquettes, which would indicate a radical difference between the chemical as well as the physical composition of peat and the other two substances, lignite and coal fines, affecting their amenability to frictional compression in the open-tube die. At Dobson's peat factory at Beaverton trials of the open-tube die press on peat were made more thoroughly perhaps than at any other place in the Province or elsewhere. The failure of the machine there as elsewhere usually showed itself in a cracked or broken die tube. At last to obviate the recurrence of this, a heavy nickel steel die was cast, which withstood perfectly the immense tensional stress occasioned by the frequent binding of the peat in the tube. In outside diameter and length it remained unaltered after a month or more of continual use. It was at the end of this period that the serious failure or weakness above referred to was discovered and set down as the probable cause of

Digitized by Google

all former troubles with the machine. The inside of the tube at about 3 inches below the lip, namely, at the point where the actual compression of the peat into a briquette took place, had worn away until the inside diameter of the tube at that point was one-quarter of an inch greater than the rest of the tube. This meant that with one stroke of the punch a briquette of 2 3-4 inches in diameter was made in this enlarged or worn-out portion of the die tube. With the following stroke and in the formation of the next block of peat the first one, now extremely dense and hard, had to be squeezed down into a diameter one-quarter inch less, namely, 2 1-2 inches in the lower portion of the tube. The inevitable result would be a broken die tube, if not a broken press. The greater the amount of ash in the peat the faster the wear in the tube; but even with peat free from sand, which is rarely found, this wear will take place.

The Whitewater Press

At the Welland peat works, as noted in the last paragraph in the revised edition of the Bulletin incorporated in the Twelfth Report of the Bureau of Mines, one of the Dickson presses was altered to make a quick short stroke, more in the nature of a blow than a punch, the open-tube die being used. This press is generally known as the "Whitewater," since it was at the town of that name in Wisconsin, U. S. A., that the principle was first embodied in a peat press and tried. The results at Welland were not satisfactory enough to warrant following up the idea. The trouble seems to be that the short stroke makes thin plates of peat, which do not always adhere to form a thick enough block, but drop out as or subsequently separate into flat briquettes. This flaking may perhaps to some extent be due to the peat being insufficiently fibrous or lacking in binding material, and need not necessarily condemn a press constructed on this principle. The real trouble will arise after a longer trial, with the wearing action on the die tube, when the result will probably be the same as with the slow-stroke press.

New Peat Factories

A number of peat fuel manufactories were established last year, or companies were formed to establish them, especially in the United States, and many new or "improved" presses, dryers, etc., were invented for use therein. But as to their success or failure little definite can here be said. At East Lexington, Massachusetts, a peat fuel manufactory of large capacity was being completed in the fall. Another was to have been erected on the peat bogs of Worcester and Middlesex counties of the same State. At Calpac, Michigan, and at Whitewater, Wisconsin, peat plants were in operation for a time, the former employing the Dickson press and the latter the Whitewater press above referred to. At South Bend, Indiana, a company has been formed to put up a peat fuel factory on bogs in the vicinity of that place. The machines will probably be made this winter in preparation for work during the coming season of 1904.

In Ontario two recently incorporated peat companies are the Toronto Peat Fuel Company, to instal Mr. A. A. Dickson's latest peat press (on the open-tube principle) and peat dryer on a bog at Picton, where some trials were made during the summer of 1903; and the Imperial Peat Company of Guelph, to adopt in a peat fuel manufactory the new White briquetting machine, one of which, of full size, is now about completed (March, 1904), and ready for work this coming season. A working model of this press has been maintained in Toronto for the past year or so, making tests at intervals.

Lignite as a Fuel

At Bismarck, North Dakota, machines are under construction for experimental work on the lignite which occurs in vast beds in that State. The desire is to compress the lignite without the addition of chemicals or binder into briquettes. For the purpose of acquiring all available data on the industry an engineer was sent to Germany to acquaint himself with the practice in that country, where a large percentage of the fuel consumed is in the form of briquettes of lignite or "brown-coal." There, however, a binder is generally necessary, such as tar or the bituminous residue from the distillation of tars.

An interesting communication has been received by the Bureau from Mr. George Gregory Smith, an engineer in Florence, Italy, who has been retained by parties interested in the lignite deposits there, to make a report on that fuel. He states that there is now in sight in the various deposits in Italy about 400 million tons of lignite, and that, with the exception of wood and charcoal, both scarce and dear, lignite is the only fuel Italy has, all her coal being imported. The letter proceeds: "As a fuel, lignite, no matter how thoroughly dried, is unsatisfactory. The result of my investigations, however, have led me to conclude that if

Digitized by Google

lignite is looked upon not as a fuel primarily, but as a chemical substance with fuel as a bye-product, it possesses far more value than it would if used primarily as a fuel either in the form of briquettes or otherwise." He goes on to say that by fractionally distilling lignite, gas, coke, tar and ammoniacal liquor are obtained, the average heating value of the gas by his determinations on Italian lignite being 4,770 calories per litre. Quoting again, "The distillation of the tar results in the following: benzine (crude), lubricating oil, aniline blue (solution), fenol (crude), and tar residue (pitch or extra carbon). The tar residue is then used as a binding material for the lignite coke. This fuel in the form of briquettes has proved extremely satisfactory. The volatile substances in the form of gas, tar and ammoniacal liquor rather more than pay the entire cost of the process, leaving the fuel practically free of cost.

"I have never made any tests of peat, but venture on a suggestion that from some of your bogs at least you might possibly obtain an approximately similar result."

With regard to the suggestion in this last paragraph, no commercial tests of such a process have ever been made in Ontario. There are in Germany, at Oldenburg, and in Russia, at Redkino, plants for coking peat and utilizing the gaseous products and the liquors condensed therefrom. The process is known as the Ziegler process and has been described in numerous journals and consular reports. The chief objection at the present stage of its development is the first cost of the plant, which is quite high on account of the elaborate arrangement for saving the various bye-products. Samples of the bye-products from the coking operation and subsequent fractional distillation of the tar have been obtained by the Bureau of Mines and may be seen here. The samples comprise tar, tarwater, gas-oil from the tar, concentrated tarwater, crude methyl alcohol, 35 per cent. methyl alcohol, 95 per cent. ditto, and crude ammonium sulphate crystals, all from the tar-water.

Lignite or brown coal has been known for many years to exist in the northern areas of Ontario, but beyond a superficial examination of the occurrences along some of the rivers little was done until the summer of 1903 in the way of determining its extent. The exploration party then sent out was equipped with suitable tools and appliances to make borings, etc., and the results of the work are embodied in a report in another part of this volume. Valuable data on the quality and area of the vast peat bogs in that part of the Province were also obtained. These lignite deposits, it may be confidently predicted, will come into use some day, either by being briquetted or distilled by some such method as the Ziegler process.

Peat-making in Ontario

The peat fuel industry in Ontario during 1903 was confined to four points, Beaverton, Newington, Welland and Picton.

The plants at Rondeau, Brunner and Brockville which were expected to reopen have for one reason or other lain idle.

The only change in the plant at the Beaverton factory was the addition of a travelling peat elevator to load the piles of air-dried peat scraped off the field into the tram car. Formerly this work was done by hand. With a few alterations the machine will be adopted as part of the permanent plant this season. At this factory 1,000 tons of peat briquettes were made during the season of 1903. An attempt will this year be made to harvest enough air-dried peat to keep the one press in continuous operation through the winter as well.

With regard to the use of cordwood for fuel under the boiler and dryer, as against crude or cut peat, Mr. Dobson, the proprietor of the works, has satisfied himself that with good mixed wood at $1.30 per cord (which is about a minimum price) it is cheaper to use crude or cut peat. He bought several acres of timbered land and cut and delivered the wood himself, finding that $1.30 per cord was the cheapest it could be done for. The crude peat on the other hand can be cut and piled along the ditches to dry, and subsequently delivered to the works for considerably less per unit of heating power. Next season, therefore, a supply will be dug for future use to replace the cordwood.

The Dobson dryer has been steadily turning out peat at the rate of 3,000 lb. or 1½ tons per hour, drying it from about 40 or 45 per cent. down to 12 per cent. water content.

A Demonstrating Plant

It is the intention of Mr. Dobson and his associates to erect another peat factory similar to, but of double the capacity of the Beaverton works, on an extensive peat bog of reported excellent quality at Caledonia Springs, a few miles east of Ottawa. Such a step is necessary at the present stage of the industry in order mainly to prove the

Digitized by Google

success of his machines and process on a larger scale and on a different bog. The bog at Beaverton is too small to warrant enlarging the present factory; and besides this the peat has characteristics not common to the large majority of bogs in Ontario. This work will be greatly appreciated by all interested in the peat fuel industry as helping to solve certain unanswered questions covering the operation of a much larger plant than the one- or two-press factories now in existence. One question has reference to ways and means of storing the immense quantity of air dried peat required for the factory's winter supply. Must it be covered or housed, or not? Another deals with the advisability of concentrating all the factory operations —mechanical drying and compressing— under the one roof, to which one point the necessarily extensive areas of bog under "cultivation" shall all be tributary, as against the adoption of a maximum capacity factory unit, any number of which could be erected at separated points in the bog, each on an area which would supply it with the necessary amount of air-dried peat. This latter is the usual arrangement in such European countries as Sweden, Germany, Denmark and Russia, where the plants used are for the manufacture of "machine-peat" only.

In connection with this the following figures will give an idea of the field area required to harvest a certain tonnage of peat during one season. Some of the figures are only approximate, so that the results arrived at are not absolutely definite. In the field methods adopted at Beaverton 1 acre is required to spread 10 tons peat for air-drying. But in an average day 2 collections or scrapings may be taken off that area so that a daily product per acre of 20 tons is obtained. At Welland, where harrowing is followed, one scraping only is made per day, but the layer removed is about twice as thick as at Beaverton and amounts to 20 tons per day per acre. Out of a period of open weather six months in duration, at least two-thirds or 120 days should give good drying weather. Therefore the season's product of peat fuel per acre will be 2,400 tons. But in the bogs of Ontario the average amount of peat fuel (finished product with 12 per cent. moisture) per acre for each foot of depth is 215 tons, so that to gather 2,400 tons from the same acre requires a bog about 11 feet deep. Provided this depth of peat is available and the peat factory has an output of 50,000 tons peat fuel per year, the approximate maximum capacity of a 6-press plant, there would according to these figures be required for field operations an area of about 20 acres. If, as with many of the bogs, the depth is but 5 feet, or even 2½ feet as at Beaverton, the area would have to be doubled or quadrupled respectively.

The Newington peat works owned by Dominion Peat Products, Limited, were completed and in operation for a short period. About 100 tons of peat fuel are said to have been manufactured. Nothing further need be added here in the way of description of the plant and machines. It is the intention of the company, according to Dr. Spencer, the president, to continue operation next season and try to establish the factory as a permanent enterprise. No official examination of the factory when in operation has been possible, so that an opinion on the feasibility or success of the process and plant will have to be deferred.

At Welland a new arrangement was made at the beginning of the season by which Mr. Alex. Dobson was given full charge of the briquetting part of the plant and operations, and an order for one of his presses. The Peat Industries, Limited, which owns the factory, was on the other hand to furnish the supply of dried peat in shape for briquetting. For this purpose field operations were continued steadily for a considerable period and something over 500 tons finished fuel as air-dried peat were piled up at several points on the bog. Another new dryer was installed after the design of the original Simpson machine with all the latest alterations or improvements. When the new Dobson press was ready for work the new dryer began operations. It then transpired, according to Mr. Dobson who was on the ground, that the dryer was quite unable to dry the necessary supply of peat. Not more than about 3 tons could be put through in a day, instead of the required 12 to 15 tons. For this reason practically nothing was accomplished towards manufacturing the compressed fuel. Mr. Dobson states that the incapacity of this Simpson dryer was due in part to the excessive amount of water (about 60 per cent.) in the so-called air-dried peat. The chief reason for its failure lies however in the heavy loss of heat by hampering the flow of the gases of combustion from the lower cylinder chamber to the upper, and by radiation into the walls and partitions of the apparatus the combined area of which is too greatly out of proportion to the contained charge of peat. In the effort to make use of all the heat in the gases of combustion a complicated and expensive machine has been constructed, not only without gain but, judging from its operations so far, with a distinct loss, as compared with other dryers, in drying capacity.

Digitized by Google

Another new peat gatherer was experimented with at the Welland bog for removing the layers of air-dried peat from the surface of the bog. The idea of the machine is somewhat after that incorporated in the ordinary street sweeper with revolving brush drawn by a team of horses. It did not prove a success.

Harrowing for Air-drying

These field operations at Welland have directed attention to a point which has hitherto been largely disregarded or entirely overlooked, namely, the method of loosening the surface of the peat bog by harrows for air-drying. This is a very convenient plan when the bog contains many roots and snags, as at Welland. A harrow will loosen the surface regardless of the snags, where mechanical diggers will probably not work satisfactorily. For this reason the harrowing method has been resorted to at Welland. In Norway and Sweden at the manufactories of moss-litter and peat-meal this method was in extensive use at one time, and is still not entirely superseded by spade digging. The two applications are, however, different, in that the surface growth of moss used for making "litter" and "meal" is much lighter and therefore more easily dried in the air than the peat below, and may consequently be loosened for air-drying in larger fragments than peat; also in scraping off the surface after drying a considerably deeper layer will necessarily be collected, on account of the coarseness of the fragments, than would be permissible with peat, since the latter would not be dry.

It was shown in the Peat Bulletin that just about twice as much air-dried peat per acre was collected from the surface of the Welland bog by the scraper after air-drying than at the Beaverton bog, or about an inch in depth at the former and a half inch at the latter. This may explain why the Welland air-dried peat was not sufficiently low in moisture content for subsequent satisfactory handling.

From the nature of peat, especially the fibrous sphagnum variety of which most bogs are composed, it is not possible to harrow the surface into the fine granular condition most suitable for rapid air-drying. The peat is torn out largely into fragments an inch or more in diameter, only a small proportion having the proper degree of fineness, of about ¼ inch. With a mechanical digging machine, on the other hand, such as has been in operation at Beaverton for several seasons, the peat is cut and broken into fine particles and then spread over the field to dry.

Since therefore it is not possible to scrape off or in any other way collect as thin a layer as desirable of the air-dried product when it has been harrowed it must be left out longer until dried to about an inch in depth. Consequently, in order to harvest the same supply daily from both methods, approximately twice as great a field area will be necessary where harrowed as where dug and spread, other conditions being equal. Owing, however, to the uncertainty of the weather, the latter process reaps an advantage, inasmuch as during every minute of sunshine and wind, an appreciable evaporation of the moisture takes place. During periods of unsettled weather this suitability for quick drying and reaping may make all the difference between collecting a harvest or not.

Peat, after being dried, is remarkably insensible to atmospheric changes. A pile of fairly fine peat will shed the severest and most continuous rainfalls as successfully as a thatched roof, and not be wetted deeper than a few inches. In the same manner, when subjected to the most favorable air-drying conditions, the moisture content in the pile does not alter below the outer layer of two or three inches thickness. These peculiarities may be due in part to the compactness with which fine peat particles lie together; but mainly would appear to be derived from some inert physical characteristic. Peat is a marked non-conductor of heat. This all serves to show that for quick air-drying peat must be finely broken up, and to dry at all must be spread out in thin layers.

On account of the intermittent and insufficient application of the harrowing method to date, it is not possible to settle on what degree of efficiency or success it may have on a large scale. No other method is at present available for bogs full of sticks or roots, so that harrowing will probably have to be resorted to until a mechanical digger shall have been designed to work on bogs containing these obstructions.

Other Peat Works

At the Rondeau bog the waters drained off towards the close of the season by the gradual fall in the lake level, but too late to allow of resuming manufacturing operations. Next season it is proposed to throw up dikes of the peat itself on the exposed sides of the area under treatment, and then, if necessary, to pump out and start work again. A dike or bank of peat is said to be about as impervious to water as

Digitized by Google

clay, which makes diking a very simple operation.

Since the fire at the Brunner works, in which most of the buildings and plant were destroyed or damaged, practically nothing has been done. The company have not yet decided on a future policy.

At Picton there is a large peat bog which, during the past year, was made the basis of an attempt to start a peat fuel industry. Mr. A. A. Dickson erected a plant in which a new horizontal open-tube briquetting press and a new dryer, both after his own design, were installed. Details of the test runs have not been obtainable, and no examination could at the time be made; but from Mr. Dickson's plans of the dryer, the principle of operation of that machine is to take the peat wet from the bog, place it in a cylindrical steam-jacketed chamber, and there, by agitation and the heat from the steam, to reduce the water to the desired content. Further work will be done with the plant at the same place this season, according to Mr. Dickson, this time by and at the expense of the Toronto Peat Fuel Company, with Mr. Dickson as superintendent.

The Milne Gatherer

Two new peat machines, both of original design, have been under development by Mr. J. J. Milne of Toronto for a year or so past. They consist of a peat harrower and gatherer, or collector, and a briquetting press. Although no tests on a commercial scale have yet been made by either, they both deserve a short mention here. The peat gatherer consists of a carriage on wheels to run on rails, from one side of which an arm thirty feet or more in length projects, almost entirely suspended by wires from the top of the carriage. This arm consists of a sheet-iron pipe twelve inches in diameter, with a flexible joint at the carriage end, by means of which it can swing from its first position at right angles to the car and track through 90 degrees back to the side of the track. The outer end of the pipe turns down sharply, at the same time expanding to a rectangular opening or mouth 3 inches by 36 inches in cross-section, which is protected by curved lips and kept at the required distance of about one-half inch from the surface of the ground or peat bog by flexibly affixed runners on either side. Two electric motors are installed on the carriage, one propelling the whole apparatus forward or backward, and the other driving a large fan connected with the collector arm or suction pipe. When in operation the carriage will travel along at the desired speed, sliding the runners and arm over the ground and by means of the exhaust fan suck up the loose particles of peat and discharge them from the outlet pipe into an attached tender car. This car must necessarily have some such covering as canvas, to allow the large volume of air to pass out while at the same time retaining the peat. Such a car has not yet been built, and possibly difficulty may be encountered in separating the air from the peat, since a large amount of the latter will be composed of dust, which may clog the apertures of the cloth sieve. Power is taken by trolley from wires above the track. After the machine has travelled the length of the track and sucked up the air-dried peat from a strip 36 inches wide (the width of the collector lip or mouth) the arm is moved back until the mouth is in position to traverse the adjoining 36 inches. The position of the mouth at right angles to the line of travel is maintained by means of two parallel motion rods and a flexible joint at the top of the diverging mouthpiece. The suction pull exerted by the fan is very strong, but amenable to adjustment. This machine is full size. It is thought that the length of the arm might be increased with advantage to forty feet or so, thus enlarging the area or strip of bog covered by the machine. Also another or second arm might be projected from the other side, the one to counterbalance the other.

The method of loosening the surface of the bog for air-drying, preparatory to collecting, will be by harrowing. Directly behind the mouthpiece of the suction pipe a harrow of the same width as the mouthpiece will be attached to and drawn by the machine, in this way loosening another layer of peat immediately after the first has been removed. By this machine, therefore, the intention is to accomplish the several field operations at one time.

The Milne Press

The Milne briquetting press which, together with the above peat collector, has been set up at the home of Mr. Milne, near Markham is a reduced working model, turning out a peat briquette of about one-eighth the weight of the proposed block. The principle of the machine consists in revolving against one another two steel disc or cog wheels whose width is that of the desired peat briquette, say 2½ inches and out of the periphery of each of which semi-cylindrical "compression cavities" are milled of the same diameter as that of

Digitized by Google

States, chiefly among people ignorant of mining, but greedy for profits. In some cases particular classes are attacked, such as clergymen or post-office employees, whose calling affords little outlet for the speculative spirit, and the very smallness of whose savings seems to urge them to take this sure method of doubling or trebling them. So long as foreign corporations not authorized to do so by license from the Lieutenant-Governor in Council do not seek to sell their stock in Ontario, the laws of the Province are powerless to reach them, or to protect the people of a foreign country. Nevertheless, the operations of such concerns tend to injure the mining business here, and to make it more difficult to procure capital for honest and legitimate enterprises.

Of the mining companies incorporated and licensed last year, five were for oil, four for oil and gas, one for gas, six for iron, three for copper, fourteen for gold, two for peat, seven for cement, and one each for coal, iron and nickel, molybdenum, stone, mica, gold and copper, and asbestos, while six were miscellaneous or undeclared in their objects.

Following is a list (1) of the joint stock companies incorporated under the provisions of the laws of Ontario during the past year, and (2) of the foreign companies licensed to carry on business here:

Mining Companies Incorporated 1903

Name of Company.	Date.	Head Office.	Capital.
			$
Belleville Portland Cement Company, Limited	26 December, 1902	Belleville	2,500,000
Blenheim and Harwich Oil Company, Limited	14 January, 1903	Blenheim	199,000
Eastern Canada Coal Company, Limited	30 January	Toronto	2,000,000
Imperial Peat Company, Limited	7 May	Guelph	1,000,000
King Edward Mine, Limited	10 June	Bruce Mines	200,000
Moose Mountain, Limited	30 January	S. S. Marie	100,000
National Iron and Nickel Corporation, Limited	21 January	Toronto	5,000,000
New York and Lake Erie Oil and Gas Company, Limited	22 June	Windsor	1,000,000
North Shore Copper and Smelting Company, Limited	24 April	Toronto	250,000
Standard Cement Company, Limited	26 February	Toronto	500,000
St. Mary's Portland Cement Company, Limited	28 April	St. Mary's	600,000
Toronto-Hamilton Portland Cement, Limited	18 July	Toronto	350,000
Toronto Peat Fuel Company, Limited	23 September	Toronto	40,000
Williams Iron Mines Company, Limited	14 October	S. S. Marie	3,000,000
The Belmore Bay Gold Mining Company, Limited	4 March	S. S. Marie	1,000,000
The Bussman-Gray Molybdenum Mining and Reduction Company of Ontario, Limited	31 July	Fort Erie	1,000,000
The Camp Bay Mining Company, Limited	20 May	Niagara Falls	90,000
The Colonial Oil Company, Limited	13 May	London	100,000
The Coronation Gold Mining Company, Limited	14 February	Ottawa	1,000,000
The Crowland Natural Gas Company, Limited	4 November	Port Colborne	80,000
The Damascus Gold Mining Company, Limited	13 November	Bridgeburg	250,000
The Erie Oil Company, Limited	27 March	St. Thomas	100,000
The Grimsthorpe Mining Company, Limited	20 November	Toronto	150,000
The Hanover Portland Cement Company, Limited	26 March	Hanover	500,000
The Hermina Mining Company, Limited	17 June	S. S. Marie	2,500,000
The Horse Shoe Quarry Company, Limited	14 February	St. Mary's	40,000
The Hutton Mining Company, Limited	14 January	S. S. Marie	100,000
The International Iron Mining Company, Limited	29 October	Port Arthur	1,000,000
The Iron and Steel Company of Canada, Limited	21 August	Belleville	300,000
The King Edward Oil Company, Limited	18 September	London	100,000
The Kipp Oil Company, Limited	7 October	Chatham	150,000
The Loon Lake Iron Company, Limited	10 June	S. S. Marie	3,000,000
The Lucinda Gold Mining Company, Limited	21 August	S. S. Marie	100,000
The Manitoulin Portland Cement Company, Limited	28 August	Windsor	1,000,000
The Peninsular Oil and Gas Company, Limited	15 July	Chatham	100,000
The Shakespeare Gold Mining Company, Limited	21 October	Shakespeare Tp	2,000,000
The Star of the East Gold Mining and Milling Company, Limited	23 September	Peterborough	1,500,000
The Sultana Gold Mine, Limited	27 May	Rat Portage	1,000,000
The Temiscaming and Hudson Bay Mining Company, Limited	29 July	New Liskeard	25,000
The Vera Mining Company, Limited	28 August	S. S. Marie	1,000,000
The Wakefield Mica Company, Limited	22 June	Ottawa	50,000
The Waterford Oil and Gas Well Company, Limited	26 December, 1902	Waterford	60,000
The Western Ontario Portland Cement Company, Limited	30 January	Attwood P. O	500,000

Digitized by Google

The gross cost of diamonds per foot was 30 cents.

Messrs. Steinhoff and Gordon of Wallaceburg were the next applicants to receive the drill. They desired to explore the country in the vicinity of the town of Wallaceburg, county of Kent, for coal. The rocks of this area belong to the Devonian system and consist of clay shales. The drill was in operation here for about two months from the first part of July until September, boring 5 holes of an aggregate length of 1,529 feet through a variable depth of surface clay to and through the shale formation to the bottom where it overlies limestone. In several of the holes a seam or two of about 1-16 inch thickness of coaly material was struck, but nothing more. In most of the holes standpiping had to be driven to bedrock, the depths ranging from 54 feet to 218 feet, and in this last extreme length, 2-inch casing was also necessary on account of the soft ground. This work was considerably the cheapest done by the drills during the year on account of the soft rock and of the level country which allowed of quickly and cheaply shifting the drill plant from one hole to another. The total cost amounted to $1,290.32, or 84 cents per foot, and the net cost to the operators to $838.70, or 54 cents per foot, while the gross cost per foot for diamonds was only 1 cent.

The drill next went to Parry Sound district to explore for iron for Mr. J. B. Miller of Parry Sound, on lot 29 in the eighth concession of Foley township. It remained in operation here for about two months during September, October and November, at a point where a vein of magnetic iron outcrops and had previously been opened up by a 17-foot shaft. The iron deposit lies in a formation of gneiss and was found by the borings to be lenticular and without sufficient average width or continuity to warrant further mining upon it. None of the holes were very deep, the nine aggregating a total length of 582 feet. The total cost of the work was $1,595.11, or $2.74 per foot, and the net cost $1,036.82, or $1.78 per foot. The gross cost of diamonds came to $1.02 per foot, not too high considering the hard nature of the rock drilled.

Immediately on completion of the drilling in Foley the plant was shipped to Burk's Falls and thence hauled to the Nickel Cliff mine on lot 17 in the eighth concession of Armour township, Parry Sound district, the drilling to be done here for C. F. Kenneweg of Cumberland, Maryland. A short account of the mine is given in the Eleventh Report of the Bureau of Mines, page 286, at the time of writing which (1901) it was being worked in an exploratory way for a deposit of nickel-copper ore found outcropping on the surface. The mineral occurred in a matrix of schist and quartz which formed a lens or pocket in a trap at a short distance from a contact with gneiss. Three diamond drill holes were bored through the overflow of trap and into the underlying gneiss, but without finding any more ore. The rocks were rather badly fractured, which necessitated occasional cementing and which in one hole nearly caused the loss of both the casing and the drill bit by binding. However, the cost of the work was quite reasonable. The drilling lasted from the end of November 1903 until the middle of February 1904. The total cost amounted to $1,696,31, or $3.21 per foot, and the net cost to the operator to $1,101.61 or $2.09 per foot, while the gross cost of the diamonds per foot was 67 cents.

Digitized by Google

Table of Mining Accidents 1903

No.	Date.	Mine or works.	Name of injured person.	Result of injury.			Above ground.	Below ground.	Nature of injury.	Cause of accident.
				Slight.	Serious.	Fatal.				
1..	Jan. 15..	Canadian Copper Company.	James A. Hodgins	....	....	1	1	....	Leg fractured: subsequently amputated; death ensued.	Run over by yard engine while coupling cars.
2..	Jan. 22..	Canadian Copper Company.	Walter Creighton	....	1	....	1	....	Arm paralyzed	Thrown from engine.
3..	Jan. 25..	Creighton	Peter Marshall	....	1	....	1	....	Hand crushed	Caught in gear wheel in rock house.
4..	Feby. 18..	Canadian Copper Co's. west smelter.	Gusta Nasi	....	1	....	1	....	Arm and leg burnt	Slag explosion.
5..	Mar. 25..	Victoria	Napoleon St. Jean	....	1	....	1	....	Head, back and heels burnt	Hit by a splash of molten matte from converter.
6..	April 7..	Helen	Toni Frikovitch	....	1	....	....	1	Head and body bruised	Hit by loose stones rolling into open pit.
			Fred Mealten	....	1	....	....	1	" "	
7..	April 19..	Elizabeth	Jas. Murdoch	....	1	....	....	1	Legs cut and body bruised	Hit by rock from blast.
8..	April 27..	Helen	J. Verreault	....	....	1	....	1	Killed	Hit by rock falling from pit wall.
9..	May 18..	Canadian Copper Co's No. 2 mine.	Jacob Kallio	....	1	....	....	1	Leg broken	Going down mine in skip.
10..	May 26..	Belmont	E. Yeomans	....	....	1	....	1	Killed	Skip dropped in shaft with men in it.
			T. Cody	....	1	....	....	1	Head and body cut and bruised	
			A. Lyman	....	1	....	....	1	Arms and body bruised	
			H. Reid	1	....	....	....	1	Bruised	
11..	June 30..	Helen	P. Prebencore	....	1	....	....	1	Head bruised	Hit by rock falling from pit wall.
12..	June 30..	Canadian Copper Co's new smelter.	Jas. Morrison	....	1	....	1	....	Arm, rib and collar bone broken	Struck by falling derrick.
13..	Aug. 14..	Superior	William Arbour	....	....	1	....	1	Killed	Fell out of bucket.
14..	Aug. 20..	Big Master	Albert Johnson	....	....	1	....	1	Killed	Struck by falling drill-steel box.
15..	Sept. 10..	Canadian Copper Co's new smelter.	Basil Ferari	....	1	....	1	....	Leg crushed and subsequently amputated	Car of rock dumped on him.
16..	Sept. 14..	Loon Lake	Wm. Pelkonen	....	....	1	....	1	Killed	Dropped in bucket down shaft.
			P. Thompson	....	....	1	....	1	"	
17..	Oct. 14..	Copper Cliff	John Jokinen	....	1	....	1	....	Leg fractured	Working in rock house.
18..	Oct. 24..	Belmont	W. Darcy	....	1	....	....	1	Head cut	Hit by falling stone.
	Total ..	Total casualties 23		1	15	7	8	15		

Digitized by Google

List of Licensees

Licensee.	Residence.	No. of License.	No. of claims.
Anderson, A. M.	S. S. Marie	1363	
Andre, G	Michipicoten River	1359	
Andre, J	" "	1363	
Barton, S	S. S. Marie.	1387	
Becker, O	Michipicoten River	1330	
Beebe, W. D	Pleasantville, Pa	1350	1522, 1535, 1545
Begg, T. J	White River	1395	
Brown, A. F	Michipicoten River	1401	1472, 1474
Buckley, H	S. S. Marie	1412	1478, 1529
Buckley, J.P	Detroit, Mich	1411	1479, 1505
Cameron, A	White River	1397	
Cameron, J. O	Michipicoten River	1328	
Campbell, T	S. S. Marie	1389	1492
Carr, J	Michipicoten River	1382	1531, 1534
Carroll, J	Anaconda, Mon	1356	1499, 1500, 1501
Chapelle, B	Harrisville, Mich	1308	1455, 1467, 1489
Cressey, E. W	Bay City, Mich	1410	1490, 1508
Davidson, J	Ottawa	1394	1539
Davis, J	Wawa	1340	
Dickson, J. L	"	1385	1450, 1484, 1485
Donovan, J	Michipicoten River	1400	
Douglas, J. W	S. S. Marie	1377	
Downey, L	Wawa	1366	1511
Doyle, J. P	"	1314	1483, 1488
Dycie, J. G	Michipicoten River	1329	
Dycie ,M	"	1307	
Dysinger, C. M	S. S. Marie, Mich	1346	1496, 1497, 1509
Edey, M. C	Ottawa	1390	1536, 1543, 1553
Edey, R. W	Billerica, Que	1391	1537, 1541, 1551
Eldridge, R. C	S. S. Marie	1386	
Ferguson, M	Michipicoten River	1379	
Fitzpatrick, H	Wawa	1367	1510
Fournier, H. A	Michipicoten Harbor	1342	1469, 1481
Francis, G. F	Pakenham	1408	
Ganley, J	S. S. Marie	1358	1524
Gibson, A	"	1360	
Godon, A	Missanabie	1335	
Godon, E	"	1378	
Godon, J	"	1337	
Godon, N	"	1336	
Godon, T	"	1362	
Graham W	Michipicoten River	1383	1528
Gravelle, A	Wawa	1352	1504
Grumbine, S	Titusville, Pa	1418	
Hall, A	Michipicoten River	1384	1527
Henry, R	S. S. Marie	1347	1502, 1507, 1508
Hogan, S. D	Michipicoten River	1368	1520, 1532
Hunt, J	" "	1399	
Keenan, C. E	Michipicoten River	1376	1523
Keenan, J	" "	1355	1526
Kitchi-Gammi Gold Mg. Co., Lt'd	S. S .Marie	1306	1452, 1453, 1456 1457, 1460, 1461
Lawlor, J. H	Michipicoten River	1361	
Legge, C. H	Gananoque	1405	1546, 1547
Legge, J	"	1404	1518, 1548, 1549
Letellier, J. T	Wawa	1331	
Lewis, M	Detour, Mich	1372	
Lewis, W. H	"	1348	
Lynch, D	Michipicoten River	1374	1519
Manxman Gold Mg. Co	S. S. Marie	1373	
May, E	Michipicoten River	1334	1458, 1459
Miller, E. H	St. Thomas	1324	1464
Miller, G. L	"	1323	1465
Miller, I. M	"	1316	1463, 1466
Miller, R. J	"	1315	1462
Morin, J	S. S. Marie	1375	
Morin, J	Wawa	1407	
McDougall, L	White River	1396	
McDougall, W. H	"	1380	
McGillivray, W	Ottawa	1391	1538, 1540, 1552
McKay, J	S. S. Marie	1345	
McKenzie, A	Detour, Mich	1371	
McRae, P. J	"	1353	

Digitized by Google



Flint Lake gold mine and mill, 1903.



Milne Peat press, showing die- or sprocket-wheel in which briquettes are compressed.

Digitized by Google

UNIV. OF MICH.

Digitized by Google



Twentieth Century gold mine, 1903.

Digitized by Google

UNIV. OF MICH.

Digitized by Google



Gold Standard mine ; shaft buildings and rock dump.

Flint lake gold mine, showing open cut.

Digitized by Google

Digitized by Google

Vein in Little Master gold mine, showing lenticular form characteristic of veins in Manitou region.



Combined gold mine, showing flat quartz vein overlain by trap.

Digitized by Google

UNIV. OF MICH.

UNIV. OF MICH.

Digitized by Google

List of Licensees—*Concluded*

Licensee.	Residence.	No. of License.	No. of claims.
Neary, A	Michipicoton River	1388	
Parks, G. F	Wawa	1357	1477, 1491, 1530
Pettit, R	S. S. Marie	1409	
Pononish, A	White River	1318	
Pratt, W	Michipicoton River	1354	1533
Preneveau, G	Missanabie	1339	1468
Reed, G	Michipicoton River	1402	1471, 1476
Reed, Susan	" "	1403	1475
Ripley, L. V	Eau Claire, Wis	1326	1495
Ripley, M. T	S. S. Marie	1327	1493
Rogers, G. H	Ottawa	1393	1542, 1544, 1550
Rothschild, B	Wawa	1344	
Rothschild, H. J. M	"	1381	
Rothschild, M. D	"	1343	
Sage, H	Albany, N.Y	1325	1494
Shafer, F	S. S. Marie, Mich	1338	1451
Shotts, G. W	S. S. Marie	1321	
Smart, Mrs. T. R	Wawa	1364	1503
Smith, A	Michipicoton River	1369	1525
Standish, M	S. S. Marie, Mich	1370	1514, 1515, 1516
Sutton, E. S. B	" "	1398	1517
Taylor, G. H	Michipicoton Harbor	1414	
Taylor, H. P	S. S. Marie, Mich	1320	
Taylor, R. H	" "	1319	
Touchette, J	Missinabie	1322	
Travis, R. L	Michipicoton River	1341	1486, 1487
Trembley, J	Wawa	1406	
Walker, W	Wawa	1365	1512
Ward, W	Pleasantville, Pa	1349	1521

Digitized by Google

Provincial Assay Office

By A. G. Burrows

The Provincial Assay Office was established in 1898 by the Bureau of Mines, with a view of aiding the mineral development of the Province. Prospectors and others are afforded a means of obtaining reliable assays and analyses of their finds at a nominal cost. It has been found of advantage for those exploring the unsettled portions of the Province where there are no facilities at hand for examining their specimens. The office has also been of service where properties are being prospected and are not yet supplied with assay offices and other means of testing the ore.

The office is located in the city of Belleville, on Victoria avenue, where a two-story brick building is utilized for the purpose. The lower flat is used as an office, with a grinding and pulp room in the rear. The second floor is fitted up with an assay and analytical rooms.

During the year 814 samples were submitted for assay and analyses, and 165 specimens were reported on as to identification and commercial value.

Work for Bureau of Mines

The following services were performed for the Bureau of Mines during the year :

Issuing reports on samples submitted by Government geologists and explorers from the newer portions of Ontario. These included iron ores from the new ranges of Nipissing, gold and silver ores from the Rainy River District, and silver-cobalt-nickel samples from the recent finds on the line of the Temiskaming and Northern Ontario railway.

Issuing check analyses on pulped samples of iron ore representing the average of Ontario ores smelted at Ontario furnaces, on which it is proposed to claim the bounty provided by the Iron Mining Fund.

Making analyses of a series of limestones and clays of the Province, for a report on the utility of these materials in the industrial arts, as cement manufacture, sugar refining, furnace lining, pottery, etc.

Work for Private Parties

The following services have been rendered the public during the year :

Issuing reports, consisting of assays, analyses, identifications, and other commercial tests. While fees on a reduced scale are charged for this work, it is required that they be paid before reports are issued. Where the samples are of sufficient size, a portion of each is retained for future reference. The assays, etc., are the property of the person submitting the sample, and duplicates cannot be issued without his order.

Supplying information where possible to owners of mineral lands who desire to be placed in touch with purchasers, and also advising as to value, uses, etc., of their materials.

Making check determinations and control assays in case of disputes as to correct values. It has been found that most variations are due to improper sampling, rather than to mistakes by the chemist or assayer.

Sending samples of typical ores and minerals to prospectors, who desire to use them for reference in their explorations.

Laboratory Determinations

The following tabular list shows the determinations made in duplicate during the year :

Digitized by Google

Digitized by Google

Ontario ores smelted at On- the year :

Digitized by Google

Digitized by Google

ore representing the determinations made in duplicate
ario ores smelted at On- the year:

Digitized by Google

Assays

Mineral.	For Bureau.	For Public.	Total.
Gold (amalgamation)	3	1	4
Gold (fire assay)	45	401	446
Silver	41	197	238
Platinum	.....	9	9
Nickel	16	19	33
Copper	19	78	97
Zinc	1	11	12
Manganese	7	9	16
Tin	.....	1	1
Cobalt	5	.....	5
Lead	1	11	12
Molybdenum	.....	2	2
Antimony	.....	1	1
Bismuth	.....	1	1
Total	138	741	879

Analyses

Determination	For Bureau.	For Public.	Total.
Metallic iron	43	64	107
Alumina	106	20	126
Silica	108	37	145
Lime	106	17	123
Magnesia	106	18	124
Ferric oxide	108	30	138
Sulphuric acid	119	52	171
Moisture	140	13	153
Alkalies	92	7	99
Organic matter	21	1	22
Phosphorus	7	16	23
Volatile combustible	25	2	27
Fixed carbon	25	4	29
Titanium	5	19	24
Chromium	1	.....	1
Miscellaneous	233	30	263
Total	1,245	330	1,575

Total number of samples for assay	814
" " identification	165
Total	979
Total assays	879
" analytical determinations	1,575
" identifications and qualitative analysis	165
Total determinations	2,619

Laboratory Methods

The laboratory is equipped for the following determinations :

Gold and Silver

(1) By fire assay, using gasoline as fuel. Ores containing sulphur and arsenic are given a preliminary roasting before fusion, which is found to give better results than desulphurization during fusion. A small gasoline furnace has been added to the equipment of the assay room, which is very useful where only a few assays are to be made. The balance for weighing the buttons is sensitive to one-one hundredth of a milligram, which gives assay values as low as 20 cents a ton.

(2) By amalgamation assay to test the free milling properties of the ore, using about 2 lb. of pulp.

Platinum. By fire assay.

Copper. By cyanide titration and electrolytic methods.

Nickel. By electrolytic method, using a set of powerful potash cells for the current.

Lead. By titration with ammonium molybdate.

Zinc. By titration with potassium ferrocyanide.

Manganese. By Volhard's titration method.

All other determinations are made by standard methods. Samples are pulped to 100-mesh, and those requiring further treatment are ground in an agate or diamond mortar to an impalpable powder.

Certificates are made out on samples analyzed at ordinary temperature, unless otherwise stated in the report. Ores carrying moisture sufficient to prevent grinding are dried at 100 C. and analysis is carried out at that temperature. One assistant was employed during the year.

Fees amounting to $839.05 were collected and remitted to the head office. Samples brought personally to the office are examined free of charge, except where a quantitative estimation is required. Circulars of rates, canvas bags and mailing envelopes are supplied free of charge to those desiring to send in samples.

Digitized by Google

Summer Mining Schools

By W. L. Goodwin

I beg to submit herewith a report on the Summer Classes conducted in the mining camps of the Province during the Summer of 1903.

The Season's Itinerary

After spending Friday and Saturday, May 22nd and 23rd, in making preparations, I left Kingston on Monday, May 25th, accompanied by Herbert Van Winckel. Arriving at Calabogie the same day, I was met by manager Ganong of the Black Donald graphite mine. Next day I proceeded to the mine and opened a class there, which was continued till Monday, June 1st. On May 28th I drove to Calabogie, 14 miles, met a number of men who had specimens to be examined, and returned in time for the class in the evening. On Tuesday, June 2nd, we left the Black Donald, drove to Calabogie, and took train for Parham station. A drive of eight miles brought us to the Olden zinc mine (Messrs. James Richardson & Sons), where a class was opened at 6.30 p.m. the next day, and closed on June 9th. The drive back to Parham station was made on June 10th, where we took train for Sharbot lake. Van Winckel returned to Kingston and I took the C. P. R. to Havelock, where I was met by Mr. J. G. McMillan of the School of Practical Science, Toronto, who shared the work with me from that time onward. We drove to Cordova Mines where, in the absence of the manager, we were received by mine captain Holland. The class was begun the next day, June 11th, at 4 p.m. and continued until June 17th. Cordova Mines left behind on the 18th, we proceeded by way of Toronto and North Bay to Sudbury, which was reached June 19th. We drove immediately to Copper Cliff, where the class was opened the next day at 7 p.m. and closed on Friday 26th. On June 27th we left Copper Cliff by the C. P. R. "Soo" branch, reached Massey station on the same day, where we were met by manager Joseph Errington of the Massey copper mine, who kindly drove us and our luggage to the mine a distance of about 4 1-2 miles. The class was begun the same evening at 7 p.m. and was closed on Friday, July 3rd. On Saturday we returned to Massey station, went by train to Sudbury, and thence by the main line westward to Wabigoon which was reached on Monday, July 6th. Here we took the steamer to Budro's landing, 22 miles, then by stage over the Government road to Gold Rock. With the exception of a short distance near the landing, we found this road in very bad condition. A class was opened at the Big Master mine at 7 p.m. the same day and closed on Saturday, July 11th. On Monday, July 13th, the journey was continued by steamer along the Upper Manitou Lake, eight miles, to the Twentieth Century mine. This camp was substituted in our programme for the Elizabeth, which had in the meantime been closed down. We were met at the landing by manager Dryden Smith, who provided transportation for our luggage. The class was opened the same evening and closed on Saturday, July 18th. On the following Monday the steamer Minneola conveyed us and our luggage back to Gold Rock, from which point we retraced our journey to Wabigoon. There by invitation I lectured that evening in the school house to an audience of about fifty. We left by the night train for Port Arthur, where we arrived

Digitized by Google

July 21st, expecting to catch a train the same day to take us out over the Canadian Northern to Kashaboie, the station for the Tip-top mine. It was found that the train of that day was not to stop at Kashaboie. The journey was continued the following day however. From Kashaboie we packed our much reduced luggage a mile back along the track, guided and assisted by the engineer of the tug which the Tip-top company run on the Upper Shebandowan lake. The company's freight cart carried us and our luggage a mile and a half to the landing, from which we steamed comfortably 5 miles in a westerly direction to the end of the lake. A tramp through the wood four miles brought us to the Tip-top mine, beautifully situated on Round lake, where Captain Richard Sandoe made us welcome. The class was opened the next day, July 23rd, and closed on Wednesday, July 29th. On Thursday, July 30th, we returned to Port Arthur, transportation to Kashaboie station being again kindly furnished by the company. The manager, Thomas R. Jones, who had arrived at the camp in the meantime, accompanied us out. On Friday, July 31st, we left Port Arthur by steamer for Sault Ste. Marie. I continued my journey to Kingston, arriving on Monday, August 3rd, while Mr. McMillan proceeded to the Helen mine to open a class there. He left Sault Ste. Marie Saturday, Aug. 1st, by the steamer Minnie M. and reached the Helen mine on Aug. 2nd. A class was opened Aug. 3rd and closed on Saturday, Aug. 8th. Mr. McMillan then went to the Grace mine where a class was opened on Monday, August 10th, and closed on Saturday, August 15th. He left Michipicoton on August 16th, reached the "Soo" on Monday, August 17th, and took the Algoma Central Railway train to the Superior copper mine. A class was opened on Tuesday, August 18th, and closed on Monday, August 24th.

Classes were thus held in eleven mining camps, covering the Province from Kingston to Wabigoon. Free transportation of our heavy luggage was given by the Canadian Pacific, the Grand Trunk, the Kingston and Pembroke, Canadian Northern and Algoma Central Railway Companies.

Black Donald Mine

The road from Calabogie to the Black Donald is in part a country road leading westward from the village up the turbulent Madawaska, and in part a new road made by the company from James Legris' house to the mine. It is a very well built road, the survey for which was being made when the writer visited that district the summer before. It is quite equal to the ordinary country roads in that district, and is used by the Ontario Graphite Company for drawing in supplies, and hauling the graphite to the station at Calabogie. It also considerably shortens the distance for farmers going between the Black Donald district and Calabogie. The mine is close to the south side of Whitefish lake (one of the innumerable lakes of that name, although this one seems to have no whitefish in it; why not call it the Black Donald Lake?) As often happens in such cases the largest and best part of the deposit led the miners under the lake, where an unlucky shot one day let in the water in a veritable flood; but another shaft had been sunk and graphite was being taken out steadily. Diamond drilling operations were going on, for the purpose of locating a deposit farther away from the lake. Mr. W. K. Ganong of St. Stephen's, N.B., the manager, gave every assistance in making preparations for carrying on the class. A vacant dwelling house was fitted up, and the class was opened with an attendance of 18, practically the whole camp, mostly North of Ireland men, with a sprinkling of French Canadians and Germans. The interest in the class was sustained till the last day, and we were joined by a number of farmers and others living in the district about the mine. This brought up the total number in attendance to 27. The average daily attendance was 15. Members of the class brought in samples of molybdenite found a short distance from the mine (lot 17, in the third concession Brougham township). The molybdenite is found on the hillside near the old portage road around the rapids at its lower end. It is not very plentiful. While I was meeting the men in Calabogie on the morning of May 28th, a prospector named Bradford showed me samples of copper pyrite from a prospect which he described as about 12 miles from Calabogie.

The graphite deposit itself is interesting, the mineral being associated with calcite, a little pyrite, copper pyrite, mica, etc. The graphite is a mixture of flake and amorphous, from which the flake concentrates easily. Mr. Ganong accompanied me on a short trip across the lake to examine a hill very prominent on account of the red color of the soil, evidently formed by the decay of a highly pyritic rock. Some specimens taken where the rock outcropped could not have contained less than 30 per cent. of pyrite.

An interesting trip was made with John Moore, prospector and farmer, and the discoverer of the Black Donald mine. We collected crystallized black hornblende and fine large masses of actino-

Digitized by Google

lite and tremolite, also crystals of light green hornblende near the power house, two miles below the mine. Hornblende is plentiful in the neighborhood. Mr. Moore showed us a number of samples of molybdenite collected at various localities in the neighborhood.

Olden Zinc Mine

This place was reached by an eight mile drive from Parham station which was rendered rather exciting by the very steep hills and sharp curves. Mr. James Adams, foreman, was in charge for Messrs. James Richardson & Sons. The mine was discovered by Mr. Leslie Benn, who lives in the neighborhood. He still continues prospecting, and is extending our knowledge of the zinc-bearing area in that district. The ore consists of zinc blende with a little galena in crystalline limestone. Pyroxene, vesuvianite, and in some parts of the vein considerable quantities of iron pyrite, are present. The ore is being stoped out from the surface, but the stope is timbered and filled in as the work advances. Near the surface there is galena mixed with the ore. At a greater depth the galena disappears almost entirely. Nineteen men were employed, mostly farmers living in the neighborhood, and they seem to make very satisfactory miners.

The class was held at 6.30 p.m. in the men's sleeping room. The attendance was almost perfect, and it was a great pleasure to give instruction to such appreciative and intelligent men.

Accompanied by Mr. Leslie Benn, the writer tramped over the surrounding country—a series of valleys, flanked on both sides by granite which has resisted erosion better than the intermediate limestone, areas of which are found here and there. It is in these places that minerals may best be looked for. Specimens of copper pyrite, pyrrhotite, molybdenite, and serpentine were examined for Mr. Chas. Foy of Mountain Grove. Serpentine was collected on the south shore of Long lake, about opposite Drew's house. Specks of molybdenite were noticed in some places. Sphene crystals were collected from the cliff near Mr. Coleman Cronk's. A prospecting pit near by shows pyrite, copper pyrite, pyrrhotite, and zinc blende. Specimens of corundum, hornblende, etc., were examined for Mr. M. J. Flynn, driller; and members of the class brought in specimens of bog ore found about two and a half miles north of the mine on the farm of Barney Quinn, lot 6 in the sixth concession of Olden township, also specular (micaceous) hematite from the farm of David Bartram, lot 7 cimens of zinc blende from the Olden mine molybdenite was noticed.

The kindness and hospitality of the foreman, Mr. Adams, and of the other employees, and indeed of the whole neighborhood, made our stay very pleasant. The total number in attendance was 22, and the average daily attendance 19.

Class at Cordova Mine

Work was begun at 4 p.m. in Cordova Hall on June 11th and another class was held in the evening at 7.30. Instruction was carried on along the same lines as those described in former reports. Considering the large number of men employed, the attendance was neither as large nor as steady as might have been expected.

In the absence of the manager, Mr. D. G. Kerr, the acting manager, Mr. Holland, received us and made us comfortable. As on former occasions, we were the guests of the company, and everything was done to forward the aims we had in view. Here we had opportunities of collecting considerable quantities of tourmaline, crystals of pyrite, beautiful milky white quartz and chlorite.

The total number in attendance was 33, and the average daily attendance 14.

Copper Cliff

The classes here were held in the Gorringe Assembly Hall, as in former years. Many changes were noticed since the last visit. The company have built a hospital near the site of the old general office at a cost of over $30,000. It is handsomely furnished and is under the superintendence of Dr. Coleman. The running expenses are met by fees paid by the employees. The site of the new smelting works was being levelled on the brow of a rugged hill, and I was much interested in the explanations given me by Mr. A. P. Turner, the president of the company. Improvements in the old west smelter had greatly increased the output.

The attendance here was not satisfactory in point of numbers, although very much so in regard to the steady work done by those who did attend. The total number in attendance was 12, with an average daily attendance of 8, but it must be acknowledged that the class did not reach the men for whom it was intended, namely the miners. Possibly a change in the place of meeting might improve matters. The Gorringe Club is more frequented by the officials and the office men than by the miners.

Digitized by Google

in the seventh concession. In some spe- There are however special difficulties in carrying on this work in large places like Copper Cliff.

Massey Copper Mine

This lies about three miles northwest of Massey station. A branch of the railway was being built at the time when we were there, but at present all traffic is over a wagon road four and a half miles long.

The ore is copper pyrite, carrying less than $1.00 in gold. The shaft is down 400 feet and sinking was going on for the 500-foot level. Some beautiful crystallizations of copper pyrite on crystals of quartz and calcite had been taken out and handsome specimens were presented to us by Edward Moore, Thomas Moore and others of the miners. Some iron pyrite was noticed in the ore, and considerable specular hematite. Copper pyrite and specular ore were collected for future use.

The foreman, Mr. O. Summers, took us underground and gave us a good opportunity of inspecting the mine and collecting specimens. Mr. Joseph Errington, the manager, and Mr. R. C. Barclay, the treasurer, made us welcome. One of the cottages just being built was fitted with tables and seats for the class, which was opened at 7 p.m. on June 27th. The attendance was fair, averaging ten daily with a total of 25 in attendance. Here, as in other places where a night shift was worked, another class was held at 4 p.m.

Having a few hours to spare at Sudbury on the way from Massey station to Wabigoon, we drove out about 7 miles to see some prospecting being done by Mr. T. A. Edison. A number of test pits were seen, about two miles northwest of Mount Nickel. Diamond drilling had also been done, and one hole, it was stated, had been put down 270 feet. Nickel ore in small quantities was noticed about some of the test pits. The ground where this work was being done was unusually level and free from gossan.

Big Master Mine

The work here was very satisfactory. The force at the mine attended the classes almost to a man. In looking over the names, one was struck with the large proportion of Swedish and Norwegian names. Some of these men were old acquaintances from the Mikado and the Black Eagle, but others have been in Canada only a short time, and were either totally ignorant of English or were still struggling very hard with the language. However, by sandwiching these with those of their countrymen who spoke English well, and who acted as interpreters, we were able to give them the benefit of the instruction. This gave us a hint, which we found very valuable in a camp visited later, where the foreigners not speaking English were in very large numbers.

A class was opened at 7 p.m. and was held daily at that hour and also at 4 p.m. The total number in attendance was 33, with an average daily attendance of 21.

The Big Master is situated near the shore of the lovely Manitou Lake, the water of which, cold and pure, is supplied to the mining camp. Mr. Pickering, the manager, ascribes the uniform good health of the camp to the pure water. There had not been a serious case of illness for two years. Perhaps something also is due to the fine lot of men whom Mr. Pickering's sympathetic management had brought together. The shaft house is 1,550 feet from the shore of the lake, where the mill is situated to which the ore is carried by a wire trolley system. One feature of the mine is the cage for hoisting the men, a thing not often seen in our gold mines. On July 9th Capt. Shovells took us below, and we had an opportunity of seeing a first-class mine shaft.

Our stay was all too short in this lovely place, and we were sorry to part with manager and men.

The Twentieth Century

Here are a number of parallel quartz veins in which the prevailing mineral is pyrrhotite with some iron pyrite, copper pyrite and a little zinc blende. Chlorite is common as vein matter. Some of the quartz veins are 30 or 40 feet broad—immense bodies, if they prove rich enough to work.

The men here, as at the Big Master, were very much interested in the study of minerals. Classes were held at 7 p.m. and 4 p.m. The total number in attendance was 29, and the average attendance 20. Here too we found some of our Mikado friends. The manager, Mr. Dryden Smith, spared no pains to make our stay pleasant and profitable. We had the freedom of the camp, insluding the raspberry patch (about two miles square) and the fish preserves (the whole of the Manitou)! We succeeded in catching lake trout in the middle of July, a thing unheard of before.

Tip Top Mine

This mine is the property of the New York-Canadian Copper Company. The

Digitized by Google

superintendent, Thomas R. Jones, and the mine captain, Richard Sandoe, were towers of strength to us.

The classes here contained representatives of many nations, Canadians, Yankees, Cornishmen, Swedes, Finlanders, Austrians, Frenchmen, Norwegians, and Irishmen, with an outer fringe of Ojibways. Many of the foreigners here unable to speak English, but experience at the Big Master had shown that it was possible to reach these. The first thing I did after settling down in the camp was to ask for an interview with the leaders among these foreigners, and in such cases the leaders are the English-speaking. Captain Sandoe introduced me to two brothers Charles Jacopsen and Jacob Jacopsen, who spoke English very well, and who also seemed to have a polyglot acquaintance with Europe. The nature of the work was explained to them, and it was suggested that, with their assistance, their countrymen and other foreigners might be able to take advantage of our visit to the camp. They fell in readily with our plans, and as a consquence the whole camp attended the classes, and with a total attendance of 40 the average daily attendance was 31, not including the Indians. The writer was much impressed with the eagerness of these new citizens of ours, not only to learn about minerals, at which they were not one whit behind the English-speaking miners, but also to learn the language of the country. Some of them had small readers, giving the names of minerals, mining tools, etc., in English and Finnish, and they were using these as text books to learn English. From conversation with a number of those who could speak English, both at the Tip-top mine and at other places in Ontario, I have formed a high opinion of the Finlanders as a desirable class of immigrants. They speak enthusiastically of the freedom they enjoy in this country, and declare without reserve that it is their ambition to become good Canadians.

The Tip-top mining camp is the most beautifully situated of any the writer has had the pleasure to visit. The houses and offices are stretched along the sandy beach of Round lake and are sheltered by magnificent pines, which have been spared by fire and axe. The offices and dining and sleeping camps occupy the centre. South of these are a number of log cabins built by the Finns and Austrians, and away to the north about half a mile removed are the wigwams of the Ojibways, a number of whom are employed in cutting wood, and occasionally in catching fish for the camp.

A visit was made to the old Huronian mine which had been closed for about 17 years. It is about 15 miles west of the Tip-top mine, and is reached by crossing Round lake four miles, traversing a one-mile portage into Crooked river, which with a small lake at each end winds its way about 6 miles farther, and then over a half-mile portage into Jackfish lake, which is about 2 and a half miles across. From the opposite shore of this lake a walk of about one mile through the woods brought us to the Huronian. The ore is said to be a very rich one. It contains iron and copper pyrite and galena, and also, it is said, sylvanite. On the way to this mine we met an old prospector, Ben. Shaw, who had been camping there alone all summer looking for a lost gold vein. He went back with us and did the honors of the deserted mine. We found the whole location choked with undergrowth, and $30,000 worth of lumber, machinery and supplies rusting and rotting at the mine and on the portage to Savanne—a dismal sight.

To return to the Tip-top mine. On July 24th Capt. Sandoe showed us over the workings. We found a wide vein (60 feet) of copper pyrite with quartz, magnetite, iron pyrite, pyrrhotite, and a mineral carrying cobalt—probably smaltite. The ore carries gold and silver. Much of it is high-grade. The vein can be traced half a mile east and west. The shaft house is three-quarters of a mile east of Round lake. To the north of the ore body is a fine-grained rock, apparently quartzite. To the south is a diorite, at first somewhat schistose and containing light-colored iron pyrite. Farther away it shades into a coarse-grained and then into a fine-grained diorite. Pyrite was seen even in the fine-grained diorite. Hornblende crystals of considerable size were abundant. Feldspar is fine-grained. The sand on the shore of the lake was panned, and magnetite and limonite were found in the concentrates. In conversation with manager Jones, it was learned that the Finns and Austrians are well educated, and that they are unusually satisfactory as employees.

It was ascertained from Mr. Jones and from the assayer, Mr. W. F. Smeaton, that A. L. 282, the gold mine farther west, also under the management of Mr. Jones, is being satisfactorily developed. A good deal of ore is blocked out preparatory to putting up a stamp mill. Roads to these mines are sadly needed. As such roads often become generally useful for settlers, as in the case of the road to the Black Donald mine, it would seem only just that the Government should share in building them.

Digitized by Google

The Helen Mine

The men employed here, to the number of about 250, are mostly of foreign birth, including Finns, Italians, Austrians, Hungarians, Poles, Swedes, Greeks, etc. The great majority do not understand English, accordingly difficulties were experienced in organizing the classes. The manager kindly placed the reading room at Mr. McMillan's disposal for the purpose, and the classes were held at 4 p.m. and 7 p.m. as usual. The total attendance was 27, and the average daily attendance 18. The attendance was made up entirely from the Canadians and Americans employed.

The Grace Mine

Mr. McMillan reports the attendance here as somewhat uncertain. Out of the twenty who were present at different times, including two from the Mariposa mine, only one-half attended in any one day. Pyrite, pyrrhotite, mispickel, and a little copper pyrite were noticed in the Grace vein. At the Manxman Mr. McMillan noted pyrrhotite (said to contain 1 per cent. cobalt), pyrite, copper pyrite and graphite. One complete set of minerals, labelled, was left at the Manxman, one at the Mariposa, and one at Mr. Boyer's camp. Several sets, unassorted, with a copy of the tables for each man were also left at these camps.

Superior Copper Mine

The opening of the class at 4 p.m. on Tuesday, August 18th, was cancelled because of an accident which resulted in the death of one of the miners. A start was made at 7 p.m. The number of men employed at this mine was about 25. They were sinking with a double shift in No. 6 shaft, which was down 150 feet. During the preceding winter and spring, sinking had been carried on in two shafts with about 50 men employed. The ore is copper pyrite in quartz, with a very small percentage of iron pyrite. In No. 1 shaft, which is down 75 feet, a considerable quantity of galena is present for the last fifteen feet. The country rock on the east side is granite and on the west greenstone.

The total number in attendance at this camp was 24, and the average daily attendance was 16.

General Remark

The usefulness of these Summer Classes cannot be doubted, but it is quite evident that they succeed better in the more isolated camps of moderate size than they do in those which have grown to the dimensions of villages or towns. In the smaller camps the men live together and move as one body. In the larger camps they are more or less scattered, and it is hard to get them to assemble after the day's work.

It is my duty again to call attention to the considerable amount of illiteracy among native young Canadians. This is apparent in the districts visited. In a few instances whole families of young men were observed who could not read or write. When the cause was enquired for, the answer was "six miles from the nearest school." In a country with districts of scattered population, such as we have in Ontario, conditions like these are perhaps unavoidable, but this serious menace (for illiteracy is always a menace) would be to a considerable extent avoided by the system of school vans and central schools now being introduced into some parts of Canada. Much might also be done (it is never too late to mend) by fostering the reading camp system which is being so enthusiastically and sensibly pushed forward by Mr. Fitzpatrick of Nairn Centre.

Several mine managers spoke of the dangers to their men due to the existence of saloons. In one case an illicit groggery was kept open a short distance from the mine. Upon asking the manager why it was not closed up, the reply was that the justice had refused to do more than inflict fines, although the law distinctly provides for imprisonment. The fines were cheerfully paid and the illegal sale went on. In another case a license was granted to a saloon within the prohibited six miles of a number of mining camps. The more isolated mining camps are often resorted to by men who have an honest desire to conquer what has become to them an overpowering temptation, and to build up in the pure atmosphere of the forest a constitution enfeebled by drunkenness. The law has provided that the temptation shall not come nearer than six miles, and men who are thus fleeing from temptation have a right to be shielded as the law provides.

Digitized by Google

Mines of Western Ontario

By W. E. H. Carter, Inspector

In the western portion of the Province beyond Lake Superior the condition of the mining industry depends largely on that of the gold mines, since these greatly exceed in number all the other mines, and during the past year or so all the gold mills operating on a commercial scale having shut down for one cause or other, a general depression throughout the region has resulted. In point of numbers probably as many mining properties are under development as at any period in recent years, but in most cases work proceeds on a small scale and in an exploratory way. The Mikado mine has shut down indefinitely for reasons given below. The Sultana on the other hand has reopened to continue the search for the faulted portion of the big ore body. There are many other good properties, such as the Big Master, fully equipped with at least mining machinery, if not milling plant also, which, if they had been properly developed, might be figuring as active paying propositions to-day.

Unbusinesslike mining methods constitute without doubt the chief cause of the present depression in the industry, and tend in many ways to keep capital out. No improvement can be hoped for until the mining public realize the absolute necessity of employing as managers of their mines only men who are qualified by technical education as well as experience to shoulder the responsibilities of a mining engineer. Continued loss of money at most of these mines because a contrary state of affairs exists, cannot but harm the reputation of the whole area as a profitable field of mining investment.

Exploration for iron continues on the various ranges from Temagami west to Atikokan, but latterly on a somewhat reduced scale on account, no doubt of the weakness of the iron market in the United States, and the consequent temporary faling off of interest in outside fields. A good deal more iron land has been acquired in the Hutton and Temagami areas, some of which in the latter will in all likelihood be worked this season in the neighborhood of the new Temiskaming and Northern Ontario railway, the only road as yet offering facilities to the district for shipment. In the vicinity of Loon lake, north of Sault Ste. Marie, several mining companies are actively exploring and developing the specular ore of that range with promise of developing productive mines. Ore production from the Helen mine in the Michipicoton area has ceased entirely on account of the financial difficulties of the operators, the Lake Superior Power Company. With the solution of these, mining will be resumed, it is expected, at an early date.

In the Lake Huron north shore copper area a few of the large number of prospects have continued in steady operation along comprehensive plans of development, with the result that several valuable ore bodies have been brought in sight. The Massey Station and Superior mines are good examples. Some smeltings of ore from the former have been made at the Victoria mine furnaces which have been temporarily leased from the Mond Nickel Company for the purpose. Some blister copper of good quality has resulted. The

Digitized by Google

Rock Lake mine closed down indefinitely last spring as the climax of continued unbusinesslike methods of mining. The development of the mine has been neglected so persistently that this unfortunate state of affairs cannot be ascribed to any known want of value in the ore body. In the western part of the Province the now well-known Tip-top copper mine is about ready for production of high-grade ore on a commercial scale, and the owners are seriously considering the installation of a smelter at the mine. This would lend impetus to the development of other copper properties in the same area.

In the nickel district about Sudbury the entire production still remains practically in the hands of the one concern, the Canadian Copper Company, subsidiary to the International Nickel Company. This company is able as a result to maintain the price of nickel at a high figure, which prohibits to a certain extent its more general adoption in the arts. Extensive additions are being made to the smelting works by which an increased output at smaller cost will be obtained. Last year's operations with the old plant made the record production of 6,998 tons of nickel.

One or two additional active operators in this nickel field are needed who will undertake to refine the metal as well as mine and smelt to matte. Unless they refine they might as well remain out of the business, since there is only one nickel refinery in operation on the continent and that belongs to the Orford Refining Company of New Jersey, which is controlled by the International Nickel Company and refines matte from this company's properties only. The Mond Nickel Company has not yet resumed operations at Victoria Mines. Considerable prospect mining was carried on during the summer months on an outlying area of the nickel belt in Levack township.

The recent finds near Haileybury, along the new Temiskaming and Northern Ontario railway, of cobalt-nickel arsenide ores, some of which are exceedingly rich in silver, have attracted a large degree of attention, and prospectors will no doubt rush in on the lands being restored to exploration. A quantity of the ore is this winter being mined and hauled out for distribution to probable purchasers and refiners, and for testing in order that a suitable process of treatment may be arrived at. It is to be hoped the work of refining the various metals will all be done at the mines; there appears no reason why it should not.

One of the oldest mining industries in the west has again revived in the reopening of some of the old lead and zinc properties in or around Dorion township, near Thunder bay, lake Superior. Already several hundred tons have been raised from one mine, and other companies recently incorporated to mine here expect to do as well on others.

It may be remarked as an indication from the miner's point of view of the state of the industry that wages on the whole are good, employment not scarce, and the condition of the mines as regards safety generally improving. Although the number of casualties reported during 1903 was the same as during 1902, an appreciable decrease is noted in those occurring underground and in the fatalities.

Gold Mines

Sultana

In May 1903 the former owners, the Sultana Mine of Canada, Limited, sold the entire Sultana property for a minority stock interest to the Sultana Gold Mine, Limited, Rat Portage, Ont. The working capital for the renewed development has, it is understood, been subscribed largely by a few local men, amongst whom is Mr. J. F. Caldwell, managing director pro tem. To Mr. Caldwell, one of the original owners, is mainly due the successful operation of this mine and its present activity. Since the close down in the spring of 1902 a few men have been retained to keep the surface plant in shape and carry on any repairing necessary. J. Johnson, mine captain, has remained in charge and will shortly increase the present force of 9 to about 15. Since May 1903, when the workings were again unwatered, the mine timbering has been overhauled where necessary, and two bulkheads placed at the south end of the workings, one on the 2nd level at 140 feet north of the Crown Reef vein, and one in the winze connecting the 2nd and 4th levels on that vein and at 60 feet below the 2nd level. In this way the heavy inflow of water from the Crown Reef workings will be excluded from the rest or

Digitized by Google

northern main portion of the mine, where development is now to be continued.

The 7th level northeast drift followed the diamond drill holes to the end, a total distance from the shaft of 607 feet, but found that the gold values in the quartz vein (1) at the face were too low to warrant devoting more attention to it. At about 500 feet from the shaft in this drift another quartz vein was cut through lying entirely in the trap, but at this point carrying only low gold values. It followed in its S. 30 degrees W. direction to where it will enter the granite, a pay chute may, it is thought, be found since all the pay ore so far has been confined to the granite formation.

The other vein or branch off the original lode which on the surface lies about 100 feet west of the latter and at the lake shore, has hitherto not been given much attention. According to the plan for future explorations, drifts will now be run to it from a suitable point in the second or fourth level south in the old workings. The other mining work proposed consists in sinking the shaft from the eighth to the ninth level, for which purpose the timbers are now being completed from the seventh down to the eighth level. There are scattered quartz stringers in the shaft bottom, but no defined vein. These will be drifted on and another attempt made to locate the faulted main lode.

Burley Mine

This is one of the properties in the vicinity of the Sultana mine. An attempt was made several years ago to locate the extension of the Sultana vein on the Burley locations, D 193, D 193 A and 271 P, which are practically all under water, by means of a caisson built in the water and a shaft sunk from it. Descriptions of the works with plans will be found in the Report of the Bureau of Mines Vol. VIII. pp. 46, 52 and 64.

From June 1899 until the summer of 1903 the property lay idle. It is now owned by the Coronation Gold Mining Company, Limited, Rat Portage, Ont., with J. Burley Smith as manager. A force of eight men was engaged puming out the shaft preparatory to carrying on further development. According to Mr. Smith the workings measured as follows: Shaft, 202 feet deep; first level, 108 feet deep; southeast drift 56 feet. Second level, 175 feet deep; southeast drift, 65 feet; northwest drift, 16 feet.

(1) Bur. Mines, Vol. XI., p. 251.

The water was making in the shaft so fast that the united efforts of the pumps to lower it below the first level were almost futile. Leakage around the bottom of the caisson may partly account for the heavy inflow; but another serious cause may lie in the opening or washing out of fissures from the lake bottom down. If some co-operative arrangement could be arrived at between the owners of the two adjoining properties, the Sultana and the Burley, by which either the Burley workings would be permanently closed as such and any ore bodies therein reached and developed from the Sultana workings, or sufficient of the adjacent Sultana property along the shore be granted to the Burley as a site for their power plant instead of necessitating its installation on the caisson, there would be much better chance of success for the Burley undertaking. Negotiations to this end were reported to be on foot at the time of my inspection, 14th September 1903.

Mikado Mine

No inspection was made of this mine on the occasion of my trip of inspection in September 1903, since operations had been suspended there the previous April. The stamp mill had been closed in November 1902. From the manager, Mr. N. McMillan, I learn that until December the workings were kept pumped out, and that the last mining done brings the measurement underground to the following :

No. 1 (vertical) shaft, depth 325 feet. Fourth level, depth 240 feet; north drift 760 feet (235 feet increase). At intervals along the latter several quartz veins were struck of about 3 feet width one assaying $19.00 per ton and the others from $3.00 to $5.00; but all pinched out again within short limits. This drift is in trap schist. At 1,000 feet north of this shaft another diamond drill hole was bored at an angle of 60 degrees west through granite first, then trap, then soft vein matter composed of mixed quartz and trap schist, and lastly trap to the bottom. Values in the vein, judging from the drill cores, were quite low.

From the incline shaft no further mining has been done, but in the ninth level south a diamond drill hole was bored at a flat angle of 270 feet south tapping No. 3 vein at 261 feet or 1,061 feet south of the incline shaft, and finding it about 10 feet wide, but with values in the core samples of only some $2.00 per ton. Several smaller intervening quartz veins poor in values were pierced before reaching No. 3 all of which are

Digitized by Google

traceable on the surface, according to Mr. McMillan, in nearly the same relative positions.

The company has now decided to indefinitely suspend operations. If any other operator should desire to prospect the ground further on the chance of finding in some of these veins richer ore bodies or pay chutes, the company, I am informed, holds itself ready to consider such a proposition.

The Golden Horn

Mining progressed steadily during the year to the date of inspection, 13th September 1903, and considerable satisfactory development was accomplished; but excepting a little more surface stripping it is still confined to the one quartz vein. The position of manager is now occupied by Mr. B. T. Thorne, with Ed. Hammill as foreman and a force of 14 men.

The shaft is 255 feet deep, an increase of 71 feet. First level, east drift unchanged; west drift 176 feet turning then south 72 feet to connect with the old shaft, which lies 10 feet farther, for better ventilation; at 51 feet south of the turn another mixed quartz and schist vein was struck which apparently does not outcrop at the surface; in the face also more quartz appears, probably forming part of the vein on which the old shaft was sunk, the quartz carrying galena, blende and pyrite. Second level, depth 166 feet (new); east drift 175 feet, and west drift 176 feet, with sumps in both and a small Cameron pump unwatering from the east one. Third level, depth 235 feet; east drift 52 feet; west drift 57 feet with, at 16 feet in, a crosscut running south 38 feet, to continue across the formation and intersect the other parallel veins outcropping on the surface in this direction.

Reference was made in the Eleventh Report of the Bureau of Mines, pp. 251 and 252, to the vein in the mine workings, and to this may now be added the fact that it is very irregular in width, waving in and out from a mere stringer to a solid quartz body 3 1-2 feet wide. The one solid band occasionally breaks up into several, which then interband with the chloritic schist forming a well-defined deposit several feet wide. Unless the gold values extend into the wall rock it can hardly pay to work the mine for this one narrow quartz band, even though it were unusually rich. Careful and systematic sampling would soon elucidate these points. Of course the other veins on the property may contain pay chutes but not enough effort has yet been put forth to find this out.

The shaft maintains a uniform incline north of 81 degrees; the timbering therein is kept in first-class condition.

A new 3-inch Ingersoll air-compressor has been installed. The rest of the plant is the same as at last inspection. For this a new power house has been erected. The other additional camp buildings consist of several private dwellings and a machine and blacksmith shop, of neat appearance and well painted.

A suitable dynamite magazine has been erected in a safe place; but no thawing house as yet. For the placing of this latter and for a general improvement in the practice of handling the explosives, instructions were given.

Crown Point

Descriptions of this property and of the work done below and above ground will be found in the Bureau of Mines Reports, Vol. IX. p. 59, and Vol. X. pp. 79 and 92. It is now three years since the mine closed down. In August 1903, according to information received from Mr. R. J. Elliott, manager for the present owners, the Crown Point Mining Company, Limited, sold the entire property to the Black Cat Mining Company, Cincinnati, Ohio, president S. P. Kineon.

The intention is to resume mining development at once, and to aid this by installing more mining machinery.

Olympia Mine

This property, mentioned in the last report of the Bureau of Mines, was under development at that time, a shaft being sunk. During most of the summer of 1903 a force of 15 men or thereabouts continued putting down the same shaft. Work was suspended, however, in September.

Mines Contract

Mr. J. W. Cheeseworth, manager of the Mines Contract and Investigation Company, whose head office is in Toronto, informs me that during 1903 exploratory development was done on five of the company's properties, on Clytie and Rush bays, Lake of the Woods, and in the Seine river country. The company is said to have control of mining locations aggregating about 11,060 acres situated in various parts of the Rainy River District. These it develops a little to show to better advantage their size and value for a sale. The forces employed in this work are usually small, in each case numbering from three to five men.

Digitized by Google

Great Northwest Mine

The property by this name consists of part of numerous locations situated on the north side of Clytie bay, lake of the Woods, controlled by the Great Northwest Mining Company of Toronto. It lies three-quarters of a mile northeast of the Indian Joe mine. Under manager J. Williams a force of six have been employed sinking a shaft since the spring of 1903. The shaft is 33 feet deep, vertical, and 8 by 10 feet in size and is sunk in a dike of schistose felsite light-green in color. A few grains of pyrite were visible, but no other sulphides. All mining is by hand, and the men are living under canvas.

Instructions were given to erect a dynamite magazine at once.

Indian Joe

This property, described in the last Report, has continued under development steadily, except for an idle period in the spring, up to 12th September 1903, J. Williams being manager with a force at present of only 5. During most of the summer 16 were employed.

The main shaft has reached a depth of 85 feet. First level, depth 80 feet; east drift 50 feet, with at 30 feet in, a crosscut south 8 feet; west drift 45 feet, with, at 30 feet in, crosscuts south 45 feet and north 20 feet. The shaft is sunk in a disturbed and schistose band of slaty trap which strikes east and west with nearly vertical dip, and contains a few parallel stringers and pockets of quartz.

The shaft is in good shape, hoisting being done by bucket on skids. The mine buildings include a shaft house 20 feet high, and a power house in which are installed a 4-drill air compressor, a duplex cylinder single drum hoist winding 7-8-inch steel rope, and two locomotive type boilers of 35-h.p. and 125-h.p. respectively. There are only two camp buildings as yet.

An explosive magazine has been built in a safe place; but some instructions were necessary for safer methods of handling the dynamite.

Cameron Island

The last accounts of this property were published in the tenth Report Bureau of Mines, pp. 79 and 92, for the year 1900. Since then no work had been done until the summer of 1903, when a 10-stamp mill was purchased and sent in for erection by next summer if possible. Two or three men are now placing foundations for the building and plant. The owners are still the Cameron Island Mining and Development Company, Limited, for whom T. F. Morrison remains in charge of the property.

Gold Reefs

A partial description of this property was given in the last two Reports of the Bureau. Development continued until the summer of 1903, when work was again suspended. The shaft was sunk 185 feet deep on an incline of 60 degrees south. First level, depth 100 feet; east crosscut 40 feet; west crosscut 45 feet. Second level, depth 185 feet; west crosscut 45 feet; east crosscut 48 feet; south drift 43 feet.

The island on which the mining has been done and the camp erected has an area of about two acres. Near it are other small rocks and reefs above or near the surface of the water, the formation of all being protogine. A slight disturbance has faulted the formation in a northeast-southwest direction along a number of parallel planes, leaving schistose bands five inches or so in width in the otherwise massive rock. The shaft has followed down one of these schistose bands on an incline of 60 degrees south, but in or along the line of strike. There was no wall or plane to determine this particular incline for the shaft and it might have been at any other angle. At 80 feet depth another fault plane was struck running nearly at right angles to the others and traceable on the surface. The crosscuts from the shaft followed along it, at both the first and second levels.

The disturbed bands are altered to a light green chlorite schist, through all of which, both on the surface and underground, narrow, irregular quartz stringers are scattered in the proportion of 5 to 10 per cent. of the whole. The massive formation also contains quartz stringers, but in smaller and more irregular quantity than the schistose portions. The gold is said to occur in connection with all or any of the quartz and to be free. Very little of any other mineral, such as iron pyrites, is visible. Judging from a few assays, the gold is not uniformly distributed, and until a thorough assay examination is undertaken, it is impossible to say where the values lie, or what part of the whole location should be developed to extract them.

Combined Mine

This mine which has been shut down for several years was re-opened a month or so prior to my visit in September, 1903. Numerous accounts of the opera-

Digitized by Google

tions of the former owners, the Combined Gold Mine Company, and of the geology of the locations will be found in the earlier reports of the Bureau of Mines, the most complete being in Vol. VII. pp. 43-45, Vol. VIII. p. 61, and Vol. IX. p. 50. The Camp Bay Mining Company, Limited, of Buffalo, N. Y., and Niagara Falls Ont., have since taken over the property, and placed Sidney Pinchin in charge as superintendent with a force of nine men.

The mine lies about two miles east of the south end of Camp bay, Lake of the Woods, or about 50 miles by steamboat south of Rat Portage, and is connected with the bay by a trestle railroad running mostly through swamps. The mill at the bay end ran for a month or so during the fall of 1902. It is now idle again, and will probably remain so until the mining development blocks out ore sufficient to ensure steady production. New camp buildings have been erected at the mine end, to avoid travelling back and forth from the old camps on the lake shore.

Mining is now confined to one location, on which a number of open cuts and short shafts had already been sunk. Of the latter, three lie near the present point of development and within 80 feet of one another along an east and west line, the east one 26 feet deep, the middle 15 feet deep, and the east 10 feet deep, and all connecting underground with the same level of 80 feet in length. The No. 2 or middle shaft is now being straightened for a skip road to follow down the vein to the north, the impression being at this point, it turns or folds down with a steep incline north. There is no doubt about the vein lying practically flat to the south of these shafts, numerous openings showing the quartz beneath only a few feet of the trap and felsite country; and to the north about 350 feet beyond the shafts the vein outcrops again at a number of points, so that taken together with other indications and findings, there appears little doubt that this sudden dip to the north of No. 2 shaft is merely a pronounced syncline in the vein. Similar characteristics exist at the other exposures over the area of 600 by 1,200 feet in which the vein has been found. The quartz averages from 5 to 6 feet in width in a horizontal fissure of the trap, the accompanying felsite having apparently been ejected subsequently along the same plane.

The new power-house at the mine workings contains a 30-h.p. boiler and a duplex cylinder hoist engine. For the handling and thawing of the dynamite safer methods were advised.

Flint Lake

This property, of which a partial description was given in the last Report of the Bureau, comprises mining locations McA 285 and 286, S 430 and 431, and a water location S 433 on Cedar river about 2 miles distant from the mine, aggregating 408 acres. Development is confined largely to McA 285, which has an area of 138 acres.

When inspected in September 1903 superintendent W. B. Drummond had a force of 15 employees, some at mining and the rest on mill construction. The mill is a Krupp ball mill and as soon as completed in the fall it was intended to make a test run on all the ore now on the dump, which amounts to between 400 and 500 tons.

Mining development has been confined as surface work largely to the outcroppings of the vein on the rocky ridges. At the northwest end of the main exposure a combined open trench and tunnel runs in 80 feet, and from here the ore was being gathered for the mill test. No. 1 shaft lies 200 feet southeast of this and is now closed and full of water. No. 2 shaft is 80 feet farther southeast, 15 feet deep, and also closed. At separated intervals for several hundred feet farther southeast the vein has been stripped and crosscuts and trenches made in it.

The vein follows what appears to be a true fissure striking N. 70 degrees W. through a country of somewhat slaty trap whose strike is however N. 81 degrees W. The faulting movement has more or less altered the two walls to a talcose schist, and where this is pronounced quartz has been deposited in stringers and lenses across a maximum width of 8 feet. Visible gold occurs in a fine state occasionally in the quartz, and with the latter some calcite and a small amount of pyrite is intermixed.

The mill building on the lake shore, was completed last year, and near it are several camp dwellings. From here to the mine, a distance of some 400 yards, a wagon road has been constructed. The mill power plant consists of a 125-h.p. return tubular boiler and a large horizontal engine set up in the same building. Besides the large revolving ball mill, which is to crush and amalgamate the ore, the remainder of the building is occupied with the various tanks appertaining to the cyanide process. Cyanidation will not however be included in the first tests to be made this fall.

A safely situated dynamite magazine has been erected; but both with regard to the storing therein and the thawing at the mine, it was necessary to give directions for better and safer methods.

Digitized by Google

Nino Mine

After some further development at this mine during 1903 operations were again suspended in September. Supplies were then being taken in by canoe from Whitefish rapids, the terminus of steamboat navigation from Rat Portage. The mining machinery belonging to the property which has lain on this portage for a year or more may be taken into the mine this winter.

Virginia Mine

The last account of operations, including a general description of the property, was given in Vol. IX. Bureau of Mines pp. 46-47. A little more development was done underground during August 1903 and more camp buildings erected, but after that all was closed down again. This property covers a number of mining locations on Sturgeon lake, about 10 miles by canoe route west of Whitefish rapids, Regina bay, Lake of the Woods.

Eagle Lake Area

Since the opening of this area there have been only two or three operators actively mining, and two of these, the Northern Light Mines Company and the Grace Mining Company, now own most of the located properties at the west end of Eagle lake, which seems to be the most valuable portion of the territory. Mill tests have been made at intervals through the year at the small Eldorado mine plant, of ore from the properties of the various companies with returns in gold that are very encouraging. As all the developed properties lie within a few miles of each other on the islands and the mainland, and all near the shore, the most feasible scheme for ore reduction appears to be the erection at a central point of a large enough mill to handle the ores from all the properties, some six or seven in number at present, especially since most of the developed veins are rather small to form the only source of ore supply for a 10-stamp mill.

The important gold-bearing veins of the area are confined to the granite formation over a width of a mile or more from its contact with the green trap, which contact crosses Eagle lake with a tortuous but on the whole northeast-southwest strike. The quartz of the veins in the trap on the northwest side of the contact has not yet been found to carry gold in paying quantities, even the veins actually in the contact being generally lean. Those in the granite will, on the other hand, pan gold, even to the merest stringers of quartz, the metal occurring therein usually free and visible both in coarse and fine grains. The commonly associated sulphides are almost entirely absent.

The mines of this area were on this occasion inspected during the last week of September, 1903.

Golden Eagle

After passing through the hands of several parties and receiving a little development from each, it looks as if the property would revert again to the original owner, N. Higbee; and if so, it will probably undergo more continuous and systematic mining than hitherto. In August 1903, 29 tons of the ore were run through the Eldorado mill, producing $307.50 in gold, or $10.60 per ton, according to the statement of the manager.

Grace Mine

This property covers mining location M H 251, on the west side of Eagle lake and is owned by the Grace Mining Company, Limited, Ridgeway, Ont., and Buffalo, N.Y. The president and manager of the company is J. H. Cassior, and mine foreman R. McKinstry, the force at the mine numbering 5. Development of the auriferous deposits has progressed fairly steadily for two years past. No. 1 shaft lies a few hundred feet back from the camp on the lake shore and at the top of the hill. It is 28 feet deep, vertical, and 6 by 9 feet in size, on a vein of trap and quartz striking about northeast, and filling a fissure which traverses both the granite and the contact between it and the green trap. The combined vein filling is not much over a foot in average width, the quartz making about half of this and varying from an inch to 26 inches in width. The quartz carries galena, blende and pyrite and an unusually thick sprinkling of visible gold. A mill test of 3 tons of the ore is said to have given $83.00 gold per ton on the plates, which is quite possible judging from the vein material now on the dump. It is a question, however, whether it will pay to mine such a narrow ore body.

No. 2 shaft at 96 feet southwest of No. 1 is 29 feet deep, vertical, and 6 by 9 feet in size on another narrow gold-bearing stringer of quartz, entirely in granite and parallel to No. 1 vein.

On the lake shore at about 1,000 feet southwest of No. 1 shaft a tunnel has been driven 128 feet northwest into the granite hill, and at the face crosscuts

Digitized by Google

Manxman gold mine, Michipicoton Mining Division, 1903.

Digitized by Google

Digitized by Google

Manxman mine; quarrying auriferous dike.

Eldorado gold mine and mill, Eagle Lake; 1903.

Digitized by Google

UNIV. OF WICH.

UNIV. OF WICH.

Digitized by Google



Iron sand concentration plant of North Shore Reduction Company at outlet of Nipigon River

Digitized by Google

UNIV. OF MICH.

Digitized by Google



Shakespeare gold mine ; auriferous body of quartz and chloritic schist.



Shakespeare gold mine, showing vent or natural opening.

Digitized by Google

UNIV. OF MICH.

UNIV. OF MICH.

Digitized by Google

another northeast-southwest vein which is exposed on the surface 90 feet above. Drifts were run on it 33 feet northeast and 37 feet southwest. The so-called vein is of indefinite outline, being composed of a mixture of quartz stringers in schistose granite along a sheared zone of this country rock.

Instructions were necessary for the remedying of certain improper practices in handling and storing dynamite. The camp includes boarding and bunk houses, office, stable, etc. In front of it a dock has been constructed for the company's small steamer.

Buffalo Mine

The above property is known both by this name and by its location number, M H 246, and is situated on the west shore of Eagle lake between the Eldorado and Grace mines. The Northern Light Mines Company, the owners, during the summer did a considerable amount of exploratory mining, of which N. Higbee was in charge. Several camp buildings have been erected on or near the shore. From the shore line a tunnel has been driven west 30 feet crosscutting to the lode, which was then followed southwest for 78 feet farther. At 553 feet west of the tunnel No. 1 shaft was sunk, 28 feet in depth and vertical. To the southwest of this a pit and a 15-foot shaft, called No. 2, have also been sunk. The auriferous deposit consists of a mixture of altered schist and quartz filling a sheared zone in a pink granite formation. At No. 2 shaft the disturbance appears to have taken two directions, both northeasterly, one running to No. 1 shaft and the other to the tunnel. The width of both branches varies from about 10 feet to 25 feet. All mining had ceased some time previous to my visit.

Eldorado Mine

This is another of the Northern Light Mines Company's properties mentioned in former Reports of the Bureau of Mines. No mining has been done since the beginning of 1903, when a shaft was sunk at the mouth of the original open-cut to a depth of 60 feet along the incline of the vein 73 degrees northwesterly. The vein of quartz fills a well-defined fissure from 3 to 5 feet wide in a green hornblende granite and strikes north 70 degrees east. Most of the ore from this work has been milled in the 2-stamp plant erected a short distance from the mine. The milling machinery includes simply the two 1,000-lb. stamps with amalgamation table and a 20-h.p. boiler. On the other side of this point and in a sheltered bay the camp has been built, including living and boarding houses, office, two private dwellings, etc.

Mr. N. Higbee, general manager for the company, was in charge of the work at this mine.

Baden-Powell Mine

The Northern Light Mines Company acquired this property in April 1903. At the time of inspection the force of employees numbered seven, under manager N. Higbee. Mining had progressed since the spring and two mill runs were made at the nearby Eldorado plant on an aggregate of 28 tons of the ore. The gold recovered amounted to about $40.00 per ton, according to the manager.

The main open-cut on the vein has been enlarged to a length of 50 feet, and a depth of 35 feet with shelving ends. A shaft way is shortly to be timbered down the centre, and thereafter all work confined to sinking. At 200 feet southwest of it a new shaft has been sunk 50 feet deep, vertical, and 6 by 8 feet in size, but is at present closed.

There are three veins of probable importance cutting across the southwest end of this South Twin island, and all traverse the same granite formation with approximately the same northwesterly strike, but varying in dip. No. 1 vein, on which most of the development has been done is the most southwesterly of the three. No. 2 lies 300 feet northeast of No. 1, and is composed of quartz lenses intermixed with a sheared zone of the granite about 5 feet in width. No. 3 vein lies 300 feet still farther northeast beginning at the shore of the island near the camp. It averages between 3 feet and 4 feet in width.

New camp buildings have been erected on the easterly side of the island and on the other side, near the mine workings, a new office.

The company recently built a 40-foot steamboat for service between Vermilion Bay station, C. P. Ry., and the mines

Viking Mine

A short account was given of the first operations in 1900 of this mine in the Tenth Report of the Bureau of Mines, page 96. Since then it has passed into the hands of the Viking Mining Company, of Toledo, Ohio. A new contract for continued development had at the time of my visit just been let, the mine having been closed since the spring.

Digitized by Google

A shaft had been sunk on the vein in the granite to a depth of 80 feet, 6 by 9 feet in size and inclining 80 degrees southeast with the dip of the ore body. All this was done by hand drilling. The vein maintains a width of 4 to 6 feet of quartz intermixed with the accompanying narrow dike of trap, which was ejected into the same fissure.

Only one camp building has so far been erected, since the force has not exceeded 3 or 4 men at any one time.

S 500

Auriferous veins were discovered on this location by E. Higbee and associates and last winter worked by them. The property is situated on another small lake about 2 1-2 miles southwest of the southwest end of Eagle lake, and contains 225 acres. According to N. Higbee, from whom this information was obtained, there are three veins on the property. Two are parallel with northeast strike, one averaging 10 feet in width and the other 6 feet, and the third, 2 feet in width, cuts across these at right angles. The formation is granite, through which a tunnel was driven 50 feet, crosscutting the 10-foot vein on the way in. Considerable other work was done in the way of stripping the veins at numerous points over the surface.

Ideal Mine

The Ideal Mining Company of Detroit, Mich., has acquired a mining location covering the north 80 acres of lot 8 in the first concession of Van Horne township, Rainy River district, and during the past season erected a camp building or two and did a little mining work. This last consists of a shaft 36 feet deep and some surface stripping. Machinery is being ordered for installation next season, when work is to proceed on a more comprehensive scale. This mine is reached from Dryden.

Redeemer Mine

When inspected on 23rd September 1903, the force numbered 9 under superintendent Gus Larson. The mine lay idle until the new machinery was installed in March, because without this it had been found difficult to keep the water out of the workings. The shaft is now 130 feet deep and maintained vertical. At 60 feet depth a short pump level was run from which water is now raised. The first level is at a depth of 100 feet, but nothing more than the station has been cut out as yet. The intention is to sink to 230 feet before doing much drifting. Satisfactory timbering has been placed in the shaft to a depth of 60 feet, the remainder to follow at once.

The machinery in the adjoining hoist house includes a 35-h.p. boiler, a 3-drill Rand air-compressor supplying power to the two air drills, and a small hoist operating the bucket in the shaft. The shaft head-frame is constructed solidly of square timbers and not covered in. A good dynamite magazine has been erected at a safe distance from the workings, and for thawing this winter a proper thaw-house will be built. More buildings for the camp are to be added shortly, the lumber being now on the ground. The Government constructed last season a 2-mile road from the terminus of the steamboat route from Dryden in to this mine, and to the Gold Moose beyond.

The mine now exhibits a well-defined vein from 7 to 10 feet wide from the surface down, composed of quartz and green trap (the country rock) intermixed. Iron pyrites impregnates the whole to the extent of about 1 1-2 per cent.

An adjoining location on lot 6 in the first concession of Van Horne, known as the Lost mine, was extensively explored over the surface during the summer by Gus Larson, superintendent of the Redeemer. The quartz vein has been stripped for about 500 feet and is from a few inches to 18 inches in width. It fills a true fissure with a strike east and west, and dip 63 degrees north in the green trap of the area and according to Mr. Larson, carries a good deal of free gold. No other work has been done since.

Gold Rock

This property consists of mining location H P 405 and adjoins the Big Master mine to the south, on the shore of Upper Manitou lake. It is owned by the Gold Rock Mining and Milling Company, of Detroit, Mich., and Gold Rock, Ont., for whom J. M. Sweeney is manager and secretary. Last winter and again this summer two shafts were sunk about 1,500 feet apart, one 50 feet deep and the other 60 feet deep A heavy inflow of water necessitated the suspension of work until mining machinery could be installed.

Two camp buildings were erected to house the force of 8 men.

Reliance Mine

This property was originally called the Independence mine. It is owned and operated by the Reliance Gold Mining and Milling Company, Limited, of

Digitized by Google

Detroit, Mich., under the superintendence of T. Armstrong with a force of eight. For 6 months previous to inspection mining had been confined to sinking another or No. 2 shaft at 300 feet southwest of No. 1 shaft, to 97 feet in depth. First level, depth 80 feet; north drift, 75 feet; south drift 75 feet. The shaft is timbered and has a good ladderway. Hoisting is done by means of bucket, block and tackle and horse, with a good brake on the rope.

The quartz vein extends down the shaft and along the north drift. In the south drift it disappears at 10 feet from the shaft.

Instructions were given to build a dynamite magazine at once.

Twentieth Century

Active development marked the past year's operations at this mine, so far as the erection of surface plant is concerned. Underground development has not advanced in nearly the same proportion, so that with the 20-stamp mill ready for a continual supply of ore we find the mine producing only enough to keep one or two of the batteries in the mill running from 2 to 11 hours a day. Out of the force of 32 employees, 8 are miners

Underground development is still confined to the main shaft, which is now 340 feet deep inclining uniformly 83 degrees south. First level, depth 80 feet; unchanged. Second level, depth 160 feet; east drift 20 feet; south crosscut 26 feet, cutting through a 2-foot quartz vein at 20 feet in; west drift 18 feet, then turning north for 47 feet. At 12 feet north from the turn the main vein was struck and drifted on west 93 feet, the quartz gradually decreasing in width from 10 feet at the east end of the drift to 3 feet at the west face. Third level, depth 240 feet; west drift, 159 feet; at 15 feet in, crosscuts run north 42 feet, and south 85 feet, and in the latter at 31 feet south another drift runs west 78 feet on a one-foot vein of quartz; at 20 feet in the main west drift and overhand stope 40 feet in length extends along the drift and is timbered over, and up the centre of it an upraise was driven to the second level; at 130 feet in the west drift the quartz vein again appears in irregular stringers from there to the face, it having pinched out from the end of the stope to that point. Fourth level, depth 320 feet; west drift 15 feet, with at the face crosscuts south 5 feet and north 71 feet. At the face of the north crosscut what appears to be the main quartz vein had just been broken into at the time of my inspection, 28th September 1903.

The surface plant has been entirely re-arranged since the erection of the 20-stamp mill, all the power machinery now being stationed in the one building adjoining the mill. This part of the plant includes the original 3-drill Rand air compressor; one-half of a 12-drill Ingersoll air-compressor; the mill enhoist engine, the drums 4 inches diam-hoist engine, the drum 4 inches diameter by 2 feet 6 inches face, using 3-4 inch steel rope, one drum operating a skip in the shaft, and the other another skip from the shaft head up a trestle road 350 feet in length to the ore bins in the top of the mill. The milling plant includes only the stamp batteries and the amalgamation plates, the ore not requiring concentration. At the top of the building there are two large ore bins one above the other, and between them the rock crusher is set up.

It was again necessary to give instructions for the adoption of safe practices in handling the dynamite.

Giant Mine

Another location, H W 185, has been added to the original two locations comprising the property, H W 74 and 75, and adjoins these to the east. The owners are the same, but P. Paulson has been made superintendent. The force numbered 7 at date of inspection, 27th September 1903. Mining had been confined to the shaft on H W 75 and it was then 212 feet deep, inclining 80 degrees westerly. First level, depth 200 feet; east drift 150 feet, with a crosscut from the face 24 feet south. This east drift will be continued to strike the ore shoot which is exposed on the surface at 260 feet east of the shaft. The shaft follows down a shattered zone of slaty trap carrying a few irregular stringers of quartz, and the first level east drift is still in the same. There appears little excuse for having sunk at this point where no ore exists, when at 260 feet east a well-defined quartz vein carrying visible gold outcrops as the only chute in sight likely to produce pay ore. The shaft is timbered with a solid collar 40 feet deep and below this to the bottom with square frames solidly lagged. The ladder-way is partitioned from the hoist-way but the ladders extend without platforms from top to bottom. An open head-frame carries the sheave for the bucket hoisting cable, which runs thence into the adjoining hoist house.

New camps consisting of office, bunk and boarding house, etc. have been built on location H W 185. A satisfactory dynamite magazine has been built, but was not kept in a cleanly condition

Digitized by Google

Gold Standard

The Gold Standard Mining Company of Morris, Minn., have changed their point of operation from their first location G 340 (2) on Sairey Gamp lake to location H W 271 of 40 acres situated on the northwest side of Nelson lake. These two locations are about a mile apart. The steamboat runs down the Manitou lakes about 35 miles from Gold Rock to a short portage on the west side of Lower Manitou, from where the journey to the mine continues by canoe for two miles farther. E. E. Hall is manager and employed 16 men at date of inspection, 26th September 1903. Operations began here in October 1902, since which time camps have been erected, consisting of bunk house, office, stable, hoist house, etc., a 3-4 mile road constructed between Sairey Gamp and Nelson lakes, and the waters of Sairey Gamp lake raised about 2 1-2 feet for better navigation by a dam at their outlet into Manitou lake. A few feet from the shore of Nelson lake, the shaft has been sunk 95 feet in depth, vertical, and 6 by 9 feet in size. The collar extends to a depth of 15 feet. Below this are square frames carrying the partitions between the two compartments and the ladderway to a depth of 50 feet. First level, depth 80 feet; east crosscut 110 feet with at the face a rise at 45 degrees incline 36 feet farther west. Mining is now confined to sinking in this shaft. On either side of the shaft along the outcrop of the quartz vein two pits were sunk from 6 to 15 feet deep. The shaft head frame is 12 feet high and open. Hoisting is done by bucket operated from the adjoining hoist house by a small engine and a 30-h.p. boiler. The quartz vein cuts through a formation of compact granular trap with a strike about north 25 degrees east and is distinctly lenticular, varying in width within short distances from a foot or so to 8 feet. The dip is not apparent from the surface exposures, and as the shaft was started down at about 25 feet west of its outcrop and has not yet met the vein with depth, not much else is known regarding its size and value.

Big Master Mine

At the time of inspection, 25th September 1903, W. Shovells was acting manager with about 30 men in the employ of the company, with mine foreman Malcolm Speer and mill foreman G. R. Vary. During the fall of 1902 two separate mill runs were made of 16 days each, from each of which about $5,000 worth of bullion was obtained, according to the manager. From then until May of this year it remained idle, but since then has run continuously. Frue vanners now replace the original strake table, which did not effect the concentration of the ore satisfactorily.

The mine also lay idle from January to April, but since then mining has been more or less active in the production alone however of the ore milled. Practically no further development has resulted during this time. All ore in sight from the surface down to the second or lowest level has been taken out, so that the mill will be forced to close down shortly for lack of ore. It is unfortunate that a more businesslike plan of development in blocking out plenty of ore in advance has not been adopted. The second level northeast drift was continued 35 feet farther to a total distance of 278 feet: at 180 feet northeast, in the pay chute, a winze is being sunk, and directly above it a connection made, partly through the open stope, with the first level and from there again with the surface, up which ladders are placed, providing a second outlet from the mine. This pay chute which lies northeast of the shaft has a length of 80 feet along the vein, and an average width of 8 feet, both of which dimensions it maintains fairly closely from the surface down. The average value is given as about $8.00 per ton. The big or east vein lying to the southeast of the above is also reported to have a pay chute, which is 90 feet long and about 5 feet wide, lying directly opposite the one mined in the west vein. These pay chutes are well defined from the rest of the vein, in that they each consist of a sudden enlargement of the quartz to about double its width elsewhere. It is stated by the manager that the quartz of the west vein carries values pretty well throughout, but that except at the so-called pay chute it is too narrow to mine at a profit.

The surface plant was unchanged with the exception of the addition of another boarding house and a private dwelling.

Little Master

A short reference was made to this mine in the last Report of the Bureau of Mines, in which it was noted that all mining work was confined to location A L 206 bordering on the northwest shore of Mud lake, which is a short distance east of Upper Manitou lake. In addition to this the Summit Lake Mining Company owns the following locations: A L 207, 208; H W 31, 35; G 16, 17, 19, 21, 22; and G 18, all in the vicinity of Mud and Summit lakes.

(2) Bureau of Mines, Vol. V., p. 100.

Digitized by Google

The company is building a 2-mile road from the mine northwest to connect with the Government road between the waters of Manitou and Wabigoon lakes. S. V. Halstead is manager and S. H. Williamson, foreman, under whom 14 men are employed.

Mining has been going on for the past year or so and at the date of inspection, 25th September 1903, it was confined to sinking No. 3 shaft, which is to be made the main working shaft. It is now 50 feet deep, vertical, and 7 by 12 feet in size, with a solid collar to a depth of 24 feet, but beyond this there are no other timbers, not even ladders, the men entering and leaving the mine in the bucket. Instructions were given to suspend hanging ladders in the shaft immediately, to complete the timbering to within a safe distance of the bottom, and otherwise to comply with the Mines Act regulations for the safe operation of shafts, which prohibit riding in the bucket.

No. 1 shaft lies 200 feet west 20 degress north of No. 3 shaft and up the hill 106 feet higher, and is 50 feet deep, vertical, and 7 by 12 feet in size. The first level is at the bottom and consists of a crosscut 26 feet west. This shaft has been temporarily closed until connection can be made underground by crosscut and upraise with the No. 3 working.

No 2 shaft lies about 350 feet northeast of No. 3 shaft, and a few feet higher up the hill. It is 100 feet deep, vertical, and 6 by 9 feet in size. First level, depth 80 feet, with crosscuts west 20 feet and east 30 feet.

Hoisting in No. 3 shaft is done by bucket, the rope after passing over the sheave on the open head frame descending the hill over trestles a distance of about 400 feet to the hoist house. The machinery here installed includes a small Jenckes hoist and a 28-h.p locomotive type boiler. The camp located on the lake shore about 400 feet from the mine workings comprises boarding and bunk houses, office, stable, etc. The company have ordered mining machinery of greater capacity amongst which will be an air-compressor, and if possible the new plant will be set up during the winter of 1903-4.

The formation covering the location consists of the green trap of the Manitou gold area, which here has been disturbed and altered along a number of roughly parallel lines to a chloritic schist. In these schistose bands, which strike in the same direction as the more solid trap, quartz has been deposited either as a general dissemination of interbanded stringers over the entire width of the altered area, or as one continuous lenticular vein. No. 3 vein is of the former class and contains only a very little quartz, while No. 1 vein is of the other variety, having an average width of about one foot. This latter vein is rich in free gold, but on account of its small size can hardly be considered of commercial value.

Similar deposits have been opened up at numerous other points on the property by means of test pits.

National Mine

This property consists of location H W 78 bordering on Three Hundred lake northeast of Upper Manitou lake, the mine workings lying about 200 feet north of the Government road. S. V. Halstead, acting as manager for the National Gold Mining Company of Detroit, Mich., the owners of the property, has during the past year with a force of about 10 men sunk a shaft 100 feet in depth, vertical, and 6 by 9 feet in size. The first level is at a depth of 98 feet with drifts north 25 feet and south 25 feet. Hoisting was done by buckets and a small Jenckes hoist engine. The latter and a 25-h.p. boiler are situated a short distance from the shaft and covered by a temporary shelter.

The miners live in a camp about a quarter of a mile southeast of the shaft on another location.

Just what the shaft was sunk on, in the way of an auriferous deposit, is hard to determine, as the rock dump exhibits nothing but compact green trap, and the surface nothing in the way of a quartz vein in the immediate vicinity of the work. The only visible vein in connection with the shaft occurred as a stringer 8 or 10 inches in width at about 100 feet south of the shaft; at other points across the strike of the formation, other splashes or lenses of quartz exist, but indicate no ore body, being merely a common characteristic of this green trap area.

All operations were suspended here a few days previous to my visit of inspection on 24th September 1903

King Edward

This property consisting of H W 171, 240 acres in extent, is situated west of the upper end of Lower Manitou lake and borders on both Carlton and Trout lakes. It has been acquired by English capitalists represented in this country by F. Bolton, Wabigoon. A force of 6 men have since June been extensively exploring the surface showings of quartz and other auriferous deposits on the location and have sunk a large number of test-pits and crosscuts. At

Digitized by Google

the date of inspection, 27th September 1903, all work had just ceased until next year, when it is expected a definite plan of comprehensive development will have been decided on. One log shanty constituted the camp.

A large portion of the location covers a boss of biotite granite which lies in the green trap belt of the Manitou area and near its western edge, forming one of many similar bosses separated from the main body of the Laurentian gneiss to the west. As a result of severe metamorphic disturbances, this boss of gneissoid rock exhibits two main lines of faulting or shearing, one of which with its northwesterly trend gives the country its fairly definite strike. The other crosses the first at right angles, or approximately north 30 degrees east. Two classes of ore deposits exist, one filling true fissures as solid quartz veins from 5 to 6 feet wide in a north 30 degrees east direction, and the other composed of schistose zones 10 feet or more in width through which quartz stringers are interbanded in about equal quantity with the enclosing schist.

Most of the mining done is comprised within an area of about 400 by 800 feet, and in this the pits disclose three prominent veins of the first or fissure class, and two of the latter or banded variety, or possibly only one, since the two trend roughly towards each other where uncovered in the pits. The quartz in all the deposits carries iron and copper pyrites, galena and blende, the first named also occurring in appreciable quantities in the schistose vein matter. Very little free gold has been seen, and the few samples taken for assay were insufficient to enable one to form any idea of the value of the veins.

St. Anthony Reef

Manager J. S. Steele, of the Jack Lake Gold Mining Company, the owners of the above gold property on Sturgeon lake, reports the following details of operation since last inspection and plans for future development. Mining ceased in March 1903 and since then no other work has been done. From No. 2 shaft the east crosscut from the bottom was driven 105 feet, and the west crosscut 35 feet with from the face of the latter a drift 20 feet long. From the bottom of No. 3 shaft the east crosscut was driven 90 feet, striking an 8-foot vein at 19 feet in on which short drifts were run; and the west crosscut driven 15 feet. At 80 feet south of No. 2 shaft an inclined shaft was sunk 18 feet deep. More surface trenching was done at scattered points over the locations. The company intends to put in more mining machinery and a stamp mill, and with this in view has purchased the entire surface plant of the Golden Star mine in the Seine River district. It will be taken north to the St. Anthony mine this winter (1903-4).

Shakespeare Mine

This property has been recently acquired for the auriferous ore body it contains. The location consists of 80 acres of lot 5 in the first concession of Shakespeare township, Algoma District, situated about one and a half miles due northeast of Webbwood, Sault branch C. P. Ry., or about three miles by road. It is now owned and operated by the Shakespeare Gold Mining Company, Limited, Sault Ste. Marie, Ont., which is capitalized at $2,000,000. James Cronan is superintendent, and James McKenzie mine captain, under whom the force numbers 11.

Since the commencement of the present development about six weeks prior to the date of inspection, 29th October 1903, a camp has been erected including boarding and bunk house, office, stable, blacksmith shop and magazine; a half mile of road has been constructed from the mine down to the main highway in the valley, and considerable surface mining done.

That portion of the ridge which contains the ore body has very little surface covering, making easy its superficial examination by crosscut and test-pit over a distance of about 500 feet northeast and southwest. At a central point a tunnel runs into the bluff to crosscut the deposit, its length to date being 30 feet. This ore is made up of interbanded lenses and stringers of quartz and chloritic schist, the latter more or less altered to a light, highly quartzose material by severe squeezing of the rocks and the subsequent circulating waters which deposited the quartz and gold. As an evidence of the latter action may now be seen cavities in the rock throughout the affected area ranging in size from the most minute passages up to a vent 5 feet in diameter, all of them lined with contorted masses of quartz, and occasionally acicular streaks of both quartz and flakes of chlorite. The gold was deposited both in the quartz, and along the walls in the schist enveloping the bigger lenses, some of the finds of the yellow metal equalling in size and value the best that the western Ontario gold areas have to offer.

Digitized by Google

The limited amount of development gives to the ore body a width of at least 50 feet, and a length of about 250 feet at the end in which the tunnel lies. To the southwest of this about 100 feet, more pay ore comes in with as great a width as the other, but with its length not yet determined. Films of native copper have been found interlaminated with the schist, and in one of the pannings made by the mine captain he thought he detected native platinum. The sulphides, chiefly iron pyrites, are confined almost entirely to the linings of the above mentioned cavities in the ore.

The chloritic schist of the deposit constitutes the body of this extensive ridge; but at intervals another darker rock of much the same material has been ejected in dikes of various widths trending along the same northeast and southwest strike. The contact with the granite lies to the north on the other side of the valley, probably half a mile away.

AL 282 or Sunbeam

This mine has continued in steady operation from the date of the last previous inspection to that of 7th October 1903 under the same owners and mining staff. There is a temporary reduction in the number of employees at present to 13.

All mining has been confined to the one working reached by the main shaft. This shaft is now 318 feet deep, and is still sinking on the same incline of about 45 degrees northwest. First level, no further drifting; the northeast drift has been dammed to catch the surface water (practically the only water which enters the mine) which is then pumped to the surface. Second level, depth 195 feet; northeast drift 244 feet; southwest drift 179 feet with at 30 feet in, a sump. Third level, depth 295 feet; northeast drift 120 feet; southwest drift 145 feet. From 25 feet in the northeast drift, third level, water is pumped to the surface from a sump.

A new open head frame has been erected over the shaft 15 feet high, and at 10 feet distant a small hoist house in which a new duplex cylinder single drum steam hoist has been installed, winding the 1-inch steel cable from the bucket in the shaft. At the foot of the hill below the shaft a 125-h.p. boiler in a separate building furnishes steam to the hoist and pumps. A new blacksmith shop and storehouse have also been built, and at safe distances from the shaft so as to avoid further danger to the workings by fire.

Although locally varying greatly in width owing to its lenticular character, the quartz vein will average in all the levels a good workable width of between 4 and 5 feet from top to bottom of the shaft. The values according to the manager, T. R. Jones, are considerably better in the lower levels than above. They appear to lie in a series of parallel pay chutes from 15 to 30 feet in length along the vein, and separated by as many feet of low grade or lean quartz. These pay chutes dip somewhat steeply northeast in the vein. The vein proper, which includes a width of one or more feet of schistose granite intermixed with quartz stringers on either side of the main quartz band above referred to, maintains a much more uniform width of 6 to 7 feet throughout. It is reported that commercial values in gold exist in this schistose portion of the vein as well as in the clean quartz band, and if so the gold is probably in the interlaminated stringers and bands of quartz therein.

By later word from Mr. Jones I learn that it is the intention of the company to erect a 10-stamp mill at the property during the winter or spring of 1904, and that as a good deal of the plant is already on hand, brought in by the former owners several years ago, the mill will probably be in operation early in the summer. Stoping on a sufficiently large scale will necessitate increased mining plant in the way of more boiler power, air compressors for air drills, etc., all of which are also to be installed.

AL 278 and 200

These two adjoining locations are situated about one-quarter of a mile south of the Seine river, near Island falls. They were surveyed and superficially prospected several years ago, but no mining of account done until the summer of 1903, when, under the superintendence of Henry J. Tharles, the Little Rock Consolidated Mining and Development Company, Limited, of Buffalo, N.Y., sent in a small force of miners and sank a shaft. The workings are reached by canoe route from Hematite siding or, as it is called, the Hospital, on the C. N. Ry., 5 miles east down Sapawe lake to Whiskey Jack creek and thence by a 2 3-4-mile trail north over a very rough, rocky and swampy country.

No buildings have yet been erected, a tent being used instead. The shaft is 50 feet deep, 7 by 9 feet in size, and inclined 80 degrees west-southwest. The quartz vein outcrops on a hill about

Digitized by Google

300 feet long, which rises out of the surrounding flat swampy land, consisting of a medium grained gray hornblende-biotite granite, the hornblende and biotite more or less altered to chlorite. This appears to have been faulted, the fault plane striking N. 32 degrees E. and dipping at about 80 degrees to the southwest. In it the quartz vein has been deposited. At the northeast end it shows first at the shaft, down which a width of 6 to 8 feet is seen. From here for 200 feet southwest to where it disappears under the swamp it maintains a width of 10 to 12 feet, and at two places has been opened out by surface cuts. The vein filling is mainly quartz, but this contains an intimate mixture of black hornblende and schist, locally varying in quantity. A little iron pyrites was visible.

From a report on the properties made by Mr. F. Hille, of Port Arthur, I gather that the vein can be traced northeasterly with a very uniform strike through both these locations, and that it was found to be auriferous, at places showing free gold.

Walsh Mine

From J. J. Walsh, late owner and still manager of this mine, I learn that in the spring of 1903, a 3-gravity stamp mill with gasoline engine power equipment was set up on the shore of Sapawe lake, and some lots of the ore from both No. 1 and No. 2 veins tested, giving good returns in gold. No. 1 vein is that described in the tenth Report of the Bureau of Mines, p. 107, as the Sapawe lake property. No. 2 vein lies about 800 feet inland from No. 1, and on it only stripping so far has been done. The old pit on No. 1 vein was sunk to a 50-foot shaft.

Recently the property was sold to parties who intend, it is reported, to become incorporated as the Sabawe Lake Gold Mining Company. A contract for further sinking on No. 1 vein has been let.

West End Silver Mine

Subsequently to the last inspection of this mine in November 1902, the operations received a serious set back in the loss by fire of the large new shaft and power buildings, and in the consequent heavy damage to most of the machinery. The newly timbered shaft enclosed by this building was also wrecked or scorched to nearly 100 feet in depth. Previous to this, mining and milling with the new and enlarged plants had progressed for two months, (February and March 1903); but afterwards all work ceased until June, when with Mr. H. Shear as general manager again, a small force started rebuilding and repairing. They are still engaged at this and now (January, 1904) have about finished so that operations can be resumed as soon as sufficient working capital is raised. With the ore now in sight in the mine levels and old stopes, not much financial aid should be necessary to set the whole on a paying basis again.

At a recent meeting of the owners, the Consolidated Mines Company of Lake Superior, Limited, the following officers were elected: president, C. P. Russell; secretary, M. A. Myers; treasurer, John Hourigan; general manager, H. Shear; and directors, A. J. Thompson and A. M. Wiley.

The last mining consisted in taking out ore from the stopes between the 2nd and 3rd levels east of the shaft, and in driving the 3rd level east to a length of 765 feet (an increase of 215 feet).

The shaft has been straightened where necessary and re-timbered with square frames at 6-foot centres from the top to the 4th or bottom level, solidly lagged, and divided into two compartments, one for an inclined cageway and the other the ladderway. The incline of the shaft is 73 degrees north. The guides for the cage extend 28 feet above the shaft house floor, allowing about 15 feet for overwinding. With the safety attachment and the hood in place men may with safety travel on the cage.

To the new surface plant enumerated in the last Report a 6-drill Rand air compressor, duplex air and steam, has been added. In the mill there are now 20 stamps and 9 Frue vanners which, with a capacity on this ore of 4 tons per stamp per day, are capable of treating 80 tons daily.

The proposed and recommended new dynamite magazine has not yet been built. A suitable thawing house heated with steam is now used. At the camp the new store and office building is completed, and several more small private dwellings are now in course of erection.

Digitized by Google

Iron Mines

Loon Lake (C.P.R.)

A description of the iron claims at Loon Lake siding C. P. Ry., near Port Arthur, and of the work done to that date on them is contained in the Bureau of Mines Report, Vol. XII., page 310. The diamond drilling then under way was continued until near the end of 1903 by the same party, Mr. Rinaldo McConnell of Ottawa, under the management of Mr. W. Demorest. The owners are not in a position to state definitely the extent of the finds, so that nothing of interest can be added to the last account.

North Shore Reduction

The iron-bearing sands which occur in places along the north shore of Lake Superior have for years excited considerable interest, but not until the past summer has any thorough attempt been made to work them. Although the sands are found both on the shores of the lake and beneath the waters of the rivers and bays, it is probable that in the latter cases local enrichments may occur by the re-working and re-concentration of the sands through the action of the waters, for which reason mainly the wet sands are being dealt with first. This involved a radical departure from the usual processes of magnetic concentration which are adapted to dry material only. To extract the magnetic iron from the wet sands necessitated the invention of entirely new machines.

The North Shore Reduction Company which has undertaken this task, has made application to the Government of the Province for certain areas of magnetic iron sands both above and under the water at several points along the north shore of Lake Superior. One of the areas lies at the mouth of the Nipigon river where it empties into Nipigon bay, and here on the sand from the bottom of the river the first attempts at separation were made during the summer of 1903. Mr. J. Walter Curry, K.C., City Crown Attorney, Toronto, is representative of the company, and Mr. S. N. Smith, electrical engineer of Minneapolis, was in charge of the work at Nipigon, where he employed an average of about 18 men until work was suspended for the winter.

Not much is yet known of the character of the sands in the river bottom at Nipigon, or whether they will be found richer in magnetite than the sands composing the high cliffs at the river's mouth. Mr. Smith thinks that an average content of 10 per cent. magnetite (about 7 per cent. metallic iron) exists, but as no systematic sampling of the ground has yet been undertaken, it is not possible to say whether the actual percentage will run as high as this or not. The grains of magnetite as well as of the quartz sand itself are small, the former probably all less than 40-mesh size. The iron would appear to be fairly uniformly disseminated through the sands of the cliffs, judging from the lack of any pronounced black streaks or areas.

Since the spring of 1903 the company have been assembling a suitable plant (see illustration) to test their process on the spot. It consists of a barge about 25 by 80 feet plan, by 10 feet depth, fitted with boiler, duplex driving engine, propeller and rudder. The remainder of the interior is taken up by a high speed engine operating the sand pump and concentrating apparatus; a smaller engine connected to the electric generator which supplies current for the magnets and lights; and a complete machine and blacksmith shop outfit. On the after-deck are the living apartments, and forward are the sand pump and outfit, including sufficient suction pipe to reach to the bottom of the river at any point, and the magnetic separating table or concentrator.

It would be premature to describe in detail the process as exemplified by this first separator, since considerable further experimenting is yet necessary to perfect its operation which may entirely alter the design. This machine consists, however, essentially of a rubber belt 3 feet wide with rough egg-shell surface and raised edges which travels up a slightly inclined plane on three brass rollers, the end ones 5 feet apart and the intermediate one acting as a tightener. The lower surface of the belt travels nearly horizontally and close to the launder underneath of the same width, along which the sand sluice from the pump flows in a stream about one inch deep. Inside the lower roller a magnet revolves at high velocity while charged with electricity from the generator by means of contact brushes on an extension of the magnet shaft past the bearing of the roller. At first a high voltage was tried, but since, it has been found, I believe, that a low voltage and high amperage gives the best results.

As the sand flows beneath this lower roller at not more than half-an-inch dis-

Digitized by Google

tance therefrom, the magnetite is picked up and held against the belt by the magnets until the belt has carried it around and on to the upper surface. During this passage around the lower roller the peculiar application of the current causes the particles of iron to roll over and over on one another, during which a stream of water is sprayed from above to wash out any included particles of sand picked up with the iron. From here the iron travels quietly to the upper roller where it is washed off by water.

The company also purchased a 40-foot tug for exploratory and freighting work. The old Hudson Bay Company's store houses on the shore below the town site of Nipigon serve as warehouses and headquarters for the plant for the present. The company expect to accomplish a larger measure of commercial success next summer at this place with a plant of increased capacity, since experiments with the process and apparatus are to continue during this winter at Chicago.

Argenteuil Mining Co.

The above company of Jackfish, Ontario, and Saginaw, Michigan, is developing mining location A L 383, 323 acres, for iron. The property lies about 1 1-2 miles north of Jackfish on the C. P.Ry, and on Jackfish bay, Lake Superior. Mining has progressed here intermittently since 1900 under the management of Mr. A. F. Beattie, the force at the present time, October 1903, numbering 11.

No 1 shaft was sunk 50 feet, vertical, and 5 by 7 feet in size, and then work was suspended.

No. 2 shaft, 170 feet distant from No. 1 shaft and 120 feet back from the lake shore, is 25 feet deep, vertical, and 7 by 12 feet in size, and is now being sunk to the 100-foot level.

A tunnel was driven towards No. 1 shaft from a point 440 feet distant, and when 420 feet in, work was suspended in favor of No. 2 shaft. The ore, according to Mr. Beattie, consists of an irregular body of hematite in a granite formation.

The surface plant has up to the present consisted only of the camp buildings—office, boarding-house and blacksmith shop. Now however a hoist and boiler-house and shaft-house are being erected for the small hoist engine and the 20-h.p. boiler, already on hand.

Williams Mine

The property by this name covers a number of lots adjoining the Loon Lake or Breitung mine to the east, both bordering on the shores of Loon lake, and is reached by a 1-mile branch line from the Algoma Central railway at Wilde, thence by boat across the lake, and from the dock by three-quarters of a mile of wagon road to the mine. The land taken up consists of the following adjoining lots at the corner of four townships in Algoma District: lot 11 and N. 1-2 of lot 12 in the 6th concession of Anderson; S. 1-2 of lot 12 in the 1st concession of Hodgins; S. 1-2 of lot one and S. E. 1-4 of lot 2 in the 1st concession of Deroche; N. 1-2 of lot 1 and N.E. 1-4 of lot 2 in the 6th concession of Jarvis, comprising in all 1,100 acres. It is owned by the Williams Iron Mines Company, Limited, which was recently incorporated under the laws of Ontario with a capitalization of $3,000,000 in shares of $1.00 par value. The head office of the company is at Sault Ste. Marie, Ont.; president, John E. Burchard; vice-president, F. B. Lynch; treasurer, M. W. Harden; and secretary and general manager, Chas. C. Williams. Under superintendent, C. W. Jessup, the force numbered 20.

For more than a year previous to the commencement of the present development by this company early in 1903, the iron-bearing zone was explored in an unusually thorough manner by the present superintendent and a small force. For a distance of two miles southeasterly from the Loon lake mine, past Loon lake and through these lots, the ground has been stripped at intervals along the strike of the vein formation. On the findings of that work the present mining was undertaken. A shaft is being sunk on the Deroche lots 100 feet in depth to date, vertical, and 5 by 8 feet in size, but with no drifting therefrom as yet. Solid timbering follows down close to the sinking, with partition between the two compartments, and ladderway with platforms, all in good shape. Unwatering is done by a No. 5 Cameron sinking pump. A boarded in head frame of square timbers 22 feet high to sheave covers the shaft. The remaining work consists of a tunnel 65 feet in length driven west into the hill at a point about 100 feet south of the shaft; and in the same vicinity several test shafts from 20 to 30 feet deep through the drift to bed rock.

The iron-bearing formation continues through to this mine from the Loon Lake or Breitung mine, in connection with which latter it was partially described in an earlier Report (3). At the Williams property however it is possible to collect additional information on account of the extensive surface strippings. The formation consists of a

(3) Bur. Mines, Vol. XI., p. 263.

Digitized by Google

fine-grained greenstone, light to dark in color, which is probably essentially a diorite, although no subsequent determination of this point has been yet made. It appears to be a wide dike of eruptive origin, traversing the older Laurentian hornblende granite of this region with a northwest-southeast strike its southwest contact lying about 300 feet distant from the mine workings at both properties. These workings represent the relative position of the iron-bearing zone at these two points, and in all probability closely so in the distance between, since the formation tends to maintain a constant strike over considerable distances. The iron-bearing zone follows the bottom of a deep valley from Loon lake to this mine and beyond, and as far as examined appears to represent the central line of a metamorphic disturbance which by both pressure and faulting, imparted considerable schistosity to the rocks for a width of at least 600 feet, wherein it approaches a slate in its lamination. Polished surfaces are common throughout this area, a proof of movement in the general disturbance. It is along this central portion that the iron is found in small lenses or bands and stringers intimately intermixed with the formation, the ore consisting of an iron black to lustrous specular hematite, compact columnar, or fibrous, to finely foliated. No large or continuous iron body has yet been uncovered, and judging from the surface exposures and the shaft the ore if struck in large merchantable quantity will not be entirely clean, but be associated with more or less brecciated slate and trap similarly to the ore at the Loon lake mine.

On the southwest side of the valley the formation is a dark greenstone, generally slaty, though granular and blocky in places, merging at the bottom into a much lighter colored, highly feldspathic rock aphanitic in texture which continues to the northeast. It weathers gray, but in the body has a light greenish-gray color. Throughout both varieties of rock a general deposition of quartz has taken place, in minute stringers to massive veins several feet wide, trending usually with the strike of the enclosing formation. The quartz all carries considerable red and brown hematite and where this has separated out into bands of clean iron up to 6 feet in width, it is of the specular variety. A banded jaspery ore is the result.

Narrow dikes of trap some quite different in composition from others cut across the formation nearly at right angles to its strike.

Mr. Jessop informed me that the ore is of as good or better quality than any now on the market, assaying 60 per cent. and over of metallic iron, 0.015 per cent. sulphur and 0.009 per cent. phosphorus.

Loon Lake Mine

This property was formerly called the Breitung mine and is described in the Tenth Report of the Bureau. An addition to the property of 218 acres of land under water in the central portion of Loon lake increases the aggregate holdings of the company to 1,219 acres in the townships of Deroche and Jarvis. The Breitung Iron Company, Marquette, Mich., still owns the property, according to the statement of the manager, but by a secondary arrangement the operation of the mine is now in the hands of a new concern, the Loon Lake Iron Company, Sault Ste. Marie, Ont. The latter company has a capitalization of $3,000,000 in shares of $5 par value; president S. B. Martin, and secretary and treasurer, P. J. Hart. Mr. Martin acts as manager also.

The new power plant is located up the hill at a short distance below the mine workings, instead of on the lake shore as formerly. New machinery has been installed comprising a 60-h.p. boiler, a 3-drill Ingersoll air-compressor, and in an adjoining building a rock crusher and some car loading fixtures. The hoist stands farther up the hill and just below the shaft in a temporary shelter. The one and three-quarter mile branch of railway from the main line of the A. C. R. has been completed in to the mine.

The tunnel was continued northwest into the hill to a length of 298 feet (131 feet increase) and at 210 feet crosscuts run 37 feet southerly, and 65 feet north to northeast; the latter connecting with the shaft. At 13 feet in the former a winze is being sunk on an incline of 75 degrees S., 58 feet deep to date, with a crosscut 12 feet long from the bottom. In the tunnel crosscut a small hoist operates the bucket in this winze. Instructions for safer operation of this machine and the hoisting apparatus were necessary.

The shaft is situated about 180 feet northwest of the mouth of the tunnel and is 175 feet deep and vertical; at 71 feet depth the northeast crosscut from the tunnel connects. Beyond a short collar no timbers or ladders have been placed in the shaft, nor any means of entering or leaving other than by the bucket. The attention of the management was

Digitized by Google

drawn to this neglect, and instructions were given to immediately timber the shaft, and to place hanging ladders temporarily for use instead of the bucket. From the south side of the shaft mouth an incline chute was sunk to the tunnel through the country rock, and all ore from the shaft now drops down here to be trammed out the tunnel to the dumps.

Some diamond drilling was done during the summer, but not pursued to great enough extent either in depth or number of holes to give much information as to the ore body.

In the last Report it was stated that iron had been found at places across a width of some 400 feet of the slate formation. It appears now from my recent examination when the snow was off the ground that outside of a central ore body, which may be called the main or important occurrence of iron, the other outcroppings consist apparently of narrow lenses or bands of the slate impregnated with iron, or of quartz veins running with the formation containing some hematite. The tunnel workings show very well the nature of the main iron body. It has a width of about 50 feet southwest-northeast, with the same strike as that of the slate formation, namely northwest-southeast, and dips with it at about 60 degrees S. W. The central portion contains the cleanest iron. Outside of this the ore is a mixture of brecciated slate fragments and iron-black hematite, occurring along fairly well defined bands in rich and lean portions. The ore to the northeast is bounded somewhat sharply by the barren slate, while on the southwest side, before the actual disappearance of the iron, quartz lenses and irregular stringers appear in increasing quantity, gradually excluding the hematite. This was observed to be the case at every exposure—surface, tunnel and crosscut, and bottom of winze. The shaft has been sunk entirely in the barren rock, the ore dipping away from it, but with the intention of cross-cutting southwest to it from the bottom.

The stock pile of ore below the tunnel mouth contains probably 1,500 tons, averaging, according to the manager, about 50 per cent. metallic iron, 0.05 to 0.25 per cent. of sulphur, and traces of phosphorus.

Further instructions were given to replace the present dynamite magazine by another situated at a safe distance from the new workings, and to build and use a suitable powder thawing house. At the camp an office has been built.

Locations in Aberdeen

On 26th October 1903 an examination was made of certain locations situated about 15 miles north of Desbarats, on which diamond drilling was in progress to test a body of specular hematite traversing these locations. The work was being done by Mr. E. F. Krelwitz of Duluth, Minn., who held options on the S. part of lot 11 and the N. part of lot 12 in the fourth concession of Aberdeen township; and the N. parts of lots 1, 2 and 3 in the fourth concession of Aberdeen additional. In May and June four men were engaged in prospecting along the surface of the outcrop, on which a number of shallow test pits and crosscuts were then sunk. About the middle of September diamond drilling commenced, and since then about 1,000 feet has been bored in a number of holes in the one locality.

This outcropping of iron has been known for a number of years (4), and about 7 years ago a line for a branch railroad was located into it, but nothing important in the way of mining was done until this year.

The sedimentary rocks of the Huronian period, consisting here of quartzites from white to pink, and from red to brown in color, cover a belt of this country from south of the C. P. R. track to a short distance north of these iron locations, a width north and south of probably twenty miles. In driving across it no break was visible in any of the many exposures, until within a few miles of these locations, where bands of slate conglomerate begin to intersect the quartzites at wide intervals, all the bands running roughly northwest-southeast. On one of these slate areas, which underlies a fairly deep valley from a quarter to a half mile wide between hills of quartzite, the iron properties have been located. The slates are generally finely laminated, grayish black in color, and have a course of northwest-southeast, with a dip here and near the iron-bearing zone of about 50 degrees S.W. Their southwest contact with the quartzites would indicate an intrusive origin, since the outer edge of the latter formation is intersected by several dikes of slate from a few feet to 30 or 40 feet wide, separated by other bands of about the same width of the now much altered quartzites. The iron, which in its massive form is an iron-black and bluish compact columnar hematite, and where disseminated a bright but fine specular

(4) Bur. Mines, Vol. X., p. 188.

Digitized by Google

variety, occurs in these several detached bands of quartzose material. Over a length of more than 100 feet a vein of massive iron averaging a foot in width stands up above the surface clinging to the southwest wall or face of the hill, the other wall having fallen away. On either side of this are other less continuous bands, pockets and stringers of the iron intermixed with the vein rock. There is thus a maximum width where exposed on the surface of about 6 feet of merchantable ore. The dimensions of the ore struck in depth by the diamond drill holes had not at that time been made public, although I was given to understand the iron shows at least as well lower down as on the surface.

A microscopic examination of a thin section of this vein-bearing rock was kindly made for me by Dr. A. P. Coleman. It was found to consist largely of quartz with some orthoclase and plagioclase, and throughout all a dirty-looking material, probably the iron. The constituent grains are more or less rounded and have been enlarged by secondary deposition of quartz, etc. There appears little doubt that it is a partially re-crystallized arkose or quartzite. Its relations to the other rocks—the slate and the quartzite or arkose—carry out this belief.

Word was received from Mr. E. F. Krelwitz towards the end of the year, accompanied by plans showing the sections of the four diamond drill holes bored for him. Holes were bored from each of two adjoining points where the drill was set up, all from the northeast side of the ore body, and pointed at an angle into the hill to cross-cut the ore at depth. Iron was struck in three of the holes at depths of 150, 60 and 160 feet respectively. The fourth hole, apparently, was hardly deep enough. At the above depths the respective widths of the ore were as follows: three bands 1 foot wide in an 8-foot width of the formation; two bands 2 feet wide separated by 2 feet of quartzite; and 10 feet in one band. The slate on one or both sides of the iron-bearing quartzose rock is ferruginous for widths of several feet. The borings also struck bands of the altered quartzite which do not outcrop at the surface, but appear to be cut off and surrounded by the slate. These several interbanded bodies of slate and altered quartzite and also the iron ore in the latter dip about vertical. Mr. Krelwitz proposes to continue drilling here early in the coming year.

Copper Mines

Tip-Top Mine

The owners and the mine staff remain the same as at former inspections with this difference, that to the latter W. Smeaton has been added as assayer. At the time of my visit, 5th October 1903, the force numbered 28; but this was shortly after reduced for a time.

Underground development has continued steadily and good progress been made in opening up the copper deposit for future ease in stoping. The shaft is now 200 feet deep, an increase of 40 feet. A uniform incline of 75 degrees N. is now being maintained which is taking the shaft down in the footwall rock a few feet back of the ore, the dip of which is too irregular to follow. In the first level, east drift, is an overhand stope 30 feet long by 30 feet high by 8 feet wide; west drift 40 feet, with an overhand stope 20 feet long by 20 feet high by 8 feet wide. These two stopes begin just beyond pillars left on either side of the shaft—as do also the stopes in the lower levels. Second level, west drift, 52 feet, with at 20 feet in an upraise, now an ore chute, to the first level, and around its foot a stope 20 feet long by 20 feet high by 8 feet wide, timbered over into an ore pocket; east drift, 63 feet, with an overhand stope 20 feet long by 5 feet high by 8 feet wide, timbered over. Third level; from face of station chamber, the drifts run east 42 feet and west 36 feet. Fourth level (new), depth 200 feet; north crosscut 72 feet. These lower workings were allowed to fill with water to the 3rd level. This development work consisting of drifts and stopes follows as closely as possible the footwall of the ore body, the remaining ore nearly all lying on the hanging wall or north side. The ore body will average probably 12 feet in width, judging from the present work, throughout all the underground workings. It is the intention to continue drifting on the various levels both ways to open up more ground as soon as arrangements are settled for treatment of the ore.

Except for the lack of the partition below the 2nd level, the workings are in good condition. It was instructed that this be placed in as soon as possible. Hoisting is done by bucket as before, but now the ore is dumped directly into cars to be trammed to the sorting bins and tables. Thence it is elevated to one of the three stock piles of coarse firsts, fine seconds and

Digitized by Google

coarse thirds, the average copper content of which is about 8 per cent. About 4,000 tons of this ore was raised from development work during the past year.

An interesting find was made in the way of a new mineral in the ore while driving the upraise from the 2nd to the 1st level on the west side of the shaft. It was noticed first as minute steel-gray crystals disseminated through the mixture of iron and copper pyrites, from which it is with difficulty distinguishable. After sorting out the ore containing it and sampling the 20 tons or so obtained, assays gave about 2 per cent. cobalt in addition to the copper.

At the mine an assay office has been built and equipped for the use of both this and the A L 282 gold mine. The small air-compressor has been replaced by a 6-drill Ingersoll compressor, and a 35-h.p. locomotive type boiler added to the former one. At the camp on the lake shore another large log building for offices and sleeping rooms, together with several more private houses, has been recently added.

Instructions for safer practices in dealing with and thawing the dynamite after removal from the magazine were necessary.

Pattison Prospect

This recently opened copper prospect on mining location R 760 of 46 acres is situated about two and one-half miles south of the 136 mile-post west of Port Arthur on the C. N. Ry., on the south shore of a small lake. It is owned by Martin Pattison and associates of Superior, Wis., and has been under development by them most of this season with a force of 10 men. The total holdings of these parties in the vicinity aggregate 200 acres. Besides giving the above information, Mr. R. M. Pattison states that the development work has consisted in sinking a 50-foot shaft and in doing a good deal of surface stripping. The copper occurs as chalcopyrite impregnating a green eruptive rock.

Two camp buildings have been erected, and a shaft head frame and blacksmith shop put up.

Black Bay Mining Co

Owing to the out of the way situation of the mine belonging to this company a visit could not be made on the occasion of my tour of inspection; but on 5th October 1903, I obtained the following information from the superintendent, Martin Sorensen: The offices of the above company are at Fort William, Ont., and Willmar, Minn., and the secretary is M. G. Riggs. At present only four men are employed. The mining locations consist of McA 217 of 75 acres and E S 106 of 171 acres, situated on the southwest shore of the Black bay peninsula and southeast of Pearl River station, C. P. R. A shaft has been sunk 119 feet deep, vertical, and 7 by 10 feet in size. First level, depth 85 feet; west drift 30 feet and now driving. The rocks passed through consist of amygdaloids to 112 feet depth and after that sandstone. Not a great deal of copper has so far been found in the shaft workings, and it is now proposed to continue explorations by diamond drill.

The surface plant comprises boarding and bunk house and office. All mining has been done by hand drilling so far.

The company own a 35-foot steam tug which plies between Fort William and the mine.

Massey Station Mine

The road bed for the line from the C. P. R. tracks has been completely graded in to the mine 3 miles from Massey Station, but rail laying has been deferred until the spring.

With the steady progress in mine development the shaft has reached the depth of 550 feet, an increase of 220 feet, maintaining fairly closely the initial incline of 87 degrees N. The first, second and third levels have not changed. Fourth level; east drift 133 feet with a crosscut 25 feet south at face; west drift 225 feet. Fifth level (new), depth 365 feet; the station chamber is cut and drifts run 12 feet east and west. Sixth level, depth 450 feet; station chamber cut and drifts started only. Seventh level, depth 530 feet with no drifting yet. Work is now confined to sinking and to driving the fourth level west so that when far enough west an upraise to the surface can be quickly made. A second outlet such as this will be imperative before stoping can commence, both as a means of proper and adequate ventilation and for an auxiliary ladderway.

The timbering in the shaft has been allowed to get too far behind the sinking, and instructions for its completion were given to the superintendent.

In the remodelled surface buildings about the shaft there are now two hoist engines, the old one and a new Lidgerwood link-motion single drum hoist of about 20-h.p. capacity.

At the camp a residence for the superintendent and a number of other private dwellings have been erected. A short distance south of the mine buildings stands the new powder thaw-

Digitized by Google

ing house heated by steam from the boiler room.

The ore body maintains the same characteristics in the bottom levels as above, and is of about the same width and richness in copper. The ore occurs in a series of more or less overlapping and succeeding lenses, which accounts for the local crookedness of the drifts, though these in the main continue along the same line. Crosscutting at the end of each lens discloses the next not far removed, about 10 feet or so to one and the same side each time. The ore-bearing rock is slate, a description of which and of the ore body generally will be found in previous Reports of the Bureau of Mines.

Under superintendent Jos. Errington a force of 35 men is employed.

Hermina Mine

This property includes portions of several lots near the western boundary of Salter township, Algoma District, the mine workings being reached by a 6-mile road west of Massey Station and past the Massey Station mine. The operators have recently become incorporated under the laws of Ontario as the Hermina Mining Company, Limited, with offices at Sault Ste. Marie, Ont., and Calumet, Michigan, and with a capitalization of $500,000 in shares of $5 each. The president is James Herman, secretary Peter Primeau, treasurer W. B. Anderson and mine manager R. H. Macdonald. The employees number 14.

A two-mile extension to the main wagon road from Massey Station has just been cut out by the company to their workings. For a camp several old lumber shanties on the property have been made use of by renovating and enlarging. They consist of office, boarding and bunk houses and stable, and are situated near the centre of the property. For the storing and handling of powder it was advised that a magazine be erected and a proper thawing apparatus and house provided at once.

Since the commencement of work by the present owners in the summer months of 1903, all the mining done has been of an exploratory nature, and confined to the surface, with the exception of one vertical shaft which is 30 feet deep. A large number of test pits and crosscuts were examined at widely scattered points.

The locations cover an area of trap intrusions in granite, the two in contact with the light-colored quartzites of this area on the south, and on the north with the unbroken pink granite country. The latter formation is a hornblende granite, the hornblende in very small percentage and altered more or less to chlorite. The trap is a compact dark green to black rock, composed largely of hornblende. It traverses the granite in roughly parallel dikes striking from east and west to southeast and northwest, with widths of a foot or so, to over 100 feet. Over the locations a number of quartz veins carying chalcopyrite in varying amounts have been found, in all but one instance lying embedded in these trap intrusions with the same strike. This one case is in the 2-foot vein at the shaft. It traverses the granite as a fissure vein, but is intersected and disturbed by a narrow dike of the trap, which indicates that these veins in the granite belong to an earlier period than those in the trap. The origin of the latter was probably due to a metamorphic disturbance which faulted and sheared the less resistant trap, leaving fissures or altered bands along which the quartz and base metals were deposited. These veins are composed of quartz, and more or less altered trap, interbanded, one of them at the northeast boundary of the property, averaging probably 25 feet in width in a length of 600 feet, in which it outcrops at frequent intervals. Chalcopyrite occurs in it in most places, but only in the recent crosscut at its southeast exposure does this approach a merchantable percentage in the surface showings. Beyond the boundary line on the next lot the vein was explored by shafts and surface work a few years ago by the Nickel-Copper Company of Ontario, Limited, at a point where the quartz is over 40 feet wide. The work, however, produced a rock dump very low in copper.

The other veins, one of which is now under development at the southeast end of the lots, are smaller, ranging from 1 foot to 3 feet in width.

Rising Sun Mine

On lot 9 in the second concession of Morin township and at 24 miles by road north of Bruce Mines, C.P.R., a shaft is being sunk on a copper prospect by T. P. McNulty, contractor, and five men, for W. F. Ashton, manager of the Copper Queen mine, five miles farther north, and representative of some capitalists of Calumet, Mich., who have purchased the property.

Operations commenced in the first week of August, my visit of inspection being in the following October, 1903.

A branch road about one-third mile long had been cut in to the workings. One log building composes the camp. At

Digitized by Google

the shaft a 12-h.p. vertical boiler and a duplex cylinder single drum hoist have been installed, but without housing as yet. The drum of the hoist, and also the sheave on the head frame are much too small for the 1-inch steel rope used in hoisting the bucket.

The shaft is 53 feet deep, vertical, and 5 by 7 feet in size with a short collar but no other timbering. It lies in one of the wide eruptions of trap found cutting through the outer fringe of the granite formation to the north, the trap consisting of the typical breccicated greenstone which forms a most persistent belt east and west between the Laurentian on the north and the rest of the Huronian rocks to the south to Lake Huron. The included rock in the greenstone which gives it this brecciated appearance consists of pink granite in all sizes from fragments to boulders of many tons weight picked up during the original ejection of the trap. The granite consists chiefly of quartz and pink feldspar, the hornblende and chlorite contents forming but a very small percentage of the whole and being often entirely absent.

The shaft explores a vein of intermixed quartz, calcite and brecciated fragments of the pink granite and green trap. Only a very small amount of chalcopyrite was visible to the present depth, and owing to the heavy covering of drift further exploration in the vicinity was precluded.

The contract calls for a 100-foot shaft, so that work will continue until this depth is reached. Later a more permanent camp may be erected.

Copper Queen Mine

At the commencement of work here by the Copper Queen Mining Company, Limited, nearly two years ago, the Government road north from Bruce Mines and past the Rock Lake mine was continued four miles farther north up to this mine, amongst the high hills. The distance from Bruce Mines is about 30 miles, and from Rock Lake 17 miles. The property comprises about 960 acres of mining lands in Morin township, Algoma District, made up as follows: South half of north half and north half of south half of lot 3, north half of lot 4 and north quarter of lots 5, 6, 7 and 8, all in the fourth concession, and the south quarter of lots 5, 6, 7 and 8, in the fifth concession, and the south quarter of lots 5, 6, 7 and 8 in the fifth concession. The locations lie between the Thessalon river on the west and Sheldon lake on the east.

Mining is progressing under the management of W. F. Ashton, with Angus Macdonald as resident foreman, and a force at date of inspection, 22nd October, 1903, of 7 men.

No. 1 shaft is 140 feet deep, inclining 80 degrees N. for the first 80 feet, and vertical for the remainder. Down the side of the hill on which this shaft was sunk a tunnel was run in west in length 135 feet, connecting at its face with the shaft at 80 feet depth therein. At 115 feet in the tunnel a cross-cut runs 30 feet north. This working is closed for the present.

No. 2 shaft, situated about 1,500 feet west of No. 1 shaft, is 85 feet deep, vertical, and 6 by 9 feet in size, and now sinking, this being the only working place at present. There is on open head frame over this shaft 20 feet high to the 2-foot sheave. The shaft collar extends to only 15 feet depth, without timbering or ladders below, the men entering and leaving the mine by the bucket. This practice is strictly forbidden by the Mines Act, as the foreman and miners here are aware. Instructions covering these points were given at the time.

A number of test pits were sunk and the surface stripped at several places between the two shafts on the various showings of copper-bearing veins.

The power plant is at No. 2 shaft in the one building comprising a 54-h.p. locomotive type boiler; a 6-drill Ingersoll air compressor; a 30-h.p. duplex cylinder link motion single drum hoist engine winding ¾-inch steel rope, and the bucket in the shaft, and pumps. On the shore of Shelden lake 750 feet to the north a small pumping plant operated by compressed air supplies the boiler and camp with water. The camp adjoins to the east, consisting of boarding and bunk houses, office, warehouse, stable, blacksmith shop, etc.

Instructions were found necessary to provide for the safe storing and handling of the dynamite.

The veins under development lie along the south contact of an eruption of trap with the granite of this area. (See geology of Rising Sun mine, page 80). The trap extends north for a width of at least 400 feet, while to the south the granite continues without further interruption apparently, for nearly a mile, when another dike of trap is seen. This latter rock is the brecciated greenstone of the district, and the granite is pink and low in its hornblende constituent. By a later disturbance the greenstone dike was fissured along several parallel lines for a width of 50 feet from the granite contact, and in this area lie the

Digitized by Google

Williams iron mine near Wilde station, Algoma Central and Hudson Bay Ry

Digitized by Google

UNIV. OF MICH.

Digitized by Google



Tip-top copper mine, 1908.

Digitized by Google

UNIV. OF MICH.

Digitized by Google

Tip-top copper mine, 1903.



Tip-top copper mine, showing shaft house and ore dumps.

Digitized by Google

UNIV. OF MICH.

UNIV. OF MICH.

Digitized by Google

No. 5 shaft. Compressor and hoist house. No. 2 shaft. No. 3 shaft.



Superior copper mine, 1903.

Digitized by Google

UNIV OF MICH.

Digitized by Google

Copper Queen veins composed of intermixed quartz, and brecciated greenstone carrying a small percentage of chalcopyrite. Considerable coarse specular hematite is intimately associated with most of the chalcopyrite, small nodules of the the latter being surrounded by the former. At the No. 1 shaft and tunnel workings the quartz vein explored is nearly clean of other rock matter, and has a width at the crosscut at 115 feet in the tunnel of 20 feet. It carries only a very small amount of chalcopyrite except in the few cases of local enrichment. Although the several parallel veins above mentioned are separated by apparently barren bands of trap, the whole width of 50 feet or so north of the granite is considered as vein matter. No. 2 shaft was started down vertically through the trap at a short distance north of the outside deposit of quartz with the intention of intersecting the vein lower down. This is a doubtful policy to adopt in the initial development of a prospect where every foot sunk should be made to open up and define vein matter.

Ranson Mine

This is now reached by a 10-mile wagon road recently completed by the company in conjunction with the Taylor Copper Mining Company, whose mine it also serves. The road runs southeasterly from Dam Creek siding, Algoma Central Railway. The force at present numbers 11, under superintendent J. C. Burns.

The underground development to date is as follows : No. 1 shaft, on the southeast quarter of lot 12 in the fifth concession of Chesley township is 213 feet deep, inclined 65 degrees N., and 7 by 12 feet in size. The first level is now being opened at 200 feet deep. The shaft is well timbered with square frames supporting the pole skids for the bucket, the partition between the two compartments, and the ladderway. The power house adjoins the shaft house containing the same mining plant as enumerated in the last report.

No. 2 shaft lies about one mile west of No. 1 shaft, in depth 75 feet, inclining about 55 degrees N. This is supposed from the outcroppings between to be on the same bands of quartz in the trap as No. 1 shaft. Work was suspended here, however, about a year ago. No. 3 shaft is about a mile southwest of No. 1 shaft and near the old original camp. It was sunk 47 feet deep and then closed.

The camp has been added to by several small log buildings. Some instructions for the safe handling of dynamite were necessary.

The No. 1 shaft follows down a vein of quartz which at the surface is 6 or 7 feet wide, but which gradually narrows until at about 60 feet depth it is replaced by narrow quartz stringers running iregularly through the trap. This state continues to the bottom, the quartz content being quite small. A fair percentage of chalcopyrite occurred near the surface, judging from the ore on the dump, but in the lower part of the workings it has nearly disappeared. This vein lies in and parallel with a dike about 100 feet wide of brecciated greenstone, in pink hornblende granite. The brecciated inclusions in the trap consist of fragments of the adjoining granite ranging in size from pebbles to immense boulders, one of which more than fills the shaft. After considerable squeezing this dike was evidently attacked by aqueous solutions which deposited the quartz and the sulphides to form the present veins and stringers. Both trap dike and quartz vein strike west 20 degrees N.E., 20 degrees S., and dip at about 65 degrees to the N.E. The disturbed area in which quartz occurs measures about 50 feet across, and all of this is considered to be copper-bearing. No development yet undertaken has been done for the purpose of proving this.

Bruce Mines

There is little of change to note with regard to this property. The same force of 20 men and sometimes more is retained keeping the workings pumped out and in shape both above and below ground for a resumption of mining on short notice. From the manager, Mr. Louis Abrahams, I learn that some intermittent drifting has progressed on the 362-foot level from No. 4 shaft and on the 382-foot level from No. 2 shaft, the intention being to connect these two, which are pointing one towards the other. No rock has, however, been hoisted. The shipments from the old dumps of tailings still continue to the smelters in the nickel-copper camps about Sudbury from which sufficient profit arises to maintain the present force at the mine.

Rock Lake Mine

All operations were supended here in July 1903. It appears that the company is short of money or at any rate tired of putting more up with little return. If more judgment had been exercised in the initial development the mine

Digitized by Google

might be in steady operation to-day. The company, however, adopted the policy of expending large sums on surface works, including a 200-ton concentrator, before ascertaining by underground development whether or not the ore body required or warranted it. If mining had even then continued steadily in advance of the stoping, instead of allowing the small amount of ore in sight to be exhausted, the property might now offer a more tempting mining venture than it is. As it is, practically nothing is known of the vein below the second of 200-foot level, for although the shaft reaches a depth of 400 feet it was sunk vertically through country rock, the vein dipping away to the southwest, and almost no drifting was done on these lower levels.

From the company's solicitor in Sault Ste. Marie, Ont., I learn that the property is now for sale, or lease under some form of working option. Before any further attempt at milling and concentration is made the ore body should be thoroughly explored and developed sufficiently in advance of the ore blocked out to insure a steady supply when stoping begins again.

Taylor Mine

This mine was not inspected last year since all work therein was suspended in August. From Mr. R. H. Taylor, one of the directors of the company, I learn that the shaft reached a depth of 112 feet with at the 50-foot level drifts 25 feet with, at the 50-foot level, drifts 25 that the company have not money enough to continue development for the present. Three men are getting out a supply of cordwood and looking after the plant.

Superior Mine

Under the same management as at last inspection mining development has progressed steadily to the date of inspection 19th October 1903, with at present a force of 24.

Shafts Nos. 1 and 4 remain unchanged. No. 2 shaft was sunk to 130 feet depth (an increase of 40 feet) and then temporarily closed. No. 3 shaft, depth 115 feet (10 feet increase). The second level crosscut was continued southwest to a length of 70 feet. No. 5 shaft, 100 feet deep (75 feet increase), with drifts from the bottom 15 feet northwest and 15 feet southeast, and a 12-foot crosscut. Work has been suspended here also. This shaft lies 450 feet northwest of No. 3 shaft, the most southeasterly working. No. 6 shaft, 1,100 feet northwest of No. 3 shaft or 650 feet northwest of No. 5 shaft, is 190 feet deep (175 feet increase), with the first level now starting at 100 feet depth.

All development is at present confined to No. 6 shaft. This has struck a very rich shoot of copper in the quartz vein, the chalcopyrite content continuing in its richness to the bottom. The sulphides in No. 5 shaft gradually diminished until at the bottom, with nothing of commercial quantity left, it was thought advisable to change the point of development to No. 6 shaft. At the latter a substantial head frame has been erected and boarded in, and a few feet north a hoist shed built from where the hoist formerly in the engine house operates the bucket in this shaft. A dry-house and a blacksmith shop were also added. The hoist runs by compressed air from the power house.

Instructions were necessary forbidding riding in the bucket and looking to the safer handling of the dynamite.

Nickel Copper Mines

For various causes only a few of the nickel-copper mines have produced any ore this year, and none of them continuously. The Victoria mine is still closed, although the same company have been developing and raising ore from another property. The smelter at Victoria has, however, run most of the year in order to clean up all remaining ore on the roast heaps. At the Copper Cliff camp mining has been until late this fall intermittent, and in progress at but two or three of the mines of the Canadian Copper Company, while certain radical changes in the methods and in mining and smelting plant might be the better put under way, and in order that the underground explorations, by diamond-drill principally, mentioned in my last report, might be completed. The mines of the Lake Superior Power Company (Gertrude and Elsie) have been closed since the failure of this and its parent corporation, the Consolidated Lake Superior Company, to meet obligations last spring.

Digitized by Google

Canadian Copper Company

As stated above, only a limited amount of ore has been raised this year up to this date of my inspection, November 1903, and most of that came from the Creighton mine, sufficing, with the reduced smelter output, to keep the roast yards well stocked. The work of exploration of the different ore bodies outlined in my last report has been carried as far as intended for the present, and as a result all of the mines that are to be worked in the near future put in a state of readiness. Also the proposed consolidation of smelting and allied operations at one point has been rapidly proceeded with. The building for the new smelter plant is nearly completed and other changes in the surface arrangements, in the railroads, roast yards, power plants, etc., have gone on concurrently, so that this winter the plant can be installed for the most part without hindrance from the weather.

The old original or east smelter has been dismantled and all plant removed. At the west smelter no alterations of account have taken place, since with the completion of the new plant this one will also be abandoned. It is being maintained, however, as formerly, and a number of the furnaces are kept in constant blast. Certain satisfactory results have been recently obtained in the course of the continued experimentation with the furnaces, according to the superintendent, these being an increase in capacity of these nominally 100-ton furnaces to about 250 tons, namely, by increasing the pressure of the cold blast (from 10 oz. to about 16 oz.) At the same time the grade of the matte is said to have risen from the former content of 30 per cent. nickel and copper to 35 per cent. The experiments with these water-jacketed furnaces in pyritic smelting using hot blast (mentioned in my last report) continued until sufficiently definite conclusions were arrived at, which, Mr. Baird states, are promising enough of ultimate success to have warranted consideration of them in the design of the new furnaces, and the arrangement of the plant for the furtherance of the pyritic process therein later on. While the stove for heating the blast worked well, its capacity was insufficient for the furnaces; and also the area or cross section of the furnace above the tuyeres was too large to effect the requisite oxidation. The boshes of the new furnaces will be designed to provide for this important detail.

The new smelter site lies in a direct line between the two former smelter plants, at about 1,600 feet southeast of the west smelter, and 3,200 feet northwest of the east one, and on a clay and rock elevation above and facing the extensive clay flat to the south and southwest. From the bottom or converter-room floor of the smelter building, the drop to the level of this flat will be about 20 feet, which is considered ample for the discharge and dumping of slag from both the converter and the blast furnaces higher up. In placing the foundations for the various structures a great deal of excavation both in the clay soil and in the solid rock was necessary and also considerable filling. Stone and brick have been used for the walls while all interior framing and fitting will be of iron and steel. A full description of the new plant will, however, be deferred until its completion. Suffice it to say, that there will be only two blast furnaces, each of 550 tons daily capacity, water-jacketed, 17 feet high and 50 by 204 inches at tuyeres, and 70 by 204 inches at the top, to use cold blast at about 40 oz. pressure; and a number of bessemer converters, to take the matte in the molten state direct from the settling wells. The standard guage track has been laid from the main or No. 3 roast yard, which lies to the north about half a mile, around to and over the ore bins at the smelter at a 5 per cent. up grade, while from the tracks in the flat below and to the southwest another branch line runs in. On the east side of the smelter building stands the new power house, to contain all accessory machinery for the smelter plant and the electric generators for power and light in all parts of the company's properties.

At the west smelter, in a small shed adjoining the power rooms, a large vertical straight-line air compressor, or blower, was set up for use in the recent tests with the hot blasts.

No. 1 roast yard contains about 12 heaps. It will continue to be used as a roast yard until the new smelter is in operation.

No. 2 roast yard has been done away with, which makes possible a more comfortable atmosphere around the town of Copper Cliff.

No. 3 roast yard, now the main one, and soon to carry on within its extensive limits all roasting operations, has increased considerably in length since last inspection. The heaps here number about 50, all of ore, in all stages of progress. The new heaps, however, are being built only about quarter the size of the former ones, each set of four now occupying the same space as one for-

Digitized by Google

merly did. A second line of tracks has been laid down the north side of the heaps. Loading and unloading of the roast heaps will be done by swinging arm derrick, to operate from the railway tracks, transferring the ore from flat car to heap and vice-versa. One such derrick is now on hand.

The same dangerous practices in the thawing and storing of the dynamite at the roast yards, and which were condemned and forbidden on my former inspection, were still in use; but assurance was given by the new superintendent that my instructions in the matter would be complied with immediately.

Ontario Smelting Works

The Ontario Smelting Works, formerly operated as a separate concern, has now become part of the property of the Canadian Copper Company, and all business connected with it is transacted at the company's head office. Mr. H. J. B. Baird, who was superintendent of this plant alone, has been appointed general superintendent of all the smelting and roasting operations of the company, Mr. P. R. Bradley succeeding him in the former position. Under him the employees number 151.

The changes in the plant noted as proposed or under way at the last inspection have been completed, and are now in operation. With the three calciners and the briquetting plant the smelting charge is furnished in such shape that one furnace is now able to treat the whole supply of low grate matte from the smelter. To increase the efficiency of the calciners, a second high stack has been built. A necessary cooling arrangement for the roasted fines from the calciners before mixing with binder and briquetting was built consisting of a horizontal revolving cylinder 3 feet in diameter by 110 feet long with spiral angle irons inside to help convey the material from end to end. The cylinder stands outdoors without cover where it keeps sufficiently cool. Additions to the power plant consist of a purifying system for the boiler water and another steam engine of 100 h.p.

Copper Cliff Mine

Mining stopped here a day or two prior to my visit. The mine had been producing ore most of the year, and it was decided to thoroughly explore the country by diamond drilling from the bottom levels of the mine in order to determine definitely the amount of ore to be looked for, and whether or not this will warrant certain important improvements in shaft and surface works for more economic ore extraction than the present conditions allow. The drilling will commence immediately.

In the early days at this mine ore containing less than about 5 per cent. nickel and copper was thrown on the dump as not worth treating, and in this way nearly 5,000 tons accumulated. With the improved methods and also because this ore and its gangue makes a good flux, the ore from this old dump is now being used in the smelters along with the roasted ore.

All mining since last inspection has been confined to the 13th and 14th levels, the latter of which is still worked from a winze from the 13th level, the shaft not yet having been projected below the latter. The following measurements of mining done are taken from the office plans and are to date of May 1904. In the 13th level southeast drift (from end of crosscut west from shaft) the stope at the face and extending up to the 12th level has been considerably enlarged from the bottom up. In the northwest drift a good deal of ore has been taken from a new overhand stope 100 feet long by 7 to 9 feet wide and 50 feet high. The winze from beneath this stope follows down this same ore body and stoping has progressed on it around the winze to a length at top (13th level floor) of 30 feet and at bottom (14th level floor) of 65 feet. Recently it has been worked deeper as an underhand stope to 35 feet below the 14th level at about the same length. Its average width is between 8 and 9 feet. The opposite or southeasterly drift on the 14th level was carried to a length of 212 feet (132 feet increase) and just beyond the shaft an overhand stope 66 feet long by 8 feet wide and 9 feet high run. From 156 feet in this drift a hole was bored by diamond drill 140 feet southeasterly piercing two lenses of ore about 20 feet apart, one 25 feet wide and the other 12 feet. Being directly beneath the stopes in the southeast ends of the 13th and 12th levels above, the new finds doubtless constitute the lower extension of the ore there worked.

These occasional new discoveries by diamond drilling of ore bodies in the lowest level of the mine and below the original main chute which pinched out on the 13th level, indicate that this latter has not actually terminated, but merely broken up into a number of divergent smaller lenses or chutes, and although none of these have approached the size of the original deposit, their continuity both in dimension and in value (nickel copper contacts) has made it well worth while mining them and

Digitized by Google

searching for more. The irregularity in the divergence of the different lenses from the base of the old deposit is such that further search by drilling in other horizontal directions and in depth may quite reasonably be expected to result in the location of still more ore.

No. 2 Mine

Before abandoning the open pit as a working place the ore mentioned at last inspection as remaining on the north wall under the overhanging portion and the arch, and all that on the south wall in front of and surrounding the old shaft for a depth south from the pit wall of about 30 feet has been broken out and raised. The old shaft, therefore, is no more and very little but rock now remains on the walls. The 3rd level or pit floor measures 100 feet east and west by 220 feet north and south.

Shaft, depth 402 feet (12 feet increase) ending in a 20-foot sump below the 5th level. The timbers for the double skip road and the ladderway with partition between have been carried from the fourth down to the fifth level. The winze sunk from the old shaft station now lies out in the open pit, covered over, the stope just below being reached from the bottom of the old shaft. From here an underhand stope has been opened out to about 40 by 60 feet plan and 30 feet deep surrounding the winze to the 4th level, down which all the ore is milled for hoisting from that point. The roof of this stope is carefully scaled as the work proceeds and preparations made for its subsequent examination when the floor has receded out of reach. Fourth level, unchanged. Fifth level; a wide and a high drift has started from the shaft station to run north under the ore body.

In addition to the wire rope signal apparatus, one for each skip road, an electric system has just been installed between the different levels, the surface and the hoist room. In the rock house the former 9 by 15-inch jaw crusher has been replaced by a 15 by 24-inch of the same type. The boiler battery contains seven units all fitted with underfeed mechanical stokers and forced draught.

No. 3 Mine

The shaft was carried down from the second to the third level shortly after my last visit; and on the completion of the timbering therein with the double skip road and ladderway, all work was suspended underground and the water allowed to rise until such time as the ore from this mine is needed. A little more drifting was done on the third or 165-foot level, but no stoping.

Creighton Mine

Except during the month of June mining has continued here steadily, but not all the time has ore been raised. Stoping in the open pit had been suspended for a short time previous to my inspection and work confined to sinking the shaft down to the next or second level, 140 feet deep (80 feet below first level). A uniform incline of 57 degrees 30 minutes is maintained from top to bottom. Just now the station chamber is being opened and the timbering of the shaft with double skip road and ladderway completed. One drift will run north under the centre of the pit, and when far enough in will be upraised to the pit floor, so that ore may be milled down and hoisted from this second as well as the first level. So far all the ore raised has been broken from the pit walls on the northeast and west sides increasing the opening to a length east and west of 110 feet and a width north and south of 60 feet. The winze from the pit floor to the west of the level station will shortly be connected with the second level drifts for good ventilation. In the rock house one of the two former 9 by 15-inch jaw crushers has been replaced by a 15 by 24-inch jaw crusher, and the grizzlies have been altered to separate the small and large sizes. Also the end bump sorting tables are being replaced by travelling belts whereon the sorting will in future be done. Adjoining the rock house to the east, a machine shop containing lathe, drill and accessories, has recently been built. Trestlework now carries the rails from the M. and N. S. Railway siding up to and above the boiler room door, so that the cars may dump the coal there. A few more dwellings have increased the extent of the little village at the mine.

In the work of defining the ore body over 5,000 feet of diamond drill holes were bored and as a result at least 3,500.000 tons of ore shown up, according to the statement of the superintendent. The ore body seems to have the form of a lenticular chimney, its greater width or strike running about east and west and its dip north at about 50 degrees along and in direct contact with a foot wall of granite. The great width of the deposit and its average nickel-copper content of about 5.5 per cent. are maintained with but small variation to the bottom of the holes at about 300 feet vertically. When the surface outcroppings outside the tested area are taken into consideration the above estimate

Digitized by Google

of ore in sight is well within the mark to this depth.

The present small development force of 35 men will, it is stated, be increased almost immediately, to about 100 men in order that the maximum output of about 600 tons of ore per day may be raised from now on.

Victoria Mine

No inspection of this mine was made, since it has remained closed down. From Mr. A. B. Hixon, the mine captain, I learn that after raising all loose ore and rock from the underground workings, and then also the pump and other machinery, the whole was for the present abandoned and the water allowed to rise. The smelter has, however, continued in operation on the ore from the roast heaps in order to clean all this up. It is expected that by the end of this year, 1903, this will have been accomplished, when operations at the smelter also will be suspended.

The ore raised since June at the North Star mine, which is about 5 miles west of Copper Cliff, has been shipped in here and all not smelted dumped along the trestle road leading up to the furnaces. These shipments will probably continue until June 1904, when the company's lease on that property expires.

In Wales where the Victoria matte was treated Dr. Mond's nickel refinery has remained idle since the close of 1902, when the Government suspended all operations pending an inquiry into the sanitary state of the process. It is likely to be started again ere long, and the resumption of mining at the Mond properties here is also said to be contemplated.

North Star Mine

A note was made in my last report of certain work done at this mine by the Mond Nickel Company in 1902, by which nearly 5,000 tons of ore were raised and shipped to the Victoria smelter. The option under which the mining was then done has been extended, according to the superintendent, until June 1904 and last spring mining commenced again. About 7,000 tons additional nickel-copper ore has since been raised and shipped by rail to the Victoria smelter and there either converted into matte or stocked.

The property consists of adjoining parts of lot 9 in the second and lot 9 in the third concession of Snider township, Algoma district, and lies about 9 miles west of Sudbury by the M and N. S. Railway from which a quarter-mile siding has been run into the mine. The owner is A. McCharles, Sudbury, the mine captain, A. B. Hixon, and the foremen Tom Tuttle and James Langden, the force numbering 39.

Mining development consists of the following: an open trench along the ore body about 150 feet in length by 5 to 20 feet (average about 15 feet) wide by 90 feet deep and inclining 70 degrees north. The foot-wall is smooth and solid but the hanging wall irregular and fractured, requiring frequent scaling. To the west of the pit and in continuation of it the surface was blasted off to a depth of 6 feet for 60 feet farther. By means of two swinging arm derricks on the north side of the opening and by buckets and a double drum steam hoist, the rock is raised to the surface and dumped immediately into the railway cars for shipment. A chain ladder runs down the footwall affording the only means of access, and one none too safe or easy, to the workings. It was recommended to commence preparations for mining hereafter at greater depth under a roof formed by the present floor of the pit, and for hoisting either by skip or by bucket on skids, since the overhanging wall is interfering with the bucket and rope in the present method.

The mining machinery consisting of 3 locomotive type boilers aggregating 150-h.p., a 5-drill Rand air compressor, and a duplex cylinder, double drum hoist of about 18-h.p. capacity was installed this past spring and the log buildings erected there for it. The camp at the junction of the siding with the main line of the railway is made up of office, bunk and boarding houses, another small dwelling and stable.

Previous to the present mining the company bored about 4,500 feet by diamond drill in some 24 holes, the deepest being about 300 feet. Most were drilled from the north side of the ore body since it dips in that direction, and in the vicinity of the present workings, where the most promising surface indications existed. Ore was found in nearly all of the holes varying in width according to the nature of these irregular deposis and at not more than from 4 to 6 feet away from the granite contact beneath the foot or south wall. This contact strikes north 60 degrees E. with dip of about 70 degrees N. 30 degrees W. A description of it from a surface examination made before the present mining had begun will be found in the 12th report of the Bureau of Mines, page 248. The norite in which the pyrrhotite and chalcopyrite lie contains scattered small inclusions of granular quartz and of granite. The ore itself averages about 35 per cent. of rock matter intermixed

Digitized by Google

as rounded fragments to small boulders. The chalcopyrite occurs for the most part along or near the walls. The values in nickel and copper aggregate about 4 per cent. on the average, the nickel being in excess of the copper.

Gertrude Mine

All work both in the mines and in the smelter, was suspended here early in the summer on account of the financial embarrassment of the operators, time and subsequent to my last inspec- the Lake Superior Power Company, one of the corporations subsidiary to the Consolidated Lake Superior Company, Sault Ste. Marie, Ont. Previous to that tion the mining work had, according to the superintendent, developed new ore bodies of considerable extent in some of the other shafts. From all of these a large tonnage of ore was being raised and the smelter kept in operation to its full capacity. All the matte so far produced is still in stock at the smelter.

Mr. Thos. Travers, superintendent, is keeping only a few watchmen at the property.

Lead Mines

In the townships of Dorion and McTavish and the surrounding area northwest of the upper end of Black bay, lake Superior, deposits of lead and zinc have been known to exist for many years. Their occurrence has been described in the reports of the Geological Survey of Canada, 1866-69 and 1872-73 and in the Report of the Royal Commission, 1890. The geological systems of this area include both Huronian and Cambrian, the latter in Dorion and the immediate westerly vicinity, made up largely of Nipigon rocks, such as grey sandstones, indurated red marls and variously colored compact limestones. Separated areas of gneiss are occasionally well developed in the above, and it is in connection with all of these rocks that the veins are found, following well defined lines of faulting. In a matrix of quartz, calcspar and barytes occur galena, blende and some copper pyrites in pockets, bands and disseminated. Some of the veins attain a width of 25 feet, although from 6 to 8 feet appears to be more near the average.

It is on one of these veins which lies off the northwest corner of Dorion township that the present development is being done by the Ontario Lead and Zinc Company, of Superior, Wis., E. C. Kennedy, president. About a year previous to October 1903, other parties carried on exploratory mining on the vein for a while. The property is reached by what was once a good road, but is now only a trail running 8 miles westerly from the C. P. Railway siding, 2 miles southwest of Wolf station.

Considerable ore was in the earlier days shipped from some of these veins to smelters in the United States and other countries, so that it does not appear unreasonable to expect that if they were now thoroughly examined again ore bodies would be found which could be profitably worked under the increased and more economical facilities of to-day. Although in large part the occurrence of the ore in the veins is somewhat pocketty, and thinly disseminated, yet enriched areas or pay chutes have been known and mined, as for instance at the Lead Hills or Enterprise mine, in McTavish.

Digitized by Google

Mines of Eastern Ontario

By Willet G. Miller

The mines embraced under this heading are situated in the region bounded to the northward by that part of the Canadian Pacific railway which stretches from the Ottawa river to the northern part of the Georgian bay.

In a paper published two years ago the writer showed that the mineral industries in this part of the Province exhibit as great a variety in kind as do those to be found in probably any other part of the world of equal extent of territory (1). Among the metals or ores produced during the past year are gold, with associated silver, copper, iron, zinc, lead and molybdenum. Pigments or paint materials are represented by white arsenic, which is also used extensively in the manufacture of plate glass, and for other purposes. Among substances used for refractory purposes, or to withstand high temperatures, is graphite or plumbago, which is also now used as a base for paints. Our mica finds its chief use as an insulating material in electrical machines. The region under review is the world's largest producer of corundum, the best abrasive or grinding and polishing material known. Two mills, with a combined capacity of over 200 tons a day, for the concentration of this mineral were built during 1903. There has been an increased output of feldspar, a mineral found in large deposits in this part of the Province and used extensively in the pottery industry, and for other purposes. The production of actinolite and other minerals, which are ground and used as roofing materials, has been carried on during the past year on about the same scale as during former years. The preparation of short fibre asbestos was begun in 1903. During the last three or four years eastern Ontario has been a producer of iron pyrites, a mineral which is used in the production of sulphuric acid, and work was done on two or three new properties of promise in 1903. A small amount of talc was raised at the only developed mine of this mineral in the Province. Talc is used chiefly in the paper industry.

Eastern Ontario possesses a number of important mineral industries which cannot properly be placed under the heading devoted to mines. The crushed stone industry is growing. There are many important quarries from which stone suitable for any building or structural purpose is obtained. The marble industry is only in its infancy although the Province possesses large deposits of material suitable for the production of this ornamental stone. The lime production scarcely seemed to equal the demand in the more southeastern districts during the past season. The clay industries are capable of large expansion. The output of peat is likely to increase now that processes for the briquetting of this fuel have been more highly perfected, by inventions during the past year. During the last twelve months important discoveries have been made in connection with petroleum and natural gas, which encourage us to hope for new sources of supply of these substances in the Province. Salt, and mineral or medicinal waters should also be considered in reviewing or enumerating the mineral industries of the Province.

(1) Journal Can. Mining Inst., Vol. 5, pp. 233-256.

Corundum Mines

Important additions have been made during the last year to the equipment of the two companies mining corundum in Renfrew and the adjoining part of Hastings county. The Canada Corundum Company which has been

Digitized by Google

operating in Raglan township for some years erected a mill which will handle two hundred tons or more of crude rock in twenty-four hours, the plant formerly in use by the company having a capacity of not much more than one-tenth of this. The Ontario Corundum Company whose works are in Carlow township formerly shipped considerable hand-picked rock to the United States for concentration. The company have now erected a modern plant which prepares the corundum for market at the mine, and has a capacity of about one and a quarter tons of concentrates per day. Reproductions of photographs of the mills of both of these companies will be found in this report.

A charter was secured during the last few months for another company, known as the Corundum Refiners, Limited. This company proposes to carry on mining and milling operations in the north-eastern part of Raglan township.

Canada Corundum Company

Quarrying and concentrating were in progress at the mine and works of this company on a scale similar to that of former years until about the end of 1903. The old mill was then dismantled, part of the machinery being added to the new plant which began operations in the first quarter of 1904.

The new mill is situated at the eastern end of the southern face of the hill on which the corundum rock is quarried. This hill affords an excellent site for a modern concentrating plant. The top of the mill is about 85 feet above the foot of the hill, thus affording an opportunity for feeding the rock from the quarries into the crushers at the top and allowing the crushed matter to pass by gravity down through the various machines to the bottom of the mill, where the corundum having been separated from the rock matter is dried and bagged for shipment, with a minimum use of elevators.

Following is a brief description of the equipment of the mill and the method of handling the rock :—

The hill on which the quarrying operations are carried on faces south and has an average slope of about 20 degrees. The dip of the rock conforms with the slope of the hill and the corundum-bearing layers,—syenite and syenite-pegmatite—outcrop at numerous points over the face of the hill. Several quarries, some of which have a depth of 20 feet or more, have been opened into these layers. Drilling is done by compressed air. After the rock has been blasted down, the large pieces are block-holed and broken up. The barren portions of the rock are sorted out, and the corundum-bearing material is carried by horse-car to the top of the mill, which is on a level with the quarries now being worked, and dumped into a bin which has a capacity of 350 tons of rock. From this bin the rock goes to a large crusher, 15 by 24 inches. The crushed material is then carried by belt conveyors to smaller crushers, one Gates, style A, and two Blake, 9 by 15 inches. From these crushers the rock goes to bins, thence by conveyor to set of rolls, of Overstrom special design. Then it goes to two sets of trommels, 11 feet in length, half going to each set. From here the undersize passes to elevators and the oversize to rolls. The crushed product is elevated to two sets of trommels, 2½, 2, 1½, 1¼, ¾, mm. From the trommels the material goes to 24 Overstrom and 4 Wilfey tables. Jigs are being added, it being thought that by their use the material can be crushed coarser and the production of a high percentage of fines will thus be avoided. After being concentrated on the jigs the corundum can be reduced to the sizes required for the market and further refined on tables or pneumatic jigs if necessary. From the Overstrom and Wilfey tables the concentrates go to bins, 50 tons capacity each, where they become partially dry by draining. They are then carried by belt conveyor to a dryer, which consists of double-deck steam tubes. After being dried the concentrates are elevated to bins in the top of the grader room. They are then run over magnetic separators, two of the Noble pattern and one invented by the company's staff, which remove the magnetite, and are then sized and graded. If the material is now not considered sufficiently pure, it is run over a set of tables or Hooper pneumatic jigs which are situated in this part of the building. From the tables the now thoroughly cleaned cencentrates go to dryers and from the Hooper jigs direct to storage bins. It may be added that these Hooper jigs are said to be able to treat about 5 tons of material, between 30 and 70 mesh, in 24 hours, but if the mesh is larger or smaller than this their capacity is less.

Steam power is used in the mill, the boiler house being a separate building. Water for the boilers and concentrating plant is obtained by a ditch which runs from a creek to the mill. The large rivers York and Madawaska, run through a wooded and sparsely-settled country, where wood for fuel is cut into logs and floated down to the mill.

A tramway, constructed during the past year, connects the mill with the York river. This tramway is less than a mile in length and affords an easy

Digitized by Google

way of conveying the corundum concentrates, which are put in bags holding 100 lbs. each, to a boat during the season of navigation, which carries them a distance of about 15 miles to Barry's Bay station on the Canada Atlantic railway.

Ontario Corundum Company

This company continued operations till the latter part of 1903 on lines followed during previous years. The corundum-bearing rock was hand-picked, and the high-grade material thus obtained was shipped to the United States for concentration. In addition to this, some of the material was roughly concentrated at the quarry. At the end of the year the new mill was completed, and high-grade corundum concentrates are now being shipped. This mill is much smaller than that of the Canada Corundum Company, but very satisfactory results are being obtained as regards the quality of material. It cannot, however, be expected that a plant of this size will turn out concentrates so cheaply as a larger one.

The mill is situated near the point where corundum was first discovered on the eastern Ontario ranges in 1896. This is on lot 14 in the fourteenth concession of the township of Carlow. The power used is steam, and water for the boilers and for washing and concentrating purposes is obtained from the small stream which runs close to the mill. After being crushed the rock goes to mullers, similar to those formerly used in North Carolina for separating the decomposed rock, chlorite and other minerals from the corundum. At the Ontario mill the fines are thus washed away, no attempt being made to save them. The coarser material after being dried and sized is concentrated on four Hooper pneumatic tables. The concentrates from these is of a high-grade.

The product of this mill is drawn to the York river, at a point a few miles up stream from the Canada Corundum Company's wharf, and shipped by boat to Barry's Bay railway station.

Feldspar Mines

Work was done during 1903 on several feldspar properties in the area in Frontenac county east of the Kingston and Pembroke railway, and adjacent to Bedford and Verona stations.

The chief of these properties, the Richardson mine, has been described in former reports of the Bureau. The spar in this deposit has made a demand for itself, owing to its good quality, among the pottery manufacturers in the United States. It has, however, not yet found its way into Great Britain, owing to the peculiar state of the trade in that country.

Additions have been made to the plant and to the shipping facilities at the mine during the last twelve months. A cableway has been installed for carrying the spar from the quarry to the lake, about half a mile distant, where the spar is loaded on scows. Thence it is taken across the lake to a short portage to another small lake, and floated by scows to the end of the branch railway line at the old Glendower iron mine. In winter the spar is teamed direct to the railway. From here it is taken by train to Kingston, about 30 miles, and thence by boat across Lake Ontario.

The spar is ground to the marketable form, an impalpable powder, in New Jersey. In addition to its use in pottery, which causes the chief demand for it, feldspar is also used as one of the constituents of the bond in wheels made of carborundum and other abrasive materials, for grinding purposes. The Richardson quarry is approximately 600 feet long, 200 feet wide, and the western face has a height of about 50 feet.

The Jenkins mine, a short distance from the Richardson, shipped about 800 tons of feldspar during the season, and had 300 tons on hand at the time of my visit in October. The spar was shipped to Trenton, N.J., and to East Liverpool, Ohio.

Another property that was worked lies between the Richardson mine and Verona station. It is known as the Worth. The owners ship the spar to Charlotte, N.Y., where they have a mill for grinding.

Mica Mines

Ontario leads the world as a producer of nickel and corundum, and she is not far behind any other country in the production of the unique mineral mica, India, Quebec and the United States being the other chief producers. The mica of India and of the United States is the muscovite variety, which is harder and not so well adapted for use as an insulator in electrical machines as the phlogopite or so-called amber mica produced in Ontario and Quebec.

Mica may be called the electrical mineral, not because it is charged with electricity, but on account of the fact that with the increase in use of electrical machines it has grown greatly in importance as a commercial material. In the old days white mica was used in stove fronts, in windows and in small quantities for other like purposes. The amber mica which was mined along with phosphate in eastern Ontario 15 years ago

Digitized by Google

or less had little commercial value, and for the most part was thrown aside with the waste rock. These old dumps have since been worked over for their mica, and mines which were opened as phosphate properties are now worked for mica only.

The phlogopite deposits of Ontario and Quebec are usually irregular in character, and mining such deposits is considered by many to be a hazardous undertaking, financially. The mica is sometimes followed down in a chimney-like form. At other times the deposit has the character of a vein with distinct walls, but while the vein material may continue to unknown depths the mica may suddenly disappear. It has also been found in one locality that at a certain depth in two or three deposits the mica becomes milky in appearance and therefore practically valueless. This milkiness is said to be due to the presence of minute crystals of rutile. The question as to why the character of the mica thus changes with depth is as yet unanswered.

Muscovite mica is a constituent of coarse granite or pegmatite dikes. The deposits of this variety of mica are therefore likely to be much more regular than those of phlogopite. Muscovite has been worked only to a small extent in Ontario. Some deposits containing a very clear white variety were opened at the foot of the Blue mountains in Methuen township some years ago. The dikes here are syenite and nepheline-syenite pegmatite. The mica does not appear to have been found in them in sufficient quantities to pay for extraction. Granite-pegmatite dikes were opened up at the head of Mazinaw lake, in the northern part of Frontenac county, some years ago but little has been done on them since.

The mica mining now in progress in eastern Ontario is practically confined to two areas, one of which is tributary to the village of Sydenham, in Frontenac county, and the other to the town of Perth, in Lanark county. One or two mines, however, are outside these areas.

Two important papers have recently be published on mica. One of these is entitled "The Mica Deposits of India" and is written by Mr. T. H. Holland of the Geological Survey of India, Calcutta. The other deals chiefly with the mica deposits of central Canada, its author being Mr. E. T. Corkill. This paper is to be published in volume VII. of the Journal of the Canadian Mining Institute.

General Electric Company

This company, whose extensive works in the United States are well-known, mine their supply of amber mica in the Provinces of Ontario and Quebec, and have a number of well developed properties in each Province. In the autumn of 1903 their mines in Quebec were closed, and operations have been concentrated during the winter on their Ontario properties, the chief of which are the Lacey mine, near the village of Sydenham, and the Hanlan mine, a few miles from the town of Perth. Heretofore the company have obtained their supply of muscovite chiefly from India. It appears to be their intention now to endeavor to procure it on this continent. With this object in view they are opening a mine in New Hampshire, and have also secured properties near the head of Mazinaw lake, in Addington county, Ontario. The company, through their energetic resident superintendent, Mr. G. W. McNaughton, are doing the most systematic mica mining that has been done in this Province.

The Lacey mine has been frequently described, and is one of the most remarkable mica deposits ever worked in any country. In the early years of its history it was an important producer of phosphate, mica then being of much less value than during later times. The mine is now equipped with an up-to-date plant. With the exception of the addition of the plant, there is nothing of special importance to report concerning the working of this mine for the past year. The company own a diamond drill and have been systematically testing the Lacey mine and a number of their other deposits during the past twelve months.

The company have also done work on other properties in the township of Loughborough. Among these is the Ashley, lot 10 in the eleventh concession, near Gould lake, and the Gosage, east half of lot 5 in the eigth concession.

In the township of North Burgess, Lanark county, the company have worked the Hanlan mine continuously. The deposit is vein-like in form with definite walls. The workings have now reached a depth of 105 feet, with a stope 150 feet in length and an average width of 8 feet. Underhand stoping is the method followed in mining.

The larger crystals of mica in this mine apear to be associated with pyroxene, calcite and phosphate, while the smaller ones occur with the latter two minerals only.

On the Burns lot which adjoins the Hanlan, work has been done in the old pits, and the deposits have been tested by the diamond drill. This lot was worked for phosphate years ago, and considerable mica has been obtained from the old dumps.

Digitized by Google

The General Electric Company have mica trimming works at Sydenham and Perth.

Kent Bros.' Properties

This firm worked two mica properties during the year, but at the time of my visit work had ceased temporarily. The work at the Stoness mine was confined to a new pit, the old workings, which reached to a depth of about 400 feet not having been unwatered.

The work of the firm was concentrated on the mine at Bob's lake, in the township of Bedford. This deposit was opened up some years ago, but at that time it is stated the quality of the mica was not considered suitable for the market. During the past year a large amount of mica has been mined on the property, the working force consisting of from 20 to 25 men. At their trimming works in Kingston the firm have employed 65 hands, and it is probable that a more suitable building will be erected for this work during the coming year.

Other Loughborough Mines

Messrs. Richardson Bros. of Kingston, purchased a mica property, lot 7 in the ninth concession, about one mile east of the Lacey mine, during the year and have had a force of men at work in the pit and in the trimming-house. This deposit is vein-like in form, the walls being very sharp and distinct. The vein matter consists of white calcite, through which is set dark crystals of mica, thus making one of the most striking deposits of the mineral that the writer has seen.

Mr. E. L. Fraleck worked an open pit about 40 feet deep on lot 8 in the tenth concession for some time. This is situated between Gould and Blue lakes. The work ceased when the winter season set in.

Work was also done by other operators on lots 8 in the eighth, and 7 in the ninth concessions.

North Burgess

In addition to the Hanlan and Burns, already mentioned, several other mica properties in this township were operated in a small way during the year.

Bedford

In this township work was begun in the autumn on a mica deposit on lot 6 in the eighth concession, thus making it necessary to credit two working properties to this township, the other being the Bob's Lake mine, mentioned above.

Actinolite and Asbestos

At the village of Actinolite, formerly Bridgewater, in Hastings county, Mr. Joseph James has continued the grinding of actinolite and other minerals in the production of roofing material which finds a market in the United States. This industry is of interest from the fact that it is the oldest continuously operated mining industry, with the exception of the production of stone and clay products, in Ontario, Mr. James having begun operations about 1884.

The International Asbestos Company, with head office in New York, have erected a small plant, which is run by water-power, at Bridgewater, and have been extracting short fibre asbestos during the year from rocks quarried in the township of Elzevir.

The character of these deposits and the chemical composition of this asbestiform mineral are discussed in the Third Report of the Bureau of Mines, pages 97 to 99. It is there shown that the Elzevir mineral is not the serpentinous variety to which the name asbestos is generally given in commerce, but that it is a fibrous variety of amphibole, with characteristics resembling very closely those of the rare variety known as antholite. It is stated that the better quality of this asbestos which is milled at Bridgewater is employed for boiler coverings, and that the finely ground material is used for wall plaster under the name asbestal.

Talc

The talc mine on the outskirts of the town of Madoc, known as the Harrison mine, has a depth of 53 feet. The shaft is 18 by 20 feet in cross section, with short drifts which prove the merchantable talc to have a width of at least 34 feet. A few carloads of the mineral were shipped during the past year to New Jersey, where it is ground and distributed to the trade.

Graphite

The working graphite mines were pretty fully described in last year's Report. Hence it is unnecessary to repeat the description here.

Work was carried on at the Black Donald, which is reached via Calabogie station, on the line of the Kingston and Pembroke railway, throughout the year. Considerable diamond drilling has been done in testing the deposits. The flooded portion of the mine mentioned in the last Report has not been unwatered, but estimates have been obtained for the building of a coffer-dam to shut off the water of the lake.

The McConnell graphite mine and works, in Lanark county, some miles

Digitized by Google

from the town of Perth, were in operation throughout the greater part of the year. At the time of my visit in November, the mine had just been shut down, but the mill was running.

Some work was done on a graphite property a few miles from Kinmount station in Victoria county.

Gold Mines

As many gold properties have been worked during the last twelve months as in former years, but owing to the unfortunate closing down of the Belmont mine in the second half of the year the output of the precious metal in this part of the year has been reduced. Considering the location, equipment, and other characteristics of the Belmont, it would seem that it should not remain idle long. If the old company do not feel in a position to go on with the work, it is to be hoped that a re-organization will take place, which will bring about the resumption of operations. Taking into account the cheap water power which has been developed by the company, the low price of labor and supplies in this district, and the fact that the mine is situated within half a day's travel from the city of Toronto, it is believed that ore can be treated as cheaply at this mine as at any mine in the world. A little work has been done on claims adjacent to the Belmont.

Three properties along the Central Ontario railway were operated during the past year. Development has been carried on almost continuously on the Cook property, adjacent to the Deloro mines, and during the first half of the year the Atlas mill and mine were worked. A cyanide plant for treating the auriferous mispickel concentrates was added to the equipment of this mill. The stock of concentrates, which had accumulated at the mill, were satisfactorily treated. It is to be regretted that the consolidation into one company of the Atlas, Deloro and adjoining properties has not been carried out. If worked under one management costs could be greatly lessened.

The Sovereign mine is situated near Malone station on the Central Ontario railway and was formerly known as the Feigle. The hill on which the ore bodies are found was worked over in a very unsystematic manner years ago. The ore which, at times, was very rich, was found in somewhat irregular deposits that appear to lie rather flat. The mine is now being operated by the Sovereign Gold Mining and Development Corporation of Ontario, Limited, whose main office is at 477 Ellicott Square, Buffalo, N.Y. The work now being done is chiefly on the extension of old pits and openings which are near the boundary line of the old Gladstone property. A boiler house was erected during the past year. There is a 10-stamp mill, put up in 1891, on the property. This mill has been kept in good repair and it is expected that it will be started up at an early date. A force of about 20 men is employed under superintendent Henry Lloyd.

Mr. W. A. Hungerford and associates have re-opened the Craig mine, which is situated a few miles from Bannockburn station, and additional plant has been put in. This property is described in the seventh Report of the Bureau of Mines. It is there said to comprise the south half of lots 4 and 5 in the third concession of the township of Tudor, 100 acres. Considerable stripping was done on the property by the original owners, and in the latter part of 1896 a company was organized to work it, which sank a shaft to a depth of 100 feet, since which time, until last year, it has lain idle.

Farther east in this district two or three gold properties have received some attention. The Star of the East property near Perry's rapids, Myer's Cave P. O., on the Mississippi river in Barrie township, Frontenac county, has had some work done on it. Samples of this auriferous ore carry quite massive iron pyrites. The Boerth mine, on lot 29 in the seventh concession of the township of Clarendon, Frontenac county, was also re-opened during the past year, and it is the intention to continue work during 1904. This mine has been described in former Reports of the Bureau, Vol. IX., p. 93, and Vol. XI., p. 203, The ore consists of auriferous quartz and mispickel. The treatment by stamp milling and cyaniding, practised at the Deloro and Atlas mines in the township of Marmora is adapted to it. There is a ten-stamp mill on the property. Two shafts have depths of about 120 and 35 feet respectively, according to former reports published by the Bureau, and there has also been considerable ore taken out of open cuts.

Copper Mines

Work was done with a few men on three or four of the Parry Sound copper properties during the past year. The shaft of the Consolidated mine on Spider lake is said to have a depth of 150 feet. It has a collar, and timber every 14 feet down but no partition. The top of the shaft is covered with a door. There is a steam hoist. No work was being done on the day of my visit.

Digitized by Google

The Ontario Colorado Mining Company, whose property lies at the outlet of Spider lake, had a shaft down to a depth of 56 feet in September. The headquarters of this company is in Detroit.

The chief work done on the Wilcox during the past year was in an open cut near the mill.

An interesting discovery of copper pyrites, which I have not had an opportunity of examining, is that in the bottom of the Coe iron mine, near Eldorado station in Hastings county. Hematite has been shipped from this mine for a number of years. This ore is said to have given place to copper pyrites in the bottom of the shaft.

Zinc and Lead Mines

The Richardson zinc mine, near Long Lake P. O., in the township of Olden, Frontenac county, has been worked with a small force of men throughout the year. Mining has been done chiefly by stoping ore from the area surrounding the upper part of the shaft, although a little sinking has been done, the shaft now having a depth of 100 feet.

The rock in which the deposit occurs is crystalline limestone of the Grenville series. The ore at times occurs in a distinct vein-like form, which breaks up into stringers and enlarges into pockets of considerable size. It consists of rather dark-colored zinc blende, through which is intermixed more or less galena. The material shipped is hand-picked at the mine to 40 per cent. or over of zinc. This usually carries from 10 to 15 per cent. of lead. The pure galena appears to carry about 20 ounces of silver to the ton. The buyers however allow nothing for the silver, and nothing for the lead unless it runs over 10 per cent. The ore is sold in Europe. Material carrying a lower percentage of the metals than that mentioned is left lying on the dump.

During the year the Hollandia lead mine, near Bannockburn station, was reopened, and equipped with a hoisting and small concentrating plant together with a small experimental furnace, with which some tons of lead were smelted. It is the intention of the owners to continue the development of this mine.

The mill contains crushing machinery together with trommels and four double compartment Hartz jigs. In the smelter are so called Missouri air furnaces which have a combined capacity of six tons of lead a day. A blast furnace is to be erected at once which will have a capacity of ten tons a day. The shaft has a depth of 61 feet.

In the first quarter of 1904 work was resumed on the Frontenac lead mine, in Loughborough township, which has lain idle for many years. A description of this mine and its plant is given in the Reports of the Geological Survey of Canada. Work is being done on a new opening, which has reached a depth of about 15 feet, and lies some distance from the old mine. The ore consists of galena and zinc blende in crystalline limestone. The deposit is similar in form to that of the Olden zinc mine. In the openings formerly worked zinc was not associated with the lead. The following analysis of an approximately average sample, taken by the writer, of some 50 tons of the ore now being mined shows the relative proportion of the metals :—

	Per cent.
Lead	18.12
Zinc	8.10
Silver	1.20 oz.
Copper	none.

Iron Mines

There are few changes to record in connection with the iron mines of the eastern part of the Province during the past year.

The chief shipper, the Radnor mine, produced about the same quantity of ore in 1903 as during the preceding year. The ore extracted here is all taken from open pits. Before being shipped it is hand sorted. A considerable amount of low grade ore is produced which is left lying on the dump. Experiments have been made with a view to concentrating this material by means of magnetic separators. The pits are in the form of a semi-circle, the ore occurring in a bed-like mass which has a very regular dip of about 35 degrees from all points on the edge of the semi-circle. It is said that diamond drill holes put down some distance in from the edge of the semi-circle have proved that the thickness of the ore and the dip remain fairly constant with depth. It was pointed out in a former report that granite dikes cut the ore in this deposit. A narrow stringer or veinlet of galena is also seen to have the same relation to the ore in one of the pits. The ore from this mine is shipped via Caldwell station, to the company's furnace at Radnor Forges, Que.

The Mineral Range Iron Mining Company, whose properties lie a few miles from L'Amable station, Hastings county, have been at work during the past year. Roads have been built, and a number of test-holes have been sunk by means of the calyx drill in the ore bodies.

Digitized by Google

The discovery of copper pyrites in the bottom of the pit of the Coe iron mine at Eldorado has already been mentioned. It would appear that a considerable change has taken place in the character of the ore in this mine.

Small amounts of iron ore have been produced from other mines in the eastern counties during the past twelve months.

This eastern district is well supplied with water powers, and it would seem that the time has arrived when some of the iron mines, now lying idle in eastern Ontario, can be profitably worked by first hand-picking the shipping ore, and subjecting the leaner material to magnetic concentration. Ores of similar character are successfully concentrated in New York state and elsewhere.

A rather full account of the distribution and character of the iron deposits in a part of eastern Ontario has been published by the Geological Survey, Ottawa. It is by Mr. E. D. Ingall, and its title is "On the Iron Ore Deposits Along the Kingston and Pembroke Railway."

Iron Pyrites

The property known as the Jarman mine, near Bannockburn station, has been worked on about the same scale during the last twelve months as it was for two or three years previously. Mr. Nichols, the chief owner of this property, has been developing a deposit of the same mineral during the last summer and autumn near the line of the Canadian Pacific railway, a few miles east of Tweed station. This deposit was opened up years ago as a gold prospect and a small plant was installed on it, but the only value of the ore is in its sulphur contents. The shaft had reached a depth of about 60 feet at the time of my visit, in the autumn. Mr. Rising has succeeded Mr. Jarman as superintendent of both these properties.

The Jarman pyrite mine has a depth (April, 1904) of 175 feet, with three levels, as follows: First at 64 feet, north drift 150 feet, south 180 feet; second at 113 feet, north drift 148 feet, south 138; third at 175 feet, north drift 105 feet, south 105. Shipments were delayed during the winter by railway blockades. The shaft on the property near Tweed has a depth of 135 feet, with some drifting.

Messrs. J. E. Harrison, C. E. Smith and others have done some work on deposits adjacent to the last mentioned one.

Other Mineral Industries

A number of mineral industries of eastern Ontario have been mentioned in the introduction. As these industries do not come under the heading of mines they cannot properly be dealt with in this place. The chief features in connection with the year's operations of most of them are dealt with in the report of the Director, where it is shown that there have been important developments in the petroleum and other industries. One of the most important group of our industries is that which uses limestone as a base. The distribution, character and uses of our limestones are described by the writer in a special paper published as Part 2 of the Thirteenth Report. Since the detailed report on peat was published last year developments of interest have taken place in this industry. The clays of the Province are growing in importance yearly and a special report on them would be of service. From the table of statistics of our annual mineral production the relative importance of the several industries will be seen.

Digitized by Google

Cobalt-Nickel Arsenides and Silver

By Willet G. Miller

Late in the autumn of 1903 the discovery of deposits of cobalt-nickel-arsenic and silver ores in the northern part of the Province was made public. Little importance seems to have been attached to the deposits by those who first saw them, it being thought that they carried a small amount of copper, the niccolite being mistaken for this metal. Mr. T. W. Gibson, the Director of the Bureau of Mines, however, when on a visit to the district in October, received specimens of the minerals, and recognized that they represented valuable ore. The writer was, accordingly, instructed to make as thorough an examination of the deposits and surrounding area as could be made at the season of the year, snow having already begun to fall in the district, before his arrival in the first week in November.

The deposits were discovered during the building of the Temiskaming and Northern Ontario railway, the Government line which is now under construction from North Bay junction, on the Canadian Pacific, to the head of Lake Temiskaming. The road-bed of this new railway runs almost over the top of the first of the deposits discovered. The ore bodies lie five miles south of Haileybury, one of the two sister villages on the Ontario side of the northern part of Lake Temiskaming. Haileybury, following the railway, lies about 106 miles north of North Bay station, which is, by the Grand Trunk railway, 227 miles north of the city of Toronto.

The Deposits Described

As the value of the deposits was learned only a short time before the surface became covered with snow, very little prospecting has been done in the surrounding area. The discoveries were made by men employed on the railway, and not by regular prospectors; hence the work has not been done as systematically as it might have been.

When I visited the locality, four veins had been located in the vicinity of a small body of water known as Long lake, which is not shown on existing maps. It lies about one-half mile south of the southern boundary of lots 8 and 9 in the first concession of the township of Bucke. The reports of other finds were not verified.

Each of the four veins visited was found to carry cobalt. Nickel also appears to be present in all of them; but as the weathering of the cobalt compounds masks, at times, the nickel colors, this latter metal was not definitely recognized in two of the deposits, although it doubtless occurs wherever the cobalt is found. Three of the veins are rich in native silver. The veins occur in unsurveyed territory, and, as the locations are as yet unnamed, we shall speak of them as Nos. 1, 2, 3 and 4. The outcrop of No. 2 lies about one-half mile southwest of No. 1, and No. 3 the same distance southwest of No. 2. The outcrop of the fourth vein is about one-half mile southeastward of No. 2.

The accompanying plan shows the locations which were surveyed since my visit, with the position of the veins.

Very little work has been done on any of the veins, and as the surface is pretty well covered with moss and soil, it is impossible to state what is their horizontal extent.

All of the veins cut through one or both of the formations known in the district as Huronian slate and breccia-conglomerate or agglomerate. The

Digitized by Google



Copper Queen mine, shaft and hoist house.

Copper Queen mine, 1903.

Digitized by Google

UNIV. OF MICH.

UNIV. OF MICH.

Digitized by Google



Shaft house, Ranson copper mine.

Baden-Powell gold mine, showing open trench.



Massey Station copper mine, 1903.

Digitized by Google

UNIV OF MICH.

UNIV OF MICH.

UNIV OF MICH.

Digitized by Google



Helen iron mine from the north.

Digitized by Google

UNIV. OF MICH.

Digitized by Google

Mineral Range Iron Mining Company. No. 3 mine.



[Mineral Range Iron Mining Company. No. 1 or Childs mine,

Digitized by Google

UNIV OF MICH.

UNIV OF MICH.

Digitized by Google



Digitized by Google

latter rock is considered to be composed of volcanic ejectamenta—grains and fragments of rocks of various kinds which have become consolidated. The slate conglomerate of older Canadian writers, Logan and Murray, is a variety. The slate along the railway cuts, in the vicinity of Long lake, occasionally contains fragments of pink granite, which are, at times, a couple of inches or more in diameter. On the faces of some of the vertical cliffs, the well-banded slate at the bottom is found to pass gradually into massive breccia-conglomerate at the top, the fragments in the latter being of varied composition and ranging in size, from small grain-like fragments to pieces of rock a foot in diameter.

The presence of dikes or sheets of some of the darker-colored eruptives was suspected, but they were not definitely recognized. In the field they would resemble rather closely some of the more massive varieties of the slate and finer-grained breccia.

The slate and agglomerate have a slight dip, and the veins referred to cut them almost vertically. The strike of veins Nos. 1 and 3 is approximately northeast and southwest; that of 4 is east and west; that of 2, northwest and southeast. Diabase and gabbro invade these fragmental rocks in some parts of the district, and appear to underlie most of the area. Whether the veins penetrate these igneous rocks beneath the slate and agglomerate has yet to be determined. About three miles to the northward of Long lake, Silurian limestone overlies the Huronian, but the limestone is undoubtedly of younger age than the veins.

Deposit No. 1

Vein No. 1 lies east of the railway track, at the edge of a swamp, about one-quarter mile north of the end of Long lake. It has been uncovered at three points, which are within a few yards of one another. As the surface of the rock is low here, and little of it is exposed, it is difficult to tell much about the form of the deposit. Medium grained, dork-colored agglomerate is found on one wall. At the widest opening the deposit has a width of over 6 feet, but the vein matter is more or less mixed with rock. The ore consists of niccolite, or the arsenide of nickel, and smaltite, the diarsenide of cobalt, together with much native silver. Niccolite contains theoretically, 43.9 per cent. of nickel and 56.1 of arsenic. Smaltite carries 28.2 per cent. of cobalt and 71.8 of arsenic. It may be added that the ore of nickel now worked in Ontario, the iron sulphide or pyrrhotite of Sudbury, in which nickel occurs not as an essential but as an accidental constituent, carries, on the average, less than 5 per cent. of the metal. On weathered surfaces the vein matter is coated with the beautiful pink decomposition product, cobalt bloom. The green nickel stain is also seen on some surfaces, but is usually masked by that of the cobalt. This nickel compound is probably the arsenate, annabergite, but nickel silicate may also be present. The secondary mineral, arsenolite, was seen on some specimens. The native silver occurs as films, or leaves and fine threads, or moss-like forms, through the nickel and cobalt minerals, especially in the niccolite, as well as in cracks in the rock and in the calcite veinstone. In weathered portions of the ore the silver shows distinctly. Some lumps of weathered ore weighing from 10 to 50 lb. carry a high percentage of silver. One sheet composed chiefly of silver, attached to a rock surface, had a thickness of nearly 0.375 inches and a diameter of about 1 foot. Professor Wm. Nicol has recognized the antimonial silver, dyscrasite, as was suspected in the field, in association with the native silver. Mr. A. G. Burrows found a sample of dyscrasite from ore body No. 1 to carry 84.08 per cent. silver with a strong qualitative reaction for antimony, none for arsenic and only traces of sulphur; which is very near the formula Ag_6Sb. Prof. Nicol also proved the presence of chloanthite, $NiAs_2$. It is associated with the niccolite, and also occurs, pretty free from cobalt, in some of the nodular masses in the calcite.

An analysis was made by Mr. Burrows of the pure chloanthite taken from a sample of the vein matter of ore-body No. 1 containing the ore in small concretions which gives the following percentages:

Nickel	23.24
Cobalt	4.11
Silver	2.78
Antimony	none
Sulphur	2.18
Arsenic	67.17
Total	99.48

The silver appears to have crystallized earlier than the niccolite, which has been deposited around it. The cobalt arsenide has formed still later than the niccolite.

Little laboratory work has yet been done on the specimens collected. Analyses of the ore, unless of samples representing a large quantity, are of little economic value, although they are of scientific interest. A sample composed

Digitized by Google

essentially of niccolite contained 5.02 oz. of silver to the ton, and nickel 26.64, cobalt 6.16, arsenic 45.64 per cent.

A small hand specimen of the rock, which occurs mixed with the ore and gives it the character of a brecciated vein, shows a sharp contact between the fine grained slate, ash rock, and a medium grained rock of similar composition.

As so little work has been done on this ore body, it is difficult to determine whether the three openings belong to one vein, or whether the ore occurs in a more irregular deposit, although the chief opening appears to be on a vein-like body. The ore is undoubtedly very rich, containing values in nickel, cobalt, silver and arsenic, and a comparatively small vein could be worked at a handsome profit.

Deposit No. 2

Deposit No. 2 is distinctly vein-like in form. The ore here is a mixture of smaltite, and probably some closely related arsenides of cobalt, such as safflorite, and niccolite.

The following table gives the results of analyses which have been made of samples from vein No. 2:

	1	2	3	4	5
Cobalt	16.8	16.7	16.76	19.80	
Nickel	7.0	6.8	6.24	4.56	21.70
Iron	6.3	7.5	.....	6.20	8.89
Arsenic	69.0	62.0	66.60	60.30	63.55
Sulphur		7.0	3.37	4.09	5.38
Insol. silica, &c.	0.9	.....	.....	2.40	0.60
Water	.....	.....	.....	2.00	.....
Totals	100.0	100.0	.....	99.35	99.92

Analyses 1 and 2 were made by Mr. O. S. James; the former represents a hand specimen from near the surface, and the latter is from a depth of about twenty feet; 3 and 4 are of average samples collected by the writer, the former from the uppermost opening and the latter from the middle or main opening, the analyst being Mr. A. G. Burrows. It was evident that sample 3 was somewhat weathered, as it showed considerable cobalt bloom. Analysis 5 is by Dr. J. Waddell. It represents a specimen collected by Prof. Nicol. This specimen was not taken, like 3 and 4, with the object of determining the average composition of the vein. Prof. Nicol states that a qualitative analysis showed the presence of small amounts of copper and lead, and the absence of antimony, bismuth and zinc.

This ore-body, unlike the other three examined, carries no silver in the parts so far uncovered. At the time of my visit three openings had been made on the vein over a length of 300 feet. The massive ore has a width of 14 inches, but vugs in the wall-rock, 2 feet or more from the vein, are filled with cobalt bloom. The rock of both walls is slate. The walls are well defined, and the vein dips almost vertically, the strike being toward the southeast. The vein lies on the hillside, a few hundred yards east of Long lake and the railway, and, unlike ore-body No. 1, is at a height of about 70 feet above the water level. Although the width of this vein is not great, the character of the ore is such as to make it promising at the present price of the metals contained in it. During the winter it is said that a shaft was sunk to a depth of 30 feet on the vein. The ore at this depth is not so massive, being intermixed with rock.

The ore has a massive appearance, and a rather dark-grey color, where not coated with cobalt bloom. When examined carefully, however, in hand specimens, especially if a polished surface be examined with a magnifying glass, it is seen to be a mixture of a gray mineral, which is chiefly smaltite, and the reddish mineral, niccolite. Smaltite and the corresponding arsenide of nickel, chloanthite, are claimed by most authors to pass into one another by the substitution of cobalt for nickel, and vice versa. Niccolite, in the analyses quoted by Dana and others, carries only a small percentage of cobalt and iron, while smaltite and the other diarsenides of cobalt frequently contain much iron and nickel. In the ore under consideration, the cobalt and nickel appear to be, for the most part, in distinct compounds. In the analysis quoted (No. 1) if we consider the 7 per cent. of nickel to exist as niccolite, and the percentages of iron and cobalt, 6.3 and 16.8, respectively, to exist as smaltite, the theoretical percentage of arsenic in the ore should be 68.47, instead of 69, as found by analysis. The percentage of niccolite by weight would be 15.94, or about one-seventh part of the whole by volume, since niccolite has a somewhat higher specific gravity than smaltite. The specimens, when examined with the magnifying glass, agree with this. The niccolite has crystallized earlier than the smaltite, which forms the ground-mass through which the niccolite grains are set.

Minute, brilliant, silver-white or tin-white crystals occur sparingly, embedded in the wall-rock and in the ore. The crystals occur

Digitized by Google

in cubes, and in combinations of this form with the pyritohedron, or rhombic dodecahedron, and octahedron. Prof. Nicol who has measured some of these on the goniometer has found them to be smaltite. The white or gray colored arsenides show a tendency to form globular or spheroidal masses, with a radiated structure. Some of these masses in the calcite have a diameter of over half an inch. The ore is at times somewhat porous, spaces being left between the globules, which are tarnished almost black on their surfaces. Where not coated with cobalt bloom, the weathered surface of the ore has a dark color, not unlike that of the wall rock. On a fresh surface, the more massive ore resembles mispickel, but is somewhat darker in color. Small grains of quartz are found sparingly in the ore. The proportion of nickel to cobalt in this case is less than that in No. 1. Tetrahedrite is found in small quantities, associated with the smalite. Mr. A. G. Burrows found a sample of this mineral to possess the following percentage composition :

Copper	36.04
Sulphur	22.86
Antimony	21.86
Zinc	8.14
Iron	9.84
Cobalt	none
Nickel	none
Lead	none
Arsenic	Not det.
Total	98.74

A deposit carrying galena and copper pyrites lies a short distance southeast of vein No. 2. Very little of its surface is uncovered and no analyses have been made of the samples collected. Grains and small masses of copper pyrites were seen in the slate, in the railway cuts, in the vicinity of deposit No. 1.

Ore Bodies 3 and 4

Ore body No. 3, so far as could be seen, is similar in character to No. 1. It lies at the southern edge of Long lake. The ore consists of native silver, smaltite and cobalt bloom, and, in all probability, niccolite also.

The location on which this deposit is situated is known as the McKinley and Darragh claim. A sample of the ore which weighed fifteen and one-quarter ozs. and showed native silver together with smaltite and considerable cobalt bloom, was found by Mr. Burrows to possess the following composition :

	Per cent.
Silver	11.10
Cobalt	15.08
Nickel	5.56
Arsenic	49.68
Sulphur	2.55
Gold	none
Iron	6.38
Insoluble	5.50
Undetermined—water, etc.	4.15
Total	100.00

Vein No. 4, although having the smallest width of the four, is, in many respects, the most interesting of the group. Here a perpendicular bare cliff of rock, 60 or 70 feet high, faces west. The vein, whose width averages not more than 8 inches, cuts this face at right angles, and has an almost vertical dip. The vein is weathered away, leaving a crack in the face of the cliff 2 feet, in some places 4 or 5 feet, in depth. When I saw it first, it had not been disturbed. Thin leaves of silver up to 2 inches in diameter, were lying on the ledges, and the decomposed vein matter was cemented together by the metal, like fungus in rotten wood. It was a vein such as one reads of in textbooks, but which is rarely seen, being so clearly defined and so rich in contents. It was found impossible to get a fresh sample of the ore with the prospecting pick, the vein being so much decomposed. The weathered specimens, however, in addition to the native silver, contained cobalt bloom; and the unaltered ore will be found, in all probability, to consist of smaltite and niccolite, in addition to the silver. It may also be added that, in one part of the vein, a distinct banded structure was noticed. Across a distance of 8 inches there were 12 or 14 layers of ore lying parallel to the walls. At the bottom of the cliff the vein cuts thin-banded, dark-gray or greenish and at times almost black slate, which has a slight dip. This slate passes gradually, so far as could be determined from the steep character of the cliff, into coarse breccia-conglomerate in the upper part. The fragments in the conglomerate consist of quartz, slate, granite and other rocks.

On some of the weathered surfaces of the native silver specimens there are small, black, spheroidal masses, with little luster. These appear to be the hydrated oxide of cobalt, heterogenite. Some of the deposits on the silver resemble asbolite. The carbonates of cobalt and nickel are also probably present. Antimony and sulphur have been detected in the ore of veins 1 and 2. Detailed analyses are required to determine the character of some of the silver-bearing minerals.

Digitized by Google

which are present in small amounts. Bismuth, copper and manganese, in an association of ores such as we have in these deposits, are to be looked for.

A sample of the much weathered ore from vein No. 4, which appeared to contain less silver than most of the samples collected was found by Mr. Burrows to have the following percentage composition: Silver 16.60, cobalt 3.91, nickel 1.42, arsenic 19.79, gold none. This ore is brownish to yellowish in color, and has an earthy appearance. Its color is due to the presence of several decomposition products, the oxides of iron, cobalt and nickel. A small amount of cobalt bloom is present.

Three other weathered samples in which native silver was distinctly visible possessed the following percentage composition:

	1.	2.	3.
Silver	23.97	27.00	26.24
Cobalt	2.85	2.80	8.34
Nickel	0.97	1.00	5.26
Arsenic	18.30	19.30	13.28

The percentage of silver in 3 represents a value of $5,237.60 a ton.

A Unique Occurrence

These recently-discovered ore bodies lie about 90 miles northeast of the town of Sudbury, in the vicinity of which are situated the well-known nickel mines. The ore of the latter is of a different character from that of the Haileybury deposits, being essentially pyrrhotite and copper pyrites. The rock associated with the Sudbury deposits, which are not veins, but deposits of irregular shape, is norite, a variety of gabbro; the ore itself is claimed by most writers to be essentially of igneous origin. It is thus seen that there is little in common between the ore bodies of the two localities, with the exception that nickel is a characteristic metal of each. The Sudbury pyrrhotites carry a small percentage of cobalt in addition to nickel. The minerals niccolite, danaite, and other arsenical compounds, have been found in some of the Sudbury deposits, but only in small quantities.

It is of interest to note that a deposit of sulpharsenide of iron, mispickel, was discovered a few years ago near Net lake, which lies about 25 miles to the southwestward of the Haileybury deposits. This mispickel, however, does not carry appreciable amounts of nickel, cobalt or silver.

On the Quebec side of lake Temiskaming, about nine miles to the northeastward of the Haileybury deposits, an ore body known as the Wright silver mine was discovered many years ago by some of the early explorers of that region. During recent years this deposit has been worked for its lead and silver contents. The deposit is unique in character, the wall-rock being Huronian breccia-conglomerate, the fragments in which are, at times, cemented together by argentiferous galena. The silver contents of the pure galena in this deposit vary from 18 to 24 ounces to the ton of 2,000 lbs., but the intermixture of rock matter considerably lessens these results. Iron pyrites has been found intimately associated with the galena and is doubtless the source of the trace of gold usually present in the ore (1).

Silver-bearing galena with copper pyrites is also found on an island in Cross lake which lies southeast of lake Temagami, and at Lady Evelyn lake. "Some of the most important of such veins noticed, occur on the 'Matawapiki,' as the last stretch of Lady Evelyn lake before reaching the Montreal river, is called" (2). These quartz veins are found on both sides of the lake here and occur at the contact of the intrusive diabase and the banded slate, and in the latter. The minerals are galena, copper pyrites, iron pyrites and zinc blende.

An analysis of a sample of the ore from Cross Lake, which consists of galena and copper pyrites in calcite, shows it to possess the following values per ton: gold $2.00, silver $9.20, copper $4.20, lead $4.00, or a total of $19.40 (3).

The only area in Ontario, or central Canada, which has hitherto been found to contain deposits of rich silver ore is that which lies near the head of lake Superior, nearly 500 miles from Haileybury. While native silver has been found in considerable quantity in these deposits, the sulphide, argentite, is the more characteristic ore. The Silver Islet mine, near Port Arthur, is well known to those interested in the metal industry. Deposits of somewhat similar character, which occur on the mainland, have also been frequently described. The report on "Mines and Mining on Lake Superior," by Mr. E. D. Ingall, of the Canadian Geological Survey, gives an account of this silver-bearing area.

The silver veins in the vicinity of Port Arthur, like those of Haileybury, cut through slate, but the Port Arthur slates are held to be of later age—Animikie—than those of Haileybury, which are what is called, in a general way, Huronian. Much work remains to be done on our metamorphic and igneous

(1) Report Geol. Survey, 1897, p. 148 I.
(2) Ibid, p. 141 I.
(3) Tenth Report, Bur. Mines, p. 180.

Digitized by Google

rocks before the various formations can be correctely correlated. Both the Port Arthur and Haileybury slates have been cut through by diabase and related rocks.

The Slate-Breccia

The rich silver-bearing veins in the Port Arthur district, like those of Haileybury, occur for the most part as vertical fissures, which cut fragmental rocks whose beds lie in a nearly horizontal position. Although the fragmental material of which the silver-bearing rocks are composed is not similar in the two district, the writer is inclined to believe that the ash rocks and agglomerates of Haileybury are of almost, if not exactly, the same age as the Animikie slates of the head of lake Superior.

In this paper the term slate has been used in referring to the fine-grained and delicately laminated rocks through which the Haileybury veins cut. This term properly refers to argillites and should not be used except as a convenient field term for all the finely laminated rocks in the area. Thin sections when examined under the miscroscope show that the specimens so far investigated represent ash rocks. Coarser varieties, in which the fragments possess a size similar to that of the grains of minerals in a medium-grained igneous rock, are found to be made up of pieces of orthoclase, plagioclase, trachytic material, chlorite and calcite, which is an infiltration product. The layers of some of the slate-like rocks which lie at the bottom of the cliffs have not been examined in the laboratory.

A correlation of these Haileybury rocks with the slates and tuffs of the area which was marked as being doubtfully Cambrian on Dr. Robert Bell's map of the Sudbury district would be interesting.

Dr. A. E. Barlow has given a very interesting account (Geol. Surv. Can., Vol. X., p. 194 I), of the contact between a granite and the overlying fragmental rocks in the vicinity of Baie des Peres, on the opposite side of lake Temiskaming from Haileybury. He has shown that this is, so far as has been observed, a unique occurrence—some of the Huronian fragmental material overlying the granite having been derived from the weathering of this rock in situ. The present writer some years ago recorded the occurrence of a small outlier of Grenville limestone in the vicinity of lake Keepawa, east of lake Temiskaming. This limestone and the associated garnetiferous schist have been much disturbed by an intrusion of granite apparently similar to that of lake Temiskaming. It would therefore appear that the Baie des Peres fragmental rocks which rest on the eroded surface of the granite are very much younger than the Grenville series of the indefinitely so-called Laurentian. The question then arises—are we at present certain that th Baie des Peres fragmental rocks are older than the Animikie?

It is known that rocks similar in character to those of Haileybury lie to the northward. In the writer's report on "Lake Temiskaming to the Height of Land" published in Vol. XI. of the Report of the Bureau of Mines, 1902, the following statements are made concerning the slate and breccia-conglomerate or agglomerate in the area examined. P. 217: "Slate is also seen at the outlet of the lake, passing into a conglomerate a short distance down the river. The latter rock appears to overlie the former." P. 219, "On the east shore near this point, the rock has a bedded appearance, the layers being ten or twelve inches thick, slate forming the lower layers with an impure quartzite above. Along this lake these rocks dip at a low angle, 15 degrees, to the southwest. The quartzite, or graywacke carrying quartz grains, lies above the slate, and the conglomerate appears to overlie the quartzite. If this is their order, they have either been inverted or they possess a different relationship from that given for similar rocks by the Geological Survey in the report on the lake Temiskaming map sheet. The question as to their relationship is of economic interest on account of the occurrence of iron ores." P. 220, "The slate along the shore here has a dip of about 7 degrees to the eastward or towards the island just mentioned. A hill up the shore to the northward was found to be composed of conglomerate containing fragments of slate, quartz, gray granite, and a porphyritic gray granite, together with a few red jaspar pebbles associated with hematite. The conglomerate appears to overlie the slate and the whole dips towards the islands, which also contain conglomerate." The word "appears" was used in these sentences on account of it having been held by other writers in the field to the south that the conglomerates or agglomerates were the basal rocks. The present writer having made a hasty examination of the area did not wish to state positively that the rocks, as he saw them, occupied their original relative position, although they appeared little disturbed. Some of the agglomerate is very loosely cemented together.

Digitized by Google

Cobalt Ores Elsewhere

Although cobalt and nickel minerals have not been found in quantity near Port Arthur, it is interesting to know that the ore of the Silver Islet and some of the other mines was at times coated with cobalt bloom. Niccolite and other minerals carrying cobalt and nickel occur in small amounts in some of these deposits. The only deposits in which quicksilver has been found in Ontario is that of Silver Islet, where chloride of silver is also said to occur as a decomposition product.

Small quantities of cobalt, nickel and silver-bearing minerals occur on Michipicoton island, lake Superior. Arsenical compounds of the first two metals have been found at several other localities in Ontario and at Calumet island, Quebec. Cobalt bloom occurs sparingly in some of the magnetite deposits near the town of Madoc, in eastern Ontario. It will be noticed that the association of minerals in these Haileybury veins is not unlike that found in some well-known deposits of Germany and other countries. Since these German ore bodies have been worked for many years methods for extracting the metals, cobalt and nickel, from ores of this kind are well proved. Hence little experimenting will have to be done on the Haileybury minerals.

Although little prospecting has been done in the vicinity of the Haileybury deposits, it would appear from the discoveries already made that ore-bodies occur there which can be worked profitably for the metals which have been mentioned. It is scarcely probable that nickel will be found in sufficient quantity in these deposits to interfere materially with the lower grade, but large, deposits of the Sudbury area.

Slate and agglomerate, similar in character to those of Long lake, cover a very large and as yet little prospected area in northern Ontario. The rocks along the government railway a considerable distance south of the deposits described in this paper, contain indications of the presence of cobalt ore.

It is stated in The Mineral Industry that "cobalt, which is used in the arts, chiefly in the form of oxide, is obtained from New Caledonia, Australia and Germany, and smelted in France, Germany and Great Britain, the Messrs. Vivian, of Swansea, being the chief buyers in the last-named country." Cobalt oxide is produced at one plant in the United States. It is said that a refinery is being erected at Mine La Motte, Missouri, for the extraction of cobalt and nickel, which are obtained as by-products in lead smelting.

The ore of New Caledonia, which is the world's largest producer, shipping about 3,000 tons yearly, is cobaltiferous wad, containing 25 to 30 per cent. manganese and 2 to 8 per cent. cobalt oxide (CoO). The ore of New South Wales is similar in character. In both countries the cobalt ore is a decomposition product, and occurs in irregular deposits.

"At the end of 1901 and the beginning of 1902 the price of cobalt ore, containing 4 per cent. cobalt, in New Caledonia, was forced up higher than circumstances warranted. For a long time the price in Europe did not justify more than 90 fr. per ton being paid for this quality of ore at the mines, but the price steadily rose to 330 fr. (about $66) until recently, since when it has receded." The black oxide of cobalt sells at from $2.26 to $2.30 per lb., or the metallic cobalt in the compound brings about $3 per lb. It would thus seem that the refiners should make a much larger profit than the miners. The market will not, however, stand a greatly increased production without the price materially decreasing. It is claimed that there has been a combination among refiners to keep up the prices of cobalt products.

A paper recently published, "Cobalt Mining in New Caledonia," by Mr. Colvocoresses, Eng. and Min. Journal, Nov. 28th, 1903, gives a later account of the industry in that country. It is shown that in 1902 the output was 7,512 tons, or nearly double that of any preceding year, the statistics being given from 1889. The prices have kept up better than it was expected they would two years ago, being in September 1903, 350 fr. (about $70) for 5 per cent. ore, with a rise of 12 fr. per ton for each 0.1 per cent. above.

Digitized by Google

The Abitibi Region

By George F. Kay

In compliance with instructions rereceived from Mr. T. W. Gibson, Director of the Bureau of Mines, an examination was made of the region southwest of Lake Abitibi, which is situated on the boundary between the Provinces of Ontario and Quebec. Part of the area examined was surveyed into townships during the past summer by the Department of Crown Lands.

The object of the expedition was to make a complete report on all points of interest regarding the economic geology and mineralogy of the area. Mr. T. D. Jarvis, B.S.A., of the Ontario Agricultural College, Guelph, accompanied the party during the first five weeks. He directed his attention to the soil and flora, and the result of his work will be found as an appendix to this report.

The party consisted of Mr. T. D. Jarvis, Guelph; H. Davis, King; George McGregor, Sudbury; Joe Blackburn, Copper Cliff, and myself. We took train from Sudbury to Metagama station on the Canadian Pacific Railway. From there, we followed the Hudson Bay Company's route to Fort Mattagami, and thence down the Mattagami river to a portage about three miles below where Niven's 1898 east and west line crosses the river. Here the work began, which was carried on continuously for more than two months. The return trip was made by way of the Blanche route to New Liskeard at the head of Lake Temiskaming.

The work was carried on by following canoe routes and by inland trips made from these routes. This is the only method practicable in a region covered with forest and without roads of any kind.

The routes followed within the area dealt with in this report, and from which inland trips were made, may be summarized as follows :

1 : Eastward from Mattagami river to Night Hawk and Frederick House lakes.

2 : From Frederick House lake, by way of Moose lake and Driftwood river, to Abitibi river.

3 : Up the Black river to the first falls.

4 : From the first falls on the Black river to Fort Matachewan on the Montreal river.

5 : From Wataybeeg lake down the Wataybeeg river to the Black river.

6 : Up the Black river from the first falls to where it is crossed by Speight's north and south line of 1902.

Several of these routes have already been described in the reports of the Bureau of Mines (1) and of the Geological Survey (2).

But in order that the points from which the inland trips were made may be more clearly indicated, and in order that a more connected report of the whole area may be presented, it has been thought advisable, in certain cases, to again describe features dealt with by the former explorers in this region. The routes from the Black river to Fort Matachewan and from Wataybeeg lake to the Black river are here described for the first time.

This report will de divided in three parts, as follows :

Part I. : The features of each part of the area examined.

Part II. : The features of the area as a whole, its topography, its resources, etc.

Part III. : The rocks of the area, their megascopic and microscopic characters.

(1) Bur. Mines, Vol. 8, pp. 175-180; do. Vol. 9, p. 129; do. Vol. 12, pp. 185-187; Report of Survey and Exploration of Northern Ontario, 1900, pp. 27-29.

(2) Geol. Sur. Can. Sum. Rep. 1901, pp. 121 122.

Digitized by Google

Part I: Physical Features

Mattagami to Night Hawk

The portage, which leaves the Mattagami river about three miles below the crossing of Niven's east and west line of 1898, indicated by its condition at the time of our visit, that it was rarely used. It runs eastward, and is about one mile twenty chains in length. The first eighty chains is wooded with spruce, balsam, birch and poplar; the soil is a gravelly sand; and the last twenty chains passes over a jackpine plain. A low ridge crosses the portage about forty chains from the river; it consists of greyish green chloritic schist. Along this ridge a short distance to the south of the trail is a small segregation of glassy quartz. The portage ends at a small lake surrounded by jackpine and spruce. Its shores are low, its water is clear, and its bottom very soft.

Delbert and Jarvis Lakes

A portage of ten chains over a gravel ridge reaches Delbert lake, which is eighty chains long, and has an average width of about twenty chains. Near the north shore about forty chains from the portage is an island of rather soft, chloritic, somewhat schistose rock, with small segregations of quartz. Similar rock is exposed along the north and south shores. The strike of the schist, where best shown, is nearly east and west, the dip being nearly vertical.

A trip was made northward from a small bay to the north of the west point of the island. The first twenty chains reveals several outcrops of schistose rock; then follows low ground covered with small spruce for one hundred and twenty chains; the succeeding sixty chains are marshy, but low ridges of basic eruptive rock are here and there exposed. No soil of value was seen.

The portage from Delbert lake is nearly straight south of the island. It is twenty chains in length and leads to Jarvis lake, which stands at a somewhat higher level than Delbert lake. Between the two lakes is a ridge of metamorphosed basic rock, carrying iron pyrites. Jarvis lake is about sixty chains long and averages about twenty chains in width. It is divided into two distinct parts by a constriction. Several outcrops of rock, resembling those of Delbert lake, are on the southern shore, but their more distinct schistosity suggests that they have been subjected to greater dynamic action. The outlet of the lake is at its eastern end; it is small and unnavigable. The portage is on the southern shore about fifteen chains from the outlet.

A trip was made southward from where the portage leaves Jarvis lake. The distance to Niven's east and west line is about two miles. The area passed over was mainly rocky, the rocks being greenstones and schists, in places carrying iron pyrites. Some fairly good poplar, spruce, birch and cedar were seen.

Niven's line was struck near IX. M. 45 chains. This line was followed eastward to VIII. M. 50 chains. Near IX. M. 35 chains is an outcrop of green schist with a strike N. 60 degrees W., and a dip of 60 degrees. The timber along the line consists of black spruce, cedar and poplar. Just to the east of VIII. M. 50 chains is an outcrop of fine grained greenish eruptive.

We went northward from VIII. M. 50 chains until we crossed the portage leading from Jarvis lake; the first twenty chains consists of clay soil covered with good spruce and balsam; this is followed by rocky undulating country, the rocks being green schists. At a distance of sixty chains from the line, a creek flowing east of south was crossed. About ten chains beyond the creek is an outcrop of light-colored altered acid porphyry. From here to where the trail was intercepted the country is quite level, parts being low and covered with dead tamarac.

The portage from Jarvis lake is about one mile sixty chains in length and leads to a fairly large stream. In the first three hundred feet from the lake there is a rise of about twenty-five feet over a ridge of chloritic schist; the next thirty chains reveals no rock but a somewhat level area covered with spruce and poplar; this is followed by wet ground well wooded with cedar and spruce for about fifteen chains; then the surface rises and exposures of decomposed eruptive rocks are to be seen, some of which contain small segregations of glassy quartz. The rock exposures are more or less continuous for about fifteen chains, when low rather swampy ground was again entered. This continued to the end of the portage.

The stream where reached is about eight feet wide and sluggish. This sluggishness is due to the fact that beaver are at present operating here, and by their dams are raising the water. Many evidences of moose were seen along this stream. The creek runs east of north and was followed for about one mile

Digitized by Google

and twenty chains, when a portage was taken to the east. The creek is very crooked and has a marshy area on either side. The banks are of clay. The portage is rather difficult to locate; it leaves the creek from a point of spruce on the eastern side. It is about one mile sixty chains in length and ends at Porcupine lake. This trail passes over a low area for about twenty chains, when it crosses a large outcrop of acid volcanic tuff; beyond, the trail passes over a low area, in places wet and covered with spruce, balsam and tamarac. About one mile ten chains from the creek, a stream fifteen feet wide and two feet deep was crossed, flowing S. 50 degrees E. The remaining part of the portage is low with no rock exposures.

Porcupine lake and its surroundings have been described by Dr. Parks (3), therefore a detailed description need not be given here. The rocks are confined to the southern and eastern shores, the north shore being low. The outcrops are considerably decomposed, and are of a basic type; the presence of serpentine suggests that the original rock was olivine-bearing. On a rocky island in the lake, distinct glacial striae were seen with a direction S. 30 degrees W. This lake abounds with pickerel and pike.

Whitney Township

An inland trip of four miles was made eastward into the township of Whitney, from a point on the shore of the lake about twenty chains south of the outlet. The first twenty chains from the lake are fairly level and covered with good spruce; at a distance of about forty chains is a low swampy area with cedar twelve inches in diameter and forty feet in height, and with spruce twelve inches in diameter; the next sixty chains is fairly level, the soil being clay, the timber spruce, balsam, birch and poplar. At a distance of about one mile twenty chains from the lake, a low outcrop of quartzose mica schist was seen. Beyond this, the soil becomes gravel and sand, until at about one mile forty-five chains a muskeg was entered, which continues until two miles sixty chains from the lake is reached; the muskeg extends some distance to the north and south and is covered with small spruce. Beyond the muskeg the country becomes level and the soil clay. At about three miles ten chains, a creek ten feet wide and three feet deep was crossed. It flows in a northerly direction, and its banks are of clay. Farther east, the region is level, consists of clay soil, and is timbered with small spruce.

(3) Bur. Mines, Vol. 8, p. 176.

The Porcupine River

The outlet of Porcupine lake is in the northeast corner. Where it leaves the lake, it is shallow and about fifteen feet wide. For half a mile it flows through an open marsh, beyond which, it widens to about fifty feet. At two miles down, a small stream enters from the southeast. A portage route leaves this creek for Night Hawk lake (4). About four miles beyond this small creek, there is a shallow rapid over boulders. From the creek to the rapid the shores are low; the timber is chiefly spruce and poplar.

For one mile twenty chains west from the rapid, the region is level, the soil clay, and the timber chiefly spruce, balsam and poplar. A large creek flowing nearly north was crossed at about one mile thirty chains. Beyond this creek, the region becomes more swampy; occasional outcrops of schistose rock protrude. At a distance of two miles forty chains from the river, the region is rather low and level and is covered with small spruce.

A trip was made eastward from the Porcupine river about two miles below the small rapids. While we were making this trip, the canoemen followed the river with canoes and supplies, and we joined them where Niven's meridian line crosses the river. Our trip was straight east, and at the end of about three miles, we again struck the Porcupine, here flowing southward. The area crossed lies in the township of Hoyle. At a distance of about twenty chains east, from our starting point, a creek fifteen feet wide and flowing to the Porcupine was crossed; it has a swift current and dark water. At a distance of one mile thirty chains, another creek, which flows southward, was crossed. The area lying within this large bend of the Porcupine is fairly level and consists of clay soil. The Porcupine was followed from the crossing of Niven's meridian line to Night Hawk lake. Its course is rather crooked, and in most places its shores are low and timbered with fairly large spruce. There are two small rapids which can be run. The rocks observed along this part of the river were principally schists, but on a small island in the river near Night Hawk lake is an outcrop of slate with a strike N 75 degrees E.

Night Hawk lake has been described by Parks (5) and Burwash (6). Only the notes which were taken while going to points from which inland trips were made will be added here.

(4) Bur. Mines, Vol. 8, p. 176.
(5) Bur. Mines, Vol. 8, pp. 175-176.
(6) Bur. Mines, Vol. 6, p. 180.

Digitized by Google

A stream enters the lake from a large marshy area on the west shore about three miles south of the mouth of the Porcupine. This stream was ascended for about a mile, and then a trip was made westward to Niven's meridian line. The creek, for some distance before it empties into the lake, winds through a marshy area. Submerged camping grounds and drowned trees over areas of many acres indicated that the season had been one of more than ordinary rainfall. From the creek westward to Niven's line the area is level and the soil sandy. Outcrops of coarse-grained hornblende-mica dolerite (7), and olivene dolerite were observed on a point extending into the lake south of the mouth of the creek mentioned above.

The Redstone river, which enters the lake about seven miles south of the mouth of the Porcupine, was next ascended. The first rapid is just above where the river was first crossed by Niven's meridian line, namely, near M. 117. The rapid is due to a ridge of dark green, fine-grained, aphanitic rock. Below the rapid, the river has low, marshy shores, its average width being about one hundred feet.

From this first rapid a trip was made eastward to the shore of Night Hawk lake. The distance is about two miles sixty chains. The first forty chains from the river is undulating and timbered with good spruce and birch. Beyond, the region gets lower, and in many places marshy. Near the lake the surface rises somewhat and the timber increases in size; no rock was seen.

A trip west from the rapids struck the Redstone again in about one mile. The soil is in places clay, and in places sand. Just above where the river was struck, is a long shallow rapid over boulders. Below, the river is crooked and filled in many places with driftwood. The Redstone is not used by the Indians above the first rapid. About half a mile above this first rapid, is an exposure of greenish aphanitic rock. Just above this outcrop, a stream thirty feet wide enters from the left. The Indians say that the Redstone takes its rise in a large muskeg several miles to the west.

Indians were camped on a small island in Night Hawk lake, a short distance out from the mouth of the Redstone. We camped on an island about one mile south of this, and there found that potatoes, squashes and onions, which had been planted by the Indians, were in a thriving condition. The soil of the island consists of fine stratified clay, underlain by soft greenish altered eruptives. Where the rocks are not covered they exhibit exceedingly well the gouges, grooves and striations produced by the Glacial ice. The striae on the northwest point of the island have a direction S. 10 degrees E. On the west side, the laminae of the clay are horizontal and contain numerous well-formed yellowish concretions. Some of them show distinctly that they have had stems or other organic material as nuclei, and that growth has taken place by the accretion of layer upon layer. Some features in regard to concretions are not yet fully understood, although considerable study has been given to them (8).

McLeod's point lies to the south of the island. Here huts have been erected on a bluff of till, which rises to a height of nearly thirty feet above the level of the lake. Nearly all the boulders in the till are of Laurentian and Huronian aspect. After some search a Devonian fossil was discovered. This had, no doubt, been carried down in the drift, during the Glacial period, from the Devonian to the north. A short distance eastward along the shore is a low area, beyond which are cliffs of stratified clay, which rise from twenty to twenty-five feet above the level of the lake. The stratification extends to the very top. The cliff has an almost vertical face and extends along the shore for about three hundred and sixty feet. It has a fairly steep slope at both the east and the west end. At the west end, facing the lake, the laminae are crumpled and contorted. The contortions are more marked near the top of the cliff than at the bottom, and, when followed eastward along the face of the cliff, soon die out horizontally. They are probably due to a readjustment of the beds, and not to alternate freezing and thawing, or to ice push, although these factors may have contributed to some extent.

Night Hawk River

The Night Hawk river was next ascended for about six miles, and then a trip was made to the westward. For the first twenty chains of the trip from the river, the soil is clay; the succeeding sixty chains is rather low and swampy, the timber being spruce and balsam of fair size. This is followed for forty chains by a fairly level gravel

(7) Dolerite is used in this report to include the diabases and certain rocks of similar composition, but which do not show the ophitic texture. See Part III.

(8) Amer. Naturalist, Sept. 1884; Concretions from the Champlain Clays, by J. M. Arms Sheldon.

Digitized by Google

area; beyond this, for forty chains, is considerable swamp and open marsh. Between the second and third miles from the river, is a ridge of fine-grained chloritic rock carrying iron pyrites. This ridge is about sitxy-five feet above the surrounding marshy area, and from its summit the country northward was seen to be low and somewhat marshy as far as Night Hawk lake. Westward from the ridge, low ground was again soon reached. From here on, the surface is in many places wet and covered with small spruce. At a distance of about three miles forty chains from the river, a wide marshy creek was encountered, and as the country for some distance ahead had the appearance of being wet and marshy, we considered it advisable to proceed no farther.

Frederick House Lake

Having returned to the river, we went back to Night Hawk lake and thence to Frederick House lake. The part of Night Hawk lake, passed through in going to the outlet, contains many islands, some of which consist of bare rock and some of stratified clay. The shore at several places presents high cliff-like exposures of distinctly laminated clays. The widths of the laminae vary; some are less than one inch, some more than eight inches. These clays also contain exceedingly well-formed concretions.

Frederick House river, which unites Night Hawk and Frederick House lakes, has a slow current and is about two hundred and fifty feet in width. It flows through a low swampy area, and no outcrops of rock were seen between the two lakes.

From a bend in the river about two miles south of Frederick House lake, a trip was made westward into the township of Matheson. The first half mile from the river is level, the soil being in part clay and in part gravel; this is followed, for about one mile, by swampy ground, when a stream fifteen feet wide and flowing S. 40 degrees W. was crossed. Beyond the creek, the region is low and marshy, the soil being chiefly sand and gravel, and the timber spruce, birch and poplar.

Very little time was spent on Frederick House lake, as Dr. Parks had already described it (9). A small, rocky island in the southeastern part of the lake was examined; the rock is fine-grained and aphanitic, its surface showing flowage structure. This is no doubt a surface volcanic. Distinct glacial striae on this island have a direction S. 5 degrees E.

A trip was made into Dundonald township from the head of a large bay, which lies northeast of the rocky island mentioned above. The first mile and forty chains is a rolling area of clay soil, clothed with poplar, birch and spruce; the succeeding sixty chains passes over a jackpine plain, interrupted here and there by narrow stretches of swamp. At a distance of two miles forty chains from the lake is a low outcrop of silicious, fine-grained rock, very similar to that on the rocky island of Frederick House lake. Three miles from the lake the region is dry and level, the soil sand and gravel. The same general features are presented for some distance farther to the east.

Frederick House to Abitibi

In the south end of Frederick House lake is a constriction, which leads into a narrow lake extending south for about two miles. This lake has clear water and is surrounded by small spruce and poplar. Near the constriction a Hudson Bay Company post once existed. Its factor, it is said, having been held in disfavor by the Indians, was cruelly murdered by them. A portage leads from a small creek in the southeast corner of the narrow lake to a small lake with low shores covered with spruce and poplar. This lake abounds with large pike.

From the south shore of the small lake a trip was made westward to Frederick House river. The first mile is rolling, the soil in places is clay and in places sand; the timber is poplar, birch, spruce and in places cedar of fair size. From the rolling area there is a rather sudden descent to a spruce swamp, which extends to the river.

Township of German

A trip was also made eastward from the south end of the small lake into the township of German. At a distance of less than twenty chains is a small kettle lake, and in the course of the next mile three more lakes of similar origin were seen. These lakes are surrounded by steep banks of gravel and contain most beautifully clear water. The area passed over in the first two miles was a rather open jackpine plain; in places large scattering white pine were seen and some poplar and birch. Between the second and third miles, the surface is rather low, in places swampy. Near the third mile, clay soil begins and

(9) Bur. Mines, Vol. 8, p. 177.

Digitized by Google

continues for more than forty chains. Between the third and fourth mile, a high tree was climbed and the following notes taken :—

For fully five miles to the eastward, the region is fairly level and appears to be covered with spruce, poplar and tamarac. To the north and south as far as the eye can reach, the region is of low relief and of rather monotonous appearance.

Having returned to camp, we followed the route in a southeasterly direction over an open jackpine plain to a small lake, from which a portage of about two miles leads to another small lake. From the north shore of this lake, a trip was made westward. For twenty chains there is a jackpine plain, then follows a rolling area covered chiefly with spruce and poplar. At about sixty chains, a shallow marshy creek, from a small lake to the north, was crossed. Westward from the creek for about ten chains, the region is high; the soil is clay, and the timber spruce, birch and poplar. Still farther west, the region is fairly level, in places marshy.

Moose Lake

Continuing our course from the small lake, we crossed a portage about two miles twenty chains long. It runs somewhat south of east and ends in a small pond, from which a very winding stream was followed to Moose lake. The first forty chains of the portage is undulating, the soil being clay, the timber spruce and poplar of fairly large size; the next sixty chains passes over a fairly level jackpine plain; then comes a wet and marshy area, over which portaging is difficult. It is a typical spruce swamp and continues to the end of the portage.

The creek which passes out of the southeast corner of the small marshy pond is very crooked and has a width of about twenty feet, except where nearly choked by alders and other shrubs. The area bordering this stream is low and marshy and clothed chiefly with spruce. The soil of the banks is clay. Paddling steadily, it took about two hours and thirty minutes to go from the small pond to Moose lake. For some distance before the lake is reached, the stream passes through a wide marsh.

Moose lake is about two miles long and one mile wide and has low shores. (10). It is everywhere shallow and presents a dreary, desolate appearance. At the time of our visit scores of ducks were seen in the vicinity.

(10) Bur. Mines, Vol. 8, p. 179.

Driftwood River

Driftwood river leaves Moose lake from the north end. Here it is about fifty feet wide and quite deep. The first ten miles of the river is free from obstruction, beyond which it is filled with driftwood at many places. (11). The miscoscopic examination of a light-colored aphanitic rock, from the first outcrop on the river from Moose lake, proved interesting. It is a devitrified glass which still retains its perlitic texture. More will be said of this rock in Part III. The Driftwood river empties into the Black a short distance above where the latter joins the Abitibi.

Up Black River

The Black river was ascended for nine miles, and then inland trips were made westward and eastward. The westward trip was into the township of Taylor, the eastward into the township of Carr.

The first half mile from the river going westward reveals an undulating surface of clay soil covered with good spruce and poplar. At the end of this distance, a stream about twenty feet wide and running N. 30 degrees E. was crossed. Beyond this creek for half a mile, the region is quite level and consists of clay soil; the same is true as far west as the Driftwood, except that the dry clay areas are occasionally interrupted by short stretches of spruce swamp. In most places this area is well supplied with small streams.

The trip eastward from the river was through an area which had been overrun by fire a few years before. The surface is undulating, the soil clay. This area is well drained, and with very little difficulty could be made ready for cultivation. This applies to at least three miles back from the river, and conditions appeared similar for some distance farther eastward.

The first falls on the Black river is close to the boundary between the townships of Carr and Bowman. The drop of this fall is about twelve feet over a massive green dolerite. From a small bay-like part of the river straight west of the falls is a portage, the first of the portages on a route which leads to Fort Matachewan. The same route may be used as far as Separation lake in going to Temiskaming. From Separation lake one turns aside from the Matachewan route and follows a series of lakes and portages to the Blanche river and thence to Temiskaming.

(11) Bur. Mines, Vol. 8, pp. 179-180.

Digitized by Google

First Falls to Matachewan

As mentioned before, this route leaves the Black river by a portage from a small bay-like expansion below the first falls. About one hundred yards west from the river one comes upon McDougall's clearing. A few hundred yards to the north of this are some Indian wigwams, and a small patch of cleared ground. No one was occupying the wigwams or McDougall's house, but the fact that none of the furnishings had been removed indicated that they had not been permanently abandoned. McDougall's house is neatly built and is provided with stoves and other modern furniture, which give one the feeling that he is no longer in the land of the tent and the wigwam, but in some part much less remote from civilization. The clearing around the house was not under cultivation, but in the small patch of ground around the wigwams, fine potatoes were growing. It was here that Mr. Wilson of the Dominion Survey took a sample of soil, which on analysis proved to be supplied with all the elements of fertility (12).

From the clearing to the end of the portage, which runs a little west of south, is about one mile. The area passed over is undulating, the soil clay, and the timber white spruce, balsam and poplar of good size. The portage ends at a small lake, which is about twenty chains in length and has low, grassy shores.

A portage leaves this small lake from the southwest corner. It is only a little more than ten chains long and crosses a gravel ridge which resembles an esker. It leads to another lake which has low shores and beautifully clear water, and from which a small creek flows from the southwest corner. The trail from this lake is almost two miles in length, runs west of south, and leads to a small marshy creek. The first sixty chains passes over a rolling area of good clay soil covered with large spruce and poplar; the next twenty chains is rather low and wet; the remainder of the portage is a jackpine plain.

The small marshy creek at the end of the portage flows into a pond, on the west shore of which are many boulders, all of Laurentian and Huronian aspect. The drainage of the pond seems to be by seepage, since it has no outlet. The portage leaving the pond follows for a short distance the edge of a marsh, then it rises to a jackpine plain, over which it continues for more than forty chains to Troy lake. Troy lake is low and marsh and is surrounded by small jackpine. Drowned trees, at some distance out from the shore indicated that the water was higher than formerly. The lake is about forty chains long in an east and west direction and about twenty chains across. The portage from the lake is about twenty chains in length and ends in a small pond, from which a portage of about sixty chains, over a jackpine plain, leads to Cherry lake.

(12) Geo. Sur. Can., Sum. Rep. 1901, pp. 121-122.

Cherry and Grave Lakes

At the north end of Cherry lake is a large open space, which suggests that at one time there may have been an Indian settlement here. To the southward beyond the lake, hills rise conspicuously from the surrounding level area. Cherry lake is about sixty chains long and twenty chains wide. Its waters are clear, and its shores are low and clothed with spruce and jackpine.

The portage from this lake is more than one mile forty chains long, runs somewhat south of west, and leads to Grave lake. The first eighty chains is low and marshy, the remainder a jackpine area. Near the end of the portage is a ridge, from which there is a descent of about thirty feet to the level of the lake.

Grave lake is a pretty sheet of clear water surrounded by jackpine. It is crossed in a southerly direction, then a portage of one mile thirty chains, with one small intervening lake, reaches a pond just north of Bethea lake. This pond receives the waters of Bethea lake by a swiftly flowing stream, which from the pond probably flows to the Black river.

Bethea Lake

Bethea lake is larger than any of those thus far described on this route. It is irregular in outline and is over a mile in length in a direction northwest and southeast, and is half a mile in width. It has clear water and is very shallow in the northwest. The first rock outcrops from Black river were seen on the shores of this lake. On the east shore is a rocky bluff, which rises about one hundred and sixty feet (aneroid) above the level of the lake. This bluff consists of a somewhat schistose doleritic rock. Similar rock, but somewhat more massive, was seen on the south shore and also on the north shore to the west of the stream by which the lake was entered. The shores of the lake, where not rocky, are of sand and gravel.

From the northwest bay of the lake, a trip was made for about half a mile to the top of a high ridge of dolerite, which runs N. 50 degrees W. It is interesting to note that a pebble about three inches in diameter of banded

Digitized by Google

hematite and jasper was found on this ridge. This is evidence that iron range lies to the north, but, owing to the scarcity of outcrops in that direction, due to the prevalence of drift, it is doubtful whether it be exposed.

A climb to the top of the rocky bluff on the east shore of the lake, enables one to get a good idea of the surrounding country. The general appearance of the region to the north, west and south is one of moderate relief, but in the directions N. 70 degrees W., S. 50 degrees W. and S. 10 degrees W. prominent ridges may be seen miles in the distance. As far as could be discerned, the timber is spruce, jackpine, poplar and white birch.

Continuing our course, we ascended, about half a mile, the small creek which enters the lake in the southeast. It is very crooked and flows through a wide marsh. At the head of the creek is a muddy lake, so shallow that we found it difficult to paddle in it. This lake, which we named Gowan lake, is over half a mile long and has low gravel shores. The route leaves the lake from a bay in the west.

From Gowan to Harold lake is two miles, and from Harold lake to Davis lake is one mile and twenty chains. The direction of both of these portages is about S. 20 degrees W. There is no change in the topography, the timber or the soil.

Davis Lake

Davis lake is a beautiful sheet of clear water about a mile in length and half a mile in width. On the northeast shore are two small outcrops of rock. The northerly one consists of a massive pyritous dolerite; the southerly one is a coarsely crystalline quartz syenite, in which there is a very small percentage of ferromagnesian constituents. These rocks are exposed only at the water's edge, and it is impossible, owing to the presence of drift, to ascertain which rock is the later. Distinct glacial striae running south were observed. Farther south is another low, glaciated outcrop of light-colored, phanceritic rock. The striae here run S. 8 degrees E. The outlet of the lake is in the south end. It very quickly expands into a small lake from which it passes out as a shallow stream fifteen feet wide. The route does not follow this stream, but leaves the small lake by a portage, which, however, crosses the stream in less than half a mile. Where crossed the stream has a width of ten feet and is running S. 40 degrees W. Beyond the creek, the portage runs S. 15 degrees W. and at the end of about two miles twenty chains, Wataybeeg lake is reached. A marshy region lies to the south of the creek for about forty chains; this is followed by an area with a rolling topography, which suggests recessional material; the last mile is dry and level.

Wataybeeg Lake

Wataybeeg lake is one of the largest within the area examined. It consists of two quite distinct parts, the narrows joining them being situated about the middle of the west side of the northern part. The northern part is about three miles long in a northern and southern direction; its greatest width is about two miles. A long sandy point projects into the lake from the east. To the south of this point is a small rocky island, the rocks of which appear to grade from a hornblende albite syenite to a quartz albite syenite. These rocks possess rather unusual features which will be described in detail in Part III. On the east shore of the lake is a conspicuous bluff of sand; a similar bluff is situated on the shore to the north of the narrows. The southern part of the lake is over five miles long but has an average width of less than half a mile. About half way down its western side is a bay, at the entrance to which is a large island. Two streams from the west empty into the bay. The shores of both parts of the lake are fairly high and consist of sand and gravel; the only rock exposed is that on the small island referred to above. The timber around the lake is chiefly second growth, the whole region having been overrun by fire, apparently twenty or twenty-five years ago. The outlet of the lake is at the north just to the west of the portage from Davis lake. This river will be described later.

The route leaves Wataybeeg lake from the south end of the long narrow part. The trail to the succeeding lake, which is small, is about thirty chains in length and passes over a high, open, sandy area, which appears to extend for a considerable distance in all directions.

A Lake on the Divide

A portage of less than twenty chains from the small lake reaches Sunny lake, which is about one mile long and twenty chains wide. This lake has sandy shores and beautifully clear, sea-green water. It lies on the Height of Land and has no outlet.

The Height of Land portage leaves Sunny lake from the southwest corner. It is about fifty chains in length, runs S. 20 degrees W. and ends at a pond, about ten chains south of which is a small lake, whose waters flow south-

Digitized by Google

ward. From this lake to Kenoja (or Kenozha) lake is about twenty chains.

Kenoja lake is more than half a mile long and about twenty chains wide. A creek flows out from the southwest corner. The route follows the creek for only a short distance, when a portage is taken to the right. An Indian named Baptiste informed us that the creek flows to the Blanche. The portage from the creek runs a little west of south for about fifty chains to another small creek, which flows northward. On the portage about ten chains from the latter creek, is an outcrop of massive granitoid rock. This creek was ascended for about half a mile to a small lake, on the shores of which are numerous granitic boulders. A portage of about fifty chains from the south end of this lake leads to Blackburn lake.

Blackburn lake is irregular in outline and its shores are rocky. The chief outcrops are hornblende schist, the dynamic action being very pronounced; on the east shore of the lake is a dike, the rocks of which grade fram a basalt near its margin to a more and more coarsely crystalline diabase as the distance from the margin is increased.

It may be said in general that from this lake southward along the route, the region becomes more rugged, the drift is thinner, and hence the rock outcrops are more frequent. It should also be added that from here on, some of the timber escaped the fire which, as mentioned above, swept over so large a part of the region.

The trail leaves Blackburn lake from a small bay in the southwest. It is rocky and about twenty chains in length, the exposures being hornblende schist with a strike nearly north and south. Along this portage is birch, balsam and spruce of fair size. This portage leads to Canoe lake, which is about half a mile long. Less than ten chains from the south end of Canoe lake is Tent lake, which is also about half a mile long. On the shores of both lakes are several exposures of altered eruptives.

Separation Lake

A portage of forty-five chains from Tent lake in a direction a little south of west ends at a fairly large body of water, which was named Separation lake, for there are two routes leading out of it, one to the Blanche river, the other to Fort Matachewan. The lake, where entered, consists of a long narrow bay running north and south. The route to Fort Matachewan leaves this bay near the northwest corner, and after a short portage Optic lake is reached. A further examination was made of Separation lake. Just south of the portage to Optic lake is a bluff of chloritic schist. Following the narrow bay to the southward, one passes an island, and rocky shores rise steeply on either side, the distance between the shores being only a few yards. Beyond this narrows the lake widens, and straight ahead is the portage which leads to the Blanche river. Turning westward around a point to the right of the narrows, one enters the main body of the lake, which contains several islands of greenish altered eruptives. Optic lake may also be reached from this part of the lake by following for less than ten chains the shallow stream which flows out to the north of these islands.

Optic, Bird and Turtle Lakes

Optic lake is about half a mile long, and on its shores are scattering white pine and spruce. The route follows the outlet in the northwest. It is very shallow and quickly expands into Bird lake, which is irregular in outline and runs in a southwesterly direction for more than half a mile. The rocks collected from this lake proved to be altered acid porphyry. The shores are covered with jackpine, birch and spruce; occasional white pine and red pine were also seen. The outlet is in the southwest bay, but where it leaves the lake, it is shallow and rapid, and hence Turtle lake is reached by a portage of less than twenty chains, which runs south over a well-timbered area.

Turtle lake is also irregular, is more than a mile in length, and contains several rocky islands. The rocks are similar to those of Bird lake, but less altered and somewhat less acid. The outlet, which is called Musquataysee or Turtle river, leaves from the west shore, just to the north of where the Indian, Baptiste has a fair-sized clearing and two or three respectable looking buildings. This river, in less than fifty yards, empties into the north end of Baptiste lake, out of which it almost immediately flows again, the inlet and outlet being only a few yards apart.

Baptiste Lake

Baptiste has lived here for thirty years. He cultivates a few acres of land, on which potatoes, turnips and other vegetables are grown. The spot is very pretty and reminds one of the site of a Hudson Bay Company post. About ten chains south of the clearing is an outcrop of coarse-grained massive dolerite carrying iron pyrites.

From the clearing to Fort Matachewan there are two routes; one follows the Turtle river, which empties into the Montreal river just opposite the Mata-

Digitized by Google



Mill at Ontario corundum mine, erected 1903.



Side hill quarry, Ontario corundum mine.

Digitized by Google

UNIV. OF MICH.

Digitized by Google



Pit at Radnor iron mine, Grattan township.

Digitized by Google

UNIV. OF MICH.

Digitized by Google

Cobbing ore, Olden zinc mine.



Radnor iron mine, Grattan township

Digitized by Google

UM. OF MICH.

Digitized by Google



Castellated trap cliffs of Nipigon bay.

Radnor mine: Banded magnetite and silicious material in low grade portions of ore body.

Digitized by Google

UNIV. OF MICH.

Digitized by Google

chewan Falls about four miles above the Fort. The other is a lake and portage route and is the better of the two, for the Turtle river is said to be shallow and to have numerous rapids.

Baptiste lake, which is a series of expansions and contractions, is over one and one-half miles in length in a northerly and southerly direction; its greatest width is about one half mile. A portage leaves the south end and runs southwest for about twenty chains over a rather sandy plain to a small muddy lake. From this lake a portage of forty chains leads southward to Narrow lake, which is about one mile long. On the shores of Narrow lake are several outcrops of fine grained, chloritic rocks, which upon miscroscopic examination reveal their original igneous origin.

A portage from the south end of this lake leads to the Fort, which is situated on the east bank of the Montreal river. This portage winds around a high hill, the distance from the lake to the Fort being less than one mile. The Fort was in charge of Mr. Lafricain, who showed us several samples of iron pyrites and hematite, which he says he obtained in this region.

Route to Temiskaming

We next went back to Separation lake and followed the Temiskaming route for a short distance. As mentioned above, the portage leaves the lake straight south of the long narrow arm and in less than twenty chains a small lake is reached, the shores of which consist of altered eruptive rock. The surrounding timber is second growth. The route follows a creek, which enters in the southeast. A short distance from its mouth is a portage of about ten chains; it is on the west side and is due to a small fall and rapid over a ridge of altered dolerite. From the head of the portage the creek was followed for about half a mile in an eastern direction. It is crooked and flows through a marshy area. A short distance beyond a pond-like expansion in the creek, a small branch enters from the right. The portage leaves the left bank of this branch. The portage was followed for a mile and a half in an eastern direction when a small marshy lake was reached. The area passed over is sandy and is covered with small jackpine and spruce. Near the east end of the portage is an outcrop of quartz diorite, the plagioclase of which is considerably decomposed.

Wataybeeg Lake to Black River

Wataybeeg river flows out of the north end of Wataybeeg lake. Where it leaves the lake it is thirty feet wide and shallow. At the end of about sixty chains is a portage of less than ten chains to avoid a rapid over large boulders. Below the portage, the current is strong, and the river is so filled with large boulders that we found it necessary to let the canoe down by a line. A second portage of less than one hundred paces on the left hand side avoids a small falls over coarse-grained dolerite carrying iron pyrites. Below this portage are high banks of sand and gravel on both sides of the river, which has here a width of more than sixty feet, but is only about one foot in depth. Soon a creek was seen entering from the east. It is said by the Indians that a route beginning with this creek leads to Davis lake. One thing is certain that Wataybeeg river above this creek has been used considerably by the Indians, whereas below, we found that it had never been travelled. It was filled at scores of places with driftwood, around which it was necessary to cut portages. It was necessary also to cut portages around the falls and some of the rapids. This river should never be used, for only very short stretches of it are free from obstructions.

In the course of less than one mile from the creek referred to above, three lakes were seen, one on the right hand and two on the left; the second of the two on the left contains clear, green water. Below this lake is a short rapid over large boulders, and about sixty chains farther down is a fall of about five feet, due to a ridge of pyritous dolerite. An island is formed in the river on each side of which is a narrow gorge.

Falls on the Wataybeeg

About sixty chains farther down is a very pretty fall of thirty feet (aneroid). At the head of the fall the river narrows to about twelve feet then widens as its white waters plunge over the rocky ledges. Three types of rock were seen here, a massive, coarsely-crystalline, pyritous dolerite, a coarse-grained granite and a gray aphanitic rock in the form of a narrow dike in the granite. The timber from Wataybeeg lake to this point is spruce, jackpine and poplar; the soil is sandy.

About a hundred yards below the high fall, the river forms a chute with a drop of about fifteen feet; this was passed by a portage on the right hand side. Below this portage the soil is no longer sand but clay, and the timber is a better grade of spruce. The river is now free from falls or rapids for more than two miles, when there is a drop of four feet over a schistose rock containing much deep green hornblende.

Digitized by Google

A short distance below this fall nine feet of stratified clay, overlain by one foot of sand, is exposed in the bank; the area back from the river at this point is rather low and level and clothed with large spruce. Similar features were noted during the next two and one half miles down the river.

At the end of this distance an inland trip was made eastward. About four and one-half miles from the river, the northwest bay of Bethea lake was struck. The first half mile from the river is a level clay area followed by higher gravelly soil for about one-half mile, when there occurs a ridge which consists of two distinct types of rock, one a coarse crystalline dolerite, the other a light-colored granite; the line of contact is not well indicated. Beyond the ridge the region becomes swampy, this continues for about one mile twenty chains, when a dry jack-pine area is entered, which continues to and beyond Bethea lake.

A trip was also made to the west from the river. The first mile and a half is level to undulating and consists of clay soil. Beyond, the area becomes lower, the timber being chiefly dry tamarac.

Three miles farther down the river is a fall of about twenty feet, due to a ridge of pyritous quartz diorite schist. Below the fall rapids occur more or less continuously for three miles. In this distance the following outcrops of rock were observed:

1. A very fine-grained aphanitic rock, consisting chiefly of actinolite and chlorite.
2. A considerably decomposed quartz dolerite.
3. A dark aphanitic rock carrying iron pyrites, which proved to be an altered diorite.
4. A rather fine-grained rock with ophitic texture, composed chiefly of augite, plagioclase and quartz.

From these rapids to where the river joins the Black, the banks are low. The soil is clay and the timber, except for a short distance from the mouth, where there is a brule, is spruce, cedar and balsam. The Wataybeeg river joins the Black about thirteen miles from the Abitibi, or about three miles below the first falls on the Black.

Upper Black River

The Black river was ascended from the first falls to the Pike river, which was explored. It joins the Black from the east about one and one-half miles below the third falls. At the mouth this stream is thirty feet wide and has a good current. About half a mile up it becomes shallow and rapids begin. Farther up is a bluff of rock on the left, and just beyond is a fall of two feet. The rocks are altered andesites. Less than half a mile above this small fall the river becomes so shallow and swift and so filled with large boulders that it was impossible to float even a lightly loaded canoe. Being unable to use the river any longer, we made an inland trip eastward to Speight's north and south line.

The line was struck at 28 M. 50 chains. Pike river was twice crossed in making this trip. The area passed over is in part rolling and in part fairly level; the soil is clay, the timber spruce and balsam. Close to the line a rather low area covered with small spruce was entered; this low area appears to be quite extensive, stretching away to the east, north and south.

Having returned to the Black river, we continued our ascent to the third falls and made an inland trip to the west. The first twenty chains from the river is high, then comes a drop to a rather level, clay area, which continues for about sixty chains, when the soil becomes sandy. The sandy area is followed by a muskeg, which has a width of about twenty chains in an easterly and westerly direction, but which appears to extend for a considerable distance to the north and south. The surface of this swamp is of sphagnum moss. A pole, driven down for more than twelve feet, did not strike the rock. The upper nine feet consists of decomposed vegetable matter, below which is a fine blue clay free from grit. Beyond the muskeg for about eighty chains, the region is fairly level, the soil is clay, and the timber spruce and balsam.

From the third falls on the Black river, to where it is crossed by Speight's 1902 line, rock outcrops are quite numerous. They are altered, fine-grained volcanics and rather coarse-grained dolerites. Clay soil is revealed in the banks of the river throughout almost the whole distance. About two miles north of the crossing of the line, second growth timber begins. It is similar to that which was seen on a large part of the area between the Black river and Fort Matachewan. Wilson reports a similar area for some distance to the east (13).

Having completed our work we ascended the Black and White Clay rivers to the Height of Land and then followed the Blanche route to Tomstown, where steamer was taken to New Liskeard.

(13) Geo. Sur. Can., Sum. Rep. 1901, p. 117.

Digitized by Google

Part II: Topography and Resources

A Drift-Covered Area

Although exact determinations of level have not been made, it is probably safe to say that the area has a general elevation above the sea of about 1,000 feet. The relief is moderate, the greater part of the area being comparatively level or undulating, with here and there ridges, which stand out conspicuously above the surrounding country. The surface is to a great extent drift covered, in this respect differing very markedly from many parts of the area which lie to the south of the Height of Land north of Lake Superior and Lake Huron. Much of the drift is stratified and consists of clay, sand and gravel. These deposits are no doubt lacustrine, the lakes having been formed in Glacial times, in front of the ice, during its retreating stages. The limits of these lakes, at the different periods of their history, could be worked out only by detailed topographic study. There is no doubt however judging from the wide distribution and heights of these stratified deposits, that the lakes were of considerable extent. While the laminated clays were being laid down in the bottoms of these lakes, the sands and gravels were being deposited along the shores or near the margin of the ice sheet.

Drainage Systems

The chief lakes are Night Hawk, Frederick House and Wataybeeg. Besides these, there are numerous other smaller lakes, but their number is not as great as on many other areas of equal size in northern Ontario.

The waters of that part of the area which lies to the north of the Height of Land flow to the Abitibi and thence to James Bay. The largest of these rivers are the Black, the Frederick House, the Porcupine, the Redstone and the Night Hawk. The main branches of the Black are the Driftwood, the Shallow, the Wataybeeg and the Pike. The waters to the south of the Height of Land flow to the Blanche and to the Montreal rivers. All the rivers are very young, possessing V-shaped valleys, and having falls and rapids. The drainage is not well established, for many swamps exist.

Evidences of Glaciation

Where the rocks are exposed, they exhibit the grooves and striations due to glaciation. The surfaces of some of the islands in Night Hawk lake are good examples of roches moutonnees. The directions (magnetic) of striae were observed as follows:

Island in Porcupine Lake.	S. 30 deg. W.
West shore of Night Hawk lake	S. 10 deg. E.
Near entrance to Night Hawk river	S. 16 deg. E.
Island in Frederick House lake	S. 5 deg. E.
Davis lake (northeast shore)	S.
Davis lake (southeast shore)	S. 8 deg. E.
Tent lake	S. 8 deg. E.
Wataybeeg river	S. 15 deg. E.
Black river (third portage)	S. 10 deg. E.
Pike river	S. 15 deg. E.

Where boulder clay is found, the boulders are quite local. This is well shown in a bluff containing many boulders, on the south shore of Night Hawk lake. An examination of these boulders shows that there are very few limestones from the Devonian area, which lies to the north, but that almost all are similar to the rocks of the vicinity. Of course limestone easily disintegrates, and this might account, in part, for its scarcity.

Resources of the Region

The chief resource of the region is its soil, which over large areas is clay, analyses of which will be found in the report of Mr. Jarvis. It may be said that the districts best adapted for settlement are located in the northern part; to be more specific, north of the line which runs west from M. 120 on Niven's meridian to the Mattagami river, and north of a line running east from the same point, namely M 120, to M 24 on Speight's north and south line of 1902. South of the line running east the soil is much more sandy than to the north, and since a large part of it has been overrun by fire, the timber is too small to be of value.

Much of the northern area has spruce, balsam, poplar and birch timber, the largest of which is found in the valleys of the rivers, especially in those of the Porcupine, Black, and Driftwood.

No minerals of economic importance were found. As was mentioned before, a pebble of banded jasper and hematite was picked up north of Bethea lake. Mr. Lafricain, of Fort Matachewan, has specimens of hematite, which he says were found in the vicinity.

Digitized by Google

Climate

No frosts occurred between June 17th and September 1st. Some of the temperatures from the record for the month of August are as follows, and show the highest and lowest points reached:

—	6 a.m.	12 a.m.	6 p.m.
Lowest temperature	35 deg. F. (on the 15th).	54 deg. F. (on the 12th),	48 deg. F. (on the 6th).
Highest temperature	58 deg. F. (on the 18th).	74 deg. F. (on the 2nd).	76 deg. F. (on the 4th).
Average temperature	47.6 deg. F.	62.18 deg. F.	61 deg. F.

It was noted from the condition of vegetation generally, and especially from the date of the ripening of berries, that the season was about two weeks later than in the vicinity of Toronto.

Requirements

Before this region can be of any practical value to Ontario, it must be made accessible. This can only be accomplished by the building of railways. If one may judge by the present activities in this direction, it is safe to predict that before many years many parts of northern Ontario, which are now inhabited only by the Indian, will be centres of agricultural and industrial activity.

Part III: Petrography

As already stated in this report, a large part of the area which was examined is covered with drift, hence the rock outcrops are not very frequent. In fact, the exposures are confined chiefly to the shores of lakes and rivers, and even here, they are so limited that in but few cases was it possible to trace in the field the relationships which the different rocks bear to one another. However, a good idea of the petrology of the region has been obtained from the microscopic study of about eighty rock specimens, which were collected from the various outcrops. Some of these were found to possess interesting and unusual features.

Many of the rocks are igneous, the primary constituents of which have not been greatly changed or the original textures materially altered. Some have been considerably metamorphosed, yet retain distinct evidence of an igneous origin. Others have been so profoundly metamorphosed that all traces of the original rock have been destroyed. Only one specimen, a slate, which occurs on a small island in Porcupine river near Night Hawk lake, suggests an aqueous origin.

Classes of Rocks

The rocks may be classed as dolerites, syenites, diorites, porphyries, volcanic tuff and schists. The schists, as here used, include those schistose rocks which have been so greatly metamorphosed that it is impossible to say whether they are of igneous or of sedimentary origin. It is worthy of note that nearly all the rocks of the above classes contain iron pyrites.

Dolerites

The dolerites, as the term is here used, are medium or coarse-grained phaneritic rocks, which consist chiefly of a plagioclase feldspar and augite, and subordinately of iron pyrites and magnetite; but one, and sometimes several of the following minerals may also be present: olivine, mica, hornblende, quartz, orthoclase and apatite. In texture the rocks vary from ophitic, that is, the plagioclase feldspars are lath-shaped and are enclosed in the augite, as in the case of diabase, to panautomorphic, in which both the plagioclase and augite possess their proper crystal forms more or less perfectly. Many of these rocks are similar to those which are frequently described as gabbros, or, from hand specimens, as diorites.

The dolerites are the most widespread rocks of the area. Specimens were collected from the following localities:

1. The portage between Delbert and Jarvis lakes.
2. A point on the west shore of Night Hawk lake between the Porcupine and Redstone rivers.
3. Along the Driftwood river.
4. The shore of Bethea lake.
5. The east shore of Davis lake.
6. The southeast shore of Blackburn lake.
7. Between Baptiste and Turtle lakes.
8. South of Separation lake on the Temiskaming route.
9. Several places on the Wataybeeg river.
10. Between Wataybeeg river and Bethea lake.
11. Several places on the Black river.

Digitized by Google

Two specimens with crystals about two millimetres in diameter were collected quite close to each other, on the north side of a long point on the west shore of Night Hawk lake, between the Porcupine and Redstone rivers. They exhibit quite different features. One specimen contains large crystals of plagioclase and augite, both of which have fairly definite crystal outlines. The crystals of plagioclase are frequently bordered by orthoclase, and in some cases there is an intergrowth of the pyroxene and of what appears to be primary hornblende, the latter partly surrounding the former. There is also present a considerable amount of decomposed biotite, a little quartz, some calcite, large crystals of apatite and some chlorite. The other specimen consists of augite, a considerable amount of olivene, plagioclase, a small amount of mica and some magnetite. The texture is coarsely ophitic. The former of these two specimens has the following composition (14) :

	Per cent.
SiO_2	51.50
Al_2O_3	18.81
Fe_2O_3	4.30
FeO	6.41
MgO	2.90
CaO	6.78
Na_2O	4.84
K_2O	1.76
TiO_2	.40
H_2O, CO_2, etc	2.41

From this analysis the norm was determined and the rock classified according to the quantitative system (15).

The result was as follows :

Class II.—Dosalane.
Order V.—Germanare.
Rang III.—Andase.
Subrang IV.—Andose.

A specimen from the northeast shore of Davis lake is a dark phaneritic rock with ophitic texture. Besides the augite and plagioclase, there is some quartz, magnetite and a small amount of biotite. The augite is in part altered to chlorite.

A dark coarse-grained phaneritic rock, obtained just south of Baptiste's house, between Baptiste and Turtle lakes shows very little decomposition. The minerals present, besides the augite and calcic plagioclase, are quartz, a small amount of hornblende and biotite, magnetite and acicular crystals of apatite. The texture is panautomorphic. A dark, coarse-grained phaneritic rock from an outcrop at the foot of the second portage on Wataybeeg river, contains a considerable amount of augite, partly altered to chlorite; the plagioclase crystals are quite distinctly automorphic. An interesting feature is the presence of small patches of most perfect graphic texture, due to the intergrowth of primary quartz and orthoclase.

A specimen from the head of the 35-foot fall on the Black river north of where Speight's 1902 line crosses the river is a green, aphanitic rock, considerably decomposed. It contains an altered orthorhombic pyroxene, a light-colored hornblende, which is probably actinolite, decomposed plagioclase, secondary quartz and a small amount of altered mica.

Several specimens consisting almost entirely of secondary minerals are probably altered dolerites.

Syenites

Perhaps the most interesting of all the rocks of the area were collected on a small island in Wataybeeg lake. Two quite distinct types were found, one of which has been called a hornblende-albite syenite, the other a quartz-albite syenite.

The hornblende-albite syenite is a medium-grained phanerite, the individual grains having a diameter of about one millimetre. This rock consists of about equal proportions of light-colored minerals and of the dark ferromagnesian minerals. The light-colored minerals are feldspars, no quartz being present. The feldspars have a pale pinkish color, pearly cleavage surface, and in patches they exhibit poikilitic effects. The ferromagnesian minerals are hornblende and biotite, the former predominating. In thin section, the prevailing texture is poikilitic; but certain parts present a somewhat graphic texture, due to the interlocking of the crystals ; the only constituent, other than the accessory minerals, which approaches automorphism is the hornblende.

The feldspars consist of a plagioclase feldspar and microcline. The plagioclase feldspar was proven, by means of its index of refraction and angle of extinction, to be albite. The albite and the microcline assume several relationships ; in some cases, the microcline is poikilitic in the albite; in some cases, the opposite is true, that is, the albite is poikilitic in the microcline; again, the two minerals are coarsely intergrown, in which case an approach to graphic texture is presented, but further examination shows that the two minerals have a parallel arrangement, and hence the texture is really coarsely microperthitic; the albite and the microcline appear to have grown contemporaneously.

The microcline usually shows poly-

(14) Analysis by Mr. A. G. Burrows, Provincial Assay Office, Belleville.

(15) Quantitative Classification of Igneous Rocks by Cross, Iddings, Pirsson and Washington.

Digitized by Google

synthetic twinning, that is, lamellar twinning according to the albite and pericline laws.

The albite is also twinned, although many of the crystals are so cut that the striations are not apparent; the prevalent twinning is according to the albite law, but a few Carlsbad twins were also observed. The striations of the albite are very narrow and straight. Of the two feldspars, the albite has suffered the greater amount of decomposition, although both are comparatively fresh.

The hornblende usually occurs in irregular crystals, although automorphic forms in sections cut across the prisms also occur; in such cases the characteristic cleavage is quite perfect. The pleochroism is from a light-greenish brown to green.

The biotite occurs in irregular shaped plates. Its color is brown. The ferromagnesian minerals are poikilitic in the feldspars; both the biotite and the hornblende are somewhat altered.

The subordinate minerals are sphene, which occurs in orange-yellow irregular crystals, and apatite, which is quite abundant in well-formed prisms, some of which are colored by iron oxide. The secondary minerals are a fibrous light-colored hornblende, which is probably actinolite, a light-green chlorite and calcite.

An analysis of this rock by Mr. A. G. Burrows of Belleville, Ont., gave the following result :—

	Per cent.
SiO_2	56.62
Al_2O_3	16.33
Fe_2O_3	trace.
FeO	4.21
MgO	7.65
CaO	5.12
Na_2O	4.34
K_2O	2.68
TiO_2	.26
CO_2, H_2O, etc	2.70

From this analysis the norm was determined and the rock classified as follows :—

Class II. Dosalane.
Order V. Germanare.
Rang III. Monzonase-Andase.
Subrang IV. Akerose-Andose.

Measurements were made of the minerals present in this rock and the mode determined (16).

The result was as follows:

	Per cent.
Albite	27.80
Microcline	17.54
Biotite	11.15
Hornblende	42.45
Apatite	.73
Titanite	.29

(16) Quant. Class. of Igneous Rocks, p. 204.

With these percentages an attempt was made to ascertain what must be the nature of the hornblende to correspond with the composition of this rock as determined by analysis. In this calculation the biotite was assumed to have the composition of the biotite in a quartz-monzonite from Walkerville, Butte, Montana (17).

It was found that the hornblende must be high in silica, high in alumina, high in magnesia, low in iron and low in potassium. A hornblende from Sanlupe was found to have such a composition (18).

Considering the hornblende to have the composition of the hornblende from Sanlupe the rock was classified from the mode. The result was as follows:

Class II. Dosalane.
Order V. Germanare.
Rang II. Monzonase.
Subrang III. Monzonose.

All the constituents agree fairly closely with the chemical analysis except the K_2O, which is too high.

The quartz-albite syenite is found associated with the hornblende albite syenite, the two types seeming to grade into each other. Magascopically, this rock differs considerably from the associated rock, in that it consists almost entirely of light-colored minerals, there being less than 5 per cent. of ferromagnesian constituents. This rock is also different in that it contains quartz, while mica is absent.

In thin section, the texture is seen to be similar to that of the hornblende-albite syenite. The feldspars are albite and microcline, which present the same characteristics as were described in the associated rock, but whereas in the hornblende-albite syenite there was less than twice as much albite as microcline, in this rock the albite is about six times as abundant as the microcline.

The quartz comprises about 13 per cent. of the rock. It is clear and has xenomorphic outlines. It is usually segregated in small patches.

The ferromagnesian mineral is hornblende, which has a rather deep-green color and constitutes about 5 per cent. of the rock. It shows the usual pleochroism, and in some crystals the characteristic cleavage is present.

The accessory minerals are sphene, apatite, zircon, and a small amount of magnetite.

This rock was also measured and the percentage weights determined.

This result was as follows :—

(17) Table XIV. Quant. Class. of Igneous Rocks.

(18) Dana: System of Mineralogy, page 393.

Digitized by Google

	Per cent.
Albite	69.86
Quartz	13.55
Microcline	11.91
Hornblende	4.26
Apatite	.03
Titanite	.29
Zircon	.06

From these percentages the approximate chemical composition was determined and the rock classified. The hornblende here was assumed to have the composition of the hornblende from Saulupe, as in the case of the hornblende-albite syenite.

The result was as follows :—

Class I.—Persalane.
Order IV.—Britannare.
Rang I.—Liparase.
Sub-rang IV.—Kellerudose.

Specimens, presenting features very similar to those of the quartz-albite syenite, were obtained from the following localities:—

1. The east shore of Davis lake.
2. The 30-foot fall on the Wataybeeg river.
3. Between Wataybeeg river and Bethea lake.

The rock from Davis lake is rather coarsely crystalline and has a small amount of both hornblende and biotite, the latter considerably altered ; quartz is present in an appreciable amount. The albite and microcline show beautiful poikilitic texture.

The rock from the 30-foot fall on the Wataybeeg river is somewhat more decomposed than the quartz syenite from Wataybeeg lake, the poikilitic texture is not quite so pronounced, and quartz is somewhat more abundant. Some of the hornblende shows twinning, and several of the crystals are quite distinctly automorphic. The secondary minerals are chlorite, sericite and epidote.

The rock from between Wataybeeg river and Bethea Lake presents no new features, except that some of the feldspars exhibit zonal weathering.

Diorites

Many of the rocks which in the field were thought to be diorites proved under the microscope to be dolerites. In fact, only one of the specimens collected has been called a diorite, and even this is not a normal rock of that class. It was obtained on the second portage from Separation lake on the Temiskaming route. It is a medium-grained phanerite, with apparently about equal amounts of ferromagnesian and light-colored minerals. The ferromagnesian constituent is hornblende, which varies in color from a yellowish-brown to a deep green; the light-colored minerals are plagioclase, microcline and quartz. The plagioclase is so decomposed that it was impossible to determine its kind ; the microcline exhibits the characteristic twinning and is more abundant than in a normal diorite. Iron pyrites is also present.

This rock resembles the hornblende-albite syenite from Wataybeeg lake, in that it has about equal amounts of ferromagnesian and light-colored minerals, and has two feldspars—a plagioclase and microcline; the hornblendes also of the two rocks are similar. It differs from the Wataybeeg specimen, in that it does not possess the distinctive poikilitic texture, has a considerable amount of quartz, and is free from mica.

A schistose rock, obtained on the Wataybeeg river, contains much deep-green hornblende, some decomposed plagioclase feldspar, a considerable amount of secondary quartz, iron pyrites and magnetite. This has been called a quartz diorite schist.

Porphyries

The word porphyry is here used in a broad sense, and includes rocks which contain phenocrysts of any kind and a ground mass. In many cases, these rocks have been so altered that the porphyritic texture is not detected in hand specimens, although it is quite evident in thin section. A few of the rocks are fine-grained and microporphyritic.

The rocks which megascopically exhibit the porphyritic texture were collected from the shores of Turtle and Bird lakes and from an outcrop at the third falls on the Black river. The Turtle lake specimens are porphyritic, aphanitic rocks, the phenocrysts being albite; the ground-mass of these rocks still retains its original flow structure, but has been entirely recrystallized, the secondary products being chlorite actinolite, epidote and quartz. The metamorphism seems to have been metasomatic rather than the result of dynamic agencies. The rocks from Bird lake are very similar to those of Turtle lake, but they have been more metamorphosed and are apparently more acid.

The rock from the third portage on the Black river is of a green color, and is distinctly porphyritic. The phenocrysts are plagioclase feldspar, which is considerably decomposed; the ferromagnesian minerals have been altered to chlorite. There is some evidence of the original flow structure; this is probably an altered andesite.

The porphyritic rocks which have been so altered that the phenocrysts are not observed megascopically are quite widespread ; some of the most interesting of these will be described.

Digitized by Google

A dark-green aphanitic specimen, obtained two miles north of Delbert lake, consists entirely of secondary minerals, of which serpentine is the most abundant; long, needle-like, light-colored crystals of actinolite are also present. There is distinct evidence of the outlines of original phenocrysts, between which a ground mass is strongly suggested. The nature of the secondary minerals suggests that the original rock was very basic.

About one mile south of the portage which leaves the south shore of Jarvis lake is a dark green, somewhat schistose, aphanitic rock, which in thin section is micro-crystalline to micro-crypto-crystalline. Although considerably decomposed, a few altered striated feldspars, which possess distinct outlines, are present; the original ground mass appears to have been fine-grained. The minerals, besides the feldspar, are pale-green chlorite, quartz which shows granulation, and a distinct amount of calcite with definite rhombic outlines. There is evidence of crushing in the zone of fracture.

An interesting type of rock occurs about one mile north of VIII. M. 50 chs., on Niven's 1898 base line. It is light-colored, aphanitic and schistose. Microscopically, it exhibits an eutaxitic texture. Lines of flowage are distinct. Metamorphism has effected a general parallelism of the grains at right angles to the original lines of flowage. The altered phenocrysts appear to have been striated plagioclase and quartz. The secondary minerals are a considerable amount of finely granular quartz, some sericite and a white opaque mineral, probably kaolin. This rock is no doubt an altered porphyry of acid composition.

At first the small fall on Pike river is a soft, greenish, non-schistose, aphanitic rock considerably decomposed. In thin section it consists of porphyritic crystals of plagioclase and a micro-crypto-crystalline ground-mass. There is still evidence of the original flow structure and of microlites; the chief secondary product is chlorite.

Micro-porphyritic rocks were collected from a small island in Frederick House lake, from Dundonald township, east of Frederick House lake, and at the fifth falls on the Black river. They are very fine-grained, aphanitic rocks, which, in thin sections, are seen to consist of numerous, small irregularly arranged crystals of plagioclase and a micro-crypto-crystalline ground mass. The rock from Dundonald township contains considerable quartz. These are no doubt altered andesites or dacites.

One of the most interesting of the undoubted surface lavas was obtained on Driftwood river, from the first outcrop below Moose lake. It is a devitrified glass. Megascopically, this rock is of a light-gray color, is rather fine-grained, aphanitic and has a dull lustre. Microscopically, the most striking feature is that the rock is divided by sets of more or less concentric fissures, which give it the globular structure characteristic of perlite. Examined under cross nicols, it is seen to be completely crystallized and to possess some features of peculiar interest. There are numerous patches, which have a radiating arrangement similar to that possessed by spherulites. These patches are found to have no definite relation to the perlitic cracks; in some cases they cross them, while in other cases they are entirely independent of them. They are distinctly a later development than the cracks. A study of the constituents of these patches shows them to be made up of a striated plagioclase feldspar and not intergrowths of feldspar and quartz. Phenocrysts of primary striated plagioclase and of quartz, with fairly definite outlines, are still present. The ground mass consists of fine-grained quartz and plagioclase, some well-formed crystals of calcite, and some pale-green chlorite.

Volcanic Tuff

Only one specimen of an undoubted volcanic tuff was found. It was obtained on the first portage west of Porcupine lake. It is massive, fine-grained and aphanitic. In thin section, the angular shapes and arrangements of the crystals stamp it as a pyroclastic. The chief minerals are striated plagioclase feldspar and quartz, the latter predominating; some chlorite is also present.

Schists

The schists are of various kinds, including chlorite schists, sericite schists, actinolite schists and hornblende schists.

A specimen of a chlorite schist from the first portage east of Mattagami river shows a considerable amount of pale-green chlorite, many light-colored, acicular crystals of actinolite, some quartz, and a light-colored, opaque mineral resembling leucoxene. The quartz has irregular outlines and exhibits undulatory extinction. The best example of a sericite schist was obtained on the southeast shore of Jarvis lake. It is micro-crystalline to micro-crypto-crystalline, and shearing action is very pronounced. The most prevalent mineral is light-colored, scaly muscovite;

Digitized by Google

quartz and crystals of calcite are also present. The actinolite and hornblende schists have no features of unusual interest.

Generally speaking, the rocks which show the most distinct schistose structure are located between the Mattagami river and Night Hawk lake and in the vicinity of Blackburn lake. The strike of these schists varies considerably. In the vicinity of Delbert lake the strike is approximately east and west; near IX. M. 35 chs. on Niven's 1898 base line it is N. 60 degrees W.; between Blackburn and Canoe lakes it is approximately north and south. The origin of these schists is uncertain, but the absence of undoubted sedimentary beds in the region, and the occurrence of many metamorphosed rocks the origin of which is distinctly igneous, strongly suggest that they are not of sedimentary origin, but are greatly altered and sheared basic and acid eruptives.

The question arises, "What is the age of the rocks which have been here described ?" It is known that many are the result of extrusive and intrusive volcanic action. It is also known that many have been subjected to profound dynamic processes. But it has not been possible in the field, owing to the scarcity of outcrops, to determine the relationships of the various rocks to one another, nor to any formation whose age has been determined. Former workers in this field and in the adjacent fields have characterized similar rocks as Huronian, using that term in a rather broad sense to include all the rocks above the Laurentian and beneath the lowest fossiliferous strata (19). With our present knowledge of these rocks, a closer interpretation, as to their age, is not warranted.

Before closing, I wish to convey my sincere thanks to Prof. J. P. Iddings of the University of Chicago for assistance in connection with the rocks here described.

Agricultural Capabilities of Abitibi

By Tennyson D. Jarvis

On June 12th 1903 the writer received instructions from Mr. Thos. W. Gibson, Director of the Bureau of Mines, to join Mr. Geo. F. Kay at Sudbury in a geological, biological, and agricultural survey of the Abitibi region, Mr. Kay being geologist, and the writer biologist and agriculturist for the party. Accordingly, on June 16th the party, consisting of Mr. Kay, Mr. H. Davis, myself and two canoemen, took a freight train to Metagama, 80 miles west of Sudbury, on the main line of the Canadian Pacific Railway. After a night spent on the floor of Metagama station our party embarked in two canoes, one large, one carrying three men, and the bulk of the provisions, and the other carrying two men and some baggage. A two-day paddle up the Spanish river and some small lakes and portages brought us to the height of land.

On Saturday June 20th Fort Mattagami raised its flag in honor of our arrival. Mr. Miller, agent of the Hudson Bay Company there, entertained our party royally, showing us everything of interest at the fort, including his general store, the English church, sawmill, garden, cattle, chickens, etc. The soil at the fort, though very sandy, has been made to yield, by the use of farmyard manure, excellent potatoes, cabbages, turnips, beets, peas, beans and other vegetables, and some small fruits. However, the country we passed through between Metagama and Fort Mat-Mattagami is extremely rocky and not at all suited for farming,—though of value to the lumbermen, being wooded with black and white spruce, poplar and some white pine. Tisdale township, the first scene of our operations, was reached two days later.

I have divided the Abitibi region into nine districts; each district is briefly described, and a summary of the notes taken on the trees, soil, and surface of the country, of the principal water courses, portages and inland surveys is tabulated for each district. The trees are named in order of abundance.

Tisdale Township

The country in this township and neighborhood is very irregular. Some parts are low and swampy with large tracts of muskeg; then again there are numerous rocky ridges which are either bare or too stony for cultivation. The floor of the low land consists of sphagnum and other bog mosses, varying in depth from a few inches to several feet. The soil beneath this floor is mostly sand or gravel.

(19) The Huronian of the Moose River Basin, by W. A. Parks.

Digitized by Google

Porcupine Lake District

The land in this district is not so low and rocky as it is in Tisdale township. The soil for the most part is sandy, and the country as a whole will not make very good agricultural land. The timber around the lake is chiefly spruce, aspen, birch, larch and scattered clumps of balm of Gileads. Inland in the township of Whitney there is considerable muskeg consisting of small black spruce and larch.

Area Traversed.	Trees.			Soil.	Surface of country.
	Kind.	Size.	Quantity.		
Portage leading to Tennyson lake.....	Spruce	Large.....	Fairly thick	Clay loam near river bank; sandy over remainder of the portage.	High and dry, and then low and swampy.
	B. Pine	Medium.	Scattered.		
	Balsam	"	"		
	B. of Gilead	"	"		
Small portage between Tennyson and Jarvis lakes.	Balsam	Large.....	Fairly thick	Sandy	Dry and level.
	Aspen.	Medium.	Scattered.		
	Spruce.....	"	"		
Country surrounding Tennyson Lake..	B. Pine....	Large.....	Fairly thick	Sandy	Level country and rocky.
	Spruce.....	"	"		
	Birch.	"	"		
	Aspen.....	"	Scattered.		
	Larch.....	Medium.	"		
Country surrounding Jarvis lake	Spruce.....	Large.....	Fairly thick	Sandy	Level country and very rocky.
	B. Pine	Medium.	"		
	Larch.....	"	Scattered.		
Inland trip 2½ miles north of Jarvis lake.	Spruce	Small.....	Large area of muskeg.	Sandy soil below sphagnum moss.	Level, and very rocky in places.
	Larch.	"			
	B. Pine	Medium.	Rocky areas		
	Birch. .. .	"	Scattered.		
	W. Cedar ..	"	"		
Short portage ¼ mile long between Jarvis and Delbert lakes.	Spruce	Medium....	Fairly thick	Sandy	High and level.
	Birch.	"	"		
	Balsam....	"	Scattered.		
Trip south to Niven's line from Delbert lake.	Spruce	Large.....	Fairly thick	Sandy soil on way to Niven's line; clay soil on Niven's line and on return trip.	Level country, high and dry.
	Aspen.	"	"		
	W. Cedar ..	"	Large cedar swamp.		
Portage from Delbert lake to Porcupine lake.	Spruce	Medium.	Fairly thick	Sandy soil near Delbert lake, and clay soil near Porcupine lake.	Fairly dry over first part of portage, low and swampy over latter part.
	Aspen.	"	Scattered.		
	Birch.	"	"		
	Balsam....	"	"		

Porcupine River

The country surrounding the Porcupine river is mostly dry, and when cleared will make very good farming land. The soil tested on the banks and in the inland country is mostly clay loam, and is well covered with vegetable matter. For about three miles up the Porcupine river, on either side, there is a swampy tract of land covered chiefly by large larches, which are mostly dead or dying from the attacks of the larch saw-fly. From here on the timber, in the immediate vicinity of the river, consists of birch, spruce, aspen, balm of Gilead, black ash, all of which are of a good size, and the land thickly wooded.

Night Hawk Lake

This lake is dotted with islands, a few of which are rocky and bare of flora, while most of them are nicely wooded, giving the lake a picturesque appearance. The banks of this lake on the south and west shores are from 10 to 35 feet high, and vary greatly in composition. Most of the banks are stratified clay deposits, but here and there are glacial deposits of sand and gravel which will be of great value to the settler in road-making. On the north and east shores the banks and surrounding country are very low.

There are many rivers running into Night Hawk lake. These rivers are broad and marshy, having low banks in the vicinity of the lake. In the marshes the yellow water-lily, buckbean, water plantain, beaver hay, rushes, etc., are most common.

Digitized by Google

In proximity to the lake are large areas of dead trees which have been killed by the water rising in the lake.

The higher land around the lake is well timbered. Here and there are large clumps of black ash and balm of Gilead; spruce, aspen, and birch are also common. On the south shore there is a grove of red pine, some of which will measure about 16 inches in diameter.

tance back from the lake. This inland country, with the exception of a few low areas near the lake, and occasional tracts of muskeg, will make splendid agricultural country.

Frederick House Lake

On July 11th our party left headquarters on Night Hawk lake and started for Frederick House river. The timber

Area traversed.	Trees.			Soil.	Surface of country.
	Kind.	Size.	Quantity.		
Around Porcupine lake	Spruce.....	Large.....	Fairly thick...	Clay and sand.....	Level country.
	Birch.....	Medium	Scattered.		
	Aspen	"	"		
	B. of Gilead	"	"		
	Larch	Small.....	"		
Whitney township, inland 4 miles east from S. E. shore of Porcupine lake.	Spruce.....	Large.....	Fairly thick ...	Clay soil; gravel and sand area.	Some fair farm land; level country.
	Cedar.....	Medium	Large.		
	Aspen	"	Scattered.		
	Muskeg....	Small.....	Large area.		
	Balsam	Medium	Scattered.		

On 4th July we visited an Indian garden, which was located on one of the islands on Night Hawk lake. The potato stalks were about seven inches high, and had not been injured by frost. Onions, turnips, carrots and cabbages were all thriving, even with the little care that was bestowed upon them. Among the weeds noticed in the gardens were shepherd's purse, curled dock, lamb's quarters, broad-leaved plantain, lady's thumb, strawberry blight, horseweed, great willow herb and cow parsnip. These grew in great abundance, indicating a rich soil.

On our inland trips from the lake we noticed the surface of the country to be more undulating, and thus drier, a distance back from the lake. This inland country, with the exception of a few low areas near the lake, and occasional tracts of muskeg, will make splendid agricultural country.

Area traversed.	Trees.			Soil.	Surface.
	Kind.	Size.	Quantity.		
Porcupine river between Porcupine lake and Night Hawk lake.	Spruce	Large.....	Thick	Clay banks.....	Level country; when cleared will make good farming land.
	Aspen	"	"		
	Birch	"	"		
	Larch	"	Scattered.		
	B. of Gilead	"	Small clumps.		
	Balsam	Medium	Scattered.		
	W. Pine ...	"	"		
	W. Cedar ..	"	"		
Hoyle township; 6 miles up Porcupine river; went west 2½ miles.	Spruce.....	Med'm to large	Fairly thick...	Clay banks.....	Level land, inclined to be a little swampy in places.
	Aspen	Medium	Scattered.		
	Cedar.....	"	"		
	Larch	"	"		
	Balsam	"	"		
Hoyle township 8 miles up Porcupine; went east 3⅛ miles.	Spruce.....	Medium	Thick	Clay soil.....	Level land and a little wet in places
	Aspen	Large.....	Scattered.		
	Birch	"	"		

Frederick House River

On July 11th our party left headquarters on Night Hawk lake and started for Frederick House river. The timber along this river is small, and not of much value to the lumbermen. The soil is clay or clay loam, and the surface of the country is more or less undulating, and thus well drained. This area will make a splendid agricultural district.

The trees around Frederick House lake are fairly abundant but not very large. Excluding a few large sand hills on the northwest side of the lake, the soil is mostly clay or clay loam. This lake, like Night Hawk, is very shallow and subject to sudden storms.

Long Portage District

This district is for the most part a high and dry sand plain, with occasional

Digitized by Google

valleys of clay or clay loam. Large Banksian pine are the most common trees on the higher areas, while spruce, aspen and balsam form the bulk of the timber on the lower levels.

Moose Lake

After leaving the third long portage we arrived at a small unnamed lake, where we camped over night. In the morning we crossed this little lake and paddled up Driftwood creek leading out of this lake and flowing into Moose lake.

Driftwood creek is narrow and winding, and deep in many places. Alders, dogwood, and small willows are very thick on the banks, and choke the river here and there. There was good looking clay soil on several bank exposures. This creek or river traverses very level land and within a mile or so of Moose lake there are broad marshes on either side of the river. Ducks were numerous in these marshes and the young were just commencing to fly.

Moose lake is certainly well named. It is practically one large marsh. The yellow water lily, rushes, and sedges are thick over the whole lake and form the ideal feeding ground of the moose. On the banks on the opposite side of the Driftwood creek marsh the trees are chiefly spruce and aspen, with a few birches and a few clumps of balm of Gilead.

Driftwood river flows out of Moose lake into Black river. For the last 6 miles of travel in this river there were many log-jams which greatly impeded our progress.

The trees on either side the river all the way from Moose lake to Black river are abundant and large. At the entrance of the Driftwood river, and for a short distance up the river, there are close to the shore small groves of black ash, and several small clumps of balm of Gilead. The clay banks were from two to several feet high, and the general surface was rolling land, becoming more so as we neared Black river.

Area traversed.	Trees.			Soil.	Surface.
	Kind.	Size.	Quantity.		
Cody township; went up small river ¾ of a mile, and then about a mile into Cody township.	Spruce Birch Aspen Balsam	Large " " Medium	Fairly thick Scattered. " "	Clay loam	Dry. Farming land
Redstone river, 9 miles up from the lake.	B. Ash Spruce Cedar B. of Gilead Aspen Elm	Medium " Large Medium " "	Many small clumps. Scattered. Swamp. Small clumps. Scattered. "	Clay loam	Level country.
Carman township; left rapids 9 miles up Redstone river and went east towards Night Hawk lake 2¾ miles.	Spruce Cedar Balsam Birch Aspen	Large " Medium " "	Scattered Thick in swamp Scattered. " "	Clay	Low and swampy over most of this area.
Dance township; left rapids 9 miles up Redstone river, and went west 2¼ miles.	Spruce Aspen Balsam W. Cedar N. Pine	Large " " " "	Thick " Scattered. " "	A few to several feet of sandy soil above clay bottom.	High and dry land. Good place for a pulp mill.
Night Hawk river	Spruce Aspen Cedar B. of Gilead Balsam Birch	Medi'm to large Medium " " " "	Thick " " " Scattered. "	Clay banks	Level country.
Thomas township. Went up Night Hawk river 9 miles, then crossed Thomas township back to lake 3½ miles.	Spruce Balsam Birch Aspen Muskeg	Large Med'm to large Small	Thick Scattered. Small area.	Clay soil over most of this trip. One sand patch ¼ of a mile across.	Level country, most of it dry and fit for farm land.
Dundonald township. Went east from Night Hawk lake into Dundonald township 3 miles.	Birch Spruce B. Pine Aspen B. of Gilead	Large " " " "	Scattered Thick. Scattered. "	Clay soil over most of area. About one mile of sandy soil covered with B. pine.	Most of this area will make good farm land.

Digitized by Google

Black River

In the Black river district the land, from the Abitibi river to the White Clay river, is mostly rolling, and is thus well drained. From the evidence of many dead trees on either side of this river, for several miles up from its mouth, I should say that the country for several miles around is flooded during the spring season. The timber along the river consists of aspen, spruce, birch, balsam, balm of Gilead, white cedar, larch, and rarely black ash and white elm. Leaving out one large brule, a few thinly wooded areas, and a few Banksian Pine plains, the timber along the banks of Black river is large and of abundant habit.

The soil over the greater part of this area varies from light to heavy clay. Here and there are sand plains or ridges of sand and gravel.

Area traversed.	Trees. Kind.	Size.	Quantity.	Soil.	Surface.
Frederick House river.	Aspen	Small.....	Fairly thick...	Clay or clay loam..	Undulating; good farm land.
	Spruce.....	"	"		
	Larch.....	"	Scattered.		
	B. of Gilead	"	Small clumps,		
	Willow	"	Scattered.		
	Birch, ...	"	"		
Matheson township, 3½ miles in from Frederick House river.	Spruce	Medium	Fairly thick ..	Clay over most of area. Sand and gravel ridge about ¾ of a mile.	Undulating; good farm land.
	Birch	"	"		
	B. of Gilead	Large.....	"		
	Aspen	Medium	Scattered.		
	Cedar.....	"	"		
Frederick House lake.	Spruce	Med'm to large	Fairly thick...	Stratified clay banks. Sand banks.	Undulating; good farm land.
	Birch	Large.....	"		
	Balsam.....	Medium	Scattered.		
	Aspen	"	"		
	B. of Gilead	Large.....	"		

Timber of the Region

Following is a list of the forest trees, in order of their abundance:

Black Spruce, (Picea nigra); White Spruce, (Picea alba); Aspen Poplar, (Populus tremuloides); Paper Birch, (Betula papyrifera); Balsam, (Abies balsamea); Balm of Gilead, (Populus balsamifera candicans); Banksian or Jack

Area traversed.	Trees. Kind.	Size.	Quantity.	Soil.	Surface.
Matheson township. Trip inland from Long portage about 2½ miles.	Spruce	Large.....	Scattered	Very fine sand ¾ of a mile; ¼ mile clay muskeg rest of way.	High and dry. Swampy.
	Birch	"	"		
	Muskeg....	Small.....	Large area, one mile from portage.		
1st long portage 2 miles long.	Banksian pine	Medium	Thick	Fine sand	High and dry.
German township 3½ miles inland from long portage.	Banksian pine	Medium	Thick	Fine sand; clay for last 1½ miles.	High and dry for first 2 miles, then low and swampy for 1½ miles.
	Spruce.....	Large.....	Fairly thick.		
	W. pine ...	"	Scattered.		
2nd long portage 2 miles long.	Banksian pine	Large.....	Thick.	Sand	High and dry.
Trip from 3rd small lake to Night Hawk lake.	Spruce.....	Large.....	Thick	Sand for first half mile, clay over next 2 miles.	High and dry over most of this area.
	Aspen	"	"		
	Banksian pine	"	"		
	Birch.....	"	"		
	Muskeg....	Medium	"		
3rd long portage 2¼ miles long,	Banksian pine	Large.....	Thick	.....	1½ miles high and dry; last ¼ mile very low and swampy.
	Spruce.....	"	Scattered.		
	Birch	"	"		
	Aspen	"	"		
	Muskeg....	Small.....	Thick.		

Digitized by Google

Pine, (Pinus banksiana); White Cedar, (Thuya occidentalis); Larch or Tamarac, (Larix americana); Black Ash, (Fraxinus sambucifolia); Norway or Red Pine, (Pinus resinosa); White Pine, (Pinus strobus); White Elm, (Ulmus americana); Soft Maple, (Acer dasycarpum).

Some of the smaller species of trees, in order of abundance, are :—

Mountain Maple, (Acer spicatum); Alder, (Alnus incana); Mountain Ash, (Pyrus americana); Shad-bush or Juneberry, (Amelanchier canadensis); Wild Red Cherry, (Prunus pennsylvanica); Mountain Alder, (Alnus viridis); Willow sp., (Salix sp.).

On the level inland country black spruce is the most abundant. The trees measure from 10 to 24 inches in diameter. On the rocky areas and sand plains jack or Banksian pine forms about 90 per cent. of the trees. This tree measures from 10 to 24 inches in diameter. In the swampy areas white cedar and larch are most common. Cedar swamps are fairly numerous and the cedar trees measure from 15 to 30 inches in diameter. Most of the larch trees are dead or dying from the attacks of the larch saw-fly. On the banks of rivers and on the shores of the lakes, where the land is well-drained, white spruce, aspen, birch, balm of Gilead, and black ash are most abundant. Aspen measures from 10 to 18 inches in diameter. White spruce measures from 14 to 24 inches in diameter; balm of Gilead from 12 to 20 inches in diameter.

There are considerable areas of muskeg. In these areas the timber consists of small black spruce and larch, from 3 to 5 inches in diameter and of very little commercial value.

Area traversed.	Trees.			Soil.	Surface.
	Kind.	Size.	Quantity.		
Inland trip to Drift-wood river from camping ground 9 miles up Black river.	Spruce	Medium	Thin	Clay soil	Rolling over most of this area. Good farm country.
	Aspen	Large	Scattered.		
	Balsam	"	"		
	B. of Gilead	"	"		
Black river	Aspen	Large	Thick	Chiefly clay	Rolling land. Good farm country.
	Spruce	"	"		
	Birch	"	Scattered.		
	Balsam	"	"		
	B. of Gilead	"	"		
	Banksian Pine	Medium	Thick in places		
	W. Cedar	"	Scattered.		
	Larch	"	"		
	Elm	"	"		
	Brule		Several square miles.		

Birds of the Abitibi

At the season of our field work many of the birds were nesting and, therefore, it was not the best time to study them. Many Warblers were seen in the tree tops, but, having broken my field glasses on the way up I was unable to determine or even describe the species. A list of the birds noted is given below :

Canada Grouse, (Dendragapus canadensis); Ruffed Grouse, (Bonasa umbellus); American Goshawk, (Accipiter atricapillus; Screech Owl, (Megascops asio); Night Hawk, (Chordeiles virginianus); Phoebe, (Sayornis phoebe); Wood Pewee, (Contopus virens); Catbird, (Galeoscoptes carolinensis); Belted Kingfisher, (Ceryle aeyon); Downy Woodpecker, (Dryobates pubescens); Flicker, (Colaptes auratus); Hairy Woodpecker, (Dryobates villosus); Cliff Swallow, (Petrochelidon lunifrons), Cedar Waxwing, (Ampelis cedrorum); Northern Shrike, (Lanius borealis); Yellow Warbler, (Dendroica aestiva); Wilson's Thrush, (Turdus fuscescens); Robin, (Merula migratoria); Loon, (Urinator imber); American Herring Gull, (Larus argentatus smithsonianus), Chickadee, (Parus atricapillus); Rusty Blackbird, (Scolecophagus carolinus); Vesper Sparrow, (Poocaetes gramineus); Canada Jay, (Perisoreus canadensis); Crow, (Corvus americanus); Bronzed Grackle (Quiscalus quiscula aeneus); Purple Finch, (Carpodacus purpureus); House Sparrow, (Passer domesticus); White-throated Sparrow, (Zonotrichia albicollis); Chipping Sparrow, (Spizella socialis); Black Duck, (Anas obscura).

Digitized by Google

Wild Animals

The following is list of the animals noted :—Moose, 31 ; Red Deer, 11 ; Black Bear, 4 ; Otter, 1 ; Beaver, 1 ; Muskrats,Hares, Red Squirrels and Chipmunks, numerous ; Garter Snake, 1 ; Toads, common ; Leeches, common.

Moose are the largest, and judging from the number seen on our survey and the abundance of tracks on the banks of the rivers and shores of the lakes, they are without doubt the most abundant of the larger animals. Their favorite haunts seemed to be along the marshy rivers running into Night Hawk lake and on the shores of Frederick House river, which flows out of it. The yellow water-lily rootstalk and marsh grasses seemed to form the bulk of their summer food.

The Red Deer are more timid than the Moose, and do not prove such easy prey to the hunters as the latter. They were found most abundantly around the little lakes in Long Portage district.

Black bear are not very common in this district, only four being seen on the whole trip. One of these was found on Molle lake and the other three on the Black river.

Thanks to the wise legislation in the protection of the beaver, this animal is becoming much more numerous and the danger of its extermination has been warded off for some time. Fresh beaver dams were very common on the smaller inland rivers. On a small unnamed river in Tisdale township, south of Tennyson, Delbert, and Jarvis lakes, there were fresh beaver dams every few yards.

At Fort Mattagami I obtained a list of the furs traded by the Indians at that place for the year ending May 1903. The following is the list : Ermine, 200 ; Bear, 50 ; Fisher, 15 ; Lynx, 15 ; Marten, 250 ; Mink, 200 ; Muskrat, 2,000; Wolf, 1; Otter, many.

The Indian hunting season extends from about the middle of September to about the middle of June. The Indians were just coming home from their winter's hunt the day we landed at Fort Mattagami on 21st June.

Fish

Perch, Whitefish, Pike, and Pickerel are the most common species found in the rivers and inland lakes of this region. Pickerel are very numerous in Porcupine lake, and Pike may be obtained in almost all of the waters.

Flies of the Abitibi

Throughout the whole trip we were constantly pestered by flies of various species. I shall endeavor to convey some idea of the habits of these tormentors and our experience with them.

The level wooded country of the Abitibi regions abounds in swamps, marshes and muskegs, which form ideal breeding places for mosquitoes. They proved to be the most troublesome pests which we encountered during our trip. They began to be very annoying soon after we took to our canoes at Metagama, and from that time until we reached Mattawa on our return there was no respite. It is impossible to convey an adequate idea of the suffering which we were obliged to endure from their attacks, and no application of oil or salve to our hands and faces seemed to have any effect in keeping them off.

Although they were very annoying at all times, they were probably most active on cloudy days and at a temperature ranging from 45 degrees to 70 degrees F. They were more numerous on land than on water, but we were nearly always accompanied by a swarm even when far from shore.

I was surprised that we did not occasionally meet with Indians in the woods. On inquiry I learned that they never hunt during the summer months when flies and mosquitoes are out, but congregate at the forts where they can protect themselves to some extent from the insects by building smudges, thus keeping the atmosphere constantly laden with smoke. Even dogs at Fort Mattagami have learned to creep close to the smudges for protection. Let it be remembered that while the hands and face were the special points of attack, the mosquitoes did not limit themselves to these exposed parts, but would even insert their probosces through our thick duck trousers and suck the blood to their hearts' content.

Black Flies

Next in importance to the mosquitoes may be mentioned the Black Flies (Simulium molestum). These are small black insects about one-eighth of an inch in length, with stout bodies and bulging thoraxes. The mouth parts are very curious, and Prof. J. B. Smith has ascertained that the females, which alone suck blood, possess, besides the usual sucking organs, genuine biting mandibles. Unlike the mosquitoes, they breed in rapidly flowing water. Although the bite of these flies is not

Digitized by Google

poisonous, it is very severe, drawing blood freely. I frequently noticed the faces of my companions streaked with blood, the result of fly-bites. We experienced the greatest discomfort from these flies on bright warm days, and between 9 a.m. and 9 p.m. They did not trouble us much during the hours of darkness, but seemed to congregate on the walls of the tent in search of light. They were not attracted by lamp-light. While the bites of the black flies were very painful, we also suffered from their getting into our nostrils, our ears, and under our eyelids. We experienced much inconvenience, too, by their congregating in large numbers in soup, gravy, and other articles of diet. This vexed our jovial half-breed cook so much that he once remarked he would not mind cooking for us if he could only board somewhere else himself.

At one time the back of my neck was so lacerated by fly-bites that it became stiff and swollen, and I was unable to turn my head for several days. Heavy applications of carbolic salve to the face and hands seemed to prevent the attacks of these flies to some extent. I observed that they were troublesome not only to man but also to moose, deer, and dogs, and that they were more active in June and early July than later in the season.

Sand Flies

These flies are very small yellowish insects, with transparent, whitish-colored wings having somewhat darker spots. I found great difficulty in capturing specimens, as it was impossible to handle them without crushing them. By placing a green leaf on the back of my hand and allowing them to crawl on it, I succeeded in securing a number by folding the leaf and inserting it into a cyanide bottle.

The bites of these insignificant-looking insects are very poisonous, causing much swelling and a painful, burning sensation. Though the sand flies look insignificant they never allow one to be ignorant of their presence day or night. They adhere very closely to the skin; they crawl up under shirt sleeves and trouser legs; and keep the whole surface of the body in a state of constant irritation. Unlike the black flies they are attracted by lamplight or firelight, and are therefore very troublesome around the camp fire.

Deer flies (Chrysops) are large flies about half an inch in length. We found them very numerous in July, and experienced much discomfort from their attacks. The bite is not poisonous, but causes sharp, severe pain. They are not troublesome excepting on clear, hot days. These flies attack deer and moose as well as man.

Bull-dog tabanus (Tabanus affinis): This was the largest of the fly torments of the Abitibi. Like the deer fly, it was troublesome only on clear, hot days in June and July.

In conclusion I may say that although the various species of flies above described are exceedingly troublesome at the present time, it is altogether probable that as the country becomes cleared and drained and the soil cultivated, they will largely disappear and life will then be as tolerable in this region as in the older parts of the Province.

Injurious Insects

Larch Saw Fly (Nematus erichsonii): Nearly all of the larch or tamarac trees in this northern country have been destroyed by the larvae of this saw fly. During the early part of July the adult flies were seen floating down the Porcupine river, and a few days later the shore of Night Hawk lake was covered with them. Pupa-cases were found in masses beneath the surface of vegetation of all the trees examined in the district. The flies deposited their eggs about the first week in July and the eggs hatched about the 12th of July.

Spruce Gall Louse (Chermes abietis): The Gall Louse was very common on the black and white spruces. The spruces along the water seemed to suffer more than the inland trees, and the white spruce more than the black.

Birch Case-Bearer (Coleophora sp.): This insect was found feeding on the paper birch and alder. In some districts it was very common and destructive to the birch.

American Tent Caterpillar (Clisiocampa americana): Found about one hundred miles north of Metagama feeding on the leaves of the wild red cherry.

Pale Brown Byturus (Byturus unicolor): This pest was found throughout the district feeding on the leaves and buds of the wild raspberry.

Pine Borer (Monohammus confusor): A few specimens of this Borer were found and the work of the insect was noticed in a few places.

American Saw-Fly (Cimbex americana): The larvae of this insect were found in considerable numbers on the willow trees around Night Hawk lake.

Lace Bugs (Corythuca arcuata): Common on the birch and alder throughout the region.

Digitized by Google



Drift boulders, south shore Night Hawk lake.



Falls on Black river.

Digitized by Google

UNIV. OF MICH.

Digitized by Google



Canoeing in shallow waters; Pike river.



Indian hut and garden, Night Hawk lake.

Digitized by Google

UNIV. OF MICH.

Digitized by Google

Indian wigwam, Black river. (Note luxuriant vegetation.)



Contorted laminated clay, south shore Night Hawk lake.

Digitized by Google

UNIV OF MICH.

Digitized by Google



Tomstown, on the Blanche river, a new centre in northern Ontario. The Government road runs directly west into Evanturel township.



Fort Mattagami.

Indian camping ground, Fort Mattagami.

Digitized by Google

UNIV. OF MICH.

Digitized by Google

Spittle Bugs (Aphrophora sp.) : Common on the red osier dog wood, spruces and many herbs.

Cabbage Butterfly (Pieris rapae) : The larvae of this insect were found in the Indian gardens around Night Hawk lake, feeding on turnips and cabbage. The adults were found throughout the region generally.

Clouded Sulphur (Eurymus philodice); Adults were quite common around Night Hawk lake.

Cut Worms (Hadena sp.) : Very injurious in gardens at Fort Mattagami, and common in the Abitibi region.

Alder Blight (Schizoneura tessellata) : Alders were covered with this insect.

Yellow Swallow Tail (Papilio turnus) : These butterflies were found in the same places as the Banded Purple, and usually accompanied them.

Fall Canker Worm (Alsophila pometaria) : Found on the birch, aspen and many other shrubs throughout the district.

Polyphemus Moth (Telea polyphemus) : These were observed floating on the water, and flying around the river banks.

Locusts : Common in dry places, but most of them were in the nymph stage.

Tettix sp.: Common in wet places and along river banks.

Pine-cone Willow Gall (Cecidomyia strobiloides) : Galls were found on the heart-leaved willow.

Day of month.	Abitibi. Max. temp. F.	Abitibi. Min. temp. F.	O. A. Coll. Max. temp. F.	O. A. Coll. Min. temp. F.	Abitibi.	O.A. Coll. Inches rain.
June.						
25	80	58	63	51	Heavy thunder storm	.42
26	68	56	66	47	Cloudy day	
27	82	59	76	47	Clear day	
28	70	54	75	49	Rained considerable in morning	
29	69	58	71	53	Clear day	
30	74	58	82	63	"	.07
July.						
1	71.5	55	82.5	61	Commenced to rain at 10 a.m. and rained all day	.24
2	73	36	84	67	Fine clear day	
3	71	38	81.5	58	Fine clear day and rained a little in evening	.01
4	73	49	72.5	61	Fine clear day	.76
5	79	53	72.5	60	"	.05
6	79.5	58	82	54	"	
7	84	68	83	57	Thunder shower in morning, rained very little	
8	81	68	83	57	Clear day	
9	84	57	88	67	Cloudy in afternoon	
10	78	59.5	90	71	Rained heavily during night	.09
11	74	44	90	62	Heavy thundershower to-day	.04
12	64	45	80.5	62	Showery all day	.02
13	61	45	80	48.5	"	
14	69	47	71	57	"	
15	69	49	65	43	Clear day	
16	69.5	51	66	49	"	
17	73	57	75	50	"	
18	64	49	77	60	Cloudy all day	
19	72	48	71	56	Cloudy all day, rained a little	
20	74	48	72	57	Cloudy all day	
21	72	46	76	54.5	Clear day, heavy thunder shower in evening	
22	80	53	77	57	Mostly clear all day	
23	82	48	71	56	A little cloudy	
24	64	47	83	58	Clear morning, showery all afternoon	
25	67	46	87	62	Showery all day	
26	70	46	87	77	Clear all day	

Scurfy Bark Louse (Chionaspis sp.) : Found on the alder at Frederick House lake.

Ash Colored Blister Beetle (Epicauta cinerea) : Found feeding on the wild vetch near Porcupine lake.

Black Blister Beetle (Epicauta Pennsylvanica) : Found feeding on golden rod.

Buttercup Oil-Beetle (Meloe angusticollis) : Found in grass.

Maple Borer (Dicerca divaricata) ; The adult of this borer was found in the middle of July around Night Hawk lake.

Banded Purple (Basilarchia arthemis) : This butterfly was found in open places along river banks.

Birch Aphis (Aphis sp.) : Aphids in this country were very uncommon, but birch aphids were found in small numbers on nearly all birches.

Potato Beetles (Doryphora decemlineata) : A few potato beetles were found in the Indian gardens at Fort Mattagami.

Aspen Leaf Roller : This insect has caused considerable damage to aspens in this region.

Balm of Gilead Leaf-Gall : This was common on many trees around Frederick House lake.

Digitized by Google

Weather Observations

In the foregoing table I have given, for comparison, the notes taken at the Ontario Agricultural College, Guelph, on the temperature of the air and other data. The maximum reading of the temperature of the air was made between 1 and 2 in the afternoon, and the minimum reading between 4 and 5 in the morning.

Abitibi Soils

Some 27 samples of soils, typical of the various districts traversed, were collected, all of them being taken from below the immediate covering of vegetable matter on the surface. They were submitted to Prof. Reynolds of the Physical Department, Ontario Agricultural College, for a physical analysis. Messrs. Bracken, Kennedy and Tennant, O. A. C. students, are responsible for the results as given below :

Methods of Analysis

In the analysis of these soils they were treated in the following manner :

(1) They were first examined and described as they appeared to the naked eye, the differences in color and physical properties being particularly noticed.

(2) They were then placed under a microscope, where the color, size, and structure of the particles were particularly noticed; also the composition of the soil, e.g., quartz, feldspar, clay, organic matter, and cinder.

(3) Twenty grammes of each sample were then weighed out, and after being placed in a copper beaker, and covered with water, boiled for an hour and a half to separate completely all particles. The soil and water was then poured into a glass jar about fifteen inches in height and three inches in diameter, and allowed to stand for two minutes. At the end of this time the water was poured off down to within two inches of the soil. The jar was then filled with fresh water, and allowed to stand another two minutes, when it was again poured off in the same manner as before. When the water became clear it was poured off as before, and the moisture evaporated from the soil remaining. This was subsequently weighed and the character of the soil found by the percentage, in weight, of the particles greater than .001 inches, it being assumed that all particles of greater diameter would settle in water in two minutes. The soils were then placed in their respective classes by use of the following table :

Classification of Soils

Soil.	Amount greater than .001 in.	Amount less than .001 in.
Heavy clay.....	0- 10 gms.	100-90 gms.
Clay	10- 25 "	90-75 "
Clay loam.....	25- 40 "	75-60 "
Loam.....	40- 60 "	60-40 "
Sandy loam	60- 75 "	40-25 "
Light sandy loam	75- 90 "	25-10 "
Sand	90-100 "	10- 0 "

The particles greater than .001 in. were then placed under the microscope and again observed.

During all these operations the aim was to get at the accurate composition of the soils.

The Samples Examined

Sample No. 1. Typical soil of Dance township: taken from near the river bank, a short distance from the rapids where we terminated our trip on the Redstone river.

Light in color and lumpy. When examined under the microscope sand is seen to be the predominant constituent. This sand is of a very fine character, and is evidently held in lumps by the vegetable matter and the clay. After a beaker analysis this soil proves to be a sandy loam, having 69.45 per cent. of sand and silt. After separating the sample into sand and slay, the humus remained about evenly distributed in each, and was in such fine particles as would readily be reduced to plant food. Judging from the analysis of this soil it should be of average fertility and of excellent texture.

Sample No. 2. A sample of subsoil collected about 200 yards from creek between Delbert and Porcupine lakes.

This soil is light gray in color. The soil grains adhere together in small hard lumps varying in size from 1 inch in diameter downwards. There is a very slight appearance of vegetable matter present. A mechanical separation showed that 21.3 per cent. of this sample is sand. Both the sand and clay have a slightly reddish tinge. This soil is therefore a clay lacking in humus and vegetable matter.

Sample No. 3. Soil taken a few yards inland from the junction of the Abitibi and Black rivers.

It is of a light gray color, with dark streaks running through it. A very adhesive soil, the sample being in a hard lump, indicating presence of much clay. On powdering a lump, considerable cinder and several little pieces of organic matter were found. A microscopical ex-

Digitized by Google

amination showed a little fine sand. After a beaker analysis this soil proves to be a clay loam, having 29.35 per cent. of the particles greater than .001 inches in diameter. On microscopical examination of these particles they prove to be mostly crystalline. Some are white in color, a considerable number light gray, and a few of yellowish tinge. They are all very small, and are apparently quartz and feldspar. This would be a very profitable soil with cultivation and the addition of humus.

Sample No. 4. Surface soil of Cody township.

This soil is dark in color and very lumpy. The lumps are very firm and difficult to break down. Looking at this soil with the naked eye, the sand, humus, and clay are in such small particles that the presence of humus would not be seen, except that it gives the whole a darker color than it would otherwise have. When examined under a microscope one finds the sample is composed of a white sand and clay mixed with very fine humus of a dark color. A beaker analysis proves this sample to be a sandy loam, containing 64.06 per cent. sand and silt. After the separation the humus seems about evenly distributed between the sand and clay.

Sample No. 5. A sample of soil in Cody township taken at Niven's line three-quarters of a mile up a stream which flows into Night Hawk lake.

This soil is of a gray color. The texture is very good. The soil grains are joined together in very small lumps. Some organic matter is present, consisting of broken roots and stems of plants. Under the microscope the soil grains appear principally in compound particles. The mechanical separation showed the presence of 43 per cent. of sand in the sample. The sand was quite dark in color; the clay was a little lighter-colored. This soil is therefore a clay loam with a small portion of humus and vegetable matter mixed with it.

Sample No. 6. Typical soil of Dundonald township.

It is a very light gray in color, much resembling clay, but not baked, being in a very friable and porous condition. The size of grains ranges from that of dust to that of peas. It shows a little organic matter in a state of decay. On microscopical examination it shows presence of fine particles with a tendency to compound structure. It is gritty and seems to be a mixture of sand and clay. A beaker analysis proves it to be a clay loam, having 29.25 per cent. of particles greater than .001 inches. A microscopical examination of these proves the presence of white and black particles of a crystalline nature and brownish water-worn pebbles. The former are probably quartz and mica. These particles range in size from that of a pin point to a few the size of a clover seed. This appears to be a good soil and one which would be fairly easy to work and give good returns.

Sample No. 7.—Carman township subsoil pulled out by a ground-hog about half a mile from camping ground on Redstone river.

It is light in color. The sand is coarse and the humus scanty. Analysis shows this to be a light sandy loam, containing 76.06 per cent. of sand and silt. When the separation was made the clay portion apparently contained some coarse light vegetable remains, in such small proportions as to be of little importance.

Sample No. 8. A sample of soil collected in Whitney township.

This soil is dark gray in color. It is in a fine mellow condition. There are very few lumps in it and those present are quite small. There is a considerable quantity of undecayed vegetable matter present in the form of small pieces of wood and leaves. Under the microscope considerable quantities of vegetable matter can be seen; some of it is in the form of humus, as indicated by the black color. There are compound particles and separate grains in about equal quantities. This would show that the soil is a loam with a large quantity of vegetable matter in it. A mechanical separation showed the presence of 69 per cent. of sand in the sample. Both the sand and the clay are quite dark in color. This proves to be a sandy loam with a considerable quantity of humus in it.

Sample No. 9. Soil taken a few yards inland from about 7 miles up the Black river.

This is in uneven clods of a light gray color. It has a gritty feeling. It is quite adhesive and shows very little organic matter. On microscopical examination it shows some very fine clear-cut particles of white sand, much brownish-gray gritty matter mixed with fine dust, presumably clay, and some dark specks of cinder. A beaker analysis shows this to be a clay loam. These particles are found on microscopical examination to be principally white crystalline pieces of quartz with a small proportion of feldspar or yellow particles.

Digitized by Google

Sample No. 10. Soil of German township.

This is of a dark color; coarse vegetable matter can be seen with the naked eye. Microscopically one finds this sample rich in fine humus, which acts on the sand, which is also very fine, causing it to form into hard lumps. This proves to be a sandy loam. It contains 66.75 per cent. sand and silt. In the separation the greater part of the humus remained in the residue along with the sand and silt, making this portion dark in color, while the clay was light in color, apparently containing but little humus.

Sample No. 11. Soil collected in Dance township from a delta deposit carried down by the river.

This soil is of a light gray color. There varying in size from a hen's egg down. are a large number of lumps present These lumps are very hard and difficult to break down. Under the miscroscope the soil grains appear to be in compound particles. There is very little appearance of separate soil grains and no noticeable quantities of humus. Apparently this soil is a heavy clay and lacks vegetable matter. A mechanical separation was made which showed the presence of 75 per cent. of sand. A slightly darkened color of the sand would indicate the presence of a slight amount of humus. This soil is clay loam.

Sample No. 12. Soil taken from Dance township.

This gives every appearance of a rich dark loam. It is made up partly of fine powder and partly of lumps about as large as a pea. It contains a large proportion of humus. Viewed under the miscroscope it is found to be composed of white quartz and a fine dark powder, probably decayed vegetable matter, in about equal proportions. After a beaker analysis a miscroscopical examination proves the presence of quartz and also shows a small proportion of feldspar. The particles of each are so small that they cannot be recognized by the naked eye. It proves to be a loam, having 51.57 per cent. greater than .001 inches in diameter. This soil has a first-class texture and is rich in humus.

Sample No. 13. Typical soil of Thomas township.

This sample was in a fine powdered state free from lumps. In color and texture it is not unlike the fine dust found on our clay roads. There is very little humus visible to the naked eye. On microscopical examination one finds that the chief constituent is clay mixed with a small amount of humus. The latter is of a light dry nature. On beaker analysis it shows 29.25 per cent. sand and silt. This would bring it under the clay loams approaching clay. In separating, the clay remained a long time in suspension in the water, and contained but little humus, while the residue, consisting of fine sand and some coarse light vegetable matter was, as stated in the analysis, present in small quantities. This soil might be easily improved by ridging in the fall to expose it to the frost, which would likely bring about coagulation, and increase its porosity.

Sample No. 14. A sample of vegetable matter collected in Carman township about two and one-half miles from the camping ground on Redstone river.

This soil is almost black in color. It is very loose and light in texture. Scarcely any lumps are present. There is a large amount of undecayed vegetable matter in it, consisting of broken bits of wood and roots. Under the miscroscope a considerable quantity of the soil grains has a separate grain structure. There is a large amount of black-colored particles present. This soil is apparently a sandy loam very rich in humus, and a separation was made which showed the presence of 59.2 per cent. of sand. The sand contained large quantities of wood and roots in small pieces. The clay was nearly black in color. This soil may be classed as a loamy vegetable soil.

Sample No. 15. Soil taken from near portage on Redstone river in Carman township.

In color it is a very light gray. It is found in irregular lumps varying in size from a fine powder to pieces the size of a large pea. It is rather gritty, otherwise giving every indication of being a strong clay. Under the microscope it shows a compound structure, and a very apparent absence of humus. The particles are all light colored and very small. A beaker analysis proves it to be a clay loam, 34 per cent. of the particles being greater than .001 inches in diameter. On microscopical examination this is seen to be composed of very small brownish particles of a gritty nature. This soil is deficient in humus, otherwise it is a good serviceable soil.

Sample No. 16. Soil taken from Whitney township, about 200 yards back from the east side of Porcupine lake.

In general appearance this is a light colored soil, lumpy and resembling a stiff clay and with very little humus. Miscroscopical examination shows a small amount of very fine humus, and the balance appears to be clay and fine silt. The analysis gives 38.95 per cent. sand, thus classifying this as a clay

Digitized by Google

loam approaching loam. After the separation what little humus the soil possessed in a visible state was found in the residue. The residue was composed of very fine silt mixed with fine vegetable matter. Under the miscroscope considerable fine humus could be seen in the clay portion.

Sample No. 17. Soil collected from an island on Night Hawk lake.

This soil is a uniform light gray color. It is somewhat lumpy. The lumps vary in size from a hen's egg down. These lumps are a little difficult to break down. Under the microscope the soil grains all appear to be in compound particles. No separate grains can be noticed, neither is there any appearance of vegetable matter or humus in the soil. A mechanical separation showed the presence of about 17.7 per cent. of sand. Both sand and clay are a light gray color, which shows that there is no humus or vegetable matter in the soil. This soil is therefore a clay.

Sample No. 18. Another soil taken from Dance township.

This is apparently a sandy loam, the sand tending almost to the size of gravel. The particles range from the size of dust to that of pin heads. It is reddish brown in color and shows a little vegetable matter, quite porous and open. A microscopical examination shows white and red particles, each of definite outline, probably quartz and feldspar, with considerable reddish brown dust. It has clearly a separate grain structure. A beaker analysis proves it to be a sandy loam having 62.95 per cent. greater than .001 inches in diameter. On microscopical examination of this, pervious observations were confirmed, and a little cinder found.

Sample No. 19. Soil taken from Tisdale township on portage a few yards from river bank.

This sample looks quite different from any so far examined, being of a fine mucky nature, dark brown and free from lumps. Examining it with the microscope a small amount of fine sand and silt could be seen, but the bulk of the sample was vegetable matter. The clay soil was rich in fine humus thus accounting for the absence of lumps. The sand contained more than 75 per cent. coarse humus. A beaker analysis proves this to be a loam, containing 59.25 per cent. sand and silt.

Sample No. 20. Soil collected in Murphy township.

This soil is nearly black in color. The soil grains are collected in small hard lumps, which can only be broken down by considerable pressure. They almost seem like small pieces of stone. It has a very poor texture. There is also a very small quantity of vegetable matter in it. Under the microscope the soil grains seem to be cemented into lumps. They are quite dark in color. A mechanical separation showed 61.5 per cent. sand. Both clay and sand were almost black in color. This soil is therefore a sandy loam with a large amount of humus in it. The cementing of the soil grains into lumps is no doubt due to the humic acid in the soil. This acid seems to have great power in cementing sand grains into lumps.

Sample No. 21. Soil taken from an island on Night Hawk lake.

It is very dark in color and in a good physical condition, being loose and powdery. On microscopical examination it is found to consist mostly of brownish dust, with considerable quantities of white quartz and brownish feldspar particles. A little vegetable matter is present. A beaker analysis shows the presence of 19.5 per cent. sand. Therefore it is a clay. On microscopical examination a small proportion of white crystalline pieces are discernible, together with a larger proportion of brown water-worn particles and a little mica. This gives every indication of being a good soil.

Sample No. 22. First long portage—very fine sand.

In general appearance it is light gray and resembles quicksand, being very fine. Very little humus is present, and what there is appears as dry, separate particles. A beaker analysis gives 91.55 per cent. sand and silt. This would classify it as sand, approaching light sandy loam. After separating the sample into its clay and sand constituents, the sand portion was not very different from the whole soil. The small amount of clay that was present was darker in color than the whole soil, which was perhaps due to the presence of some humus.

Sample No. 23. Soil collected in Thomas township from glacial deposits one and a quarter miles inland from Night Hawk lake.

This soil is of a gray color. It is quite loose and friable. There is a large number of small stones in it and also some vegetable matter. Under the microscope the soil grains appear to be entirely separate from each other to a very great extent. There is a small quantity of black-colored soil grains. This soil is a mixture of sand and gravel with a small amount of undecayed vegetable matter and humus in it. The gravel would constitute nearly one-half the soil. A mechanical separation showed the presence of 81.7 per cent. of sand in this sample after the gravel had been removed.

Digitized by Google

Sample No. 24. Soil taken from Thomas township, a sample of the vegetable matter which covers most of the soil in this region.

This is a humus or peat soil. It is found in black lumps, with much organic matter in a partial state of decay. When some of the soil is powdered it feels gritty to the touch. When examined under the microscope a few white particles of sand are found. A beaker analysis shows besides a few white particles of quartz a considerable number of water-worn pebbles about one-half the size of pin head. They are not sufficiently numerous, however, to have any material effect on the character of the soil. When this organic matter is mixed with the white clay loam it should make a fairly rich soil.

Sample No. 25. Soil taken from Hoyle township at the portage on Porcupine river.

This soil is of good texture, having a few small lumps, due to the action of the clay and humus. The color is light gray. Under the microscope it appears to be well coagulated, and the humus which is in a fine state is in sufficient quantity to make the soil fairly rich. The sand portion contained a lot of humus and the sand particles were very small, resembling clay except that they did not adhere to each other. This would seem to be an excellent soil both in point of fertility and ease of working. A beaker analysis showed 6.10 per cent. sand and silt. We would therefore classify it as a sandy loam, approaching loam.

Sample No. 26. Soil collected in Matheson township, typical of a part of that district.

This soil is light gray in color. It is very loose and friable. The lumps are small, few in number, and easily broken down. There is a very small amount of vegetable matter in it. Under the microscope the soil grains appear in compound particles and as separate soil grains, in about equal proportion. This soil appears to be a loam lacking in vegetable matter. A mechanical separation showed the presence of 52.4 per cent. of sand. Both sand and clay were of a uniform light gray color. This soil is therefore a loam lacking greatly in vegetable matter and humus.

Sample No. 27. Soil obtained from near Porcupine river.

It shows many lumps of clay in which the cinder has been incorporated; also considerable cinder in the free state. It is black and gray in color, according as the cinder or clay predominates.

A microscopical examination only confirms the above. A beaker analysis proves this to be a clay loam, there being 36 per cent. of sand, silt, and cinder. But this can hardly be accepted, as a considerable part of that 36 per cent. was cinder and not sand. I would therefore call it a clay with a large amount of cinder.

Conclusions

Of these 27 samples of soils, according to our classification 4 are of clay; 8 of clay loam; 3 of loam; 8 of sandy loam; 2 of vegetable matter; 1 of sand; 1 of glacial deposit of sand and gravel.

We see a wide variation in these soils and therefore we would expect them to be fitted for a great variety of crops. These soils examined were taken from below the vegetable matter. When vegetable matter is mixed with them, they will make good rich soils suitable for agriculture.

Digitized by Google

Economic Resources of Moose River Basin

By James Mackintosh Bell

Lignite coal has long been known to exist in the Moose River basin of northern Ontario. Limonite and other iron ores and gypsum have also been briefly described in the same region. It was with the special object of deciding definitely whether the lignite occurred in workable quantities suitable for exportation or for future local use, and as far as possible studying the other economic mineral resources of the region, that a small expedition was sent by the Bureaw of Mines into New Ontario during the summer of 1903.

The party consisted, besides the writer, of an assistant —Dr. W. A. Parks of Toronto University—and of four voyageurs, Louis and Joseph Miron, Kenneth Spence, and "Joe" Kechiperach; and I may here mention that one and all performed their duties in a most excellent manner during the long season. The party left Missanabie station on the Canadian Pacific Railway on the 18th of May, and arrived at Mattawa in returning on the 17th of September.

The Territory Explored

The country covered by the summer's explorations is roughly bounded on the south by the fiftieth parallel of north latitude, from Riverside Portage on the Missanabie river to near New Post on the Abitibi river. From New Post the boundary of our sheet strikes east-northeast to Kesagami lake. Thence northward it follows the Kesagami river to Hannah bay. Passing westward along the seashore, it ascends the Moose river some eighteen miles to the mouth of the Kwataboahegan, and this river it follows to a point some ninety miles up its course, whence it turns southwest to Wabiskagami river and Riverside portage.

The path to the starting point of our work at Coal brook, which enters the Missanabie from the east, lay by the Missanabie river. The water of the Missanabie was exceedingly high, and in consequence, as we were heavily laden, more portages had to be made than is customary, and our advance for this reason was so much delayed that it was the 6th of June before we reached Coal Brook, where it had been intended that our operations on the coal should begin. There we found that the water in Coal Brook was so high that all outcrops of lignite were hidden, and it was decided that that portion of our work should be left till the water subsided, and accordingly we continued our way northward. At the mouth of the Opazatika river the party was divided, Dr. Parks continuing northward to examine the deposits of lignite on the Kwataboahegan river, while I ascended the Opazatika some twenty-five miles to study the iron-bearing rocks which occur at that distance from the mouth of the stream.

The Opazatika River

As the Opazatika is an almost unknown river, I shall here diverge slightly from a general discussion to give a brief description of this large and important tributary of the Missanabie, which I myself ascended almost to its head waters in 1901. The river joins the Missanabie at a point some forty-five miles below Hell Gates, and about the same distance above the mouth of the Mattagami. The river is formed by the union of several streams entering Opazatika lake, an irregular sheet of water eight to ten miles long and two to three miles in width, which lies some six miles east of the Missanabie river at the entrance of the Cabanshee, or Brunswick lake portage. From Opaza-

Digitized by Google

tika lake to its mouth the river has a length of a little over one hundred miles. In high water the Opazatika is an easy route towards Hudson Bay, but in midsummer the water is exceedingly low, especially in the lower part of the river. Moreover, the portages are poorly cut out, and towards the north not at all; only here and there slight traces of trails being seen. North of Opazatika lake are several small lake expansions, below which follow over fifteen miles of more or less broken water as far as Red fall. About fifteen miles below Red fall is Zadi lake, and for this distance the Opazatika flows with slight current. Zadi lake is a small shallow body of water, with an average width of about a mile, a length of about five miles, and a maximum depth of some twelve or fifteen feet at summer water level. It is separated from Neshin lake of almost similar dimensions by a short stretch of river on which occurs Philip's portage. Just below Neshin lake is the canyon of the Opazatika, from which point to the foot of Breakneck falls, a distance of about twenty miles, the course of the river is broken by numerous falls and rapids. Below the Breakneck falls the Opazatika enters the James Bay coastal plain, afterwards to be described, and flows with swift current to its junction with the Missanabie. The Breakneck falls are among the most remarkable physiographic features of the region, there being a straight drop of over sixty feet. The hydraulic importance of this fall will be more fully appreciated when it is mentioned that the volume of the river at its mouth where its width is some 293 feet is 4,276 cubic feet per second, as measured at the end of the month of June.

Returning from the small iron deposit of the Opazatika, a day was spent in examining the poor and unsatisfactory beds of lignite outcropping along the Missanabie above the Opazatika. This work completed, two weeks were occupied in carefully examining the beds of lignite occurring along the banks of the Soweska river, which is the larger and more southerly of two fair-sized streams which enter the Missanabie, about thirteen miles above the mouth of the Opazatika. The Soweska is a small swift-flowing river, about one hundred and fifty feet in width at its mouth, which takes its rise in the large muskegs and swamps thirty or forty miles to the west. It is navigable for light canoes in spring for about twenty-five miles from its mouth, but its lower course is much broken by small yet decided rapids.

The Wabiskagami

Returning to the Missanabie, we ascended the stream to the mouth of the Wabiskagami. The Wabiskagami joins the Missanabie about twenty-two miles below Hell Gates. It is the largest and most important stream, entering the Missanabie from the west between the Mattawishquaia and the Kwataboahegan. It rises in Wabiskagami lake, which is reached by a route of several long portages and small lakes that leaves the Missanabie river below the Skunk islands. Another route is said to be by the Pewabiska river; but the Indians avow that this stream is almost impassable save for the smallest canoes. Wabiskagami lake is reported to be a beautiful sheet of clear water ten to twelve miles long and three or four miles wide. It is to be regretted that we were unable this summer to visit it, but in descending the Missanabie I did not know of the route to the lake, and presuming it to lie approximately where marked on the existing maps of northern Ontario, I ascended the Wabiskagami river itself. We passed up this stream some sixty-five or seventy miles from its mouth, though in reality at the end of this distance by the river we were only about thirty miles in a direct line from the confluence of the river with the Missanabie.

The general upward trend of the river valley for this distance is some 10 degrees south of west, but the river is so crooked that there are numerous and continuous variations from this course in every direction. At the point where we turned back the valley of the river apparently bends much more to the south, and as far as can be judged from Indian stories, the lake is about twenty-five miles farther in that direction.

The Wabiskagami is a fine clear watered stream, carrying much more water than most of the coastal plain rivers during the summer. Though its current is always swift and often rapid, still its fair depth makes it a comparatively easy stream to navigate even in ascending, but only within the coastal plain, for within the old land area numerous short rapids break its course and make travelling slow and difficult. At its mouth the river is probably a hundred and seventy feet in width, wider in some of the shallower spaces above, but on the whole averaging much less. The Wabiskagami is physiographically an interesting river, and will be described in greater detail further on in this report.

On our return to the Missanabie we started the descent of that stream. In

Digitized by Google

going down an astronomically checked survey of the river was made to locate as accurately as possible the various outcrops of lignite. A stop of some length was made at the gypsum deposits of the Moose river, and this interesting mineralogical occurrence carefully studied. A detailed map was made of the Moose river in the vicinity of the gypsum. We reached Moose factory on 4th July, and were soon afterwards joined by Dr. Parks, who had meanwhile been occupied up the Kwataboahegan river.

The Kwataboahegan rises in Moosonee lake and in the surrounding swamps and muskegs at about one hundred and twenty-five miles off to the west of the Moose river. Some half way down its course it is joined by the Agwasuk from the north and the Mituskwia from the south, both of which considerably augment its volume. It enters the Moose river by several mouths at Hancock rapids some twelve miles above Moose Factory. In the lower reaches of the river the Kwataboahegan is wide, shallow, and swift, but higher up the river is narrow, deeper, and less rapid, while some of the tributaries are merely stagnant streams meandering through the swamps and muskegs.

After a few days spent in re-outfitting at Moose Factory our party was again divided, Dr. Parks going up the Abitibi river to carry on explorations for lignite, while I went to examine Kesagami lake, which lies about half way between Moose Factory and Abitibi House on lake Abitibi, on the winter trail. It is the winter home of a large portion of the Moose Indians, who resort thither on account of the fishing, and is also occasionally visited by Indians from New Post, Abitibi House, and even from Rupert's House. The lake is drained by the Kesagami river, a large stream, which, uniting with the Kattawagami to from the West river, enters Hannah bay at the mouth of the Harricanaw. The Kesagami river is an exceedingly difficult river to navigate. On the coastal plain it is merely swift, but inside the old land area, fall after fall separates shallow stretches of boulder-filled rapids from each other. For this reason, when the Indians visit Kesagami lake in summer they usually go not by the Kesagami river but by the French river and one of its tributaries. This was the route we followed. The French river joins the Moose from the east nine miles above Moose Factory, and just at the head of tide water. The lower French river is wide and shallow, and its course interrupted by short stretches of rapids. The route leaves the main stream by the Nettogami river, which joins the French some twenty-five miles above its mouth. This stream is followed for about sixty-five miles as far as Agaskagou lake, whence a portage of a mile and a half leads to Kesagami lake.

The Nettogami River

The upward course of the valley of the Nettogami has a direction about south-southeast for forty-five miles, where it makes a sharp bend to the north for two miles to Nettogami lake or marsh, from which it again bends south-southeast as far as Agaskagou lake. The Nettogami throughout its course is shallow and rapid. For thirteen miles below Agaskagou lake as far as Fox rapids the river is easily ascended, the rapids being small and far apart, and the river fairly deep.

Below Fox rapids follow four miles of very swift water, as far as Wastabaskinan chute, which is a straight drop of four feet. A mile or so of rough water continues below the chute, at which point the river enters the marshy floor of a former lake, and meanders for several miles with a slack and even current. This marsh with numerous spots of open water dotting its surface, the Indians know as Nettogami lake, and in spring, it is, I am told, so thoroughly covered with water as to deserve to be dignified with the name of lake. Below Nettogami lake the river winds and bends for nine miles with exceedingly rough rapid water, and this stretch is usually passed by a portage about six miles in length, the distance being relieved by several small lakes about midway across the portage. Seven miles below the foot of the portage the river, always rapid, plunges over a cascade with a drop of about twelve feet, passed by Gilbert's portage on the west bank. Between Gilbert's portage and Kage-ga-te-chinook, a mile below, the Nettogami dashes and swirls in all directions between huge gneissic boulders. At Kage-ge-te-chinook the river drops about six feet. About one mile below this are the falls of Kawaskitoukik. Here the river is hemmed in to a width of twenty or thirty feet, and flows in a foaming cascade for almost a mile, having a total drop of about one hundred and ten feet, passed by a three-quarters of a mile portage on the east bank. Less than half a mile below Kawaskitoukik the river plunges over a cascade with a drop of fifteen feet, passed by a portage on the east side. A mile still lower down is Kabaquay-she-wish-iwan falls—a cascade of exquisite beauty with a drop of about thirty feet direct. After flowing calmly

Digitized by Google

for a mile beyond these falls, the river again plunges some eighty feet in a roaring cascade passed by Axe Handle portage on the west side. Below Axe Handle portage slightly over a mile of rough water is followed by a series of chutes having a total drop of eighty feet passed by Ashian portage. Below Ashian portage the river continues rapid for some three miles to the foot of Pischew rapid, where it enters the coastal plain, and from this points to its mouth, a distance of twenty-one miles, though the river is always rapid and shallow, there is no serious impediment to navigation save at the point where it crosses an inlier of Pre-Cambrian rock within the coastal plain some nine miles above its mouth.

Returning to Moose Factory from Kesagami lake, a few days were spent in and around Moose Factory, when we porceeded up the Abitibi river and joined Dr. Parks who was occupied near the Blacksmith rapid. Here most of our time was spent in examining the lignite on the Abitibi itself, but in addition short trips were made up the Big and Little Cedar rivers to see if the lignite beds observed on the main river outcropped on these tributaries. A traverse was undertaken across country to Mattagami river to examine the occurrence of limonite at the Grand rapid, and still another to Gypsum mountain, which crosses the boundary line between Algoma and Nipissing at mile post 276. A careful, paced survey was carried up the Abitibi river from the mouth of Big Cedar creek to the foot of Coral portage in order to locate definitely the various deposits of lignite on the stream.

We left New Post on 31st August, and having a pleasant and successful trip out reached Mattawa, as has been said, on 17th September.

Stratigraphy

It is intended primarily that this report should deal with the economic geology of the region under discussion, but as an introduction to this phase of the subject, I wish to discuss briefly the general stratigraphy and physiography in order to elucidate the genesis of the various economic occurrences.

The geological succession of the rocks of the Moose river basin is as follows in ascending order :

Pre-Cambrian :	Laurentian,
	unconformity ?
	Huronian,
	unconformity.
Palaeozoic :	Devonian,
	unconformity.
Pleistocene :	Glacial,
	Post Glacial.

Pre-Cambrian rocks, so prominent throughout northern Canada, appear only in the southern and southeastern part of the region described, the rest of the area being overlaid by Palaeozoic and other still more recent formations. Exposures of rocks of all ages, especially the older ones, are poor and unsatisfactory throughout the area, and visible contacts are rare. However, in a few places the relations existing between the Pre-Cambrian and Palaeozoic are well shown. One of these contacts is on the Wabiskagami about twenty-five miles west of its mouth, and here the Devonian sediments lie unconformably upon the upturned gneissic beds which strike north 20 degrees east and dip at an angle of 45 degrees to the south of east. This is the best contact which I have seen in the region, but the boundary between the two series is always shown physiographically on the various rivers, and it is chiefly from this knowledge that the boundary is delineated, as follows : Striking somewhat north of east from the Wabiskagami it crosses the Missanabie just above Bull bay, whence turning directly east it passes the Opazatika near the mouth of the Squasiche river. From the Opazatika the contact bends east-northeast and crosses the Mattagami below the foot of the Long portage. The sandstones, shales, etc., outcropping at Sextant portage on the Abitibi overlie unconformably a pre-Cambrian eruptive rock, but though this rock causes the rapid there occuring on the river, still it is probable that the true present boundary between the Pre-Cambrian and Palaeozoic lies a little farther south between the Sextant portage and the Otters. The contact crosses the Little Abitibi some ten miles south of the Bad river, whence it continues northeast, and traverses the Nettogami twenty-one miles above its mouth. Continuing northeast it crosses the Kattawagami about twenty-five miles south of Hannah bay, whence it strikes at first east, then slightly east of north to Rupert's bay. Inliers of Pre-Cambrian rocks appear on the Little Abitibi, the upper French and the Nettogami river.

Pre-Cambrian Gneisses

With the present state of knowledge it is exceedingly difficult to attempt any sub-division of the Pre-Cambrian, though doubtless, further careful work will show that this great series is capable of reduction. In general, however, the Pre-Cambrian consists chiefly of gneisses and schists, and to a less extent of slates,

Digitized by Google

quartzites and iron sediments, as well as acid and basic eruptives. Apparently, gneiss occupies the lowermost part of the series with both an acid and a basic phase. Macroscopically, the acid phase is apparently a granite, showing every phase of metamorphism from that in which shearing is scarcely visible to that in which the rock is laminated into wide bands of the component minerals. The rock is for the most part coarse-grained, and consists chiefly of three minerals—quartz, orthoclase and biotite, with various accessory minerals. Garnetiferous gneiss is common, as is also hornblende gneiss, which, however, grades into the basic phase. Two types of the acid gneiss will be described microscopically—one from the Wabiskagami (1) and another from the Nettogami (2).

The Wabiskagami gneiss represents what may be described as a feldspathic phase of the Pre-Cambrian gneiss. It contains the original minerals—microcline, orthoclase, plagioclase, biotite, quartz, magnetite, and secondary chlorite, epidote, muscovite, hematite, and hydrous iron oxide.

Microcline is the chief mineral of the rock. It occurs in large tabular individuals showing strongly double cross striation. All of it is more or less decomposed, with a separation of hydrous iron and hematite, and the formation of secondary muscovite. Practically every individual is more or less strained, and some are mere cores surrounded by a mosaic of granulated feldspar, with which is associated some quarts. Magnetite is rather rarely included in the microcline and orthoclase. The latter gives rise to the same products of decomposition as microcline, and is always clouded. The plagioclase is a somewhat acid oligoclase, which is usually fairly fresh, but shows the effect of pressure. The biotite is strongly pleochroic, but is for the most part altered to irregular masses of dark green chlorite and a very little epidote. The chlorite, which is also pleochroic, includes idiomorphic grains of magnetite. Quartz is not a very common mineral, and that which is not shattered shows undulatory extinction.

The Nettogami gneiss is in many ways similar to the one just described, but it is much more silicious and less metamorphosed. The constituent minerals are quartz, orthoclase, microcline, microperthite, plagioclase, biotite and quartz. Orthoclase is the most frequently occurring mineral. It is in large individuals interlocking in allotriomorphic structure with the other component minerals. It is usually fairly fresh, but shows a slight alteration to muscovite. It exhibits a remarkable pale pinkish birefringence. Microcline is abundant, and exists under the same conditions as orthoclase. Microperthite is seen in a few large individuals. The plagioclase is a somewhat acid oligoclase. The oligoclase and microcline show bending and even fracture. Quartz is a common mineral, and is often surrounded by a narrow rim of hydrous iron oxide. It not rarely shows wavy extinction, and is sometimes granulated. Biotite is rare, but is found in long narrow automorphic plates within the feldspar.

The Wabiskagami gneiss is visibly foliated, while that from the Nettogami is apparently almost massive. In the former the effect of dynamic stress is a much more striking microscopical phenomenon than in the latter, but even in that it is by no means wanting.

An interesting point about both the Nettogami and Wabiskagami gneiss, both acid, is the rarity of ferro-magnesian minerals. There are intermediate phases between the acid gneisses and the true basic gneisses. In general the basic gneiss is much less common than the acid gneiss. In the field there is sometimes visible a gradual gradation between the two facies, or again there is a somewhat sharp change from the acid to the basic. The acid gneiss of the Nettogami bears no lithological resemblance to the basic gneiss from the same locality with which it is closely asociated. Apparently the two represent original acid and basic differentiations of the same magma.

The basic gneiss from the Nettogami consists chiefly of monoclinic amphibole and plagioclase, with a little quartz, titanite and apatite. The rock is remarkably fresh, and is apparently in great part recrystallized with the production of a roughly parallel structure. The plagioclase is labradorite of slight basicity (maximum extinction of 23 degrees in the zone normal to 010). It contains inclusions of apatite and hornblende. With the labradorite are associated a few small grains of quartz. The amphibole is a dark-green, pleochroic hornblende, mostly fresh and locally rendered poikilitic by inclusions of titanite. Dynamic metamorphism is exhibited not only by the parallelism existing between the individuals of labradorite and hornblende, but by the bent condition of the labradorite.

The acid and basic gneisses, with the granites and pegmatites which cut them, have been called Laurentian. In many

(1) From just above Palaeozoic boundary.

(2) From the Pre-Cambrian (here Laurentian) inlier.

Digitized by Google

ways they bear a strong lithological resemblance to Laurentian gneisses elsewhere, but as a rule they are not so pronouncedly laminated.

At many points throughout the region the gneisses are impregnated by a newer granite, often pegmatitic, but sometimes merely coarse-grained. This granitic material seems to have resulted from the refusion or possibly merely recrystallization of the gneisses. In places this more recent rock has entirely replaced the gneiss. Again, fragments of distinctly banded gneiss varying in width from a few inches to many feet are included in the irruptive rock. This impregnation of the gneiss is excellently shown on the Nettogami river. The strike of the foliation of the gneisses varies considerably, but in general it may be said to be east and west. The dip both north and south is for the most part at a higher angle than forty-five degrees.

Pre-Cambrian Schists

The green schists of the region have been generally considered younger than the gneisses, and have been called Huronian. Many of them, however, are merely basic phases of the latter. Some may be younger, and the fact that they are interstratified with true sedimentary quartzites evidently derived from the erosion of the acid gneisses seems to point to this conclusion. Much study will be necessary before the exact relations between the schists and gneisses can be discovered. Schists occur within the area which we examined on the Nettogami, and with quartzites on the Blue or New Post river and on the Little Abitibi river. The schists are as a rule much altered chloritic rocks consisting chiefly of altered feldspars and chlorites, but considerable variation occurs, and many of them have been recrystallized with the formation of many secondary minerals. A typical green schist is that from the upper Nettogami (3), which appears under the microscope as a much squeezed igneous rock.

In the hand specimen it is a fresh and almost entirely recrystallized highly foliated rock. Beneath the microscope the following minerals are identifiable: Green hornblende, biotite, quartz, epidote, zoisite and magnetite. The ferromagnesian minerals are much more prominent than the quartz, and are arranged in a sort of rough parallelism with it. Several rounded areas consisting of muscovite zoisite, and apparently much altered feldspar, seem to be the remnants of large individuals of feldspar. It is very probable that these areas represent original phenocrysts. The hornblende and biotite both strongly pleochroic, are often intergrown, or again a plate of biotite passes in longitudinal extension abruptly into one of hornblende.

The iron-bearing limestones found on the Opazatika river and subsequently described in greater detail, from their lithological resemblance to similar rocks in lake Superior, are tentatively considered as Huronian, but they may not be so, and their relations with the underlying granites and gneisses seem to oppose this conclusion. They seem to lie horizontally and apparently truncate the upturned gneissic beds. If this attitude is true bedding and not cleavage, then these rocks need not be connected in age with the quartzites and schists which are always distinctly plicated.

Greenstone Dikes and Bosses

The gneisses, quartzites and schists are cut by numerous greenstone dikes and bosses of varying petrographical composition. The greenstone dikes are wide and more continuous and prominent in outcrop than any other of the solid rocks in the region. I shall here describe several types of these rocks from thin sections under the microscope. Of these phases the most important are the coarse-grained gabbro facies, the diabase-dolorite facies, and the diabase-porphyrite facies.

The first is perhaps in general the most common, being often seen in the larger dikes and in most of the bosses. There are gradations from a typical augite gabbro through hypersthene gabbro to anorthosite. A splendid example of gabbro is the rock forming the wall of the southern part of the canyon of the Abitibi, and visible also at the Oil-Can fall just above. Macroscopically, the rock is dark grayish-green in color, apparently consisting in great part of feldspar, and distinctly coarse-grained and granitoid in texture.

Beneath the microscope the rock is seen to be composed of the original minerals, plagioclase feldspar, monoclinic pyroxene, biotite and olivine, with the secondary minerals epidote, muscovite, talc, serpentine and titanite. Plagioclase is by far the most important mineral. It occurs normally in broad tabular individuals showing polysynthetic twinning after the albite law. The plagioclase is evidently a labradorite giving maximum extinction angles in the zone normal to 010 of 34 degrees. The alteration of these basic

(3) Specimens from Wastabaskinan.

Digitized by Google

feldspars resulted in the formation of zoisite, epidote, etc. They sometimes show wavy extinction, and their peripheries exhibit local granulations with the production of secondary quartz—both fruits of dynamic action.

Pyroxene is much less common than plagioclase, and occurs in large individuals in between the labradorite. It is very light dirty gray-green in color, very faintly pleochroic, and is probably a diopside or malacolite. It is often twinned. The mineral shows sometimes the double prismatic cleavage, but exhibits usually only one with numerous irregular cracks. It is occasionally rendered slightly poikilitic by inclusions of small plagioclases, quartz and magnetite. It is associated with a dark brown biotite and with titaniferous magnetite. The former occurs in medium-sized plates which are strongly pleochroic, and the latter in large irregular grains surrounded by rings of strongly doubly refracting titanite. The titaniferous magnetite includes a beautiful bluish-green isotropic mineral, which is apparently pleonaste. The olivine in frequent irregular grains is partially serpentinized. In general the rock is beautifully fresh, and has undergone a slight amount of strain.

The diabase-dolerite type (4) is also a commonly occurring rock limited chiefly to dikes. It is a medium-grained, almost black rock weathering rusty brown. Even in the field it shows the ophitic structure of diabase. In the thin section it is a beautifully fresh rock composed of the following minerals: original plagioclase, monoclinic pyroxene, olivine and magnetite; and secondly, serpentine and hydrous iron oxide. Plagioclase, pyroxene and olivine are about equally distributed in the rock. The plagioclase occurs usually in long laths typical of diabase, and holds in its interstices the irregular shaped pyroxene and olivine. A few however are large, wide and tabular, with their edges invaded by the ferro-magnesian minerals. These look like altered phenocrysts. The plagioclases, which show occasional zonal structure in the large individuals, and polysynthetic twinning in the lath-shaped feldspars, are apparently labradorite of medium basicity.

The pyroxene is very light gray-green in color, shows distinctly the double cleavage, and is probably diopside. Both pyroxene and plagioclase are fresh, but olivine in large grains shows alteration along the cracks to serpentine. This secondary mineral in transmitted light is usually light-green in color, but is occasionally stained a bright yellow ochre, with formation of iron oxide. The olivine is also sometimes similarly colored. Magnetite is abundant in irregular grains, in association with the pyroxene.

The diabase-porphyrite type of rock, (specimen from the foot of Kabaquay-shewishiwan falls), unlike the last specimen described, is considerably decomposed. In the field it appears as a somewhat fine-grained rock, containing large very light-green, or practically white phenocrysts. Beneath the microscope the ground-mass is more prominent than the phenocrysts, and consists of an interlocking mat of monoclinic pyroxene and plagioclase feldspar. The phenocrysts are all of plagioclase feldspar, which is also the commonest mineral in the ground-mass, occurring in long laths and interlocking in ophitic structure with the pyroxene. It is a fairly basic labradorite, showing a maximum extinction of at least 31 degrees in the zone normal to 010.

The pyroxene, which is light gray-green in color, and is often twinned, is apparently diopside. It is seldom fresh, and has undergone considerable paramorphic alteration to uralite. A few secondary idiomorphic grains of biotite have also resulted from the decay of original pyroxene. Magnetite is abundantly associated with the ferro-magnesian minerals.

This type differs from the last in containing a somewhat finer-grained ground-mass, and in the greater development of large phenocrysts which are merely incipient in the diabase-dolerite type.

The Palaeozoic Series

Stretching from the Archaean boundary northward underlying the flat coastal plan are the Palaeozoic rocks of the Moose Basin which, with the recent rocks above them, cover by far the greatest part of the region under discussion. The series consists of interstratified conformable conglomerates, sandstones, shales, limestones and gypsum beds for the most part lying almost horizontally, but in places folded into gentle synclines and anticlines. The series is unconformable with the intensely corrugated Pre-Cambrian rocks beneath them, and also with the glacial material above.

(4) Example described is from Pischew rapid, Nettogami river.

Digitized by Google

From fossils collected on the Mattagami and Abitibi by Dr. Robert Bell and others the beds have been classified as Devonian about the horizon of the Corniferous (5) ; but perhaps further study of the Palaeozoic rocks may show the presence of upper and lower formations. A collection of fossils was made this summer by Dr. Parks from the Kwataboahegan river, where fossiliferous limestones are splendidly exposed (6), and a few additional fossils were collected by us both on the several rivers which we ascended; and it is hoped that these may help to elucidate the age of the rocks.

On the Kwataboahegan, it has been said, limestones are well exposed and form the bed of the river for miles along its course. On the Moose river limestone causes the shallow rapids that so seriously impede navigation in a dry summer. On the Missanabie I know of no outcrops of Palaeozoic rocks, but the Wabiskagami near the Pre-Cambrian boundary shows exposures of ripple-marked sandstones and conglomerates as well as exposures of rusty sandstones and limestones. On the lower Opazatika there are no decisive outcrops. The Mattagami for miles along its course shows limestones freely appearing. On the Abitibi every rock of the series, with the exception of the gypsum beds, is seen, and there are frequent exposures all the way from the mouth to the Pre-Cambrian boundary below the Otters portage. On the Little Abitibi limestones appear frequently, and the Nettogami and French rivers are floored with the same rock almost throughout their entire course on the coastal plain. Limestone and sandstone appear on the Kattawagami and on the Harricanaw. These rocks also outcrop at Netiticie on the south coast of James Bay, and I am told on the west coast of the bay north of Moose Factory. Also they are apparently the fundamental rock beneath the western part of James Bay itself.

It is not probable that in general the Palaeozoic rocks are of great thickness, as shown by the several inliers of Pre-Cambrian rock within their boundaries, but the thickness possibly increases northward. The greatest known thickness is that shown in the outcrop just below the Sextant portage, and this appearance it will be of interest to describe somewhat in detail. The outcrop consists of sixty to seventy feet of intercalated blackish, reddish, and light-gray shales, with thin beds of dolomitic limestone and thick layers of coarse grits and sandstones. The lowest exposures are of slightly consolidated conglomeratic grits and sandstones, above which come the interstratified shales and thin calcareous layers.

The reddish shales predominate, and as the beds are mostly loose and poorly indurated, in weathering they break down and cover all the underlying rocks with a thick talus of red clay of a beautiful hematite red color, which from a distance with the bright green of the poplars in the background makes a very pleasing picture. Several large springs break through the higher strata at this point, and have cut deep ravines through the soft rocks. These gorges are unobstructed save for the larger pieces of rock which fill them and are added to from time to time as the rock disintegrates. The whole series points to rapid but intermittent elevation of the region with a deposition of beds of varying lithology.

Another interesting outcrop of Devonian rocks is that at the contact of the Devonan with the Pre-Cambrian on the Wabiskagami river. The outcrop shows well stratified grits, sandstones and limestones. The lowest exposures immediately above the plicated gneiss are coarse grits gradually becoming finer, and merging into arenaceous limestones which, with true limestone, form the main mass below the contact.

On the Nettogami at the mouth of the Kiashko river and again about one mile above it are cliffs of a re-cemented limestone breccia twenty to thirty feet in height, rising vertically from the river, or overhanging it, which are prominent features in this region of small relief. Some of the limestones lower down the Nettogami, just above the Laurentian inlier, and others seen on the Abitibi along the eastern shore at the Long rapid, consist of a mass of orbicular fragments of limestone, loosely held together, which with the slightest blow fall into small separated pebble-like fragments.

Pleistocene Geology

Overlying the Palaeozoic rocks are those of the Pleistocene period, which outcrop far more prominently than any others in the region and influence profoundly the geology and topography. The Pleistocene rocks may be sub-divided into Glacial and Post-Glacial, between which there is a slight unconformity.

(5) See Rep. Can. Geo. Survey, 1877, page 5 C.

(6) See "Devonian Fauna of Kwataboahegan River," by A. W. Parks, pp. —— of this Report.

Digitized by Google

Rocks of Glacial Age

The Glacial Age consists of at least two glacial epochs and one interglacial period, and it is very probable that further work in the drift will allow still greater subdivision. The rocks of the Glacial Age consist of hard clay conglomerates, less consolidated boulder clays, loose sand, blue clays, arenaceous shales, lignitic clay shales, and lignites —the last four composing the coal-bearing measures of the interglacial period.

The entire area is more or less covered by glacial drift, though the stratified interglacial rocks are not general in their occurrence, and not only are they practically limited to the region of the coastal plain, but they are by no means equally distributed throughout that area itself. They are found at intervals all along the Kwataboahegan river, along the Wabiskagami, from a short distance beyond the Pre-Cambrian boundary to its mouth; on the Missanabie from the foot of the Long portage northward; on the Abitibi below the Abitibi canyon; and on the Mattagami, Nettogami, and other streams farther east. As they are of economic importance owing to the lignites which they contain, their somewhat erratic distribution is marked on an accompanying map.

The greatest thickness observed of the stratified interglacial beds was on the Wabiskagami river, where sixty feet of lignitic shales were seen along the stream. This thickness is apparently local, and as a rule the lignite measures average only a few feet thick. The sediments seem to have been deposited in numerous shallow unconnected freshwater basins, as judged by their distribution and lithology. The interglacial beds suffered tremendous corrasion from the ice of the second glacial epoch, which greatly diminished their thickness. The total thickness of the whole drift varies considerably, though in general it is thickest towards the south of the area and decreases gradually towards the sea; a maximum may be set at about one hundred and twenty-five feet towards the Pre-Cambrian boundary. Fossilized shells were found at one point on the Kwataboahegan by Dr. Parks in the interglacial sediments.

The stratified interglacial beds do not always lie horizontally, although this is their general attitude. On the Wabiskagami are wide shallow synclines and anticlines as well as more pronounced departures from horizontality. On the Abitibi at the Blacksmith rapid and at several other points elsewhere, the upturned interglacial beds are truncated by the deposits of the second glacial epoch. These irregularities are due to ice-shoving rather than orogenesis. It was observed that where there was the greatest thickness of coal-bearing measures, there was relatively, strangely enough, a smaller thickness of lignite.

Post-Glacial Rocks

Following glacial times the sea advanced once more over the Moose Basin, and the whole region as far south as the Pre-Cambrian boundary was beneath water. After marine sedimentation had continued for a comparatively short period of time, the sea departed northward—a regression which is still continuing. The shells contained within these clay marls and sand, which compose the Post-Glacial formation, are those of species still living in the shallow waters of James Bay, and of these may be mentioned Saxicava rugosa, Macoma calcarea (Tellina proxima), Tellina groenlandica, Mya truncata, Mya arenaria, Cardium islandicum, Pecten islandicum, Maconea fragilis, Fusus toxnatus, Natica clausa, and Rhynchonella psittacea.

The Post Glacial sediments are the most consolidated of the Pleistocene rocks. They often form steep wall-like cappings to the glacial drift, and do not disintegrate in the hand. Their greater induration is due to the cementing of the sand and silts by calcium carbonate derived from the dissolution of the numerous contained shells. Their distribution is practically that of the stratified drift, though the outcrops are much more general, the formation wedging out towards the Pre-Cambrian boundary and increasing in thickness northward. They are exposed everywhere within this area where erosion since their uplift has not removed them. Their maximum thickness is eleven feet on the Soweska, and possibly twelve or fifteen feet near Moose Factory, where only the upper part of the glacial drift appears. When first seen in descending the Missanabie river at Bull Bay the Post-Glacial rocks have an elevation of about three hundred feet above Hudson Bay.

Digitized by Google

Physiography

The main physiographic features of northern Ontario are the broad upland plain or plateau and the wide coastal plain, separated from each other by a fall line which traverses the numerous rivers. The broad upland plain or plateau is the drift-covered northern extension of the rocky Laurentian highland lying north of lake Superior, while the coastal plain is the landward continuation of the low shelving shores of the southern part of James Bay. The fall line is the line which joins the points at which the various rivers that drain the upland descend on to the coastal plain.

The Height of Land Plateau

A traveller across Canada by the Canadian Pacific railway will remember the indescribable dreariness, the apparently endless rocky hills and barren sand plains, denuded of timber by forest fires, which stretch away in either direction from the railway line as it passes north of Lake Superior. Naturally he will imagine that the country increases, or at any rate continues, in dreariness and desolation northward, but instead at less than fifty miles north of the railway the windswept hills disappear, and away from the numerous rivers stretches a vast north-sloping level plain covered with a luxuriant vegetation.

The interior is everywhere singularly level, so much so in fact that drainage is often poor and numerous swamps and muskegs result, especially in the northern portion. Almost no hills occur, and the few elevations which have been able to resist the long continued subaerial denudation are so exceptional as to be worthy of mention. Near the shores of Kapuskasing lake, Mount Horden rises to a height of two hundred feet above the lake, and faintly relieves the monotony of the landscape, but the slope to its summit is so gradual and the whole so drift-covered that I was unable to tell when I reached that point. The low hills around lake Opazatika have perhaps a relief of a hundred feet above the lake, and along the Abitibi river near New Post elevations rise somewhat more above the level of the nearest water. Solid rock hills appearing above the drift are almost never seen away from the lake and the river shores, but I am told by the Indians that a relatively high range of hills of this sort is crossed in travelling in winter from Moose Factory to lake Kesagami. Some years ago I crossed several low hills near the Palaeozoic boundary between the Opazatika and Mattagami rivers. It has been mentioned that these residuals of erosion, known as monadnocks, become more numerous southward, and the country on the lake Superior shore and for thirty miles north of it is high, rough and rocky. The same thing applies to a less extent to the eastern part of the province of Ontario, and the region just north of lake Abitibi is one of fairly uneven relief, while that south of it shows many monadnocks of considerable altitude.

This upland plateau, with its singular evenness of surface, intensified since glacial times by its regular mantle of drift, is a remarkable example of an elevated plain of erosion or peneplain. More advanced peneplaination on the one hand, and greater deposition of drift on the other, with possibly a slight differential uplift, have combined to make the smoothness of the surface greater towards its centre than at the periphery.

Lakes of Moose Basin

Lakes are common physical features in the rocky country to the south and east of the plateau, but in the flat country northward the few which exist are mere ponds of insignificant size. The largest lakes are marine-dammed basins which occur as expansions on the larger rivers and their main tributaries, while the smaller lakes in the interior away from the main channels of drainage are shallow, ice block holes which break the monotonous green of the forest. As typical examples of the former may be mentioned Opazatika lake and the various expansions of the Opazatika river lower down its course, while lake Mokaki, between the Opazatika and Kapuskasing, is one of the numerous ponds which dot the southern and middle interior of the upland.

Kesagami lake is one of the large lakes of Ontario. Its situation is near the edge of the northeastern extension of the coastal plain. It, with the numerous ponds which surround it, represents a specialized feature which departs somewhat from the regular rule of lake distribution, and will be discussed later in detail. All the lakes of the region are shallow and increase in shallowness

Digitized by Google

Coal exploration party ; Missanabie River.

The upper Nettogami river, showing timber.

Digitized by Google

Digitized by Google



Couchiching falls, Abitibi river.



Brecciated limestone cliffs, Nettogami river.

Digitized by Google

UNIV. OF MICH.

Digitized by Google



Peat island, lake Kesagami.

Peat cliffs, lake Kesagami.

Digitized by Google

UNIV. OF MICH.

UNIV. OF MICH.

Digitized by Google

Pond Portage rapids, Missanabie river.



Falls near mouth of New Post brook.

Digitized by Google

UNIV. OF MICH.

Digitized by Google

northward. Neshin lake and Zadi lake, of the Opazatika river, are with Wanzatika lake, the remnants of a much larger physical feature.

The River Systems

The Moose River Basin, of decidedly large extent, is one of the most prominent drainage areas of central Canada. Most of its various tributaries run independently and cross the fall line separately to unite on the plain below. The Moose has four main branches —the Missanabie, with its principal tributaries, the Pashoskoota, the Congking, the Albany branch, the Mattawishquaia, the Opazatika, and the Wabiskagami; the Mattagami with tributaries, the Poplar Rapids, the Ground Hog and Kapuskasing; the Abitibi, with its affluents, the Frederick House and the Little Abitibi, and lastly the French, with several joining streams of small importance.

On the plateau,the main streams traverse the country from south to north in roughly parallel lines, and flow now broken by rapids miles in length, again by short wild chutes and falls, or else steer their course placidly with slack water for many miles. This portion of all the rivers abounds in splendid sites for water power. On the Missanabie may be mentioned the falls of St. Peter, a chute of twenty feet, Thundering Water falls (drop 24 feet), Riverside Portage falls (drop 25 feet), Long portage falls (drop 140 feet), and many others. On the Opazatika I have already mentioned the splendid capacities of the Breakneck falls, and there are many others on this stream which are worthy of description. On the Mattagami, the Smoking Falls, with its almost straight drop of ninety feet and its deep canyon below, through which surges the great river, is but one of the many sites of hydraulic power on that river. On the Abitibi there is a splendid series of falls, chutes, and cascades, terminated by the Abitibi canyon.

In the upper part of the plateau the rivers flow slackly, with an occasional rapid or fall, but for the most part with no great continuous current, while in the lower part they dash with tremendous velocity and enter the coastal plain as roaring cascades. The middle stretches are a combination of the two phases. In the upper reaches of the river, as a rule no true shores exist, willows and alders growing right from the water's edge, with the land sloping gently away from it to the level of the plateau. Often, however, the rise takes place abruptly from the river or a very short distance back from it. Lower down the river the rise from the water's edge is as a rule more abrupt and decided.

The level of the plateau gradually slopes north, but with much more uniform descent than that of the rivers, so that often above a fall or rapid after a long stretch of calm water even the main river flows almost on the level of the plateau. Just below the higher falls the banks can be seen to rise steeply up the plateau on either side. Where the rock ridge which causes the fall, beneath the drift is wide, as in the case of the northern boundary of the plateau, and where the rivers have been able to wear back their channels for some distance, canyons have formed through which the waters dash and surge with great force. Long canyons are common in the lower parts of the river, while boulder rapids, or sharp chutes, or falls, prevail in the upper stretches. The best example of a canyon is that of the Abitibi. Here the stream having dashed for some four miles over a series of falls and chutes, debouches by a narrow entrance into a wide, deep basin, only to plunge at the opposite side in a cascade and run for two miles through the canyon. The height of the steep walls of the canyon is quite two hundred feet, and the bank rises away from the edge for fully a hundred feet more. An interesting fall is that on the Blue Water river or New Post brook just behind New Post. At this point the small stream enters the Abitibi with an almost vertical fall of ninety feet, flowing directly over the edge of the plateau in a veritable hanging valley.

It has been mentioned that the line which joins the points where the rivers descend from the plateau on to the coastal plain, is marked on each river by an abrupt descent. This demarcation is the fall line, where occurs as a rule the last decided drop between that place and the sea. On the rivers flowing directly north, across the edge of the plateau, the drop is great and sudden, as seen on the Missanabie, Abitibi, Opazatika and Mattagami, but east and west flowing rivers, running diagonally across the contact, have a more gradual but nevertheless decided descent. None of the numerous falls on the various rivers which mark the termination of the plateau, are directly at the junction of the Pre-Cambrian and Palaeozoic, but the rivers have cut back their valleys, and the falls are now some distance from the contact within the old land of the plateau.

Digitized by Google

The Coastal Plain

It is evident from the geology of the Moose Basin that the region north of the Pre-Cambrian area has undergone several oscillations in level, and that the present modern coastal plain is superimposed on the ancient coastal plain of Palaeozoic rocks, which must certainly have stood above sea level during the deposition of the glacial drift. The boundaries of this modern plain are somewhat uncertain, but coincide with that of the Post-Glacial sediments which represent it geologically, and in general with the southern boundary of the Palaeozoic already delineated.

The coastal plain of the Moose Basin is almost absolutely flat, but it has a gradual quaquaversal slope from the encircling Pre-Cambrian border to the centre on James bay. Down the slope of this coastal plain the various rivers flow with swift though even current, joining like the ribs of a fan near the mouth of the Moose river.

The plain has a height above the sea of perhaps three hundred feet at the edge of the old land, from which it gradually slopes to sea level.

The interior of the country towards the north near the sea is a vast muskeg covered with sphagnum, and broken occasionally by large lake-like swamps, and at wide intervals by a sand or gravel ridge rising a few feet above the general level and supporting a healthy growth of spruce and poplar in delightful contrast to the monotonous muskeg wooded with scrub spruce and tamarac.

The numerous shallow streams which thread their way across the top of the plain have narrow strips of dry land along their edges, proportionate to their size and the amount of drainage effect which they exert. The main streams, the Moose and the Abitibi, and to a less extent the others, are bordered by strips of heavily timbered land varying from several hundred yards to half a mile; while in the case of a stream the size of the Soweska (fifty yards wide), the strip is only one hundred and fifty yards wide, though much greater on the alluvial flats. The large swamps and occasional shallow lakes which exist particularly toward the north of the coastal plain, are water-filled depressions left by the retreating sea, with areas being rapidly invaded by the all powerful muskegs. Of such nature is the huge swamp in which the Soweska river and Little Kwataboahegan rise, and Moosonee lake is probably a less advanced stage of the same thing.

The interior of the southern part of the coastal plain is more inviting to the eye and drier than the northern part. In fact, ridges supporting a healthy timber growth are not uncommon. These occasional ridges elevated a few feet above the muskegs run approximately north and south, and often are brokenly continuous for miles, wedging in to the wider areas of dry land on the old land to the south. The most conspicuous and quite the highest of these ridges is the so-called Gypsum mountain, which crosses the Algoma-Nipissing boundary at Mile Post 276. The name is, at this point, not a good one, as the greatest elevation is scarcely twenty feet above the muskeg, and it is more correctly a low rise which runs for miles and supports a luxuriant growth of banksian pine. From a high tree in this locality I was able to see a considerable hill for this flat country off to the southeast, which seemed to be a continuation of the gypsum ridge. The altitude of the distant hill does not probably exceed two hundred feet, but in the monotonous level country which stretched to the horizon in all directions around me it stood out in relatively mountainous relief.

River Habits and Effects

In general the coastal plain is too recent a physical feature to be maturely dissected by its drainage channels. In fact, in this particular it is decidedly new. The principal rivers, the Missanabie, Mattagami, Abitibi, and French, which flow down the coastal plain, have remarkably straight courses for miles, being held in wide shallow valleys. At the southern limit of the plain the height of the valley wall is probably one hundred feet, and this gradually lowers in the direction of the sea. As a rule, both sides of the main river valleys rise directly or almost so from the level of the river, but in much of the upper part of the main streams the rivers swinging from side to side of the valley have produced on one side precipitous banks rising from the river level, and on the other alluvial flats—the beginning of a flood plain.

The smaller rivers, which traverse the slope of the coastal plain, show exceedingly crooked river channels which swing from side to side across the valley; narrow flood plains alternating with scarped banks on both sides of the stream. All the larger rivers

Digitized by Google

have already cut their way through the post-glacial and glacial material, and are now running on or near the Palaeozoic strata, which in many places they have also deeply cut. The smaller streams, on the other hand, are cutting their channels through the glacial drift.

Beautiful examples of alternating spur and valley are seen all along these northern rivers where the numerous small streamlets descend from the level of the coastal plain to the river, making deep gorge-like valleys in the clay marls and boulder clays, separated by broad spurs from each other. The Missanabie, Abitibi and Mattagami, show in many places terraced valley sides along their courses. The numerous springs which enter the rivers flow from beneath the clay stratum, and do not increase the dissection of the plain. On the Wabiskagami river the narrow flood plain is surmounted by residuals of erosion of the coastal plain, thus showing the presence of two cycles of erosion, the last one being but a short time started. One of the most remarkable of these remnants occurs just below the edge of the old land. A hill of limestone overlaid by boulder clay one hundred feet high rises above the surrounding low limestone flat, and is separated from the main part of the plain by a narrow shallow pond or loop lake—the original course of the river.

Land slips are common all along the large rivers of the coastal plain, particularly on the French, and strips of the bank covered with trees a hundred yards or more in length and half as broad frequently give way and slide into the streams. These slides occur chiefly in the spring, and are probably caused by the unequal thawing of the slippery clays. During the months of June and July, also, it is a common sight to see streams of mud flowing down the banks into the river.

The rivers of the coastal plain flow with a swift but as a rule even current. In other words, they flow at grade save at the few points where the rivers have worn their channels through the recent strata and have exposed inequalities in the Palaeozoic rocks beneath, where the current is sufficiently accelerated to be termed rapid; or where river erosion has laid bare a portion of the underlying Pre-Cambrian, and a decided chute results. On the smaller streams the numerous boulder rapids are unimportant, and were the rivers not so shallow, would not be serious obstacles to navigation.

The Moose in midsummer often contains so little water that it is practically impassable for miles even with light canoes. In the summer of 1901 the lower Moose in the limestone shallows and rapids below the gypsum beds showed only small streamlets of water trickling here and there between the limestone shingle in a valley channel quite a mile in width. Of course, that was an exceptional season.

The rapid which occurs at the mouth of the Abitibi is due to the fact that that river, not nearly as powerful as the Moose, has been unable to cut down its channel as quickly as the latter, and in consequence a serious rapid occurs at the junction. Another rapid on the coastal plain is at the point where the Nettogami crosses the Laurentian inlier on that river, and a similar feature is the rapid at Sextant portage on the Abitibi.

In the high water of early spring, when the rivers often rise fifteen and twenty feet, all rapids are obliterated, the water covers the flood plains and invades the lower part of the coastal plain itself. The effect of this phenomenal rise of water with the immense amount of thick ice which it carries in its train, is to build up along the edge of the plain a steep ridge composed of clay and boulders, to grind to matchwood any trees along the bank which may come in its way, and to pack as hard as a pavement the gently sloping boulder-strewn banks of the river.

The shores of all the larger rivers on the coastal plain are bordered in low water by wide stretches of sand and silt (bank rims) covered with erratics of every size and description, but chiefly consisting of flat limestone shingle and rolled Pre-Cambrian cobbles and boulders. These bank rims are the shoreward equivalents of the bars which occur so frequently in mid-stream. Both bars and bank rims are in spring covered with water, but in late summer are often many feet above it, and are bright with a luxuriant growth of wild flowers and grasses. Near the confluence of the Kwataboahegan with the Moose, the bank rims extend out for three hundred yards at least from the true bank, and the bars of the lower Moose often show a surface a quarter of a mile wide above water in summer. By addition of alluvial material, and that brought by shore ice in spring, the bars grow into islands, and the outward edge of the bank rims into new banks, supporting a large growth of timber, and running parallel with the old and true bank from which it is separated by a shallow depression.

Digitized by Google

La ke Kesagami

Kesagami lake, quite the largest sheet of water in northern Ontario north of Lake Abitibi, is a most interesting physical feature. It is a shallow expanse of water in the heart of the muskeg country, with shores unprotected either by large forests or hills of magnitude, and exposed to the continual sweep of the storms from Hudson's Bay. It is of exceedingly irregular outline, but its main axis lies north and south. From its wide open northern portion three large deep bays—Opimicon, Muchimanitounuck, and Newnham bay, stretch off to the south, and three short bays off to the north. Kesagami river enters the most eastern of the large southern bays —Newnham bay—and flows out by the most eastern of the small northern bays.

The greatest length of the lake from embouchure to debouchere is twenty-four miles and a half, and its maximum width through the northern end of Big island is some nine miles. The lake is not deep at any point. In the bay west of the outlet, the greatest depth is apparently nine feet five inches—six feet being the average. Between Peat island and the western mainland the greatest depth obtained was eight feet, and six feet was more common. Newnham bay is very shallow. Its average depth is not more than four feet, while in Muchimanitounuck one sounding showed nine feet three inches.

Cliffs of Peat

The most extraordinary feature about the lake is the fact that its shores are almost entirely surrounded by cliffs of peat which rise above the water sometimes only a few feet, but often twelve or fourteen feet in height. Not only are the shores of the mainland of this material, but those of the main islands are so as well. The dash of the waves on the soft, spongy material have worn away the banks to a marked degree, and they now present to the water front the most bizarre forms of overhanging cliffs, deep caves, caverns, thick columns, and pillars. From time to time huge sections of these cliffs fall off, and are soon worn to a black powder, which is kept washing up and down by the surf all along the shore. In some places the slightly carbonized tree trunks derived from the peat beds thickly cover the lake bottom near the shore.

The exposed points, such as that between Opimicon and Muchimanitounuck bays are long, narrow gravel spits from which all the peat has been removed, and many of the smaller points as well as a portion of the eastern coast south of the outlet of the river is heaped with large rolled galet. It was observed that there is a tendency for these narrow boulder and gravel points to be drawn out in fish-hook shape southward. The bays often show narrow sand beaches bordering the shore, but this seems as a rule to be material washed from the bottom of the lake and covering the base of the peat cliffs. At a few points the stratum beneath the peat is exposed, and in every instance, where seen, it was noticed to be composed of a hard, dense, almost boulderless bluish clay, evidently glacial. At a point on the western shore some six miles southwest of the outlet a bank of unassorted silt-like, pebbly clay outcrops. This bank is of small lateral extent, but is interesting as the only place on the eastern shore where anything other than peat or muskeg appears away from the immediate shore line. On the opposite side just north of the entrance to Newnham bay occur banks 25 to 30 feet high of fine-grained light-yellowish sand, with lensoid layers of fine gravels interstratified. The outcrop shows false and irregular horizontal bedding. The bank exposes an open cliff face to the lake front, which is being rapidly removed by the continual action of the water, and the sand falling down has given a wide beach ten to fifteen feet in width. Several sand cliffs of similar nature to the one just described occur along the shore of Newnham bay. The banks gradually decrease in thickness along the beach to the west and north, disappearing beneath the peat beds. They appear to be the remnants of glacial or post glacial beds which were afterwards raised and exposed to the action of the waves in a wide open body of water previous to the deposition of the peat.

At many localities along the shore of Kesagami lake the peat beds do not appear, but only the growing sphagnum, and at these places open muskegs stretch away to the horizon. I am told, however, that none of the country around Kesagami lake is ever flooded even in spring. Agaskagou lake, an expansion of the Nettogami, which lies just to the northwest of Kesagami, is an exceedingly shallow pond two miles wide by the same in length. It is in many ways similar in character to the larger lake, but in no part do peat cliffs appear around its shores. The wide hillock which is crossed by the portage trail from Agaskagou lake to Kesagami is similar in character to the sand banks of Kesagami lake it-

Digitized by Google



Digitized by Google

self. The extensive muskeg country all around Kesagami contains many small lakes and ponds within its borders. My Indian guide told me that rocky hills occur one day's travel (say thirty miles) south of Kesagami lake, and just to the south of Muchimanitounuck are low hillocks of sand, gravel, and perhaps solid granitic rock.

Kesagami lake and the numerous ponds which surround it seem to be the remnants of what was once a much larger body of water. For some time this body of water must have stood at a comparatively uniform level, allowing of the growth of sphagnum swamps all around its borders, and along the numerous shoals and islands. Then when the uplift of the region followed, the growth of sphagnum on the more open part of the lake exposed to the waves ceased, but continued in the smaller ponds and in the more protected parts. The dashing waves were able to wear away much of the thin beds of peat along the shore and cut back the beds as cliffs. Hence has resulted the present form of Kesagami.

Economic Geology

It has been already mentioned in the beginning of the report that the main object of our summer's trip was the study of the economic mineral resources of the Moose basin. While it has been found that the region is entirely lacking in vein deposits of metallic minerals, as it is natural to expect, especially in an undisturbed region like the coastal plain, yet the bedded deposits of limonite, lignite, gypsum, and kaolin have, I think, proved to be of greater extent and value than at first anticipated.

Iron Carbonates

The Opazatika iron-bearing limestones cross that river about 25 miles above its mouth, and form a deposit of scientfiic interest, and of possibly economic value. The exact nature of the body is difficult to understand, owing to the broken and generally unsatisfactory condition of the rocks and of their small visible lateral extent, but apparently it is a bed of more or less ferruginous, magnesian limestone, appearing on both sides of the river at and just below the crest of the second rapid above the Breakneck falls.

The iron-bearing rocks are exposed for some 225 yards continuously on the east bank of the stream, and appear as several isolated outcrops on the opposite side for a somewhat shorter distance. Besides the main exposure on the eastern bank there occurs a regular heap of large pieces of carbonate, which are apparently in place at a point some 250 yards south of the prominent outcrop, but the high state of the water, covering much of the carbonate beneath water, made it impossible to make sure of this point. Back from the bank of the river no outcrops of solid rock appear, but I think it lies at no great distance beneath the glacial drift. The inconspicuous exposures on the western bank and the upper, doubtful outcrop on the opposite side, are almost hidden by the large number of loose boulders, which have been washed from the overlying beds of boulder clay and hard pan. The main outcrop of carbonate on the eastern shore rises above the water as a low cliff seven to eleven feet in height depending on the level of the river. The carbonates are here overlain by a rusty layer of the products of their own disintegration.

Lithologically these iron-bearing rocks of the Opazatika iron range consist of poorly ferruginous magnesian limestone, of richly ferruginous limestone, and of silicious limonite or Gothite. The fresher specimens of limestone are light yellowish pink in color, but most of the outcrop by the oxidization of the iron carbonate always contained with the other carbonates, is colored a deep ochre or dark red. In texture the rock is, as a rule, soft, dense and fine-grained, containing numerous geodes of quartz crystal and veinlets of specular hematite. It is sometimes botryoidal and even stalagmitic.

Under the microscope a fairly fresh specimen of ferruginous limestone is seen to consist of a mosaic of grains of carbonate more or less oxidized with the formation of hydrous iron oxides, and containing a few areas of chalcedonic silica. The amount of iron carbonate contained in the limestone is variable from place to place, but it sometimes contains so much of this material that it might almost be spoken of as a somewhat oxidized siderite. Again, in places the rock has been greatly silicified, by the dissolution of the calcium and magnesium carbonate, by the action of waters containing carbon dioxide, and with the deposition of silica in their place. Its iron carbonate has been entirely oxidized to hydrous iron oxide, and has been added to by the infiltration of further iron oxide formed by the oxidation of superior iron carbonate in ferruginous limestone, now entirely re-

Digitized by Google



The Peat Cliffs of lake Kesagami, with pillars.

Drawing by J. M. Bell.

Digitized by Google

moved by the glacial erosion and by other means. These enriched masses occur at intervals throughout the beds, but apparently are more frequent towards the centre of the deposit and at lower horizons. It was observed that the carbonates immediately overlying the inferior gneiss were richly ferruginous. At the outcrop the iron-bearing rocks are never sufficiently rich to be termed iron ore, but workable bodies of this valuable material may exist at short distances in the interior or beneath the surface along the river. The following analyses represent chemically the character of the Opazatika iron-bearing rocks.

	Loss, CO_2 etc.	SiO_2	Al_2O_3	Fe_2O_3	CaO	MgO	S	P	MnO_2	H_2O	SO_3
Silicious hydrous hematite.....	6.40	53.14	1.10	34.84	1.95	1.14	.15	.028	.66	..	..
Purely ferruginous limestone..	44.40	1.00	.56	4.42	29.36	19.56	..	..	..	.31	.23
Pure siderite	37.9	..	..	62.1							

The carbonates apparently lie in horizontal attitude, though as no decided bedding planes were observed, this separation of the rock may be cleavage. The rock is so much shattered that a slight blow of the hammer causes a large piece to break into small angular bits, and at points along the bank these fragments are simply held in place by a thick paste of red hydrous iron oxide. As the bottom of the carbonate beds is not exposed, it is impossible to estimate the thickness, but this would not seem to be considerable because at several points small fragments of a coarse pegmatite were found enclosed in the ferruginous material.

Apparently the carbonates have resulted from the direct precipitation from a sea water rich in iron magnesia and lime on the surface of the upturned gneissic beds cut by dikes of pegmatite. The feldspars of these underlying crystallines have been in part replaced metasomatically, leaving remnants unattacked towards the bottom of the deposit.

No fossils are found within the beds, and their age is in consequence a matter of conjecture, but from their lithological resemblance to the iron-bearing calcareous, magnesian rocks of the Mesabi range on lake Superior they have tentatively been classed as Huronian, though as a matter of fact they may be more correctly correlated with the ferruginous carbonates of the Devonian of the coastal plain.

It is rather difficult to estimate the extent of the iron-bearing rocks, but if we realize that it is at least 250 yards long and probably 500 along the river, that its width is certainly not less than that of the stream at the point (about 75 yards), and that a minimum thickness may be set at fifteen feet and is possibly greater, it will appear to be a fair-sized bed and one in which workable bodies of iron ore may possibly be found. As the carbonate contained no magnetite, we could not trace its continuation towards the interior of the country by the usual methods of magnetic surveying.

Limonite on Mattagami

On the Mattagami River, about 25 miles above its junction with the Missanabie, and some 16 or 18 miles below the foot of the Long portage and just north of the Grand rapid, there occurs a large deposit of limonite. The mass of ore appears on both sides of the river, which has here a width of about 400 yards, and in low water it can be seen in the bed of the stream. The deposit was discovered by Dr. Robert Bell, and described briefly by him in the reports of the Canadian Geological Survey (6).

The largest exposure of ore is on the northern side of the river, where it appears at frequent intervals along the bank for 1,166 feet, while on the opposite bank it outcrops almost continuously for 327 feet. The greatest observed thickness is shown on the southern bank, where it ascends at least 15 feet and perhaps 19 feet above the level of the river, depending on whether the overlying four feet of loose limonite is or is not in place. The greatest width of any single outcrop is seen on the northern bank, where a 45-foot surface of ore is exposed. The limonite occurs at the base of cliffs of limestone lying almost horizontally 30 to 40 feet high overlain by fine-grained boulder clays and silt. Its continuation toward the interior is hidden by these overlying rocks, and its appearance at the foot of the cliffs often obscured by the talus resulting therefrom.

All the limestone overlying the ore contains iron carbonate; the lower part, or that in close proximity to the ore, being often decidedly ferruginous. The mass of the ore has resulted in part

(6) Rep. Can. Geo. Survey, 1875, page 321.

Digitized by Google



Digitized by Google

from the direct oxidation of the siderite in this iron-bearing limestone and in part by the replacement of calcareous and other impurities contained within the iron carbonate of the limestone by hydrous iron oxide, deposited either as siderite and subsequently oxidized, or directly as hydrous iron oxide in cavities. This ferruginous material is brought in solution as carbonate by waters containing carbon dioxide, and is doubtless leached from the wide area of siderite-bearing limestone above the ore stratum.

The other smaller part of the deposit has been formed in a slightly different way—namely, by the direct deposition of hydrous iron oxide in the cavities in the loose talus of limestone and boulder clay at the foot of the cliff. Doubtless this has also been in part a process of replacement of the iron-bearing limestones and other soluble rocks contained in the debris by hydrous iron oxide. This enrichment is still proceeding by the oxidization at the surface of the waters of

iron-bearing limestone is approximately Corniferous (Devonian), and the ore is hence of later date than that epoch. Some of it is undoubtedly post-glacial, as seen by the glacial material which it contains, and a small portion is certainly modern.

In texture the ore is sometimes soft and spongy, often botryoidal and reniform, again dense, hard, and resembling hematite. In color it is rusty yellow, brownish, purplish, or even bluish-black. Lithologically, for the most part, the ore is an exceedingly pure and high-grade limonite or brown hematite, excellently suited for the manufacture of steel and commercially fit for any use to which the best of iron ores are adapted. The following are the results of the analyses of several specimens and enclosing rock :—

(1) Of the limestones containing very little iron.

(2) Of the more richly ferruginous limestone.

(3) Of the breccia ore.

(4) Of the pure ore.

	SiO_2	Al_2O_3	Fe_2O_3	CaO.	MgO.	CO_2	H_2O.	SO_3	Organic	S.	P.	MnO_2
1	.56	.20	1.03	48.43	5.32	43.93	.18	.58	.39	.....	.....	.....
	.38	.26	1.76	53.80	.82	43.00	.18	.30	.....	.....	.....	.....
2	3.42	1.38	2.48	32.32	16.18	43.03	.20	.21	.....	.....	.....	.....
3	9.44	.70	68.95	.76	.27	18.93	.....	.....	.....	.10	.22	5.44
	21.56	2.52	48.97	3.32	1.39	15.73	.....	.....	.....	.08	.11	5.66
4	2.90	.40	81.82	.75	.....	12.88	.....	.....	.....	.09	.08	1.58

the numerous chalybeate springs which flow from beneath the limestone and enter the river at this point. Much of the ore along the river bank on both sides is not a solid limonite, but is more correctly a very rich limonite breccia or conglomerate containing unreplaced bits of limestone and pebbles of quartz and other rocks as well as small masses of clay. The upward limit of the ore is exceedingly irregular; sometimes rich limonite is seen standing in vertical contact with limestone which contains little or no iron carbonate, or again there is a more gradual transition from limonite through partly oxidized carbonates, to limestone quite unchanged. In general there is a tendency towards greater enrichment along the jointing planes.

The Mattagami river at the point where the ore body appears runs apparently in a very shallow syncline towards the centre of which the beds have a slight dip from either side. The middle of the trough was doubtless a locus of extensive deposition of ore previous to its being the bed of the river. The age of the ore is somewhat uncertain. The

In the mass of the ore there is a considerable amount of unoxidized carbonate, as well as other impurities in the breccia ore. At a favorable point on the south shore a shot was fired in the limonite, and a fragment over three feet deep blown away. Little or no deterioration in its quality could be observed at this depth. On the north side the ore, covered by a talus of limestone fragments and boulder clay, is at the surface cut off to the west by a high cliff of limestone and to the east it disappears beneath the debris. On the south side the ore is lost both to the east and west beneath the loose talus material. The remarkably abrupt contact of the ore body with the sideritic limestone to the west on the north side, has led me to the conclusion that by far the greatest part of the ore has been brought by circulating waters, and is not so much due to the direct oxidation of the carbonate in situ.

When it is remembered that most of the ore is of high grade, that the area exposed is large, that the actual ore body may prove to be much

Digitized by Google

Sketch of portion of the
MOOSE RIVER
Scale: 1/4 miles = 1 inch
Gypsum beds as
Limestone as
Timber
Limestone
Shallow Rapids
Upper South-East bend
Heavily timbered
Lower South-East bend
Limestone
Limestone
Limestone

larger when the overlying mantle of drift has been removed, and that finally, it exists in an easily workable position, the value of the deposit will be readily appreciated.

Mr. Borron mentions(7) a deposit of limonite similar to that of the Grand rapid as appearing on the Oba river, and is of the opinion that there are many similar ore bodies within the Moose Basin. The limestones outcropping on the Wabiskagami river just below the Pre-Cambrian boundary, were in places observed by the writer to be so ferruginous as almost to deserve the name of impure iron ore. Chalybeate springs are frequently seen throughout the entire coastal plain along the various rivers from the Albany to the Harricanaw, and may show the wide extension of this iron-bearing horizon of limestone.

Gypsum on the Moose

On the Moose river, starting about twelve miles below the mouth of the Mattagami river, are the gypsum beds known to the natives of the country as the "white rocks." These were briefly described by Dr. Bell in the publications of the Canadian Geological Survey (8), and were afterwards mentioned by Mr. Borron (9).

The beds are found on both sides of the river, although they are not seen on the numerous large islands of midstream. There are two separate groups of gypsum beds. The upper extends along the northwest side of the river for two miles and a half, and along the opposite side for about two miles and three-quarters, while the lower is as far as known, limited to the southeast side where it starts some three or four miles below the foot of the upper bed and continues for about one mile.

The gypsum beds of the Moose are an important part of the topography of the Moose Basin, and appear as a series of low cliffs facing the river front. The thickest and purest beds are shown by the upper exposures on the northwest side. The beds are overlain by limestone bearing crinoidal fossils, although it only apears at the end of the beds and in the shallow synclines shown on the cliff face. The truncated anticlinal folds of gypsum, with the limestone in the flat-lying synclinals, are overlaid by a varying thickness of a breccia of gypsum, limestone and clay. Above this beds of boulder clay and clay marl, which are sometimes gypsiferous, fill up the inequalities and produce a bank of even crest line. The breccia overlying the gypsum and limestone varies considerably in character. Above the gypsum it is practically all a gypsum breccia, while above the limestone it is wanting, or is mixed with limestone and decidedly thinner; its place being taken by glacial or more recent material.

Approaching the gypsum bed from the southwest along the river, limestone is exposed about one-quarter of a mile above the gypsum for 150 yards, and it is evident from the disturbed and deformed character of the outcrop that the gypsum, which is the cause of the local warping, underlies it at no great distance. A talus of shattered limestone continues from the limestone in situ to the first apearance of the gypsum. This limestone is a dense, fine-grained, light-grayish rock, evidently containing considerable iron carbonate, which oxidizing in places gives the limestone locally the rusty appearance of an iron ore. Encrustations of iron pyrites and geodes with scalenohedrons of calcite also occur. Springs of clear water and others with ferrous carbonate, which oxidizes at the surface, enter the river at this point.

From its first apearance to the point at which it finally disappears below the overlying limestone the gypsum shows many changes in its thickness above the water; sometimes in the anticlines rising to a considerable height, again in the synclines almost or entirely disappearing. The average thickness of the gypsum bed is about 10 feet, although it is often less, and has a maximum of 16 feet above the water level. In quality it is sometimes a grayish, pinkish, greenish, or even snow-white, saccharoidal gypsum; again it is a coarsely crystalline, brownish, and whitish-gray gypsum; often it is a laminated, whitish saccharoidal gypsum with stellate-shaped spots of brown selenite; and lastly, it is a clear, transparent selenite. The lower beds are generally purer than the upper, and there is a tendency towards the more finely crystalline varieties with depth. The overlying breccia is thoroughly indurated, but its value is diminished, if not ruined, by the mixture with limestone, clay, and other impurities. Selenite is in this breccia a variety commonly seen.

Extent of Beds

A description of the beds at several points along their course will give a clear idea of their general character. Measurements are made from the first appearance of gypsum.

At 50 yards the gypsum rises from the limestone shingle two feet back from

(7) Report on the Basin of the Moose River, p. 72.

(8) Rep. Geo. Sur. Can., 1875, page 321.

(9) Report on Basin of Moose River, p. 61.

Digitized by Google

the river shore to a height of eight feet two inches, and is overlaid by 15 1-2 feet of many-pebbled boulder clay containing numerous large pieces of gypsum just above the solid material. In quality the gypsum is chiefly grayish, saccharoidal gypsum with some selenite.

From 165 to 275 yards, banks of mixed grayish and brownish finely crystalline gypsum rise eleven feet above the water, and disappear beneath the sands and boulders of the river bottom at two feet below the water.

At 500 yards, nine feet three inches of saccharoidal brownish gypsum rise from the water's edge, and are overlaid by twelve feet four inches of roughly stratified drab and lighter-colored sandy marl.

From 600 to 975 yards no outcrops of gypsum occur, and the trough is filled by interglacial lignitic clay, from which issue springs of dirty water coated with some oily material, which smells not unlike petroleum.

At 975 yards limestone with a decided sharp tilt up-stream appears, and just beyond the gypsum again outcrops.

At 1,000 yards whitish saccharoidal gypsum with some rusty crystalline selenite rises ten feet four inches above the water, and is overlaid by two feet of gypsum breccia, above which are deposited twelve feet six inches of limestone bearing boulder clays and clay marl.

At 1,100 yards to 1,225 yards gypsum is absent, but a syncline of drab-colored, much broken porous limestone appears, in which trough the lignitic measures again show up.

At 2,095 yards ten feet of beautiful white gypsum rise from the water, overlaid by six feet of brecciated gypsum, above which is 13 feet of boulder clay and marl clay, sufficiently indurated to stand alone. The gypsum retains this great thickness for almost 1,000 yards.

At 3,050 yards fifteen feet of fine whitish, saccharoidal gypsum is overlaid by fifteen feet of clay marl. From this point on the quality of the gypsum deteriorates, and the thickness of the brecciated upper portion of limestone and gypsum increase relatively to the purer lower portion.

The cliffs of gypsum presented to the water front are often bizarre and grotesque; sometimes appearing as a series of snow-white columns divided by deep caves and caverns; again shelving gradually in a series of overlapping conchoidal sheets from the base of the overlying marl to the river edge. The interior of the country is pitted in all directions with deep, steep-edged holes, sometimes round like a chimney, sometimes oval shaped, separated by low, rounded hillocks or by flat, abruptly-rising mounds. The holes are due to the sagging of the overlying beds of drift into spaces produced by the dissolution of the underlying gypsum, since the deposition of the drift and the hillocks indicate partly the retention of the original position held by the bed, and partly perhaps further swelling of the gypsum, due to greater hydration.

There can be no doubt that the gypsum bed has resulted from the hydration of anhydrite. Ample evidence of this fact is shown in the corrugated, distorted, and deformed nature of the limestone beds which overlie the gypsum, as compared with the slight departures from horizontality everywhere throughout the Palaeozoic basin of James Bay, save where gypsum is found.

The character of the upper gypsum beds on the southeast side does not differ materially from that of the opposite side, though in general the quality is not so good, and the amount of brecciated gypsum predominates over the unbroken material. The beds appear almost continually along the river, and like those of the other side of the stream are overlaid by broken limestone and gypsum, and by a varying thickness of boulder clay and marl. The cliffs are more cavernous and indented than on the northwest side. The general topography away from the bank resembles that on the opposite side. The gypsum beds, though generally massive, show at several points on this side, the anticlinal swelling of the upper beds especially, and the consequent fracturing of the overlying limestone.

The best part of the gypsum bed is from 1,400 to 2,100 yards from the southwest end of the outcrop, where ten to twelve feet of whitish, saccharoidal gypsum rises from the water, and is covered by three to six feet of clay, mixed limestone and gypsum breccia, and by six to ten feet of boulder clay and marly clay.

The lower gypsum beds on the southeast side are composed almost entirely of grayish crystalline gypsum with spots of brownish selenite, which apparently contain considerable impurity. They are not so remarkably caverned and pillared as the upper cliffs, and occur usually as sloping banks a few feet back from the summer water level. The maximum thickness is about thirteen feet, which is attained towards the southern part of the exposure from which it thins and wedges out towards the north.

Digitized by Google

Gypsum Mountain

In the midst of an immense wet, swampy muskeg, with only a scant growth of stunted spruce and tamarac, a most remarkable feature is Gypsum mountain, with its high land wooded with a large and healthy growth of Banksian pine, spruce, poplar and birch. A mountain in the true physiographical sense Gypsum mountain is not, as it stands only a few feet above the muskeg; but in contrast to the low, almost interminable muskeg around it, it stands out with a relief almost deserving that title.

Approaching the mountain from the south, along the Algoma-Nipissing boundary line, the gypsum first becomes apparent some 1,325 yards south of Mile Post 276 as a low gentle rise from the muskeg, and soon the surface shows the same hummocky, uneven character as observed in the interior near the Moose river beds. The width of the bed along the line is some 2,300 yards. At right angles to the line westward the beds extend about 350 yards, when dipping below the muskeg they disappear from view, but the high, aspen-covered land farther to the west may indicate their continuation. East-southeast from the line the gypsum beds were traced three-quarters of a mile, where they showed no sign of giving out; in fact, had increased in thickness, and it is very probable that they extend brokenly, if not continuously, in a general southeasterly direction across the head waters of the French river, where gypsum was seen by Dr. Parks in 1898.

The surface of the land within the limits of the gypsum is exceedingly rough and uneven, and the topography is often strange and fantastic. The rugosity increases towards the middle, where the deep holes and intervening elevations present a labyrinth of wonderful natural bridges, snow-white pillars, majestic columns and deep narrow caverns. Here and there the larger holes are basins filled with water of sparkling transparency from which threads of water flow to feed a fairly large creek that winds through a maze of caves and tunnels to the east of the boundary line. These clear-watered natural reservoirs, with their surrounding cliffs and floors of shining white gypsum and with the high Banksian pines above, reflected in the marvellously clear water, give a scene of exquisite beauty. The ponds are often twenty to thirty feet in depth, and are at most twenty-five or thirty yards across. It is probable that limestone overlies the gypsum of Gypsum mountain, as it does on the Moose river, but it was not seen in place, although many large angular fragments were observed. Gypsum mountain was possibly a shoal during the deposition of the Post Glacial sediments of the Moose Basin. At its highest point are numerous large boulders, with sand containing Pleistocene sea shells.

The gypsum of Gypsum mountain is for the most part of excellent quality. It is more uniform in texture than that of the Moose river, and consists almost entirely of whitish saccharoidal, sometimes slightly grayish rusty crystalline gypsum. The thickness of the bed is probably great. Cliffs twenty feet high were frequenty seen, and the downward extension of the bed may greatly increase this thickness. The general attitude of the beds is horizontal, but their mode of formation has corrugated them into innumerable small anticlines and synclines.

Other Gypsum Deposits

Unfortunately we were unable this summer to visit the gypsum of the French river, and I can here only repeat without further elaboration, the result of Dr. Parks' brief investigation in 1898. The beds are situated at the junction of the Kawukekamastuk and Wakwayowkastik rivers, at about eight miles southeast of Gypsum mountain, and in the direct line of the continuation of those beds. The exposure rises from twelve to fifteen feet above the water, and appears along the river for approximately twenty chains. In quality it consists of both grayish and whitish crystalline gypsum, much intermixed with streaks of pure selenite. The bed is very probably a continuation of that of Gypsum mountain.

A deposit of gypsum appears on the Harricanaw river on the western side of and near the head of Gordon island. The deposit is only of interest scientifically, as it is too small to be of any economic value. Overlying a horizontal limestone, sometimes exceedingly porous and dark in color, again more compact and lighter in color, is a bed of hard, dark crimson clay. Within this clay are small patches of beautiful red crystalline selenite, and in the lower part of the stratum, just above the limestone, are a number of small layers of satin-spar gypsum, none of which exceed four inches in thickness. The hard red clay extends along the river for about half a mile, and has a maximum thickness of perhaps ten feet. Reddish clay, similar to that in which the gypsum occurs, is also exposed opposite the foot of Gordon island, on the mainland.

Digitized by Google

Following are analyses of two samples of gypsum, made by Mr. A. G. Burrows, Provincial Assayer, Belleville. They are from the upper beds of the Moose river, and represent respectively the pure white saccharoidal gypsum, and the light brownish crystalline variety.

Constituent.	Sample No. 1.	Sample No. 2.
Water	21.35	21.01
Silica	None.	Trace.
Ferric oxide and Alumina	Trace.	Trace.
Lime	32.80	32.90
Magnesia	.70	None.
Sulphuric acid, SO_3	44.98	45.98

Shales and Clays

Dr. Robert Bell remarks in the Report of the Geological Survey of Canada for 1877-78. "On the Abitibi River, which was explored by one of my assistants in connection with the work of the season, bituminous limestones and carbonaceous shales were found, belonging to the Devonian formation, and which have a strong resemblance to the petroleum-bearing strata of the same age in the Athabasca-Mackenzie valley. These rocks occur all along the Abitibi between twenty-nine and thirty-nine miles from its mouth, and in one place the limestone contains a little free petroleum."

While in the Moose River Basin this summer these carbonaceous shales, spoken of by Dr. Bell, were investigated by Dr. Parks and myself, but we were unable to find anything indicative of petroleum. There is a faint odor resembling that of petroleum on breaking a fresh piece of shale, and a rather frequent appearance of a bluish-red scum on the surface of standing pools, which is commonly supposed to be due to petroleum, but which is much more probably due to the oxidation of iron pyrites, the odor being that of sulphurous acid, and the scum hydrous iron oxide.

The shales are however interesting in that they are the Devonian equivalents of the carbonaceous clays of the inter-glacial period. They consist of soft, dark-gray, often rusty and sometimes carbonaceous shales, interstratified with light gray green shales, also occasionally rusty.

In general the rocks show both cleavage and bedding, which are usually parallel, and dip at low angles to the horizon; but in some places there are pronounced local variations from horizontality, and the shales at times are much deformed and shattered. These more marked irregularities are often apparently due to ice pressure during the Glacial age. The shales, fine in grain and remarkably uniform in texture, show main joints running in a southeasterly direction, besides irregular, circular and conchoidal jointing. The shales in weathering break down, and form soft, plastic dark and light-gray clays, which are indistinguishable from those of glacial origin.

They first appear on the shore of the Abitibi at the foot of the Long rapid, and outcrop at frequent intervals for about four miles. The most prominent exposure is that which appears on the eastern shore, just above the head of Plum Pudding island, and which continues along the river as a series of high cliffs for rather over half a mile. These have a maximum height of thirty-seven feet, of which the lower twelve feet above the water are composed of soft grayish shales with lenticular, orbicular, calcareous concretions, and the upper twenty-five feet are of black and rusty carbonaceous shales. The beds dip up stream and inland at an angle of twenty-five degrees. The river at this point probably runs on the eroded crest of a low anticline.

The great clay banks which appear so prominently in the coastal plain region may contain numerous deposits of clay suitable for making fire bricks, pottery and possibly even china. Doubtless, also, the sands with which they occur may be of economic value in the manufacture of glass.

The chief requisite for a fire clay is, I believe, that it should contain as small an amount of fusible material as possible—the less the better, and four per cent. is about the limit.

Beneath the lignite on the Abitibi, Soweska and elsewhere occurs a beautiful, fine plastic clay, generally light gray-green in color, but sometimes stained dark brown, or almost black, by carbonaceous material. These clays are uniform in texture, paint-like in appearance, and are free apparently from sand and grit. They occur widely spread, but are best shown at the deposit of lignite on the Blacksmith Rapids (10). I had thought that these clays might be used for fire clay, if not for pottery, but apparently they contain too much fusible material for the former, and are in reality better suited for the latter purpose. Potter's clay is a fusible variety, usually containing some oxide of iron and carbonate of lime; the latter ingredients

(10) See Borron's Report on the Basin of the Moose River, 1890, p. 72.

Digitized by Google

causing it to effervesce slightly with acid, and the former giving it, after burning, a red or yellow color. It will be interesting to compare the analyses of several clays from the Moose Basin with those used at large pottery establishments at various points.

Locality.	SiO_2.	Al_2O_3.	Fe_2O_3	CaO.	MgO.	K_2O.	Na_2O.	SO_3.	H_2O+C
Blacksmith rapids, Abitibi river...	62.76	18.47	3.18	.88	.91	2.98	.29	.10	11.04
" " "	55.56	21.87	7.171	.241	.60	Tr.	3.00	3.47	6.82
(11) Stevens Pottery, Baldwin, Ga	46.07	21.72	15.75	.25	.67	.48	.....	.....	.34
(11) Uhles Pottery, Evansville, Ind	59.50	26.22	.80	.362	.76	2.96	.....	.....	.....
(11) Stoneware clay, Woodbridge, N.J	67.84	21.83	1.57	.28	.24	2.24	.....	.....	6.70
(12) Fire clay	69.33	23.62	.561	.49	Tr.	.....	.....	.....	.....

Kaolinic Clay

Of the deposits of clay in the Moose Basin none are more interesting than the unstratified beds of kaolinic material which it is believed are sufficiently pure to be used for the manufacture of fine china. Mr. Borron describes at length a deposit of kaolin, or china clay (13) on the east bank of the Missanabie river, about five miles below Coal brook, which he considers to be of great economic importance. At the time of our visit we were unable to examine the deposit, owing to the high water, but it is doubtless a parallel of an interesting body discovered this year by our party on the Wabiskagami river eight miles above its mouth. The deposit lies on the right, or southern, bank of the stream, along which it is traceable for about four hundred feet, rising above the summer level to a height of at least ten feet. It is overlaid by a talus of soft boulder clay, which in places entirely obscures the underlying material. The kaolinic clay is soft, plastic, and unctuous, generally almost white in color, but sometimes stained deep hematite red or yellow ochre by impregnation of iron oxide. Much of it is remarkably free from sand, but other parts contain lenses and small pocket-like areas composed of grains of clear glassy quartz sand mixed with pure white kaolin.

The analysis of clay from the Wabiskagami is that of a representative sample—a mixture really of the pure white clay with the ocherous material and with the white quartz sand. It may be compared with several kaolinic clays.

It will be seen that the kaolinic clays from the Wabiskagami contain considerably more silica than either pure kaolin or the commoner china clays, but the quartz grains are mostly in large fragments which could be easily removed by suspension in water, as is the mode of obtaining Cornish clays from the disintegrated granite, leaving a remarkably pure material, save perhaps for the large amount of ferric oxide. When dried, the Wabiskagami clay is hard and dense, but is easily powdered. The powder is fine and white, and contains large grains of quartz easily separable from it.

The kaolinic clay from the Wabiskagami, with its remarkable freedom from all impurities save iron oxide, and with often even this lacking, is undoubtedly a valuable deposit. It is apparently the product of the decomposition of a granite containing little ferro-magnesian mineral, and probably highly feldspathic, such as binary granite or aplite. This material is ice-transported and unstratified. It was doubtless deposited either in the condition of rock flour or more probably as large fragments of disintegrated rock mixed with finer ground material of the same rock species.

Material.	SiO_2.	Al_2O_3.	Fe_2O_3.	CAO.	MgO.	Alk.	SO_3	H_2O+C
Wabiskagami clay	53.78	29.58	5.09	.44	Tr.	Tr.	.08	11.
(14) Pure Kaolin	46.5	39.5	.....	.....	.....	.....	.....	14.
(15) Cornish China Clay	53.16	45.61	.31	.41	.51	.....	.....	.....
(15) Meissen China	57.70	36.80	.30	Tr.	5.20	.....	.....	.....

(11) See 16th Annual Report of U. S. Geol. Survey, Mineral Resources. Non-Metallic Products, pp. 94 and 95.

(12) From Knapp's Chemical Technology, Appleton's Cyclopedia.

(13) Borron's Report on the Moose River Basin, p. 71.

(14) Dana's Mineralogy, 1902.

(15) Knapp's Chemical Technology, Appleton's Cyclopedia.

Digitized by Google

Gypsum beds, Moose river.



Gypsum beds, Moose river, showing cavernous structure.

Digitized by Google

UNIV. OF MICH.

Digitized by Google



Gypsum cliffs, Moose river.



Devonian shales etc. below Sextant portage, Abitibi river.

Digitized by Google

UNIV. OF MICH.

Digitized by Google



Near view lignite, Soweska river.

The upper Soweska river.

Digitized by Google

UNIV. OF MICH.

Digitized by Google

Fourth lignite seam, upper Soweska river.



Lignite on Soweskatriver, showing test pit in seam.

Digitized by Google

UNIV. OF MICH.

Digitized by Google

Deposits of Lignite

Lignite, or brown coal, may be described as a fuel about half way in the state of carbonization, between peat on the one hand and bituminous coal on the other. The term is a loose one, and includes materials of wide divergence in chemical composition, in texture, and even in mode of occurrence. The "braun kohl" of Saxony and Brandenburg is so soft that it is dug in the fields with spades, and piled in great stacks to dry, when it is said to form a valuable fuel. On the other hand, the lignites of the western states and those of Alberta and Manitoba are generally black in color, comparatively highly carbonized, and so much consolidated that they have to be broken with a pick. The lignites of the Moose Basin are, considering their recent age, in a remarkably advanced state of carbonization. Some of them may be compared with the tertiary lignites of the Souris valley, Manitoba and of Lethbridge, Alberta, but others are typical brown coals, and resemble the German material.

Dr. Robert Bell was the first to describe the occurrence of lignite in northern Ontario (16), but his investigations were limited to Coal Brook and the Missanabie river. Mr. Borron carried on explorations for lignite in 1885, but also chiefly on Coal brook on the Missanabie (17). Jr. Parks mentions the occurrence of lignite on the Abitibi river at the Blacksmith rapid (18).

As already mentioned, the lignites of northern Ontario are of Glacial age, occurring in stratified beds of clay-shales. The coal measures, as these inter-Glacial beds may be called, occur extensively throughout the whole region. Their distribution has been given in the general discussion. They by no means always carry beds of lignite, but in general they are always more or less carbonaceous. It is noteworthy that the localities at which the greatest thickness of inter-Glacial clays occur are the most barren of lignite. On the Wabiskagami, for instance, where the coal measures are well exposed for miles along the course of the stream, practically no lignite beds are visible, although many very thin seams are interstratified with the hard, very evenly bedded clays. On the Nettogami river, just above the Kiashko river, thick beds of black clay shales, very regularly disposed, rise from the river with almost cliff-like precipitance. From a distance the beds look as if composed chiefly of lignite, but investigation showed the color was due not to thick strata of this material, but to a great many very thin seams of a rather peaty lignite intercalated with the thicker beds of clay and arenaceous shales. The Glacial age of the coal measures was determined at numerous points by the occurrence of boulder clay containing striated pebbles both above and below them. It is very probable that the lignite beds are not all of the same period, and that they belong more correctly to several rather than to one inter-Glacial period, but I know of no direct evidence in favor of this hypothesis. There is a great difference in the state of carbonization of the beds, but this is due apparently not so much to difference in age as to the amount of deformation which the beds have undergone. When undisturbed they retain a distinct peaty character, but where folded they are often highly carbonized. It is impossible to connect with each other the isolated and often widely separated coal seams of the inter-Glacial coal measures. In general there is a marked similarity in their mode of occurrence and in the beds which overlie and underlie them.

Beds on the Missanabie

Owing to the high water on our way down the Missanabie, we were unable to examine the deposit of lignite on Coal creek, and I had not time to return to it later in the season. However, as the occurrence had been carefully studied by Mr. Borron, and described by him,(19) I did not think its investigation as important as that of the several little-known deposits occurring elsewhere.

A small deposit of lignite occurs on the Missanabie on the southeast side, some nineteen miles below Coal brook, and about two miles and three-quarters above Cedar island. The seam is exposed in a steep bank of till, which rises from the river at an angle of sixty-five degrees for the first 100 feet, and at a much flatter angle for 40 or 50 feet more. The vertical height of the hill is about 75 feet above the summer water level. The bed has a maximum thickness of thirty-four inches, of which the upper eighteen inches is impure and mixed with clay, and the lower sixteen inches of fair quality and quite uniform in texture, being made up chiefly of slightly carbonized moss, sticks and rushes. The bed is traceable for only a few yards, where it either thins out or is lost in the heavy talus from the bank above. It is underlain in des-

(16) Rep. Geo. Sur. Can. 1875-77.
(17) Report on the Basin of the Moose River, p. 62.
(18) Rep. Bur. Mines, Vol. 8, p. 188.
(19) Report on the Basin of the Moose River, p. 65.

Digitized by Google

cending order by one foot of stratified sandy clay, ten feet of unassorted sand and small pebbles, thirty feet of sand merging into yellowish boulder clay, thirteen feet of sand with numerous small pebbles, sixteen inches of stratified fine-grained yellowish clay, seven feet of mixed sand and boulder clay, and thirteen feet or more of a hard dense clay conglomerate, containing numerous quartz grains and pebbles. Above the lignite lies about thirty-five feet of boulder clay and blue clay merging probably upward into post-glacial marine strata.

Another small seam of lignite is visible on the southern bank of the river, almost opposite the mouth of a large stream which enters the Missanabie about one-half mile below the mouth of the Soweska. This bed is traceable for at least 600 feet, though it is often obscured by heavy talus of clay and boulder clay, and its termination to east and west is completely hidden. The vegetable nature of this lignite is very apparent, and it may more correctly be called a peat. The seam, which has a maximum thickness of about three feet six inches, is made up of thick laminae of moss and sticks divided by thin layers of silt. This is evidently the same lignite bed as already described by Dr. Robert Bell, who gives the following section (20): "Immediately beneath the lignite is a layer one foot thick of irregularly mingled clay and spots of impure lignite. Next below this are forty feet of unstratified drift, full of small pebbles, under which are a few feet of stratified sand and gravel. Resting upon the lignite are five feet of hard, lead-colored clay with seams and spots of a yellow color, and layers of red gray, drab and buff. Above all, and forming the top of the bank sixty feet high, are ten feet of hard, drab clay, with striated pebbles and small boulders, and holding rather large valves of Saxicava rugosa, Macoma calcarea (Tellina proxima), and Mya truncata."

During the wet spring weather on the Missanabie, streams of soft, sticky clay are continually flowing from the wet upper beds of glacial clays, undermining the more consolidated post-glacial, and causing it to break away. The lignite bed just described, and its enclosing stratum, were with difficulty studied, owing to the great amount of this material which covers it, and it is quite probable that the seam which I saw may be only the inland continuation of that seen by Dr. Bell, much having been removed by erosion.

(20) Rep. Geo. Sur. Can., 1877, p. 4C.

Traces of shaly lignite appear on the southern bank of the stream at a few feet above the summer water level, about four miles below the last described seam or at about six miles above the mouth of the Opazatika. The appearance is unimportant, the lignite consisting of mere podlike lenses in the stratified clays.

The lignite which outcrops just below Big rapids on the Missanabie on the northwestern bank of the stream shows up at intervals for 350 feet. It appears at nine feet above the summer level of the river, and at eighteen feet below the level of the bank above. The lignite itself, though often imperfectly mineralized, is nevertheless of good quality, and consists almost entirely of somewhat carbonized wood. It is not in a true seam, but is instead a bed of lignite fragments and sand, probably re-assorted material broken up by the last glacier and worked over by the action of post-glacial waves. In my examination I found no point at which the thickness of the bed exceeded one foot, though Mr. Borron intimates a greater thickness and possibly the thickest part has been removed by the decay of the bank (21). The lignite is overlaid by gravel and sand, and underlaid first by a thin stratum of sand, and then by hard clay conglomerate.

The pieces of lignite are often large, but when exposed to the air, they tend to break up into smaller bits. However, when obtained even a short distance away from the outcrop, the lignite is apparently more adhesive, and can be kept for weeks (22) without falling to pieces. It breaks with a conchoidal fracture, the fresh surface showing the compact texture and rather brilliant lustre of jet. The analysis of lignite from the Big rapid shows it to be of good quality. It is unfortunate that it should occur in such small quantity.

Peaty lignite occurs in the interglacial beds already mentioned as overlying the gypsum of the Moose river. The quality is fair, but in quantity these are mere pockets.

On the Opazatika

Several seams of impure lignite occur on the lower Opazatika River, the most important being at two and a half miles, at three miles, and at three miles and three-quarters above the mouth. The lowest outcrop shows two small seams in a bank of stratified clay and boulder clay about twenty feet in

(21) See Borron's Report on the Moose River Basin, 1890, p. 68.

(22) A sample was kept for five months intact, at the end of which it suddenly broke up and fell apart.

Digitized by Google

Digitized by Google

height on the western side of the river. The seams are about three feet apart. The lowest is of fairly pure but very mossy lignite. The seam is only a few inches thick, and is overlaid and underlaid by blue clay. The upper seam is an exceedingly compact argillaceous brown lignite, also narrow and unimportant.

The second bed on the western side of the river shows lignite of rather better quality than the first. It is composed chiefly of moss and rushes, not much carbonized, which break off in long strips sixteen inches long. The seam is some nine inches thick, and is traceable for 225 feet along the bank, and reappears again about one hundred yards still farther up stream.

The third outcrop shows a lignite bed about twelve inches thick, of rather poor quality, underlaid by blue clay and overlain by rusty clay and sand. The seam extends along the bank for about 300 feet. All the lignite beds on the Opazatika and Missanabie lie practically horizontally, the small departures from this attitude being scarcely observable.

The Soweska Seams

The Soweska river shows the greatest amount of lignite outcropping along its banks of any of the streams so far examined in the Moose Basin, there being eight distinct points at which it occurs within a distance of four miles. Of these the lower three are practically one seam; while the other five, although they may be one seam, are so widely separated from each other that they cannot be so connected. The seam lowest down the river starts about three miles from the Missanabie in a straight line, or some five miles following the bends of the river. In was at this point, Ells' bend, that most of our work was done.

The seam first appears on the left or northern bank of the stream, at the point where the bank rises from the low level of the flood plain to that of the elevated plain above, and is continuous all around the convex side of Ells' bend, a distance of about 1,000 feet east and west, and rather over 900 feet north and south. The seam does not appear on the concave side of the stream, this being a low flood plain below its level.

In the next bend the second appearance of the lignite shows up on the opposite or right hand side of the river, the concave side being a flood plain which cuts off the southward continuation of the first appearance. This second showing of lignite is traceable for 650 feet along the bank, when it is cut off, owing to the sloping of the bank, but reappears some 700 feet farther south, where cut banks again are visible on the right hand side of the stream. This third outcrop of lignite is visible for but 250 feet, when it is buried beneath a heavy talus of clay and sand.

These three appearances of lignite all belong apparently to one and the same seam, which has thus a total north and south extension of at least three-quarters of a mile, and a minimum width east and west of one-quarter of a mile, as shown partly by the exposures along the bends of the river, and partly by the records of holes drilled with a long articulated auger in the interior away from the bank of the stream.

There is a great irregularity in the thickness of the seam. It has a maximum of about five feet, averages over three feet, and thins out almost to zero at the northern end of the seam at the third appearance. Where it first shows up in the northeast of Ells' bend, it has a thickness of three feet nine inches, and is composed of brownish and blackish layers of rather argillaceous material. The seam is about forty feet above the summer water level, is overlaid by boulder clay and post-glacial stratified beds, and underlaid by hard blue clay merging into dense clay conglomerate.

One hundred and eighty-five feet farther west, the seam lies 38 feet up the bank, and has increased to four feet two inches in thickness, but much of it is still argillaceous (opposite 11 on diagram). Two hundred and fifty feet beyond (or fifty feet west of 9), the seam has diminished to two feet three inches in thickness of which quite one foot is of good quality and the rest is fair. Two hundred feet more to the west (opposite 7 on the diagram) the lignite is four feet two inches thick, of which three feet five inches is of good quality. Two hundred feet still farther westward is a three-foot outcrop of splendid lignite (opposite 5). Three hundred and seventy-five feet to the south of the last, the outcrop is about five feet thick, composed as follows:

1 ft. 6 in. Poor, argillaceous lignite.
6 in. Superior lignite.
2 ft. Argillaceous lignite.
1 ft. Good lignite.
2 in. Argillaceous lignite.

At this point the lignite is overlaid by a few inches of stratified grayish clay, above which lies twenty-five feet of yellowish, weathering blue clay with occasional pebbles, some of which are striated. This is surmounted by four feet of post-glacial argillaceous sand containing numerous marine shells. Beneath the lignite lie 38 feet of blue clay with numerous boulders, merging

Digitized by Google

Elf Bend, Soweata river; location of lignite deposits. Scale, 200 feet—1 inch.

Digitized by Google

in depth to a hard arenaceous clay conglomerate grit.

Near the point where the seam disappears beneath the sloping bank on the south side of Ells' bend, it has a thickness of three feet four inches measured from above as follows:

.9 ft. Argillaceous lignite.
.4 ft. Blue clay.
.3 ft. Fair lignite.
1.8 ft. Rather argillaceous lignite.

Where the lignite bed reappears at the second place of occurrence on the other side of the river, it has diminished in thickness to a little over two feet, the seam occurring in a high, steep bank forty feet above the level of the river, underlaid by yellow weathering arenaceous clay with pebbles, and the clay conglomerate. It is overlaid by fourteen feet of clay containing few boulders, and four feet of post-glacial marl-like silt. The seam, which is about half of good lignite and half of argillaceous material, retains the average width of somewhat less than two feet throughout its outcrop. It is of the same quality and thickness as at the third point of appearance on the next bend above.

When we reached Ells' bend the seam was by no means exposed all along the out face of the bank; in fact, in comparatively few places did it outcrop prominently, and was for the most part hidden by talus. However, we proved its continuity by cuts in the bank, made at frequent intervals. To make certain of the extension of the seam inland, five bore-holes were sunk by an articulated auger (as shown on the accompanying map).

As the most inland of the holes passed through an increasing rather than diminishing thickness of coal, at a point four hundred feet from the edge of the bank, I considered it unnecessary to continue investigations further.

Drilling at Ells' Bend

In drilling we were much inconvenienced by the quicksand nature of the stratum at the bottom of the post-glacial silt, etc., which filled into the narrow drill holes as fast as the auger could be removed, and we found it necessary to put a hole three feet wide down from the surface to the top of the boulder clay, the edges of which were surrounded by timbers kept in place by nails and willow hoops. Another inconvenience was the occurrence of the small pebbles in the clay overlying the lignite, which were continually sticking in the auger and stopping its progress. In fact, in several holes we were obliged to desist for this reason, and we were never able to drill in the hard, boulder-filled stratum beneath the lignite. We found it unnecessary to erect triangles to haul out the auger, the high aspens growing along the bank of the Soweska making an excellent substitute.

The quality of the Ells' bend lignite is for the most part fairly good. It is not very highly carbonized, but it is very much better as a fuel than its analysis or even appearance would warrant. While we were camped on the Soweska we used it almost entirely as fuel, and it proved most satisfactory. When taken from the seam in large pieces, it is almost black and of a dull, earthy aspect, this appearance being due to the large quantity of free water which it contains. When dried, though it adheres well and does not break apart, it is much lighter in color and less coal-like in aspect. Even when put into the fire wet, it burned easily, emitting a strong bituminous smell, and left apparently a comparatively small amount of ash. Even the argillaceous varieties burned freely, though of course with a proportionately larger quantity of ash.

It is my opinion that the relatively high percentage of ash in much of the Soweska lignite is within certain limitations not so serious a detriment to its value as it would be in the case of other coals containing a greater amount of fixed carbon. It has been observed that the lignites with a very small proportion of ash, as at the Big rapids of the Missanabie, exhibit a tendency to crumble, while the Soweska lignites with a much higher percentage of ash retain their coherency, and apparently burn quite as well.

The lignite of Ells' bend is almost entirely formed from moss, though at a few points along the seam many small sticks occur between the layers. These sticks are but slightly carbonized, though squeezed almost flat parallel to the bedding planes. The lignites lie practically in undisturbed horizontal positions; though there may be a very slight dip down stream.

It is hardly probable that the lignite of the Soweska is worth transporting to distant markets in southern Ontario, but there is no doubt that it will be eminently valuable as a fuel for the people who will undoubtedly inhabit the fertile valleys of the rivers which form the Moose Basin.

The fourth point where the lignite ocurs on the Soweska lies almost two miles and a quarter southwest of Ells' bend. The seam outcrops for about 240 feet in a bank some 60 feet high. The

Digitized by Google


moss etc. on surface
indurated post-glacial with marine shells
Yellow-weathering blue-clay with occasional pebbles, some of which are striated
lignite
Thick blue clay with boulders merging in depth to an arenaceous clay conglomerate
water level
alluvium

Cross section of Soweska river at Ells' Bend. Scale 34 feet — 1 inch.

Drawing by J. M. Bell.

Digitized by Google

maximum thickness is about two feet five inches. The quality is for the most part poor, being decidedly argillaceous. The bed is overlain in ascending order by six feet of sand, over ten feet of boulder clay, and eleven feet of stratified marl which is decidedly consolidated and stands out in an overhanging cliff above the bank below. Beneath the lignite lies the usual clay conglomerate.

The fifth point of occurrence of lignite is rather over a mile west of the last described. Here a seam, mostly of good lignite, but with some decidedly argillaceous material appears for a little over 300 feet. The seam, which has a thickness of two feet six inches, is overlain by a boulder clay and marl-like silt, and underlain by yellow, weathering sand.

Numbers six is probably a continuation of number five. It appears on the opposite side of the river in the next bend of the stream above. The bed which varies in thickness from three feet three inches to four feet two inches, is exposed about half-way up a bank sixty feet high, at intervals for 125 feet, being lost at either end in a talus of thick, soft, aqueous clay which rendered investigation both dangerous and difficult. The lignite is very impure, being mixed with sand, clay and gravel. It is overlain by unassorted clay and by stratified silt, and underlain by three to five feet of stratified soft, sandy grit, bearing striated boulders, beneath which is the widespread hard clay conglomerate.

Number seven is brokenly continuous for 670 feet; and where it first appears is exposed about half-way up a bank 55 feet high. It varies in thickness from three feet to over five feet. Almost half-way along its course, where it has a thickness of five feet, two inches—the upper two feet being good lignite, and the lower three feet two inches sand mixed—it is overlain by 15 feet or more of boulder clay, and 10 feet or less of post-glacial stratified silt, containing numerous shells. Beneath the lignite lies two feet of stratified sand with thin layers of lignite, followed by hard clay conglomerate. Where the lignite is cut off to the west by the slope of the bank, it is directly overlain by reassorted silt. At this point the following section was made, measuring from the top of the bank :

0 ft. to 7 ft. Marl-like silt.

7 ft. to 10 ft. Lignite, more or less impure.

10 ft. to 14 ft. 6 in. Bedded sand with a little gravel becoming coarser.

14 ft. 6 in. to 17 ft. 6 in. Rusty, fine gravel, coarser in descent.

17 ft. 6 in. to 20 ft. 9 in. Fine-grained sand.

21 ft. to 25 ft. Gravel, talus-covered.

25 ft. to 37 ft. Clay conglomerate, talus-covered.

The sands underlying the lignite are often exceedingly rusty, and at one point a layer some two inches thick is so much so that it might almost be termed an iron ore.

A short distance above number seven on the opposite side of the river, number eight appears. It is a narrow seam, only eight inches thick, of very woody lignite, some fifteen feet above the summer water level. It does not increase in thickness, and runs out within 300 feet.

It is quite probable that when further exploration has been carried out along the Soweska, lignite will be found at many more points than shown by my map, as it was quite impossible to examine all the banks in a detailed way, and much lignite may be concealed beneath the heavy coating of talus which covers all but the steepest banks. At present the widespread occurrence of the lignite, in decided seams continuous for comparatively long distances, is a very encouraging feature, even if in places the quality is disappointing.

On the Kwataboahegan

The deposits of argillaceous lignite on the Kwataboahegan River were examined by Dr. Parks, who reported nothing of economic value. The lowermost deposit occurs on the north bank some 60 miles above the mouth of the river. The seam, which has a maximum width of two feet six inches, outcrops almost continuously along the edge of the river for 450 feet in a bank 40 feet high. Though compact and hard, it is never pure, and is for the most part mixed with clay. Above it lies above 25 feet of hard, blue clay, surmounted by six feet of shell-bearing post-glacial material. Below the seam is a hard stony clay, containing many shells. This is of great scientific interest, as it is the only point in the Moose Basin where interglacial shells are known to occur.

About half a mile above this point on the opposite side of the river, appears a lignite bed which is probably a continuation of the one just described. The whole is argillaceous, and the upper part is mixed with blue clay. It is overlain by bluish clay, and underlain by hard, stony gray clay. For a mile and a half up the river from this second exposure, or for about two miles from the foot of the first outcrop of lignite, traces of coal are observable as narrow

Digitized by Google

black streaks on the face of cut-banks. These streaks appear to occupy a fairly decided position in the bank, though in places it is evident that the material which they contain has been reassorted. There is no doubt that a discontinuous bed of impure lignite exists at this horizon with a slight dip down stream, being about three feet above the level of the river at the northwestern point of exposure and only a few inches above at its lowest appearance.

About one mile above this first series of exposures, traces of lignite again show up along the river bank, and are visible at intervals for some two miles. The seams are never continuous, but are apparently mere broken lenses and scattered bits of lignite interstratified with blue clay and hard-pan. Dr. Parks thinks these may represent the remnants of the westward continuation of the first series of seams described. He considers that the blue clay above the lignite, and the gray clay beneath it, are more or less constant, the lignite being slightly unconformable with the latter, while in places the lower levels of the blue clay are interstratified with the lignite. This condition is identical with what was observed on the Soweska. The blue clay is in places replaced in part by sand, and merges upwards into gray boulder clay. The blue clay varies in thickness from a few inches to twenty or thirty feet, while the gray clay in some places reaches a thickness of fifty feet, forming the conspicuous element in the clay banks of the region. The lignite itself is both arenaceous and argillaceous. It consists of thin layers of indurated moss, with partings of clay or sand. It burned with considerable difficulty in the camp fire, leaving a large residuum of clay or sand.

On the Abitibi

Inter-Glacial coal measures are exposed at intervals all along the Abitibi from the top of the Long rapids to the mouth of Big Cedar creek, but in comparatively few places are these at all likely to be productive of coal. Drilling operations were conducted at four points—first, at a point about three-quarters of a mile below Little Cedar creek; second, on both sides of the Abitibi at the Blacksmith rapid; thirdly, just at the foot of the Long rapids; and fourth, at a point about one mile and a quarter above the foot of the Long rapids; and at only one of these points, viz., at the Blacksmith rapid, can our operations be said to have met with success.

At three-quarters of a mile below Little Cedar creek, the work was started. Though true lignite is not exposed in the shore at this point, still, as there is considerable thickness of more or less lignitic clay, it was thought that lignite might lie beneath the surface in the interior, and accordingly Dr. Parks, who conducted the drilling operations on the Abitibi, decided to put down a few holes away from the river bank here. Five holes in all were sunk, and though several passed through stratified lignitic clay the hope that true lignite would be found was not realized. The lignitic clay is apparently interstratified with a fine blue clay which underlies gray boulder clay. In places it lies horizontally, but again is deformed, probably either by ice pressure or by subsequent landslips.

East Side Blacksmith Rapid

Lignite appears on both sides of the Abitibi river at the Blacksmith rapid. A prominent outcrop occurs on the east bank about one-quarter of a mile below the foot of the rapid, and at about three feet above the water and twelve feet back from it. At this point along the shore the lignite has a longitudinal extension of only twenty-two feet ten inches, though the thickness of the bed is ten feet seven inches. It is not correctly speaking, a pocket, but is a remnant of what was probably once a thick and extensive bed. most of which has been removed by succeeding glacial corrasion. The original bed of peat, probably very little consolidated, was shoved by the advancing ice sheet into a series of close tight folds which were afterwards overridden by the ice, much of the peat ground to powder, and partly, at least, carried away. In what is left the beds are folded into a steep anticline, the crest having been truncated; while northwards for 280 feet are frequent outcrops of dark brown boulder clay containing fragments of lignite, and colored by the powder which resulted from it.

The northern limit of the anticlinal lignite remnant is much thicker than the opposite limb, the latter thinning to a few feet just beyond the crest and dying out altogether within a very short distance. The northern limb, which dips at first at an angle of seventy or eighty degrees, gradually approaches horizontality, and at fifteen feet from the crest of the anticline has diminished to two feet in thickness. The strike of the upturned bed is S. 65 deg. E., and I see no reason why the lignite should not continue into the interior in that direction, but ice shoving differs so markedly

Digitized by Google

at different points that all of the seam may have been removed, or on the other hand the present extension of the beds may be much greater The lignite is overlain at its outcrop on the river by three to five feet of consolidated boulder clay resembling hard pan, filled with huge cobbles, and this our auger could never penetrate, so that out of five drill holes sunk in wide pits with great difficulty in the interior, none with certainty even reached the horizon of the lignite. Above the boulder clay lies six feet of post-glacial re-assorted gravel and sand. Beneath the lignite is a hard brownish clay, mixed with a light pea-green clay. At the crest of the anticline a deep pit was sunk in the lignite, and from its bottom a drill hole carried down in the coal to see how deep the tilted beds extended, but after passing nine feet five inches of lignite, all our efforts could not force the auger further, so hard was the lignitic material.

The thickness of the boulder clay above the coal is variable, and at 67 feet north from the crest of the anticline of lignite, its upper surface has descended much lower in the bank than at the lignite anticline. A section at this point showed from the base up as follows : seven feet of rusty weathering unstratified boulder clay; two feet interstratified soft and indurated coarse and fine sandy gravels with some very rusty layers; two feet eight inches interstratified thin layers of sand and rusty, very slightly carbonaceous clay, (the latter predominating), having stratification, with a slight tilt of the beds inland; two feet of grayish rusty weathering hard clay, becoming darker in descent, and assuming stratification; four feet seven inches marly silt-like material, containing a few large and many small boulders, and a few small shells.

Quality of the Lignite

The quality of the lignite is excellent. In its small exposure it is remarkably pure and unmixed with either sand or clay. It consists in part of moss-formed material, and in part of trunks and roots of trees, both of which are as a rule well carbonized—though in places the mineralization is not complete in the centre of the larger trunks. Some of the roots still retain their original position with reference to the beds. The moss-formed lignite is jet black in color, though its vegetable origin is apparent. The woody lignite is not always so dark in color as the moss-formed, but when broken, after a short exposure to the air, it often shows a beautiful brilliant lustre. For the most part the lignite of both kinds is coherent, but part of the mossy material, especially that around the larger trunks, which are sometimes six or eight inches in diameter, is loose, friable, and poorly consolidated. Small concretions of iron pyrites are not uncommon in this soft material.

This coal would make a good fuel for all practical purposes. It burns freely in the open air, leaving a very small residue. If it extends inland, as there is reason to hope, then there will be a quantity of good coal for the future settlers in the region.

West Side Blacksmith Rapid

Prior to the commencement of operations on the west side of the river at the Blacksmith rapid, lignite outcropped only in a few spots along the talus-covered bank, but abundant test pits and open cuts showed the existence of a considerable body of the coal on this side of the stream. The lowermost lignite occurring was exposed by a cut at the foot of the rapids, and from this point the lignite was found by frequent open cuts to extend up stream for 160 feet at least (from open cut "S" to cut XIX.) A great deal of lignite in pieces and streaks was shown by a cut at 100 feet north (from cut "S"). Southwards (from open cut XIX) the boulder clays are barren of any signs of lignite and quite light-gray in color for 128.2 feet. Then they become pronouncedly lignitic and a hard, dense, almost black clay filled with pebbles and fragments of lignite, appears along the river for 176.7 feet, where it passes into true lignite. The lignite continues for 46 feet 5 inches, when it dips rapidly below the overlying boulder clay, and disappears.

All efforts to drill any distance down from the surface in the interior were fruitless. Six holes in all were tried, but none were successful in reaching what was supposed to be the level of the seam. All of these holes had to be dug out with picks and shovels for a depth of six or eight feet down to pass the pebbly alluvium and quicksand of the Post-Glacial, and this part timbered. Then, when drilling did get started on the boulder clay, it was always sure to be stopped by a stone before any depth had been attained.

On the river bank itself wherever true lignite was exposed, we had comparatively little trouble in drilling to find the thickness of the coal, etc., but in the boulder clays, especially in the hard black lignitic clay, it was absolutely impossible; in fact, a short distance below the surface even the pick made very little impression on this material. In

Digitized by Google



Digitized by Google

working on it, it gave the impression of having the consistency of hard, black India rubber. Test pits were sunk in it at intervals, but with a depth of a few feet no increase in the quantity of lignite was observed.

The thickness of lignite at various points is interesting. At a point two feet from the water's edge on open-cut XIV., a bore hole showed a thickness of three feet of coal, underlain by a grayish, smooth, plastic clay. At 21 feet from the water the thickness of lignite in the same open-cut is nine feet. At this point the lignite lies 5 feet below the brink of the bank, at the water's edge 15 feet felow and at 34 feet 4 inches in from the water, at 7 feet below the top of the bank; so that there must be a sharp rise in the upper surface of the coal from the water to the first drill hole and then a gradual slope inland. This may represent a thinning of the coal seam inland at this particular point, or it may be merely a local corrugation. Very probably much of the seam close to the river has been removed by fluviatile erosion.

At the top of open cut XIX a drill hole was sunk ten feet in lignite containing a very little clay, and at this depth the auger stuck, owing to the caving in of the walls of the hole. This hole was sunk at a point ten feet above the water level, and about 15 feet back from it. Another was lowered just in front, at the water level, which traversed ten feet of blue lignitic clay and then one foot of lignite. On entering the lignite bed, a flow of water was tapped which flowed for some weeks laden with lignite. Beneath the lignite is a hard boulder clay. It is very probable that the clay overlying the lignite is re-assorted alluvium, and not glacial material.

On the southern exposure of lignite on cross-cut XV, which was run N. 60 degrees W. from the river bank, at a point 31 feet from the water, a drill hole was sunk which passed through 18 feet of lignite, 10 feet 2 inches being below the river level. Beneath the lignite lies a somewhat lignitic clay; above it 9 feet 10 inches of sand, silt, etc., measured from top of bank down as follows: 3 feet sand and silt, 2 feet of gravel with marine shells, 4 feet 10 inches of boulder clay. Hole XVI, which was sunk 100 feet inland from this point, reached with great difficulty a depth of 16 feet. This passed through a little lignitic material between 14 and 15 feet, but did not enter the main mass of lignite, if indeed it exists. It is quite possible that the lignite lies lower than 16 feet from the surface, as a decided slope inland of the surface of the lignite is observable at the outer outcrop. Another drill hole was sunk just above the water level, at a few feet back from the river, and right in line with hole XV. This hole passed through first one foot of loose river gravel, and then 13 feet of lignite, beneath which lay the usual tough blue clay. Evidently the lower surface of the lignite slopes towards the centre of the river at this point. There is also a gradual slope of the bottom of the bed to the south, since a drill hole (XXV) 14 feet 3 inches south of XV showed 13 feet 6 inches of coal below the water level.

The quality of coal on the west side of the Abitibi is in general inferior to that on the opposite side. It consists of a loose, incoherent, black lignitic powder, highly carbonized, through which are scattered with variable frequency angular fragments of woody lignite often six or seven inches long by three or four inches thick, and as many wide. The powdered material is chiefly moss-formed lignite, though part of it is broken up woody lignite. Apparently the lignite becomes less friable in depth. In places there is a little loose clay mixed with it, especially in the upper part, and it contains a little iron pyrites. There is never any stratification, and the whole might almost be spoken of as an uncemented lignite breccia.

I do not think it probable that the two deposits of lignite on the west side of the river are the opposite limits of a syncline, and it seems to me much more likely that they are the remains of a thick seam of lignite which was first corrugated by the shoving of the ice, and afterwards shattered, powdered, and probably deposited in holes in the underlying plastic clay. If this is the case the two deposits are quite distinct and separate. This theory accounts for the inequality of its thickness, for the lignitic boulder clay lying between the two lignite deposits, and also for the extraordinary nature of the lignite itself, which has the carbonization of superior lignite with the lack of homogeneity of peat.

It was most unfortunate that none of our drill holes penetrated to the supposed horizon of the lignite in the interior, to ascertain definitely whether or not the coal existed. For my own part I think it does, there being no apparent reason why a total outcrop of lignite of over two hundred feet, with always a considerable thickness and a maximum at twenty feet, should suddenly die out away from the river bank. Of course glacial corrasion has been most unequal and irregular, and it is possible that all the lignite in the in-

Digitized by Google



Section showing lignite bed, east side Blacksmith rapid, Abitibi river.

Digitized by Google

terior has been removed, but the opposite is equally likely to be true. This can only be proved by the sinking of numerous shafts to the depth of twenty or thirty feet. At any rate, there is in situ and in view a considerable quantity of lignite (at least 1,600 tons), which is not an unimportant resource of the region.

Several drill holes were lowered on the west bank of the river below the Long rapids on an extensive outcrop of carbonaceous clay, in the hope that lignite would be struck in these coal-bearing measures with depth, but the hope was not realized.

Other Deposits

About one and one-quarter miles above the foot of Long rapids, a small seam of rather argillaceous lignite was discovered by Dr. Parks on the west side of the river. The seam lies about 38 feet above the summer river level, and some 77 feet back from it. It has a maximum thickness of 3 feet 6 inches, is overlain by sandy clay, and underlain by interstratified beds of fine sand, fine bluish clay, and coarse gravelly sand resting on Devonian shales. The seam is a mere lens, dying out within a few feet in either direction. A drill hole sunk one hundred feet back from the bank at this point failed to reach the level of the lignite, owing to the numerous boulders in the overlying boulder clay.

From Indian report I have learned that considerable lignite outcrops along the Kesagami river, but I was unable to visit the locality. It is very probable that when the numerous streams which enter the Missanabie from the west, between the Soweska and Kwataboahegan, have been explored, a great deal of lignite will be discovered. These streams flow through that section of the country most likely to be productive of coal deposits of economic value. Of the largest of these streams may be mentioned the Atagwaigon and Ash, which could easily be ascended at the time of high water.

Peat Bogs of Coastal Plain

At first glance the great muskegs of Northern Ontario, with their almost interminable extent of sphagnum and their miserable scrub spruces and tamaracs, seem absolutely valueless, but as a matter of fact, they may before very long be a really valuable asset. The moss extends downward into peat, and there is every stage of carbonization from that which is still green and growing to that which, were it not for its lack of homogeneity, would be called lignite. The extent of these peat bogs is enormous. They cover thousands of squares miles, and in fact clothe practically the entire region of the coastal plain, except on the mere borders of the rivers. No detailed investigations have been made of the thickness of these peat bogs, but they vary from a few inches to probably 25 or 30 feet. On the smaller rivers, beds of peat are often seen along the river bank above the drift. Several were observed on the Soweska, and on the Kwataboahegan, where a thickness of from six to ten feet is commonly exposed.

It is, however, on Kesagami lake that the most interesting sections of peat appear. This remarkable body of water is almost entirely surrounded by beds of peat, which appear topographically as low cliffs rising abruptly from the water front, and often caverned and pillared in a most grotesque and extraordinary manner. The peat, which has a maximum thickness of quite twelve feet, and averages about seven, is underlain by hard gray boulder clay, and overlain by growing sphagnum moss. Above the underlying clay it is black in color, and grades upwards through brown-black to brown, and light-brown. A great many sticks, branches and trunks of trees are interstratified, and these vary with the moss-formed peat in the state of carbonization, decreasing from the bottom up. The peat is almost always pure, though along the face of the cliffs some silt has been washed by the waves into the less coherent portions, and deteriorates the quality at the outcrop, but of course this defect is local.

On page 175 is a table showing the composition of lignites from various parts of the world, including some from northern Ontario, also samples of peat from Kwataboahegan river and lake Kesagami.

A specimen of lignite from Moose river, obtained by Dr. Bell in 1875, analyzed as follows:

	Slow coking.	Fast coking
Fixed carbon	45.82	44.02
Volatile combustible matter	39.60	41.39
Ash	2.84	2.84
Water	11.74	11.74
Ratio of volatile to fixed combustible... .. ..1:1.16		1:1.06

Climate

The climate of the Moose Basin has been so often described that I need hardly mention it here. In general there is little or no variety north of the height of land as far as Moose Factory. The snow usually melts during the last

Digitized by Google

two weeks in April, and the ice leaves the rivers about the same time. Vegetation is delayed, and it is the end of May before the leaves appear on the deciduous trees. June, July, August, and the early part of September are warm, sometimes excessively hot, and with a plenteous supply of rain. The latter part of September, October, and much of November are chilly and rainy, with occasional flurries of snow, but with much fine autumn weather. By the end of November winter has begun, and lasts until the beginning of April. This season is bright and delightful, and though exceedingly cold, yet the air is so bracing, especially in the interior, that I doubt if its severity is felt as much as in more southern latitudes. Apparently, however, the seasons are subject to great variety. For instance, the summer of 1901 was very hot and dry, hardly any rain falling from the end of May until the middle of September, when torrents of rain deluged the country for the two following months. Last summer, 1903, was damp and with scarcely any really hot weather, while the autumn was partly fine and partly rainy. Light summer frosts have been known to occur in the Moose Basin, but are not common. All the hardier vegetables and even Indian corn and tomatoes are grown at New Post on the Abitibi. Cereals, with the exception of barley and oats, have scarcely been tried, but I see no reason climatically why they should not thrive as well as around Sault Ste. Marie. The bishop of Moosoree has in his garden at Moose Factory some small apple trees and plum trees which, though they have not borne, are apparently growing well.

Soil

The soil of the great central interior on the old land plateau is excellently suited for agriculture. It is a rich clay loam of great fertility. Where tried for vegetables, as at New Post, it is wonderfully productive. I have walked for miles across country, passing over only this splendid soil. It is unfortunate under these circumstances that so much of this region, especially the northern part, is swampy, because with such singular uniformity of surface draining, when the country is opened up, may be difficult. Towards the south of the upland there are not nearly so many areas of swamp; in fact, no more than one should expect to find in any new and unopened region, or as existed in southern Ontario prior to the clearing of the forest, and the character of the soil on the whole is much better. In general, the width of the clay belt is about ninety miles where it crosses the Missanabie, and about sixty miles on the Abitibi.

It has been mentioned that by far the greatest part of the coastal plain region is covered with muskegs, and is in its present condition unfit for agriculture; but the alluvial flats of the various rivers which are not flooded in spring, the numerous islands, and finally river bank strips of land varying in width from a few yards on the small streams to one-quarter or one-half a mile along the large rivers, are quite suited for farming. It is apparently mainly a question of drainage. The impervious clay substratum does not allow a free

Locality.	Water.	Ash.	Volatile.	Fixed carbon.	Remarks.
Golden City, Colo., 56 ft. below surface	13.43	3.85	37.15	45.57	Gray ash.
Carbon, Wyoming	6.80	8.00	35.48	39.72	Light gray ash, nearly white.
Monte Diabolo, Cal.	3.28	4.70	47.05	44.90	
Germany	.....	4.60	52.50	42.90	Drill brownish black, powder same. Compact ash, brick color.
Minerve Land.	.....	10.00	57.40	32.60	Compact, brilliant, black color, irregular fracture. Powder brownish black: yields coke.
Big Rapid, Missanabie	20.06	2.95	40.12	36.87	Woody lignite. Ash greenish yellow.
Abitibi, Blacksmith rapid.	16.46	7.28	39.66	36.58	Moss lignite. Black, ash yellowish green.
Soweska river (23)	12.25	25.34	42.96	19.45	Lignite. Black and fairly good. Ash greenish yellow.
"	7.56	10.88	57.38	24.18	Woody lignite.
"	13.92	31.04	39.00	16.04	Argillaceous lignite. Ash yellowish.
Abitibi, Blacksmith rapid.	10.34	32.67	33.67	23.32	Conglomerate lignite. Ash reddish brown.
Kwataboahegan river	11.39	36.22	38.20	13.59	Argillaceous lignite. Greenish ash.
1¼ miles above foot of Long rapid Abitibi	8.17	57.64	27.50	6.87	Lignite. Yellowish ash.
Peat, Kwataboahegan R.	13.56	4.73	59.80	21.91	
Peat, L. Kesagami	14.38	16.80	47.55	21.27	

(23) The high ash in the case of the Soweska lignites is probably in part due to the fact that the specimens for analysis were taken from the outcrop, into which much impurity had filtrated along the stratification planes.

Digitized by Google

movement of water in so level a region, especially as with clay and boulders packed up along the edge of the bank there is a slight slope towards the interior rather than towards the river, especially near the sea. However, I observed in the southern part of the plain, where the forests had been recently burned off, and with it the muskeg moss, that the underlying soil was laid bare and was in these places quite or nearly dry, or merely moist, for miles, and where the moss had been entirely removed was supporting a rich growth of wild grass. This was especially observable on the completely timber-stripped area on the Opazatika near Scott's island, and in the land passed over in a trip made across country from the foot of the Long rapids of the Abitibi to the Grand rapid on the Mattagami. I therefore believe that much of the land, particularly the southern part where the sphagnum growth is light, can by burning off the moss be made suitable for farming. The northern part, with its treeless muskegs and with moss of great depth, seems a more difficult problem. The land around the upper Nettogami river beyond the Pre-Cambrian boundary and around lake Kesagami itself is nowhere good. Where not peat bog, muskeg or tamarac swamp, it is too sandy or gravelly to be of any value agriculturally.

The southern shores of James bay from Moose Factory to the Ontario-Quebec boundary line are bordered by wide plains but slightly elevated above the level of high tide, covered in summer with a luxuriant growth of wild grass and flowers, which at the end of the season is quite four feet in height. Formerly the home of hundreds of caribou, it would with the opening of the country become immediately suitable for the grazing ground of domestic cattle.

Forest Trees

The forest trees of northern Ontario are: White spruce (Picea (24) alba), Black spruce (Picea (24) nigra), Balsam (Picea (24) balsamea), Tamarac (Larix americana), Banksian pine (Pinus banksiana), Cedar (Thuya occidentalis), Aspen poplar (Populus tremuloides), White birch Petula papyracea), as well as White pine (Pinus strobus), Red pine (Pinus resinosa), Swamp elm (Almus americana), and Black ash (Traxinus sambucifolia), which are found sparingly towards the southern part of the area. Among the common shrubs may be mentioned several species of Falix Mountain maple (Acer pennsylvanicum), White alder (Alnus incana), Green alder (Alnus viridis), Red cherry (Prunus pennsylvanica), Choke cherry (Prunus virginiana), Mountain ash (Pyrus americana), Service berry (Amplauchier canadensis), Hazel (Corylus americana), Juniper (Juniperus communis), and Hawthorn (Crataegus coccinea), towards the south.

The distribution of these various trees and shrubs is important, as showing the capabilities of the region from a climatic standpoint. Some years ago I saw a fine grove of swamp elm growing on the Kapuskasing, 70 miles below the lake of the same name, and this year I observed some on the Skunk islands of the Missanabie, as well as near the mouth of the Blue Water river below New Post. White and red pine grow on the Abitibi as far north as Iroquois falls, and I saw a lonely white pine down the Kapuskasing some thirty miles south of the White Spruce river. These points may, I think, be said to mark the northern limit of growth of these particular species.

In the dry land throughout the country white spruce, the two poplars, balsam, and birch are the principal forest trees, and these grow with a luxuriance and, when allowed, to so healthy a size that there is no doubt of the good character of the soil. In the muskegs and swamp land is a stunted growth of black spruce and tamarac, though even on the edge of the muskeg the black spruce is quite large enough for pulp wood, while the tamarac in the more southern swamps of the region, though now mostly killed by the larch saw-fly, was once of large size. Cedar grows commonly along the river edge, and Banksian pine at the few points where solid rock is exposed or where the soil is sandy. The latter is a beautiful tree which often attains a circumference of four or five feet. Large cedar occasionally have a circumference of ten feet; though the soundest specimens and those of greatest and straightest height are of much smaller horizontal dimensions. Spruce has a maximum circumference of seven feet or a little more. Aspen and cottonwood are a little smaller, and birch seldom if ever exceeds four feet.

Often for miles along the river and stretching for miles into the interior in the more southern part we have this splendid forest, but in general by far the greatest part of the country is wooded with second growth and not by original forest, from the midst of which stand out sometimes single individuals and often large tracts of the forest of bygone days. The timber along the Missanabie and Opazatika is almost entirely of second growth, that along the

(24) Abies.

Digitized by Google



Drift in lignite, east side Abitibi river. Lignite in foreground.



Opened lignite seam, west side Blacksmith rapid, Abitibi river.

Digitized by Google

UNIV. OF MICH.

Digitized by Google

Grand or Breakneck falls, Opazatika river.



Thundering Water falls, Missanabie river.

Digitized by Google

UNIV. OF MICH.

Digitized by Google

Ojibway Indian "en costume."

Digitized by Google

UNIV OF MICH.

Digitized by Google

Indian villagers of lake Abitibi.



Black Donald graphite mine and works, 1903.

Digitized by Google

UNIV. OF MICH.

Digitized by Google

Kapuskasing and Ground Hog is better, while that along the Abitibi is the best of all, and in the upper reaches of this stream, the river is bordered for miles by excellent timber. On the coastal plain the timber on the main Moose and Abitibi is chiefly second-growth, with here and there patches of good timber, but the Kwataboahegan is edged for miles of its course by a superior forest growth, and the same thing applies to the Kattawagami, or eastern branch of the West river.

The Ravages of Fire

It is unfortunate that so much of the timber of the north has been destroyed by recent fires. During the dry summer of 1901, a conflagration swept the whole country from the Kabinagami as far east at the Little Abitibi, and another even more terrific in its fury devastated the region southeastward from lake Kesagami almost as far as Grand Lake Victoria, on the upper Ottawa. On the Missanabie from the Skunk islands to the mouth of the Soweska there is scarcely a green tree standing, the few remaining patches standing out as oases in a desert of blackened rampikes. The burned area extends on the Opazatika from below the foot of Skunk island to the Opazatika canyon, though fortunately more clumps of green have escaped the fire. On the Mattagami there is a clean sweep from the Grand rapids almost all the way to the mouth of the White Spruce river, which joins the Kapuskasing about 30 miles above its confluence with the Mattagami. In 1901 before the fire had passed over the country I journeyed down the Kapuskasing and Mattagami, and made frequent observations on the magnificent forest which then extended along both these rivers, and which stretched away in virgin fertility from the river banks. This summer an Indian from the White Spruce told me of the terrible destruction which the fire had wrought. The force of the fire had somewhat abated by the time the Abitibi river was reached, and, though great stretches of the country, from New Post northward have been deprived of timber, there is still much fine forest along the lower reaches of the river. I do not know exactly how far west the fire spread, but in our trip up the Wabiskagami our course lay for 30 miles in a more or less westerly direction, and for that distance we passed through a wilderness of blackened tree trunks.

The loss from these forest fires is enormous. When it is realized that this one fire devastated an area of at least 3,000 square miles and destroyed as well hundreds of moose, bear, caribou, and innumerable small animals, it will be realized in a slight degree how great has been the destruction. Let one travel for miles, be it overland or by water, through these blackened deserts, without seeing or hearing a living thing, let him listen in midsummer to the sighing of the wind through these leafless rampikes, and he will realize the sadness of the Indian lament that he must now leave his hunting grounds and go elsewhere, far to the eastward or westward, to seek new spots where the game yet lives. I was in the country during that terrible fire of 1901, and I shall always remember the days we passed in semi-darkness, hourly expecting to have to take to the water to save our lives. Fortunately we were beyond its path to the east, but other members of my party were not so fortunate, losing all their clothes and equipment, and one old Indian died from the effects. It has been said that most of these fires have been started by lightning. Some may have been, but most of them are ignited not by the Indians, although they are unfortunately far too careless, but by occasional white tourists who find their way down the various rivers every year to the Bay, and who do not realize the awful danger of a fire once started in the great spruce forests of the north. It may be suggested that these great forest fires have the advantage of destroying the moss on the muskegs and making these lands fit for agriculture, but the damage done far outbalances the gain in this way, and it will be ample time to clear the drier muskegs when the country is opened up.

The flora of the Moose Basin is not especially distinctive. It is that which prevails from the Gulf of St. Lawrence to the edge of the prairies of Manitoba, and many of the commonest species are found also in southern Ontario. During the months of June and July the wide banks of the streams are turned into veritable gardens with cyprepedrum jubrum, rosa blanda, lilium tigridum, anemone alba, and many other species, and until late in September various species of solidago and aster brighten the valley with color. Many a northern pond is beautified by its pond lilies and patomageton, and even the desolation of the brules is relieved by a marvellous growth of blue and red fireweed. The ferns of the north are also beautiful, and many a narrow valley is for the short summer turned into a tropical paradise by the luxuriance of their foliage. Osmunda regalis is the commonest and most showy, but there are many other species.

Digitized by Google

Northern Scenery

The scenery of northern Ontario is often beautiful, and though occasionally monotonous and lacking diversity, it is nevertheless a region well worthy a visit from lovers of the beautiful. High up on the upland plain the numerous lakes with their rough, rocky shores casting sombre shadows in the dark waters; their deep bays; their many tree-girt islands, separated by narrow channels; and their long, gravelly points, all remind one of the charms of the Thousand Islands of the St. Lawrence. Lower down on the various streams the change from the long sweep of still water to a wild dashing rapid, cascade, or fall, is often charming. The grandest and wildest scenery occurs in the last few miles of the streams on the upland plain at the point where they descend rapidly towards the coastal plain. The rapids passed by Riverside portage on the Missanabie are a magnificent sight. Here the river is hemmed in to a width of a few yards, and dashes with tremendous velocity between high walls of gneiss. Half way down the cascade an extraordinary columnar pillar sixty or seventy feet in height rises from the water, and around this the water seethes and boils with terrific force. From time immemorial the Indians have known this strange place as Conjuror's House.

The Breakneck falls, with their straight drop of 60 feet; the deep, rusty-walled cauldron below; the beautiful tree-covered island dividing the falls in two; and the wild canyon which continues below the falls make a splendid bit of scenery. The view from the ridge along the Abitibi canyon is one long to be remembered. Two hundred feet below foam in fury the waters of the great stream, here dashing over a ledge in a steep, sharp fall, there surging through a whirlpool, or again seething against one or other side of the dark cliffs which border it. In the brilliant sunshine these rocks appear various shades of gold, purple and red, while in the sombre shade they seem of an inky blackness. Lower down the canyon towards the north where the precipitous walls in places give way to more gradual slopes, the dark gorge is relieved by the splendor of the northern forest, while off to the south the deep canyon is lost in the tree-covered hills which stretch away to the horizon.

The lower Moose, with its low monotonous shores, and its many flat bars and islands, presents nothing especially attractive to the eye, but there is something inexpressibly majestic about the great sweeps and bends of a mighty river, with the banks merging and disappearing in the distance at the sky line.

Wild Animals

Every year a few sportsmen are attracted to those great, lonely wilds, and seek rest and quiet from the strenuous life of our busy southern cities in these ideal pleasure grounds. In a few years, more and more will take advantage of the delightful scenery and good hunting of the region, and these will be but the fore-runners of hundreds who will come in the future, as our urban population grows.

Moose were exceedingly plentiful during the summer. Formerly this giant of the forest was never seen around Moose Factory, but this season we saw several within a few miles of the post. One was seen by my men near lake Kesagami, and the Indian who was my guide told me that this was the first he had ever known to visit that part of the country. Caribou do not seem to be so abundant, and none were seen during the summer. Red deer are not uncommon as far north as New Post. Bear occur commonly, especially in the upper part of the coastal plain, where they find excellent food in numerous berries on the new brules. All fur-bearing animals apparently are decreasing, and the fire of 1901 made terrible inroads into their numbers. We saw occasional marten, mink and otter, but not a single beaver, notwithstanding the fact that many of our side trips during the summer were made into unfrequented lakes and streams admirably suited to be the home of this interesting animal; though at several points we saw signs of him in fresh cuttings.

Aboriginal Inhabitants

I am told that the number of Indians in the Moose basin is rapidly diminishing. This is due in part to the large annual emigration southward to the Canadian Pacific railway, and also to the terrible decimation of the tribe of late by tuberculosis and measles. The latter disease swept off quite one-fifth of the population of Moose Factory during the summer of 1902, and this summer during my short stay in the region the mortality from tuberculosis was really tragic. In fact, the present condition of the Moose Indian is most deplorable. The Hudson's Bay Company has much diminished in grandeur of late, and the chief depot formerly at Moose has been removed to Charlton island, so that the Indians who formerly found work in unloading the ship at

Digitized by Google

Moose Factory, and in charging the various vessels which carried the outfit of other posts have been deprived of this employment. Moreover, many of the Scotch servants of the company have been discharged and have gone to the railway with their families, so that the supply of cattle formerly kept at the Factory has been greatly lessened. This removes another means of livelihood from the natives—that of cutting fodder for the cattle. Then again, their natural means of livelihood is no longer productive. The supply of fur-bearing animals in the region is undoubtedly small, and though moose is increasing, still this animal is in numbers far too few to supply the Cree Indians with meat during the long winter—a lack which a comparatively large number of muskrat, hare, and partridge by no means fills. Of late it has become more and more necessary to depend on the imported provisions of the company, and without the wherewithal to obtain these their long winters are passed in a state of semi-starvation, in which condition they are a ready prey to disease. Many of them have taken to living around the Hudson Bay post at Moose Factory, even dwelling in houses in winter—a procedure absolutely fatal to them in that they do not understand the first principles of ventilation, and the change from the fresh air that circulates freely through their wigwams to a hot and stuffy, dark, dirty room is disastrous. As compared with the well dressed, well-fed, healthy Ojibways of Lake Abitibi, New Post, or New Brunswick House, they are a miserable, squalid, poorly clad, and sickly people, quite unlike one's idea of the noble red man. Yet in spite of their condition they are a charming, simple, imaginative, and at times grateful people; and I do think some serious efforts ought to be made to alleviate their distressing condition. Though not by nature specially industrious, still at the same time they are not lazy, and as a rule if they have work to do they do it to the best of their ability. The advent of a free trader to Moose Factory a year ago gave work to most of them, but I do not think that it was of a kind likely to prove of lasting interest to them, and rival trading does not improve the morale of the Indian.

Every effort is being made to ameliorate the state of the Crees by the Bishop of Moosonee and Mrs. Newnham, but the path of these benefactors is not an easy one, and they receive little or no support from outside. Mrs. Newnham has herself built a well equipped though small hospital, well cared for by Miss Johnson, a deaconess and carefully trained nurse. When I was at Moose Factory this summer, I saw several Indians leave the hospital cured of their various complaints, and others well taken care of during their last few hours of life. During the epidemic of measles a year ago the presence of the hospital with its willing workers doubtless saved almost the complete annihilation of the tribe.

The condition of the Ojibway, who occasionally hunts as far north as lake Kesagami, is infinitely better than that of his northern Swampy Cree neighbor. In the first place, he has had less of the evil, and to the Indian deadly, contact with white men. His hunting grounds are wider and better stocked, and he gets a better market for his furs. On our return journey in the autumn we fell in with a band of Ojibways on lake Abitibi, and I was really surprised at their opulence. They were well and neatly dressed, and abundantly supplied with food for the winter. Moreover, they were apparently an intelligent, self-reliant, and independent people, in delightful contrast to the importunate Crees.

It is with pleasure that I acknowledge my indebtedness for the many courtesies extended to me and to my party during the past summer by the various officers and servants of the Hudson's Bay Company, and by the missionaries of the Church of England in northern Ontario. Especially do I wish to thank the Bishop of Moosonee and Mrs. Newnham, whose kindness to us, as well as to all strangers who have found their way to the shores of James Bay, turned that far away outpost of civilization into a veritable haven of rest.

Digitized by Google

Devonian Fauna of Kwataboahegan River

By William Arthur Parks

The fossiliferous rocks deposited on the northern flanks of the great Archaean axis of Ontario occupy a vast area to the south and west of James Bay. They reach from the border of the old land to the waters of the sea and are responsible for many of the physiographic features of the coastal plain. To their presence must be ascribed the character of the Moose river from Moose Factory almost to the long portage, as well as for that of all the tributaries of the Moose, the Albany and the other streams of the coastal plain. Little has been done to determine the exact horizon of these rocks, but it seems probable that a fringe of Silurian deposits lies on the flank of the upland, at least in places, while the major portion of the Palaeozoic area is composed of rocks of an age comparable with the Upper Helderberg.

The writer has at various times had an opportunity to examine the series as presented on the Abitibi, the Moose, the French, the Kwataboahegan and other streams of the Moose system. Generally speaking, the assemblage of fossils at these different points is practically similar, but far too little work has been done to enable us to say that but one horizon of Devonian rocks is exposed in the basin of the Moose river. It is in no wise the purpose of the present paper to attempt to classify the deposits of the Palaeozoic in this region, but merely to add to the available information concerning the series as a whole. More particularly it is desired to describe the fossils of the Kwataboahegan river, a tributary entering the Moose on the north side about 12 miles above Moose Factory.

The following notes are the result of a little desultory collecting while engaged on work in connection with the recent expedition to investigate the coal of the Hudson's Bay slope. The rocks on the Kwataboahegan teem with fossils and form a rich hunting ground for the palaeontologist. While it is thought that the accompanying list is much more complete than any previously obtained, it must be admitted that but a small percentage of the forms actually occurring are recorded.

The strata exposed on the Kwataboahegan present limestones of a yellowish brown color, literally filled with organic remains, mostly in the form of casts. The general appearance of this rock is strikingly like that of the Guelph limestone and dolomite of southern Ontario. A grayish limestone is also seen, but the stratigraphical relations of the two series remains to be worked out. The gray rock is poorer in the remains of molluscs, but is far more prolific in corals and brachiopods than the soft yellow variety. This latter rock is much better exposed on the Kwataboahegan than elsewhere in the Moose basin, exactly comparable rocks not being observed by the writer on either the Abitibi or the French river. As above stated, the conditions of last summer's work did not admit of any attempt to differentiate strata. The following lists must be regarded therefore as simply indicative of the general fauna of the Devonian as exposed on the Kwataboahegan river. It is to be hoped that at no distant date an opportunity will arise to carry out in detail the interesting work of comparing the Palaeozoic strata to the north with those to the south of the Archaean protaxis.

In the summer of 1902 Mr. W. J. Wilson made a small collection of fossils from the rocks of the Kwataboahegan, a list of which appears in the Report of the Geological Survey of Canada for 1902. All the species collected by Mr. Wilson were observed with the exception of Gomphoceras beta. Although from time to time occasional fossils have been recorded from the Moose

Digitized by Google

basin by Dr. Bell and others, so far as the writer is aware, the work of Mr. Wilson furnishes the only record from the Kwataboahegan. Gomphoceras beta is therefore added to the list of species seen last summer. The unidentified forms of Mr. Wilson's collection are not considered.

Anthozoa

Great numbers of corals are to be seen in both the yellow and the gray limestone, particularly the latter. The corals, more especially the rugose varieties, resist the action of the weather better than the enclosing rock, and are therefore found free along the shore of the stream. The following species were obtained:

Favosites basaltica, Gold.
Favosites hemispherica, M.-E. and H.
Favosites turbinata, Bill.
Favosites winchelli, Rom.
Favosites gibsoni, sp. nov.
Alveolites squamosus, Bill.
Alveolites vallorum, Meek.?, indet.
Syringopora nobilis, Bill.
Syringopora nobilis, Bill.
Syringopora perelegans, Bill.
Syringopora hisingeri, Bill.
Diphyphyllum, arundinaceum, Bill.
Diphyphyllum simcoense, Bill.
Phillipsaster gigas, Owen.
Phillipsaster verneuli, M-E and H.
Acrophyllum oneidaense, Bill. (doubtful).
Streptelasma prolificum, Bill.
Zaphrentis gigantea, Lesueur.
Crepidophyllum archaici, Bill.
Cyathophyllum exiguum, Bill.
Cyathophyllum halli, M-E and H.
Cladopora cryptodens, Bill.

As far as possible the revision of the Canadian corals by Lawrence M. Lambe was followed in identifying the above species (1), Rominger's species, Favosites winchelli, is however, retained (2).

Favosites gibsoni
sp. nov.

On the Kwataboahegan river a single specimen of a remarkable favositoid coral was obtained for which the above name is proposed. The corallum forms an almost circular stock with a diameter of six centimetres. The specimen obtained is 17 cm. long and is sharply broken at both ends. In this length of 17 cm. there is no perceptible tapering of the corallum, so that it is a fair conclusion that the coral attained a considerable length, possibly several feet. The corallites are disposed so symmetrically around a central axis that we are forced to ascribe an erect position to the living colony. Whether the corallum branched, as in most of this type of favositoid corals, it is impossible to say; the specimen shows no evidence of this manner of growth, but it would be premature to say that it did not exist. The corallites arise by intermural gemmation at the axis of the colony, and grow upwards three centimetres, in which distance they diverge from the axis three-quarters of a centimetre. Here they turn abruptly outwards, and continue to the surface in a direction strictly at right angles to the central line of the corallum. The corallites are practically equal in size, the largest being slightly under a millimetre in diameter. They are strictly polygonal, in most cases hexagonal, in shape, and are closely apposed, there being no trace of interstitial tissue. The intermural pores occur in the sides of the corallites and are of comparatively large size, one quarter of a millimetre in diameter, and separated from each other by double that distance. The large size of the pores and their considerable frequency necessarily occasions accidental confluence across several corallites, so that the weathered surface shows small veriform depressions where this has occurred. The tabulae are somewhat flexuous and in many cases incomplete (squamulae); about five occur in the distance of one millimetre. It will be seen therefore that the irregularity of the tabulae will be interfered with by the intermural pores, giving rise, in vertical sections, to zooidal chambers connected by large channels, which in some cases are seen to cross several corallites. Septa appear to be entirely absent.

A most remarkable feature of this coral is the concentric lines of growth, appearing most distinctly on the cross fracture which has been subjected to weathering. The first of these lines appears at a distance of one centimetre from the centre; about ten rings are to be seen from this point in a similar distance outward, being more closely crowded as the periphery is approached. A photograph of the weathered end is reproduced in Pl. II., Fig. 2, and a sketch in Pl. VII., Fig. 1. The weathered effect is seen to arise from the fact that the wall matter is more soluble than the infiltered calcite filling the cavities. This will account for the radial, tube-like appearance. The concentric rings are seen to owe their original to a differential weathering in the walls of the corallites, due to a difference in texture ob-

(1) Contributions to Canadian Palaeontology: Vol. IV., Pts. I & II.

(2) Geol. Sur. Michigan, 1873-1876 (Lower Peninsula).

Digitized by Google

taining at the same time in all the corallites of the colony, thus giving rise to uniform concentric rings. On a polished surface the resistant portions appear as clear lines across all the corallites, while the more readily weathered parts are represented by alternating milk-white portions. As the clear portions withstand the action of the weather while the rest of the wall is disintegrated, it follows that the unaltered part will appear as a ring embracing all the corallites and surrounding the axis of the corallum. The reason for the hardening of all the corallites at the same level is no doubt to be sought in the different activity of the organism in the different seasons. Thin sections show excellently this difference in growth; the clear portions appear as such, while the white parts appear dark under the microscope, no doubt owing to a less dense structure and the inclusion of air. Further, distinct lines of growth can be made out. It appears that the substance of the wall of the corallite was deposited in layers with a greater or less slant towards the centre of the tube. In summer the growth was rapid and the slant steep as shown in the dark parts of the section, while in winter the growth was slow and the inclination of the lines of growth much less pronounced, as shown in the clear portions of the section.

Stromatoporoidea

The only Favosites that at all resembles this species is F. cariosus, Davis, figured but not described in the Fossil Corals of Kentucky. The corallites are however, much larger and lack the lines of growth characteristic of our species. The corallum seems to be smaller, but without any description of Davis' form it is impossible, even hazardous, to make comparisons. (Plate I., Figs. 1-5; plate II., Fig. 2; plate VII., Figs. 1-2).

This interesting class of organism occurs in great abundance throughout the region, and in many cases the specimens are preserved with such perfection as to render their identification possible. The determination of species of Stromatoporoids is always attended with great difficulties, first, because it is practically impossible to obtain all the material desirable for the presentation of the various features; second, because the preservation is in many cases imperfect; and third, because the specific differentiation depends on point of minute structure showing such gradual differences that it is almost impossible to draw the dividing line.

In the following notes the writer has attempted to identify with known species as many forms as possible, and to create new species only where the characters of the specimen are different from some emphasized point in the description of known species. He is prepared to admit however that on the one hand all the species might be considered new, or on the other hand, by the neglecting of certain characters they might all be ascribed to previously described types. There is little doubt that the surface character of stromatoporoids alters with age. Deep sections show that the inflection of the laminae into monticules is acquired in later life. Unless a surface peculiarity is persistent from the younger to the oldest laminae, it can have no specific value. Certain surface characteristics as granulation, etc., may by thus persistent but mamelons, etc., are not. In the lack of any recognized system in this matter the writer has preferred to put stress on the minute differences of structure, but has been forced to regard surface character when that character has been used by authors to define their species.

Syringostroma restigouchense Spencer

A specimen was obtained agreeing in a general way with Spencer's species from the Silurian of New Brunswick. The form of the coenosteum is the same, and the nature of the surface, with its astrorhizal markings almost identical. In vertical section, however, a considerable difference is observable : the pillars are less stout and less uniform in size, while the concentric elements are thinner and more sharply defined. On the whole, however, there is no more difference than is to be expected in the same species at a slightly higher horizon.

Syringostroma aurora sp. nov.

This species forms an extensive somewhat flexuous coenosteum attaining a thickness of two inches or possibly more. The surface is minutely granular and has well marked astrorhizal systems about 15 mm. apart. The astrorhizal canals are distinct but extremely delicate, and the different systems seem to anastomose. In vertical section the resemblance to S. nodulatum is pronounced, but only five vertical pillars occur in a distance of two mm., while Nicholson gives six or seven as thus occurring. Further the very points which distinguish S. nodulatum from S. restigouchense are lacking in S. aurora. In the latter species there are no mamelons which is the chief character of S.

Digitized by Google

nodulatum, and the astrorhizal systems instead of being less developed are much more extensive. Had not Prof. Nicholson emphasized these points of difference as characteristic of S. nodulatum there would be no difficulty in considering the species identical; as it is we must regard S. nodulatum and S. aurora as the products of the evolution of S. restigouchense in two different geographical regions. The presence of mamelons is doubtless a character acquired by age; deep vertical sections show a constant increase outward in the bending of the laminae into these structures. Plate II., Fig. 4, and plate III., Figs. 1 and 2.

Syringostroma densum

Nich.

A specimen referable to this species was collected. Like nearly all the examples from our region, however, certain points of difference are observable, more particularly in the nature of the astrorhizal systems, the centres of which are 15 mm. apart, while in a specimen of S. densum in the collection of Byron E. Walker, Esq., they occur at a distance of five mm. In our specimen the surface is minutely granular, precisely like that of Stromatoporella turberculata, Nich. The surface is not described by Nicholson, but Mr. Walker's specimen shows no granulation of this nature.

Clathrodictyon laxum

Nich.

This specimen conforms very closely to the description of the type.

Actinostroma moosensis

sp. nov.

This specimen very closely resembles A. stellulatum, Nich., but as the European variety has not hitherto been reported in America, and as the present specimen differs in some distinct details, it is thought better to establish a new species.

The coenosteum is apparently massive and doubtless attains considerable dimensions, fragments being obtained several inches in diameter and from one to two inches thick. The laminae are distinct, and disposed in concentric layers from one-fifth to one-sixth of a millimeter apart. Considerable crumpling is observable in the laminae particularly where they bend upwards to form the mamelons. This surface character seems to be more strongly marked than in A. stellulatum, as a constant and distinct mamelons about four mm. apart cover the whole surface of the coenosteum as well as the surface which may be produced by fission along the laminae. Distinct astrorhizal systems are present situated from each other a distance of from 12 to 15 mm. The astrorhizal canals are well marked, and continue their course for the most part independent of the mamelons. The systems are superimposed and are easily seen in vertical section. As our specimen more closely resembles the second type of the species A. stellulatum, described by Nicholson in his Monograph, it will be observed that certain differences occur, as in his species the mamelons are from five to six mm. apart and correspond with the astrorhizal systems. In all the types described in a stellulatum the maximum distance apart of the astrorhizae is 8 mm. while the present example 12 mm. is the minimum and an extreme of 20 mm. has been observed. Further, the astrorhizal systems are well developed with numerous and long canals, sufficiently extensive to anastomose despite the considerable distance between the astrorhizal centres. In vertical section, the laminae are seen to be very distinct, continuing their course quite independent of the vertical pillars. These elements are about one-fourth of a millimetre apart, and appear to be of equal strength to the laminae. As they are much more slender than in most species of Actinostroma, one is inclined at first sight to think he is dealing with a Clathrodictyon, because it is manifestly impossible to cut a section parallel to more than a few of the pillars. The round cut ends of the astrorhizal canals are distinctly seen in vertical sections, Tangential sections show the ends of the vertical pillars, and the hexactinellid structure characteristic of Actinostroma, and owing to the distinct eminences of the mamelons the section shows concentric rings with centres a variable distance apart. (Plate III., Figs. 3 and 4.)

Through the kindness of Prof. J. M. Clark, State Paleontologist, Albany, N. Y., the writer was enabled to compare this specimen with one from Hackberry, eight miles above Rockford, Iowa. This specimen was unnamed, but is essentially similar in external characters to that under review. He has also had the privilege of comparing the specimen with samples of A. stellulatum in the collection of Byron E. Walker, Esq., Toronto. A small fragment of what is probably a variety of the same species was also obtained. The microscopic structure is identical, but there are no visible astrorhizae and the mamelons are much closer together.

Digitized by Google

Professor Nicholson remarks that Actinostroma tyrrelli, Nich., is the representative in America of A. stellulatum; from his description it would appear that the three species are much alike, and that A. stellulatum occupies, in respect to the development of mamelons and astrorhizal systems, a position intermediate between A tyrrelli and A moosensis of the northern Palaeozoic areas of Canada.

By comparing the type specimens of Stromatopora solidula and S. expansa in the museum at Albany with our species, it is seen that the form is that of S. expansa, while the structure is closer to S. solidula. An unnamed specimen from Hackberry near Rockford, Iowa, which I take to be S. expansa, Hall and Whitfield, exactly corresponds to the present species in all external appearances. Sections, however, show some striking differences. The vertical pillars in A. moosensis are much farther apart and less continuous through the laminae, it being almost impossible to prepare a section in which a pillar can be traced through more than two interlaminar spaces. The laminae themselves are somewhat more closely apposed in A. expansa.

The two species, A. expansa and A. moosensis, are so much alike in external appearance that it has been thought advisable to reproduce the vertical and tangential sections of both in order to compare them under the came conditions. (Plate III., Figs 3 and 4—Actinostroma moosensis, Kwataboahegan river. Plate III., Figs. 5 and 6—Actinostroma expansa. near Rockwood. Iowa. Plate II., Fig. 3—Actinostroma moosensis).

Clathrodictyon problematicum

sp. nov.

It is with some diffidence that a new species is founded on the specimen about to be described, as but one fragment is available and that is almost destitute of surface characters. The same or a closely related species occurs at Le Roy, N. Y., a section of which I was enabled to compare although the specimen itself was not available.

The concentric laminae are very irregular in direction, but are quite well marked and are distant from each other about a third of a millimetre. The vertical pillars appear in no case to pass through the laminae, and in vertical section vary in distance from each other from a quarter of a millimetre to more than one millimetre. The pillars do not seem to arise from inflections of the laminae, but are quite independent, in fact the laminae are much more persistent than in typical Clathrodictyon. The surface appears to be without mamelons but is slightly undulating and most minutely granulated. Astrorhizae were not observed. In cross section, owing to the flexuous nature of the laminae, the cut edges of these structures are observable as well as occasional round dots representing the vertical pillars. No information is obtainable regarding the general shape and mode of growth of the coenosteum. The mass of the stromatoporoid is traversed by caunopore tubes about two-thirds of a millimetre in diameter, terminating on the surface two mm. apart. The species is very closely allied to Stromatoporella selwyni, Nich. In vertical section the resemblance is exact in the size of the visicles, the only difference being in the slightly less inflected nature of the laminae at the points of departure of the radial pillars. In tangential section however there is a marked difference, as none of the perforated tubercules of S. selwyni are present to give the circular cross section figured by Nicholson. An artificial surface produced by fission in C. problematicum shows a granulated surface, but the little tubercules are only about one-fifth of a millimetre apart, whereas in S. selwyni the distance of separation is one-half millimetre. Further the eminences are much larger in S. selwyni, and the greater ones are perforated, a characteristic not observed in C. problematicum. The tendency at the present time is to regard the presence of caunopore tubes as of no diagnostic value.

As Nicholson regards the perforated granules to represent the terminations of the zooidal tubes which he makes the main means of differentiation of the genus Stromatoporella, it is apparent that our species, in which these elements are entirely lacking cannot belong to this genus. The only other established genus at all capable of receiving it is the genus Clathrodictyon, and it is accordingly placed here but with the limitation already commented upon. (Plate IV., Figs. 5 and 6).

Stromatopora tubulifera

sp. nov.

One small fragment only was obtained of the species to which the above name is provisionally given. The general form of the coenosteum seems to be of the same nature as Stromatopora concentrica. No mamelons or surface indications of astrorhizal systems were observed. A polished vertical section suggests Syringostroma densum, Nich., but a very close examination shows the

Digitized by Google

lack of closely applied concentric laminae and the continuation of minute clear vertical lines, representing the zooidal tubes, for as much as two-thirds of a millimetre. This condition is never seen in Syringostroma densum, nor are the occasional large pillars of that species visible in our example. In thin vertical sections the resemblance is entirely lost, and the typical structure of the genus Stromatopora is at once seen. The latilaminae are apparent as well defined lines a variable distance apart, the average being about one millimetre. Concentric elements between these lines are barely distinguishable, and the radical pillars are apparently absent. A distinct radial structure is however seen, owing to the excellent development of the zooidal tubes. These structures extend from latilamina to latilamina with a slightly flexuous course, about 15 appearing in the horizontal distance of one millimetre in the case of thick sections; in very thin sections about half that number occur separated by about their own width of infiltered matter. In transverse section the zooidal tubes appear as distinct rings, by no means constant in their distance of separation, but averaging from a fourth to a sixth of a millimetre apart. The zooidal tubes show distinct tabulae and in the better preserved portions of the specimen are seen to present these structure to the number of 16 in a millimetre. Although the surface of the specimen is too ill preserved to show any astrorhizae, it is likely that such structures were well developed as numerous large round holes are to be seen in vertical section particularly immediately above the latilaminae. (Plate IV., Fig. 1, 2, 3 and 4.)

Echinodermata

Of this class of organisms nothing was observed except numerous indeterminable crinoidal columns.

Polyzoa

Great numbers of polyzoa were observed, nearly all being examples of the family Fenestellidae. Most of these fossils are in a very poor state of preservation, and but few were collected. The identification of the Polyzoa even when in good condition is a labor of time. Among those obtained, one much resembles Polypora perangulata, Hall, and another has a less striking resemblance to Polypora shumardi, Prout. The latter specimen has its fenestrules closer together horizontally and farther apart vertically than in P. shumardi.

Cyclotrypa borealis

sp. nov.

One small specimen was obtained of a species of Cyclotrypa closely related to C. communis, Ulrich, and even more nearly to C. collina (3). But as both of these species are ascribed to the Hamilton formation, and as the present example differs in some details, it is thought advisable to establish a new species as above. Zoarium, flat, discoidal, probably incrusting, epitheca unknown. Total width of the specimen about five centimetres, with a thickness of five or six millimetres. These figures do not necessarily express the total size of the zoarium, as but a portion is accessible. Surface, gently undulating; monticules very slightly raised, about 12 millimetres apart. Zooecia circular from .2 to .3 millimetres in diameter. Between the monticules they are separated by about half their own diameter. The zooecia on the monticules are the largest and are separated from each other by correspondingly great distances. Zooecial tubes, circular and thin walled. Lunaria apparently absent. Mesopores angular, forming rings around the tubes; size of the mesopores variable, some being as large as the zooecia while others are about one-fourth that size. An average of nine mesopores surround each tube. Commonly only one or two mesopores occur between the neighboring zooecia, but as many as six were observed. Acanthopores apparently absent. Vertical sections show the zooecial tubes to possess diaphragms at intervals of about one-fourth of a millimetre, while the mesopores are more frequently crossed by horizontal divisions which are crowded towards the periphery and show a tendency to coalesce into continuous plates.

The species is closely related to Cyclotrypa (Fistulipora) collina, Ulrich, but may be distinguished by the much greater distance apart of the monticules. The minute structure seems to be almost identical, and although an epitheca was not observed, the vertical section shows a distinct structural line where the zoarium rests on the substratum. (Plate II., Figs. 1 and 2).

Brachiopoda

The fauna of the series is not particularly strong in this class of organisms. The soft yellow rock shows very few brachiopods, but the gray limestone is much richer. Species were iden-

(3) Geol. Sur. Illinois, Vol. VIII., pp. 476-478.

Digitized by Google

tified as follows, all from the gray limestones:

Stropheodonta pattersoni, Hall.
Stropheodonta inequistriata, Conrad.
Stropheodonta demissa, Conrad.
Stropheodonta perplana, Conrad.
Stropheodonta concava, Hall?
Strophonella ampla, Hall.
Spirifer duodenarius, Hall.
Spirifer arenosus, Conrad.
Spirifer euryteines, Owen, cf. fornaculus, Hall. ?
Spirifer divaricatus, Hall.
Spirifer fimbriatus, Hall (Reticularia fimbriata).
Spirifer murchisoni, Castelnau.
Spirifer varicosus, Hall.
Leptostrophia, cf. magnifica, Hall.
Camarotoechia tethys, Bill.
Rhipidomella livia, Bill.
Atrypa reticularis, Linn.
Chonetes cf. lineata, Hall, cf. yandellana, Hall (Wings lost.)
Chonetes antiopia, Bill.
Chonetes cf. logani var. aurora, Nor. & Pratt. (very doubtful).
Meristella nasuta, Conrad.
Amphigenia elongata, Vanuxem (imperfect cast only).
Grypidula galeata, Dalman.
Athyris spiriferoides, Eaton. (rare).

Atrypa reticularis is by far the most common form, and occurs in great numbers and with some diversity of ornamentation; it is common in the yellow rock as well as in the gray limestone.

In addition to the species enumerated above many casts of small forms, belonging to the Rhynchonellidae were observed.

Gasteropoda

The number of univalves existing in the seas of the period must have been enormous. The yellow rock is literally filled with the traces of these organisms. In no case however is the shell preserved, so that the identification of species becomes a very uncertain matter. Casts of the interior are common, but only occasionally is the impression of the exterior preserved. The external and internal casts of species of Loxonema or Murchisonia are among the commonest fossils of the area. While the imperfect state of preservation makes the identification of individual specimens difficult, the occasional finding of external casts with the ornamentation preserved, shows that diligent search would result in the establishment of many new species. While many of the species of gasteropods are common to both this area and the exposures of Upper Helderberg rocks in southern Ontario and the State of New York, some few features are significant. Particularly noticeable is the fact that some forms such as Pleurotomaria delicatula or P. camera and P. adjutor, which Hall regards as very rare in the rocks of New York, are among the commonest of the small gasteropods of the area to the north. The great numbers of Platyostoma lineata are worthy of note. In the following list the forms identified from internal casts only are so indicated. It is apparent that the authenticity of such forms is always open to question.

Loxonema robusta
Hall

Numerous internal casts and imperfect impressions of the exterior. The characteristic markings of Loxonema were not observed. As this form is so common, a photographic reproduction of a large internal cast and of the gutta percha impression of a smaller external impression is shown in Plate V, Fig. 2.

Loxonema subattenuata
Hall

The same remarks as for L. robusta apply to this species.

Ca'lonema bellat.la
Hall

Very numerous impressions of the exterior of this form are excellently preserved, and show types in which the whorls are flattened, and also types in which they are well rounded with distinct sutures. Numerous internal casts are also found, the identification of which is very doubtful. Some, in which the sutures are suppressed and the whorls flattened, are in all probability referable to this species. while others are more likely representative of some species of Pleurotomaria or Holopea. (Vide postea). The different shapes of this species as figured in Hall's work Pal. N.Y. Vol. V., Pt. II., Plate XIV., are all represented here.

Euomphalus decewi
Bill

Several indistinct casts of the interior, and an impression of the exterior are representative of this species which appears to have been quite numerous.

Euomphalus

Cf. laxus, cf. clymeniodes; fragmentary casts, very doubtful.

Digitized by Google

Euomphalus
sp.

Very poor fragmentary cast of the interior.

Platyostoma lineata
Conrad

Very numerous; great numbers of casts, one showing a portion of the shell with the external markings. This species seems to have been attacked, in many cases, by a most remarkable parasite, which incrusts the whole surface, giving at first the impression of an external shell which has adhered to the enclosing rock and resisted the disintegrating forces long after the inner shell had succumbed. Microscopic sections indicate that this is not the case, but that the shell is covered with a strange and undescribed parasite. This organism is now under study and a report on its structure and probable affinities will appear shortly.

Murchisonia desiderata
Hall

Both internal and external casts. The external impressions of the revolving band are very indistinct, but it seems to lie a little lower on the whorl. The specimens appear to be a little more slender and delicate than Hall's species.

Strophostylus unicus
Hall

Two imperfect casts are provisionally referred to this species, but there is a strong probability that they are undescribed species.

Holopea
sp

Three internal casts apparently not belonging to any species mentioned in this report. Somewhat resembles Pleurotomaria ityx, Hall, from the Hamilton formation, but can not well be ascribed to that species. On the mere external casts it would be unjustifiable to found a new species. A photograph is therefore given of the three specimens in Plate V., Fig. 1.

Murchisonia
sp. indet.

A cast of a species with the revolving band midway on the whorls and therefore distinct from M. desiderata.

Pleurotomaria delicatula

Var camera, var nov. Shell depressed, trochiform; spire slightly elevated, apex minute. About five whorls appear, rapidly enlarging to the peristome. Aperture unknown. Shell wider than high. Surface marked by strong striae curving gently backwards from the suture to the revolving band. Four striae occur in the space of one millimetre. Revolving band distinct with fine striae showing curves directed backward. Striae of the revolving band twice as frequent as on the whorls. Revolving carinae absent. Answers very closely to Hall's description of Pleurotomaria delicatula. As this species is very rare in the rocks of New York State Hall's description is meagre. Our species seems to differ in certain points. The revolving band is situated above the centre of the whorl, so that a view from above shows distinctly the carinae of the band. The striae also are as distinct below the band as above, even more pronounced; this feature is directly opposed to Hall's description of P. delicatula (4).

Pleurotomaria adjutor
Hall

Many good casts of the small variety of this gasteropod were obtained. While there is no doubt of its identity, some slight differences are to be noted. The shell is always small, about half the size of the variety figured by Hall. The revolving band is proportionately wider and the striae are not multiplied as they are in Hall's figure. The carinae are fully as well marked as the crests of the revolving band and the lower carina is as distinct as the upper. This variety might be known as Pleurotomaria adjutor, var minima.

Bellerophon pelops
Hall

Very numerous internal casts probably referable to this species.

An external cast resembling B pelops but the peristome is not inflexed at the notch, and the revolving band is elevated and extends only a short way up the shell.

Although the Gasteropoda are so well represented, for the reasons already stated their identification is uncertain. Nevertheless, it is certain that sufficient time would yield external impressions for the identification of all the species. The occurrence of Pleurotomaria adju-

(4) Palaeontology of New York, Vol. V., Pt. II., Plate XIX., Figs. 18 and 19.

Digitized by Google

tor in considerable numbers (it is doubtles the most prolific of the small gasteropods) is very interesting as Professor Hall comments on its rarity in the rocks of the State of New York.

Scaphopoda

The remains of these organisms are very numerous, but in no case was any trace of the shell preserved. Internal casts abound, but the exterior markings are not well preserved. The abundance of these forms is very characteristic of the area.

Coleolus tenuicinctum
Hall

Numerous fragmentary impressions of the exterior closely corresponding to Hall's figures.

Coleolus tenuistriatus
sp. nov.

External impressions numerous. Best preserved and type specimen is four centimetres long, with a width at the mouth of five millimetres. Shells distinctly curved. Delicate oblique striae passing from the left towards the mouth of the shell. (Plate VI., Fig. 9).

Coleolus
sp.

A much larger specimen, with the striae running from an imaginary longitudinal line with a slight obliquity towards the mouth. Greatest diameter eight millimetres. The whole shell could not be less than ten centimetres long. The annulations are more pronounced than in the type specimen of C. tenuistriatus, but they are of the same general character, and may be merely the result of the larger size of the individual. (Plate VI., Fig. 8).

(Zittel places these forms under the Pteropoda, but lacking definite information, Hall's systematic arrangement is retained.)

Lamellibranchiata

As in the case of the Gasteropoda the remains of bivalves are common but ill-preserved. Without the expenditure of considerable time in the field it is impossible to do justice to this class of creatures. In the following notes no attempt will be made to establish new species, as the material is much too fragmentary, but the writer is of the opinion that a large number of new species of lamellibranchs will eventually be found in this field.

Conocardium cuneus

Var. trigonale, Hall. Very numerous and the best preserved of the lamellibranchs.

Goniophora
sp. indet.

The internal cast of a strongly angulated variety somewhat resembling G. perangulata, Hall, and even more like some of the European forms. A photographic reproduction of this cast is seen in Plate V., Fig. 3.

Modiomorpha
sp. indet.

Several imperfect casts. Do not correspond to any of Hall's figures. Compare Glossites patulus, Hall, Pal., N.Y., Vol. V., Pt. II., page 501, Plate XCVI., Fig. 15. Compare also the outline of Modiomorpha tumida, Whiteaves Contributions to Canadian Palaeontology, Vol. I., page 296, Plate XXXVIII., Fig. 10. (Plate V., Fig. 4).

Megambonia
sp. indet

Slightly resembles M. cardiformis, Hall.

Cypricardinia

Probably C. indenta, Hall. Pal. N.Y., Vol. V., Pt. II, Page 485, Plate LXXIX.

Mytilarca
sp.

Very poor specimen, possibly M. ponderosa, Hall.

Avicula textilis
var. arenaria

A good sample of this handsome form was obtained on the Abitibi river. Not seen on the Kwataboahegan.

Lyriopecten dardanus
Hall

Two good examples.

Cephalopoda

Like the other molluscs the cephalopods have left numerous remains in the rocks of the period. The shell is not preserved and identification is difficult. The following were noted.

Digitized by Google

Orthoceras thoas
Hall

Orthoceras pelops
Hall

Specimen badly worn. Identification very doubtful. Rather larger than any of Hall's figures.

Orthoceras luxum
Hall

Orthoceras
sp. indet.

Possibly O. procerus, Hall, but the specimen is so badly preserved that identification is impossible.

Orthoceras
sp.

This specimen consists of a small portion of the septate region, which shows a close resemblence to O. jaculum, Hall, in the size of the shell and the distance apart of the septa. That it is not identical is seen in the fact that the siphuncle is very small and central and the cross section of the shell is slightly elliptical, too little of the specimen is preserved to justify the founding of a new species. Compare also O. stylus, Hall. Pal, N.Y. Vol. V., Pt. II., Page 253. (Plate VI. Fig. 4).

Orthoceras extremum
sp. nov.

Shell straight. Though but a small fragment is preserved it appears to contract gradually towards the apex. The apical angle would probably be about 10 degrees. Transverse section elliptical. The third septum is 15 millimetres by 10 millimetres. As scarcely any evidence of crushing is apparent these figures express the degree of ellipticity, but possibly a little allowance should be made. Three air chambers are shown with a depth of two and a half millimetres each. The convexity of the septa is slight. Chamber of habitation comparatively large, extent unknown. siphuncle small and remarkably excentric. Surface unknown. Resembles O. inopatum, Hall, but is distinguished by its elliptical outline and the extremely excentric position of the siphuncle.. A small fragment, possibly of this species, shows a portion of the shell which is marked by minute annulations on the exterior. (Plate VI, Fig. 7).

Orthoceras algomense
sp. nov.

Shell probably straight, tapering very abruptly. If the angle shown by the chamber of habitation and the upper part of the septate region is continued to the initial point, the apical angle would be 18 to 20 degrees. Extremity unknown. Cross section sub-elliptical. At the fifth septum the greater diameter of the ellipse is 43 millimetres and the lesser 25 millimetres. The side of the ellipse in which the siphuncle is situated is much more convex than the opposite portion. Septa 7 millimetres apart near the chamber of habitation, but gradually approach one another towards the apex. The above described fifth septum has a convexity of six millimetres. Siphuncle is six millimetres from the more convex side of the shell. The chamber of habitation is 5 centimetres long in the specimen, but is not all preserved, the aperture being entirely gone. The characteristic points are the unusual cross section and the rapid tapering of the shell. The septate portion of another and larger specimen was obtained in which septa are separate from one another a distance of from five to six millimetres. No trace of the shell is preserved, but it appears to have been quite smooth. A sketch of the specimen and a view of the fifth septum to show the peculiar outline and the position of the siphuncle are given in Plate VI. Figs. 1 and 3.

Orthoceras pulcher
sp. nov.

The above species is founded on a rather fragmentary specimen, but one sufficiently preserved to exhibit distinctive characters that separate it from any known species of American Orthoceratids. It approaches nearer to O. crotalum, Hall, than any other species, and may be distinguished from Hall's species by the more undulating nature of the annulations and the greater distance between the crests. The specimen is somewhat crushed, so that it is impossible to give an outline of the cross ection, but it is probably somewhat elliptical. The chamber of habitation is 50 millimetres long and the width at the last septum is 32 millimetres in the greater diagonal and twenty millimetres in the less. The septa are three millimetres apart. The annulations of the body chamber are distinct and present a series of convexities and concavities, the former of a sharper degree of curvature. The two uppermost crests are fifteen millimetres apart; the second and third crests are separated by thirteen millimetres; the third and

Digitized by Google

fourth by twelve, and the fourth and fifth by ten millimetres. If the rate of decrease in size is uniform with that presented by the chamber of habitation the apical angle must be about twelve degrees. The outer shell is entirely unknown. In addition to the annulation the inside of the shell must have been pitted, as the cast shows small monticules distant from each other from one to three millimetres. Owing to the crushed condition of the specimen the convexity of the septa cannot be given. (Plate VI. Fig. 2).

Gomphoceras beta
Hall

Collected by Mr. Wilson.

Hercoceras auriculum
sp. nov.

Two internal casts, showing the chamber of habitation and a few of the septa. Chambers of habitation at least three centimetres long, with a width of two centimetres at the aperture. Contracts rapidly towards the apex, which is unknown. Shell sharply bent, and exhibiting on its lateral margins distinct nodes distant from each other about six millimetres. First six chamber three milimetres thick. Septate portion seems to contract very rapidly towards the apex and the thickness of the air chamber is considerably less towards the concave side of the shell. Sinus not observed. The siphuncle is in all probability excentric and situated close to the convex side of the shell. (This is seen in a third specimen which is doubtfully referred to this species). These specimens are much too imperfect for the proper description of a new type, but they are very distinctive in the character of the nodes. The distance of the field of occurence alone justifies the formation of a new species. This species resembles Gyroceras (Halloceras) paucinodum, Hall, and Trochoceras biton, Hall, more than any other described species of Helderberg age. The shell, however, seems to contract more rapidly than in G. paucinodum, and as two specimens were found of about the same size it is a fair assumption that they were adults, in which case Hercoceras auriculum is a much smaller cephalopod than Hall's species. The characteristic flat ventral surface of G. paucinodum is absent in the present species, the outline of which is not far from circular.

The specimen differs from Trochoceras biton in the stronger nature of the plications and in the sharper curvature of the shell. Hall's figure and description of T. biton are too meagre for a close comparison, but it appears that his species is considerably larger than H. auriculum. (Plate VI., Fig. 5 and 6).

Trilobita

The remains of trilobites are numerous and exceptionally well preserved in comparison with the other classes of organisms. In nearly every case a portion of the test has been preserved in excellent condition, so that the minute tuberculations of the crust and the facettes of the eyes are distinguishable. In the rough rock where the mollusca and brachiopods are to be seen only by casts, milk-white fragments are observed on close examination to represent portions of the tests of trilobites.

Calymene platys
Green

This species seems to be the most prolific in the region, eight specimens, representing the different parts of the crust being found. The average specimen is large, measuring six or seven centimetres by ten centimetres. One buckler shows parts of the crust with the minutely tuberculated surface intact.

Dalmanites anchiops
Green

Pygidia only of this species were collected. Some of these pygidia retain the caudal spine and are doubtless referable to the above species; others are devoid of the spine, the absence of which doe not seem to be due to fracture. These are, in all probability, identical with the following.

Dalmanites stemmatus
Clarke

This species has been recently described by Prof. Clarke in The Oriskany Fauna of Becraft Mountain, Page 15, Plate 1.

Phacops cristata
Hall

One small buckler and several pygidia, in all probability referable to this species.

Digitized by Google

Proetus

sp.

A single pygidium of a species of Proetus was found which has some minor points of difference from any described form. It would be very unwise to found a new species on such fragmentary material, but a description of the pygidium follows. Semi-elliptical, wider than long, width to length about seven to five. Axis distinctly convex with ten annulations. Surface of annulations of the axis minutely tuberculated. Pleurae gently convex from the furrow to a well-marked marginal sulcus. Annulations of the pleurae twice the number of those of the axis. Furrow between each pair of annulations slightly greater than between the two annnulations springing from the single axal annulation. A single line of tubercles on each annulation of the pleurae. Annulations cease at the sulcus. Sulcus relatively broader than in other species of Proetus, regularly convex, and marked on its distal border by a narrow, thickened ridge. The posterior point is unfortunately lost, but there is evidence that the margin was inflexed at the extremity of the pygidium.

Resembles P. conradi, but differs in the greater width of the non-annulated border, and in the fact that the double tuberculated annulations of the pleurae continue to the axis without coalescing. Also differs in the marginal ridge. Differs entirely from the common species, P. crassimarginatus, in the character of the annulations (Plate VIII., Fig. 1).

Conclusions

While the number of species mentioned in this paper would form but a small percentage of the forms occurring in the rocks exposed on the Kwataboahegan river, they are nevertheless sufficient to reveal the age of the series, which is unquestionably to be referred to the Devonian. It would also appear that the organisms denote an age comparable with the bottom of the Upper Helderberg. In some cases the assemblage would denote the Oriskany. While generally comparable with the above cited formations, certain differences are to be noticed, as already mentioned in this paper. By an exact comparison of the fauna of the northern with that of the southern rocks many questions as to the migration of species in Devonian times would be settled. Some of the minor differences which bear on this point have been referred to, but it is obvious that close investigation, and a comparatively complete collection is necessary to unable us to speak with decision in this matter.

Oil and gas are known to occur in the rocks of this age in southern Ontario, and there is no reason to doubt that similar valuable deposits may be met with north of the Height of Land. The rocks are very rich in organic remains, as may been seen by a reference to Plate VIII, Fig 2. The decay of such enormous numbers of organisms must have given rise to large quantities of petroleum. Whether this product is entirely dissipated remains for future exploration to reveal. Great beds of gypsum are associated with the limestones at various points in the regiou. The relationship of these deposits also remains to be worked out.

In closing this paper the writer must request the indulgence of the reader for many fragmentary notes. Many undetermined species are referred to, which, in a more accessible region, would be dismissed without comment. At this distance from their place of occurrence, however, it was thought advisable to refer, even if as to some of them in an uncertain manner, to nearly all the specimens collected.

In the preparation of this report the writer is deeply indebted to Professor John M. Clarke, the accomplished palaeontologist of the State of New York, for valuable advice and for the privilege of comparing type specimens in the Museum at Albany. His acknowledgments are also due to Bryon E. Walker, Esq., Toronto, for the loan of specimens for comparison and for the use of his extensive palaeontological library.

Digitized by Google

The Northern Nickel Range

By A. P. Coleman

In accordance with the instructions of Mr. T. W. Gibson, Director of the Bureau of Mines of Ontario, my main field work last summer was devoted to mapping the northern nickel range, which had not hitherto been worked out geologically, though much of its extent was known roughly by the work of prospectors. Mr. M. T. Culbert, who had been my assistant the previous year was reappointed, and from his energy and experience in the work rendered excellent service. He continued in the field for some weeks after my summer's work was over in order to complete the investigation of some points in connection with the northern iron range, and at the northeast end of the northern nickel range where it connects with the southern range.

As usual we received much aid and hospitality from mine owners, managers and prospectors, for which thanks are due. The maps and reports of the Geological Survey of Canada were of great assistance in our work, though prepared long before the relationships of the nickel-bearing eruptive were known. For the more detailed work which we carried on township maps provided by the Crown Lands Department were made use of, and in portions of the range maps of mining locations furnished mainly by Messrs. Demorest and Sylvester, engineers of Sudbury, were employed. The township maps were found to be variable in accuracy, some being excellent, but others not so good.

As the literature on the Sudbury Mining District was mentioned somewhat fully in our last report it will be unnecessary to go over the ground again(1).

Topography of the Range

The topography of the northern nickel range differs materially from that of the southern range as described last year. In general the contact of both of the inner (southeastern) and outer (northwestern) sides of the nickel-bearing eruptive with the adjoining rocks is found to lie in a series of rugged hills having very steep slopes, often with vertical walls, and so arranged that to follow the boundary requires a great deal of rough travel; while the basic edge (outer or southeastern) of the main southern nickel range is generally low and often very uniform in level. However, this had one advantage since the hillsides afforded excellent rock exposures, so that the boundary could usually be fixed with certainty. While the boundary is commonly on hilly ground, none of the summits rise very high above the general level, the relief seldom exceeding 200 or 300 feet.

Except at the southwestern and eastern ends of the northern range, where the eruptive curves down to meet the southern range, there is comparatively little drift encountered, much less than in the previous summer's work; and in general the drift consists of gravel and sand plains rather than clay flats. On the whole the northern range seems to be at a greater elevation than the southern, probably because the range is narrower, allowing the resistant rocks on each side to approach nearer together, and also because the easily weathered basic edge is usually much less developed than it is on the southern range.

The region is very poorly provided with canoeable waters, though there are a few fair-sized bodies of water along the range, such as Windy lake, Moose lake, Trout lake and Joe's lake; but in general the canoe was of little service. There is also a great scarcity of wagon roads, and those that do exist, being largely winter roads made by the lumbermen, are very rough and often mucky. With the exception of the road northeast of Onaping, built by owners

(1) Bur. Mines, 1903, pp. 235-6.

Digitized by Google

1

2



3



4



5

PLATE I.

Fig. 1: FAVOSITES GIBSONI *sp. nov.* Page 181. Vertical radial section, to show the tabulæ and the manner in which the corallites spring from the axis of the corallum. Enlarged three times.
Fig. 2: Horizontal section to illustrate the intermural pores and the walls of the corallites. Enlarged three times.
Fig. 3: The same enlarged six times. Owing to the imperfection of the photograph this figure is repeated in a pen and ink sketch, Plate VII, Fig. 2.
Fig. 4: Tangential section to show the polygonal shape of the corallites and the absence of septa. Enlarged 25 times.
Fig. 5: Horizontal section showing the lines of growth in the walls of the corallites. Enlarged 30 times.

Digitized by Google

UNIV. OF MICH.

Digitized by Google

1



2

3

4

5

PLATE II.

Fig. 1: CYCLOTRYPA BOREALIS, *sp. nov.* Page 185. Tangential section, enlarged about 25 times.
Fig. 2: Ditto. Vertical section, enlarged about 25 times.
Fig. 3: ACTINOSTROMA MOOSENSIS. *sp. nov.*. Page 183. Photograph of surface. Natural size.
Fig. 4: SYRINGOSTROMA AURORA, *sp. nov.* Page 182. Photograph of surface to show the flat mamelons and the long, fine astrorhizal canals. Natural size.
Fig. 5: FAVOSITES GIBSONI, *sp. nov.* Page 181. Photograph of weathered end. Natural size. See also pen and ink sketch, Plate VII, Fig. I.

Digitized by Google

UNIV. OF MICH.

Digitized by Google

1



2



3



4



5



6



PLATE III.

Fig. 1: SYRINGOSTROMA AURORA, *sp. nov.* Page 182. Tangential section, Fig. 2: Ditto. Vertical section.
Fig. 3: ACTINOSTROMA MOOSENSIS, *sp. nov.* Page 183. Tangential section. Fig. 4: Ditto. Vertical section.
Fig. 5: ACTINOSTROMA EXPANSA, *Hall.* Page 184. Tangential section. Fig. 6: Ditto. Vertical section.

All figures enlarged six times.

Digitized by Google

UNIV. OF MICH.

Digitized by Google

1



2



3



4



5



6



PLATE IV.

STROMATOPORA TUBULIFERA. Page 184. Fig. 1: Vertical section, enlarged 33 times. Fig. 2: Tangential section, enlarged 33 times. Fig. 3: Vertical section, enlarged 6 times. Fig. 4: Tangential section, enlarged 6 times.

CLATHRODICTYON PROBLEMATICUM, *sp. nov.* Page 184. Fig. 5: Vertical section, enlarged 6 times. Fig. 6: Tangential section, enlarged 6 times.

Digitized by Google

UNIV. OF MICH.

Digitized by Google



PLATE V.

Fig. 1: HOLOPEA, *sp.* Page 187. Front, apical and umbilical views of different specimens.
Fig. 2: LOXONEMA ROBUSTA, *Hall.* Page 186. View of internal cast of a large specimen and of the gutta percha impression of the exterior of a smaller one.
Fig. 3: GONIOPHORA, *sp.* Page 188. Photograph of internal cast showing the great angularity of the shell.
Fig. 4: MODIOMORPHA, *sp.* Page 188. Photograph of the cast of the exterior.
All figures of the natural size.

Digitized by Google

UNIV. OF MICH.

Digitized by Google



PLATE VI.

Fig. 1: ORTHOCERAS ALGOMENSE, *sp. nov.* Page 189. View of chamber of habitation and the upper septa of the type specimen. Fig. 3.—Ditto. Fifth septum, showing the outline and position of the siphuncle.
Fig. 2: ORTHOCERAS PULCHER, *sp. nov.* Page 189. Front view of the type specimen.
Fig. 5: HERCOCERAS AURICULUM, *sp. nov.* Page 190. Chamber of habitation of the smaller specimen. Fig. 6:—Ditto. Side view of the larger specimen showing the nodes and the degree of curvature. The dotted line indicates the probable outline of the ventral side.
Fig. 4: ORTHOCERAS, *sp.* Page 189. Portion of the septate region and outline of septum with siphuncle.
Fig. 7: ORTHOCERAS EXTREMUM, *sp. nov.* Page 189. Front view of type specimen and outline of septum.
Fig. 8: COLEOLUS TENUISTRATUS, *sp. nov.* Page 188. Large coarsely striated example. Fig. 9: Ditto. Apical portion of smaller form.

Digitized by Google

UNIV. OF MICH.

Digitized by Google

1



2



3



PLATE VII.

Fig. 1: FAVOSITES GIBSONI, *sp. nov.* Page 181. Pen and ink sketch of the weathered cross fracture, enlarged twice. Fig. 2: Ditto. Sketch of a portion of a horizontal section, showing the tabulæ, intermural pores and lines of growth. The intermittent activity of the organism is well shown in the continuity of the light and the dark portions across several several corallites. Enlarged about 20 times.

Fig. 3: PLEUROTOMARIA DELICATULA, var. CAMERA, *var. nov.* Page 187. Sketch of the best preserved specimen, enlarged 6 times.

Digitized by Google

UNIV. OF MICH.

Digitized by Google

1



2

PLATE VIII.

Fig. 1: PROETUS, *sp.* Page 191. Pygidium enlarged 5 times. (The photograph does not show the thickened margin.)

Fig. 2: YELLOW LIMESTONE FROM KWATABOAHEGAN RIVER. Page 180. Photograph of a fragment reduced one-half, to show the highly fossiliferous nature of the rock. The surface of this specimen shows:—Orthoceras luxum, Orthoceras procerus (?) Coleolus tenuistriatus, C. tenuicinctum, Pleurotomaria adjutor, Modiomorpha sp., Platyostoma lineata, Bellerophon sp., Euomphalus sp., Athyris spiriferoides, Cypricardinia indenta (?) Atrypa reticularis.

Digitized by Google

UNIV. OF MICH.

Digitized by Google

of mining locations in Levack township for the purpose of developing their properties, none of these roads follow the edge of the nickel-bearing eruptive, and so give little aid in tracing it. On this account most of the work of the summer had to be done by tramping, often for a distance of several m. through the bush, from points that could be reached by wagons. As the pine had been cut in many places, the township lines are often almost obliterated, and walking along them, bad enough originally from the precipitous nature of the country, has become very slow and difficult. There are however some tracts of splendid pine still uncut, as in the township of Trill, where lines are easier to follow. Fire has not swept the northern range to the same extent as the southern, so that for the most part the cutting and blazing of the lines is much more distinct, and less time is lost in looking for lines. The older surveys however are largely grown up with small trees, especially where fire has run, and in such places one is often at fault.

While each edge of the northern nickel range tends to be rugged and hilly, the space between is generally not quite so rough, and the same is true of the Laurentian country to the north and northwest. Toward the southeast after a very precipitous row of hills formed of the indurated tuffs bordering the acid edge is passed, the relief becomes much less marked, and there are sand or gravel plains or clay flats through which the Vermilion river and its tributaries meander, often in a quite extravagant way. The underlying rock in this part of the district, when exposed, is black slate, which is much softer and more easily weathered than the tuffs beneath or the overlying sandstones, the latter often rising as low ridges still farther to the south.

Large tracts of the low ground through which the river winds are of good soil, now being rapidly taken up by settlers, mostly French Canadians, though some old country English families are settling here also. The townships in which our work was done are however almost devoid of good land, owing to their rugged rocky character.

Our survey covered parts of Drury, Trill, Cascaden, Dowling, Levack, Morgan, Foy, Bowell and Lumsden, Wisner and Hanmer, Norman and Capreol townships, the series beginning at the southwest and sweeping in a gentle curve to the northeast and north, a southward bend beginning however in Norman township. Both the basic and acid edges of the nickel-bearing eruptive were mapped, though more care was put on the basic edge where ore bodies might be expected to occur. Our aim was to fix the boundary wherever it was crossed by a township line, i.e., at about every half mile, and in most cases there were satisfactory outcrops, though drift deposits and swamps concealed the contact in a few places, especially in Cascaden and Trill townships. In no case were the drift-covered gaps longer than two miles except in the broad sand plains south of Capreol, where the outline of the eruptive is still uncertain.

Distances were determined by pacing in a few places, chiefly in Cascaden from corner posts or other fixed points, and the position of the contact was usually determined with a probable error of less than 100 yards. In the more important parts where mining or stripping of ore bodies had been done the basic edge was followed continuously when not drift-covered. For work in such places the dial compass had to be used on account of the strong local attraction. In the accompanying map of the Northern Nickel Range the boundaries of the eruptive band are given in solid lines where observed in the field, intervening spaces being dotted. Ore deposits or large gossan areas are marked with +. The basic edge of the eruptive is colored brown and the acid edge red, the two colors blending in the middle.

Stratigraphical Relationships

While our special purpose was the mapping of the nickel-bearing eruptive throughout its whole extent northwest and north of the main or southern nickel range, so as to close up gaps and if possible connect the two ranges geographically, it was necessary also to make a study of the adjacent rocks in order to determine the exact boundary of the eruptive. It was found, as foretold in last year's report, that the two ranges join at the ends, making a continuous belt of eruptive rock enclosing a rudely oval, or rather boat-shaped area of sediments, classed by Dr. Bell in the earliest survey as probably Cambrian in age. The only possible gap in the belt is in the townships of Maclennan and Falconbridge, where extensive lake deposits form plains of sand and gravel, leaving very few outcrops. Assuming that the hidden parts resemble those that are exposed, there is little doubt that the belt of nickel-bearing rock is unbroken, and that the northern range is connected at both ends with the better known southern one.

Along with this goes the further probability that the whole mass of eruptive rock is sheet-like, forming a basin or short synclinal trough, as suggested in a

Digitized by Google

diagram given in last year's Report; so that the enclosed sedimentary rocks appear to rest upon the eruptive sheet. Along three-quarters of the inner margin of the nickel-bearing rock it is in eruptive contact with the base of the sedimentary series just mentioned; but a band of Huronian rocks of an older type intervenes between the two in Rayside, Snider, Creighton and perhaps Fairbank townships north of the main nickel range. The relationships here have not been finally worked out.

The outer or basic edge of the belt is also in eruptive contact with the rocks beneath, which, as far as the northern range is concerned, consist entirely of what is generally mapped as Laurentian, granitoid gneisses with basic schistose bands, the "basal complex" of some American geologists. On the south side, as shown in last year's Report and also by Dr. Barlow (2), the relationship is much less simple, quartzites, graywackes and various green schists and eruptives generally called Huronion, making the boundary in many places, and granites or granitoid gneisses of somewhat doubtful age forming the boundary in others.

In general we may say that the synclinal sheet of nickel-bearing eruptive rests on undoubted Archaean rocks, Laurentian on the north and Huronian with various eruptives as well as probable Laurention on the south, its contact on both surfaces being of an eruptive character, so that it may be called a laccolithic sheet on a gigantic scale.

It had long been known that the northern nickel range splits up near the centre of Bowell township, one branch running slightly north of west into Foy, and another southwest to Morgan township; but the real relationship was doubtful. Our mapping of the boundaries has shown that the basic edge of the eruptive follows the last mentioned direction, and that the extension into Foy is a narrow dike-like offset or apophysis, the only extensive projection from the eruptive yet discovered in the northern range.

(2) Geol. Sur. Can., Sum. Rep. 1902, p. 263.

The Range in Detail

The Southwest Corner

Fairbank lake, in the township of the same name, is almost entirely enclosed in the nickel-bearing eruptive, and gives good exposures of the rock on various points and islands. To the southwest about a mile and a half from the lake is the old Chicago mine, at one time called the Inez mine, with a fair wagon road leading three or four miles south to Worthington on the "Soo" Railway. The mine, which was worked partly as an open cut and partly from a shaft reaching a depth of 160 feet, is on a short offset to the south of the basic edge of the norite. The ore was apparently found in small pockets enclosed in very mixed rock, greenstone, green schist, porphyrite and a white rock almost free enough from green minerals to be called anorthosite. Two or three roast beds may be seen, and the roasted ore seems to have been smelted to matte and shipped to the railway by a curious single rail tramway in cars hanging beneath the rail. The tramway was worked by horses, but is now in ruins.

There are several buildings at the mine, as well as houses for the manager and miners a quarter of a mile to the north, but few of the buildings are now occupied, though two or three French-Canadian settlers have taken up farms in the neighborhood. Near the manager's house the norite leans up against Huronian rocks, and is here medium-grained and speckled gray in color, not so dark as in most parts of the basic edge farther east. The road to Fairbank lake, after passing a somewhat sulphurous spring and a farm house, turns north, and then east to the southwest bay, the ground being mostly low and swampy, though outcrops of similar but coarser speckled gray rock occur along the trail about 600 paces from the lake. As one goes north by canoe the rock on the shore of the lake becomes somewhat reddened where weathered, but remains rather gray on fresh surfaces, while on the north shore close to the tuffs which form hills between Fairbank and Vermilion lakes, the eruptive becomes dark-green and fine-grained, sometimes having an almost schistose cleavage. None of the outcrops toward the acid edge look like granite, though thin sections prove that the rock contains some quartz, and probably also orthoclase. This dark-green fine-grained phase of the acid edge of the nickel-bearing eruptive was found only at the southwestern end of the range.

The actual contact of the eruptive with the tuffs was not observed owing

Digitized by Google

to the amount of drift and the density of the woods on the divide between the two lakes.

Sultana Nickel Mine

The wagon road from Worthington to the Chicago mine has been continued three miles northwest to the Sultana nickel mine in lots 7 and 8 in the sixth concession of Drury township, and lot 8, in the first concession of Trill; and as the basic edge of the norite is not visible on the road, though rock crops out at several points, it probably runs somewhat parallel to the road, but farther to the northeast.

On lot 6, in the sixth concession of Drury, on what is called the Sultana east mine, gossan shows on a hillside with more or less are extending along its flank, which at first runs northeast and then turns east. Strippings of ore and test pits occur all along the boundary for about 150 yards. To the southwest the hill sinks into swampy ground, and neither ore nor norite was found in that direction.

Following the township line west of these outcrops, except for one hill of gray norite, the whole distance of at least half a mile to the Sultana mine proper, runs through swamp. At the Sultana a steep hill rises toward the southwest, much as at Sultana east, and a large number of test pits and outcrops show that the ore leans up against the wall of rock on this side of the valley also. On the flat beneath the hill camps for eating and sleeping, and offices, etc., have been put up, occupied at the time of our visit by Mr. Vasey and a party of men engaged in exploring the property with a diamond drill for the Lake Superior Power Company.

The strippings and other workings follow the foot of the hill in a direction about 10 degrees west of north for about a quarter of a mile (22 1-2 chains) from the cornerpost between lots 7 and 8 in Trill, so that the actual workings are in lot 8 of Trill; but one or two small outcrops occur on the hillside at a distance of 9 or 10 chains south of the cornerpost also. Part of the deposit is therefore in Drury, and the known extent of the ore is three-tenths of a mile. It is probable that careful search would disclose ore still farther to the south along the edge of the hill, but the bush is thick and no other hints of gossan were found.

Most of the ore to the north of the camp is along the lower flanks of the hill, but an offset runs 9 chains to the west a little north of the cornerpost, and two large strippings at this point show ore at the hill top 117 feet above the flat at the bottom.

There are three shafts, respectively 13, 19 and 22 1-2 chains to the north of the cornerpost, and beyond the last shaft the hill turns off to the west, and no more ore is to be seen. The deepest shaft is said to be down 110 or 120 feet; and there is a considerable quantity of ore on the dumps. A drill hole sunk a little to the east of the last shaft showed 36 feet of clay and sand, then norite followed by some ore, and finally greenstone with more or less ore. The dip of the rock surface between the shaft and the drill hole is about 40 degrees to the east.

In general the ore in this locality seems to lie in depressions of the hill as if it had settled into the lowest places. As the rocky hills bounding the swampy valley to the east and west seem to be converging toward the south, it is not unlikely that ore may be found beneath the swamp or drift in that direction, but up to the present none has been reported; nor is it known if an offset runs southwards into Drury township.

The rocks forming the hill west of the gossan are not Laurentian, as suggested on the maps, but are more like Huronian, since they include green schist and diorite, with irregular patches of what appears to be norite penetrating them and showing on the flank of the hill toward the low ground. Much of the hill has the look of crush conglomerate.

The norite north of the Sultana is greatly mixed with older rocks, especially a flesh-colored arkose, and for half a mile in that direction, if it were not for the finding of the basic edge near the mine and the acid edge still farther north, one would be in doubt as to the relationship. It appears that there was a great amount of crushing and faulting of the older rocks with the eruptive toward this narrow southwest end of the great boat-shaped trough: but the thickly wooded surface prevents a very complete study of the geology. Just west of the Sultana mine the boundary of the norite is hard to trace, but about a mile to the northwest it is clearly seen again not far from a wagon road, now fallen into ruin and grown up with bushes, on the way to the Trillabelle or Gillespie mine; and from this northward to the third concession the road follows the contact, and ore may be seen at various places against a wall of hills like that at the previous localities.

Digitized by Google

Trillabelle Mine

In the third concession on the line between lots 10 and 11 of Trill there is a fairly well beaten trail or portage running east and west connecting with a canoe route eastwards to Fairbank and Vermilion lakes; and here just to the west of the old wagon road granite of a Laurentian aspect rises as a rocky hill above the swamp so usual at the basic edge of the nickel-bearing eruptive. Next to this, going north, is a dark-green rock containing some boulders, evidently a Huronian conglomerate or breccia, and against it ore is to be seen. Half a mile farther north the wagon road ends at the mine called by our guide the Gillespie, but in the Bureau of Mines report the Trillabelle (3) where a considerable amount of work was done many years ago.

Here and 170 paces beyond are a few foundations of stone, remains of a hoisting plant and various log houses; and ore or gossan against the hill which rises to the west. The rock observed is mainly greenstone with boulders suggesting a crush conglomerate, though a gray fine-grained rock near the northern pits may be norite. The dip of the rock face against which the ore lies at the points previously mentioned is from 35 degrees to 45 degrees to the east.

Half a mile north morainic hills conceal the bed rock and the next outcrop observed is probably the basic eruptive edge, the rocks higher up the hill to the west being bouldery greenstones like those mentioned before.

For a distance of 550 paces east of the line between lots 10 and 11 and near the middle of the fourth concession the rocks observed are a somewhat recrystallized arkose, evidently Huronian, and beyond this only bouldery drift is seen for 200 paces, probably covering the basic edge of the nickel-bearing eruptive, which here rises from under the drift.

The acid edge of the eruptive at this southwest corner is best studied from a chain of small lakes. Beginning at Fairbank lake a fair portage leads west to Cameron lake, mostly over drift, though the acid edge is only a little way to the north and shows on the north shore of the latter lake near its outlet. From Cameron lake a very poor trail leads west to a small unnamed lake lying across the boundary between the tuffs and the eruptive. The hills rising 270 feet (by aneroid) above this lake are about the highest in the region, and from the top one commands a wide view. They consist of the hardened sediments against the acid phase of the eruptive and present a greater variety of rocks than usual, including conglomerate, with large granite boulders, coarse white quartzite, dark-gray chert, a flesh-colored felsitic-looking rock and hardened gray chert; all brecciated and intermixed.

The sharp ridge of mixed rocks runs northeast to Ross lake, which lies astride the boundary, and the acid edge on the shore is a fine-grained gray rock with considerable quartz, unlike the edge on Fairbank lake.

(3) Bur. Mines, 1894, p. 248.

Windy Lake Region

Rounding the sharp bend which the nickel-bearing eruptive makes in Trill the outer contact runs north and northeast toward the west end of Windy lake, through difficult country largely swampy and drift-covered, so that for about two and a half miles the boundary has not been fixed, though it is known that Laurentian rocks crop out near Armstrong lake and that the boundary is to the east of this. The acid edge is unusually dark-green in color like that on Fairbank lake, and runs northeast from Ross lake to lot 3 on the Cascaden town line.

The nickel-bearing eruptive runs diagonally across Cascaden and Dowling townships and is most easily studied along the Canadian Pacific railway and on the shores of Windy lake. On the line between Trill and Cascaden the eruptive reaches a narrow arm of water running southward from a small lake, and extends northeast along another arm which forms the boundary against the Laurentian, here consisting of gneiss and greenstone. Without a canoe it was found impossible to cross to a location taken up years ago on the north shore of the small lake, where there may be an outcrop of ore. The rest of the margin in this township is most easily reached from Windy lake and then by a canoe route running southwest from it.

From the southwest bay of Windy lake a good trail runs 760 paces to a pond, 315 paces to another pond, and finally, after a little more than half a mile of trail in all, reaches a lake of considerable size. The trail runs over drift deposits including a moraine; the ponds are without outlets, suggesting kettles; and the unnamed lake appears to be mainly or wholly within the Laurentian.

On Windy lake itself the northwest shore, where not drift-covered is Laurentian also, of the usual kind in the region, consisting of reddish or grayish bands with darker gray layers of

Digitized by Google

finer grained schist. The islands off shore and the large peninsula projecting from that shore are of norite. On the peninsula the boundary is largely hidden by morainic and esker ridges, but it is distinctly seen on the shore of the southwest bay. The rest of the shores of this beautiful lake are of norite or the intermediate rock between the basic and acid phases.

Much the best section of the nickel-bearing eruptive is provided by the railway cuttings to the west and east of the little station Onaping; and a number of rock specimens from these cuttings have been described by Prof. Walker(4.)

Beginning on the northwest near Windy Lake station, which is some distance west of the lake, Laurentian granite and gneiss with darker schistose inclusions is found until the shore of the lake is reached, when gray dioritic-looking norite is found, the actual contact however being hidden by drift. The rock remains the same in appearance for 100 yards, but soon changes to a reddish syenitic phase of fine or coarse grain, which continues to Onaping station, and is followed toward the southeast by greenish-gray rock having a peculiar ophitic-looking structure. The color and general appearance of the eruptive at the ends of this section are much alike, but the intervening phase of flesh-red syenite-looking rock is very different.

The acid edge of the eruptive rises as very steep hills to a height of 300 feet above the station, and the railway is forced to follow the valley of Onaping river in a sharp curve in order to cross the range of hills. The southeast side of these hills consists of hardened sediments, at first a gray, fine-grained graywacke conglomerate with pebbles and a few boulders of quartzite and granite, and sometimes also of gray chert, extending along the railway for about 1,000 feet; and followed by characteristic black vitrophyre tuff, often crowded with small fragments of gray material.

At another point on the acid edge, about half a mile south of Windy lake, a coarse Laurentian-looking conglomerate comes next to the eruptive, with many large pebbles or boulders of gneiss or granite embedded in it. This is succeeded by the graywacke conglomerate and finally the tuff, and similar relations are found to the southwest, where a Huronian conglomerate with granite pebbles and boulders comes next to the acid edge of the nickel-bearing eruptive.

(4) Quar. Jour. Geol. Soc., Vol. liii (1897), pp. 56-59.

The Levack Ore Deposits

To the northeast of Windy lake the basic edge may be traced, with some interruptions from gravel plains, to Onaping river; but no gossan or ore was observed between the Gillespie mine in Trill and the Onaping river in Levack township. The old mining road from Onaping to the Levack ore deposits is now in very bad condition from the heavy teaming of the lumbermen operating in the region, and also from flooding, due to their dams on the lakes intended to sweep down the logs in the somewhat shallow river and its tributary creeks. A diamond drill plant was taken along this road to the Strathcona mine during the past summer for the Lake Superior Power Company, but the difficulties met in transporting the heavy machinery were very great. The road leads along the river from the station for about 2 1-2 miles, largely over gravel plains, then crosses a bridge and follows the valley of a tributary toward the northeast, keeping along the foot of a range of Laurentian hills just at the margin of the norite. The actual margin is often occupied by small, narrow lakes, as though the norite had decayed more rapidly than the granite; and at several points where the norite still rises above the general level it is now weathering extraordinarily fast. The best instance is near the dam at the mouth of the creek draining Moose lake into the Onaping, where the spheroidal weathering is of a very characteristic kind. The rock, which is gray and coarse-grained, is irregularly fissured into blocks from 2 or 3 to 20 feet across. The weathering takes place along the fissures, leaving mound-shaped surfaces with channels between; and may go so far as to leave rounded blocks resembling drift boulders resting on the decayed surface, with material like fine gravel beneath the block representing the products of decay. In many cases the actual margin of the norite is not to be seen, but Laurentian rock rises to the northwest out of a lake or swamp and norite to the southeast.

About four miles from Onaping along the road just mentioned thick beds of gossan lying against the Laurentian attract attention at the Tough and Stobie property and test pits show that some ore underlies it, though no norite is to be seen. The Laurentian is of the kind usual in the region, granite running into gneiss and greatly mixed with fine-grained greenstone; and the ore, which consists of pyrrhotite, with a little chalcopyrite, sinks beneath the surface of the muskeg through which the creek winds.

Digitized by Google

Less than half a mile farther along the road there is another outcrop of gossan and ore like the first one, but with a lower hill of Laurentian on the northwest and a small lake on the other side. A little beyond this lake there is a gap in the Laurentian hills, suggesting an offset, and it is said that an ore body has been found some distance out in the granite, but we found no trail to it, and left it unvisited. Beyond this apparent offset there is another marginal lake, and then the route passes through low hills to what was once called the Levack mine, in lots 1 and 2 in the fourth concession at the end of the wagon road, about nine miles from Onaping.

Here two properties, the Strathcona and the Stobie No. 3, or Big Levack mine, have been opened up by stripping and test pits, and have been surveyed magnetically as shown by the systematically arranged survey pegs.

Strathcona Mine

Mr. Ernst A. Sjostedt, who examined the Strathcona property last summer report on it as follows:

"The mineral zone runs diagonally N. E. and S.W. across the north half of lot 3 and south half of lot 4 in the fourth concession of Levack township, and is bounded to the northwest by a range of syenitic granite, with which it forms a direct contact, and to the southeast by a wide range of norite, which usually forms one side of the mineralized zone throughout the Sudbury district. The largest body of ore is shown at the northeast end of lot 3, although the line of magnetic attraction is practically continuous across both lots, and ore is shown at various points on lot 4 as well. Near the northeast end of lot 3 the principal prospecting work has been done, a space of 3 or 4 acres having been cleared of timber and underbrush, and in places the formation stripped, exposing the capping and gossan, which generally reaches a depth of 2 to 8 feet. Part of the ore body is here shown up by a great number of cuts and pits, also by two shafts, of which No. 1 shaft is 45 feet deep, being 8 feet through barren cap rock, then through 25 feet of good mixed ore, then through 12 feet of solid pyrrhotite, and a 10-foot hole having been drilled in the bottom of the shaft, showing clean ore the entire distance. No. 2 shaft (250 feet north of shaft No. 1) is 30 feet deep, 6 feet being in cap rock and 24 in solid pyrrhotite.

"Pit A (320 feet north of shaft No. 1), and pit D (40 feet north of pit A) show ore within 2 feet of the surface, and trench C, along a low hill-side about midway between pit A and shaft No. 2, shows a face of ore 50 feet long, in the centre of which a pit was sunk through 12 feet of solid ore.

"From the data furnished by the above mentioned pits and shafts, covering an area about 600 feet in length and width, the amount of ore in sight on lot 3 is some 60,000 tons, but this includes an area of less than a tenth of the ground covered by equally promising surface indications, consequently there is every reason to expect a much larger body. The ore exists mainly in solid masses within a zone of 200 to 600 feet wide, and some 1,400 feet long. On page 199 are a number of analyses of samples taken from the above mentioned workings, which will show the character of the ore."

The Big Levack mine just to the east of the Strathcona presents a very irregular margin of gossan and ore spread over Laurentian hill-slopes and sinking to the southeast under muskeg with a dip of about 20 degrees in some places, but steeper in others. Some norite is present mixed with the ore; most of it, however, and probably also of the ore has been weathered away, but may perhaps be found beneath the swamp.

The second set of mines seems much more extensive than those nearer Onaping. Beyond the Big Levack mine the nickel-bearing eruptive bends off to the east in swampy ground with small lakes and only one small patch of gossan was observed on its border.

Moose Lake Region

The acid edge of the nickel-bearing eruptive in Levack and the northeastern part of Dowling is best studied from Moose lake, which spreads out irregularly over a length of three miles along this margin. Moose lake may be reached by a road running northeast from Larchwod to Joe Seemo's farm on the banks of Onaping river near its junction with the Vermilion; and then by a trail leading through the woods to a bay on the line between Levack and Dowling townships. From the river to a pond with no outlet near the bay only drift is to be seen on the portage, but the acid phase of the eruptive here shows itself, and practically the whole of Moose lake is enclosed in it. The outlet of the lake into the stream mentioned before as joining Onaping river two miles north of the station is over the eruptive, and the same rock is found at various points on the lake and on the next small lake to the northeast, generally called Trout lake, and another to the east of it.

The acid edge runs northeast and southwest as a range of hills often with

Digitized by Google

sharp minor ridges, sloping to the southeast and precipitous to the northwest, resulting perhaps from faulting during the sinking of the basin, or possibly representing a main direction of joints. All the survey lines cross these ridges diagonally. The contact of the nickel-bearing eruptive, with the tuffs to the southeast is often drift-covered, and on this edge as well as on the basic edge there is frequently a valley or narrow lake in this position. The sedimentary rocks to the southeast also form sharp ridges parallel to the eruptive ridges, and occasionally a narrow hill consists of the acid edge of the eruptive on one side and on the other of the tuffs.

The best exposure of the contact between the acid edge and the sediments found in the region occurs on the shore of a pond a little east of the end of the portage from the south to Moose lake. This body of water, unlike most others,

Morgan Township

The basic edge of the eruptive crosses a small lake just east of the Levack mine and enters Morgan township on the fourth concession line, then turns a little north of east to Island river, which follows the edge for more than a mile and turns northeast once more to the fifth concession, and finally passes into Bowell township from the northeast corner of Morgan township. The boundary may be reached partly from Trout lake and partly from a lumber road leading over sand and gravel plains from Chelmsford to a camp near the junction of Island and Sand Cherry rivers. Travel in the region is, however, very troublesome from fallen timber and the unusually rugged and precipitous hills along the contact. The best exposures seen are near the lumber camp, where a steep hillside rises above

Sample from	Sampler.	Insol.	Fe.	Cu.	Ni.
Shaft No. 1, 8 ft. from bottom	D. C. Schuler			.57	2.78
" piece from dump	E. A. Sjostedt			1.35	3.55
" 2, from dump	D. C. Schuler			.70	3.85
" 25 feet depth	"	5.08		2.11	3.54
" piece from dump	E. A. Sjostedt			.14	4.65
Pit A, surface	D. C. Schuler			.67	2.24
" B, surface	"			5.47	2.02
" B, bottom	"	6.10		1.54	3.37
" C, surface	"			.33	2.40
" C, trench	"	3.40		1.24	3.27
" C, 13 ft. pit	"			.28	2.72
" D, low ground	"	4.00	50.4	.30	3.21
Diamond drill hole, near A, 26 ft.	A. B. Wilmott			.65	3.80
" " 40 "	"			.58	2.60
Shafts, all over dumps	R. H. Aiken	5.01	54.3	2.23	3.15
Near norite wall	"			1.49	1.68
"	"			2.43	1.70
Average		4.71	52.3	1.31	2.97
Samples taken by Messrs. Cohen & Bradley, experts for J. R. DeLemar, N.Y.				1.99	2.67
Total average				1.70	2.82

cuts across the strike, and near its outlet into Moose lake the edge of the nickel-bearing eruptive shows a reddish-gray medium-grained rock, followed to the southeast by coarse flesh-red granite or gneiss, possibly a pegmatite dike. Then comes rock much like the first mentioned, succeeded by conglomerate with a fine-grained gray crystalline base and granitic-looking pebbles, lasting for about 120 feet, doubtless the basal beds of the sedimentary series. Beyond this is coarse white quartzite for about 70 feet, and then conglomerate again for about 200 feet, after which there is a curious breccia of paler and darker chert with some pebbles and boulders of granite for 1,000 feet, evidently the same as had been found along the railway southeast of Onaping beneath the vitrophyre tuffs.

Island river, having the nickel-bearing eruptive on its southern face pushing projections into the Laurentian rocks forming the summit. The former rock is not very gray, sometimes even rather reddish-looking, and of variable texture, coarse-grained and fine-grained parts running into one another, the finer grained material sometimes cementing blocks of Laurentian rock into a breccia. The Laurentian, which strikes east and west with a vertical dip, has the usual characters and consists of coarse gneiss with bands of gray-green finer grained material, the whole sheared in places into what looks like felsite. Near the edge it is greatly broken as if by the action of the eruptive mass to the south. No ore or gossan was found from the west edge of the township to lot 1 in the sixth concession, almost at

Digitized by Google

the northeast corner, and prospectors have taken up no locations between the two points. Near a small lake where the four townships, Foy, Morgan, Lumsden and Bowell, meet there are two locations with two or three patches of gossan, on which very little work has been done.

The southern or acid edge of the eruptive in this township has the usual characters, and is in contact at various points with the basal conglomerate so often found below the tuffs. The eruptive band is at its narrowest about the middle of Morgan township, having at one place a width of only a mile, and there seems less variation in character between the basic edge and the central and southern parts of the band than it is customary to find in other parts of the nickel range. Perhaps this fact should be brought into connection with the absence of ore referred to above. The thickness of the molten eruptive may have been insufficient to provide any large quantity of sulphides by gravitational segregation.

In Powell Township

In Bowell township the northern nickel range has long been known through the work of prospectors, and a row of locations has been taken up beginning at the southwest corner and running quite across the township, passing in the third concession into the next township, Wisner. About at the centre of the row of locations a long offset branches toward the west, extending out of Bowell into Foy and ending almost exactly in the middle of the latter township; and the whole of this offset is included in mining locations also, so that there has been more interest shown in ore deposits of this township than in any other on the northern range.

The locations are best reached by colonization and lumber roads from Azilda (Rayside) to Trout lake (a larger body of water than the one of the same name in Morgan township). Crossing Trout lake by canoe a trail leads inland from its northern bay and branches toward the southwest, west and northeast. A part of this trail which was cut out for the use of packhorses during the development of some of the properties is still in good condition, but toward the ends in each direction the path is rough and hard to follow, especially where the timber has been cut and fire has run.

Beginning at the southwest corner of the township the basic edge of the nickel-bearing eruptive is found a little north of the corner post of location W D 251, and in a general way the trail follows the edge, except where hills or swamps turn it aside, or where morainic ridges hide the contact. Gossan shows against the steep slope of the Laurentian toward the northeast corner of the location, and there is a swampy pond below, with hills of norite to the southeast. Near the west end of WD 241 an outcrop of gossan and a test pit along the trail indicate the boundary, and more gossan is seen toward the east side of the location, then drift hides the contact until WD 231 is reached where three similar small outcrops of gossan and ore occur against the Laurentian.

In WD 238 a small offset projects northward from the edge running into a narrow valley in location WD 37, where there are strippings showing gossan. The valley is enclosed by steep and bare Laurentian hills. A small lake in locations WD 242 and 239 appears to represent the boundary, and Roland lake a little to the northeast occupies the same position, having Laurentian on the north and norite on the south.

In a general way there is a valley running along the southeast edge of the Laurentian, which rises as a very rugged range of hills to a height of from 200 to 270 feet, with patches of ore along its foot. Southwest of the valley, which is often occupied by a narrow lake or muskeg, gray hills of norite rise to about the same height as the Laurentian.

In WD 35 the offset running to the Ross mine in Foy leaves the edge of the main range. In WD 36 near its northwest corner and probably extending into the previous location there is a promising outcrop of gossan and ore at the edge of the granite, but east of this to Trout lake no ore was observed.

Offset to Ross Mine

The longest offset on the whole circumference of the nickel-bearing eruptive extends for six miles nearly westwards from WD 35 to WR 5, reaching what is called the Ross mine, in the exact centre of the township of Foy. The path is at first good, but before the west boundary of Bowell township is reached fire and fallen timber and the debris left by the lumbermen injure it greatly, and beyond this care is needed in following it even in green timber, since it has scarcely been used for a number of years and the blazes are growing dim.

Just after turning off from the main range there is a considerable showing of

Digitized by Google

ore on a hillside, and the adjoining rock consists largely of white plagioclase crystals so crowded together as to appear like anorthosite. Small seams of magnetite occur in this rock as well as sulphides. To the northwest in WD 150 a wide expanse of gossan is exposed by stripping and numerous test pits extending nearly to Nickel lake, where there is a log house occupied during the development work. Turning west the band narrows greatly and fine-grained norite penetrates between blocks of coarse-grained norite, of a gray gneissoid, rock, of greenstone, and of a white rock with porphyritic feldspars, the whole rusty or gossan-covered. The adjoining Laurentian is coarse red granite, an unusual variety in the region. On the shore of the next lake to the west a similar mixture of rocks is seen, and some gossan rises above the water.

From this point to the neighborhood of Ross mine little ore or gossan was seen, although the band of norite, narrowing and widening, seems to be continuous or nearly so the whole way; but somewhat similar outcrops of gray rock rising through drift-covered ground leave some doubt as to the relationships. Evidently the early prospectors considered the whole length to belong to the nickel range, or they would be have taken up locations along it. The greatest width of the offset, so far as observed, is in WD 234, where the rock seems to extend for about 500 feet, but usually it is much narrower, in one case apparently only 20 feet.

Our exploration of the locations just east of the Ross mine was greatly hindered by the work of a colony of beavers which had recently built a dam backing up the water for half a mile or more in various directions into the flat wooded land along the creek. WR 5, the original Ross mine location, includes two outcrops of ore and gossan standing as usual against a hill side of Laurentian, and dipping under the muskeg borders of a small lake; but the amount of ore to be seen is not large. Most of the Laurentian encountered along this offset is coarse-grained and flesh-colored, but some masses of gray-green rock, in general appearance not unlike the norite, are enclosed in it.

South Edge of Eruptive

The acid edge of the eruptive crosses from Morgan township into Lumsden in the fifth concession, and is fairly well exposed near the north shore of a small unnamed lake just north of the concession line in lot 9, as a gray rock weathering reddish. The neighboring sediments to the south look like quartzite with pebbles and merge into the tuffs, and these rocks continue to the northeast as a range of high hills, sinking however where Nelson river makes its way through. Along this valley gravel plains and morainic ridges conceal the rock. On the line between lots 6 and 7 to the south of a small lake crossing the concession line between Lumsden and Bowell the acid edge forms a hard gray-green rock, or some other eruptive appears to intervene between it and the sediments; but on the town line in lot 5 and also in lot 4 we find the usual relationships, the granitic-looking acid edge seeming to blend with a greatly metamorphosed coarse conglomerate. In places, if it were not for the coarser grain and different texture of the included pebbles and boulders, the matrix of the conglomerate could not be distinguished from the eruptive, and great care was necessary not to overrun the contact between the two rocks.

In location WD 252 at the southwest bay of Trout lake there is once more a fine-grained dark-green rock between the eruptive and the tuffs, in places very much like a basic eruptive rock itself, but in others charged with a few pebbles of granite, and having the characters of "slate conglomerate." In this marginal rock there are veins containing quartz with zinc blende, galena and a little copper pyrites, and at one point a shaft has been sunk to open up the ore. The quartz formed quite large crystals before the sulphides were deposited, and on breaking the ore the six-sided cross sections of the prisms are well marked. No very large amount of ore was to be seen, and the deposit does not seem to be of great importance so far as the present development work goes.

There is a small opening near a blacksmith shop a little east of the east bay of Trout lake, also on similar dark-green eruptive-looking rock, but even less ore is to be seen here than in WD 252. These small ore-bearing veins are found in the adjoining sediments or in greenstones connected with them and not in the nickel-bearing eruptive itself, but the eruption of the latter may have some connection with the formation of the deposits.

A very good section of the contact of the acid edge with the sediments is exposed on a small peninsula projecting from the south shore of Trout lake where the lumber road reaches the water. Two or three islets to the north show the nickel-bearing eruptive in its usual phase along the southeast edge, while the peninsula ends in a conglom-

Digitized by Google

erate having apparently two kinds of matrix, fine-grained green material containing epidote and quartz and rather coarse reddish or grayish quartzite, both including many small and large pebbles of granular quartzite and of granite. Irregular projections of the acid edge granite penetrate the conglomerate for 100 yards or more. Next to the southeast is a narrow range of precipitous hills of hard splintery cherty-looking brecciated rock, then comes a breccia of a less cherty kind with, however, a few granite boulders, probably the base of the tuffs. The section described is about 1,200 feet in length. Still farther to the southwest are the usual tuffs, less flinty and unaffected by the neighborhood of the eruptive.

Wisner Township

The basic edge of the eruptive runs almost due east from the northern side of lot 12 in the third concession to lot 4 in the township of Wisner, and then bends to the southeast toward Vermilion river and Norman township. The portion up to lot 4 has been surveyed as locations, but prospectors seem to have found no ore along the rest of it. This part of the nickel range is best reached by lumber road to Frenchman's lake and then by a canoe route to Joe's or Marion lake which crosses the nickel-bearing eruptive diagonally. The two Frenchman's lakes are in the sedimentary rocks, the south end being enclosed in the soft black slaty variety of the tuffs, but moraine materials hide the bed rock as one crosses to Joe's lake.

The basic margin of the nickel-bearing eruptive has the usual characters north of Joe's lake, the boundary to the north being Laurentian and a swampy valley running at its foot with low hills of norite to the south. Not much gossan or ore is to be seen in the locations across this township, though considerable showings occur on WD 16 and WR 14 near the head of the lake.

The acid edge is very well shown on Joe's lake, which it crosses near the south shore, and the bare surface of the rock near a small lake to the southwest gives an uninterrupted section across the boundary. The edge of the eruptive is granitic-looking and seems to blend into a conglomerate with a fine-grained crystalline ground-mass which might be taken for granite containing small and large boulders of granite, often with vague edges. This conglomerate is penetrated by indistinctly bounded projections from the eruptive and seems to have been greatly recrystallized in consequence of its presence. About 360 feet to the south the conglomerate has a ground-mass suggesting arkose or quartzite with a few pebbles of granite, and this dips beneath the small lake.

A parallel section on the shore of Joe's lake shows a similar conglomerate followed by breccia-like tuffs at a distance of 400 feet south of the acid edge, but with a few feet of a fine-grained green-gray rock without pebbles between.

The eastern side of Wisner township is most easily reached from the Vermilion river near Dawson, and a canoe route leads across from the second Frenchman's lake to this point. The rock showing between the two lakes is mainly tuffs, but half a mile west of Dawson a large dike of diabase rises beside the trail, perhaps the continuation of a dike found by Mr. Culbert on Onwatin lake about two miles southeast. Near Dawson gravel plains and muskegs cover the rock along Vermilion river, but the norite forming the northern edge of the eruptive is found rising as hills a mile west of the upper end of Bronson lake, near a small lake at the corner of lots 3 and 4 in the fourth concession of Wisner township. At the boundary the norite leans against a Laurentian hill, but no ore or gossan was to be seen; and similar relationships are found to the northeast towards Vermilion river, but gravel terraces hide the rock nearer the river.

Near the head of Bass lake, the next expansion of Vermilion river south of Bronson lake, the acid edge shows itself with the usual metamorphosed conglomerate to the south, here having a width of 800 feet before the tuffs are encountered.

Norman and Capreol

The boundaries of the nickel-bearing eruptive in these townships were mainly fixed by my assistant, Mr. Culbert, and the following account is given in his own words:

"The northern nickel range makes a sharp turn in the township of Norman, its outcrop there assuming a southward direction. In the northern concessions of Capreol township another change in direction is found, the strike being northwest and southeast to Massey creek as far as it was followed. The line of outcrop of the basic edge, owing to its comparatively rapid weathering, determines the position of a narrow valley from the Whistle property to Massey creek. This valley widens in many places, often containing lakes which conform to the strike of the eruptive. Examples are lakes Selwyn, Waddell, Ella and Clear.

Digitized by Google

"The basic phase along this part of its outcrop resembles the norite of the northern range, being a light mottled gray and is comparatively narrow. Darker phases occur in spots and resemble the rock at the Blezard mine, but the few small patches found near Moose lake are easily overlooked. Many peculiar contact varieties are found such as the poikilitic kind near the Blue lake ore deposit, which to the eye appears quite coarsely granular, but is found under the microscope to consist of large aggregates of feldspar optically continuous with inclusions of bi-silicates. The transition to the micrographic phase takes place within a short distance, and the total width of outcrop of the eruptive is a minimum in the townships of Norman and Capreol, being but little over a mile as a rule. The micropegmatite is of the usual flesh-colored rather coarse-grained variety found in the northern range and corresponds in mineralogical composition.

"On the east side the eruptive is in contact with Laurentian granite and gneiss. The granite is pinkish-red, with abundant quartz and few of the dark minerals in places where the acid magma has not incorporated inclusions and masses of earlier rocks. In many parts hornblende porphyrites and green schists occur, often running out in basic bands into the acid material and forming gneiss, or again occurring as immense blocks or large masses of considerable area which the action of the erupted material failed to shatter. A large mass of this kind occurs half a mile south of Moose lake near the small marsh on the road to Blue lake.

"The acid phase to the west comes in contact with the usual conglomerate, highly indurated with well-rounded pebbles and boulders of granite, greenstone, schist and quartzite. On passing westward this rock becomes softer and tufaceous, with no large boulders showing.

"A large diabase dike of great width, in some places a few hundred paces, was found in the valley of Massey creek on the boundary of Capreol and Maclennan townships in the third concession. It also outcrops on lot 5 in the fourth concession of Capreol on the shore of the small lake on the line between lots 5 and 6. This is probably the same dike that crosses lake Onwatin and which apears on lot 8 in the second concession of Wisner near the southwest post, the outcrops all being in a nearly straight line. The rock has a distinct green color due to a considerable content of olivine.

"Wherever the contact between the norite and the Laurentian appears on the surface indications of ore are found, either in thin patches of gossan or outcrops of ore bodies. Sulphide particles can be found on the contact wherever the rock is tested, and the red gossan product is present along its entire length in the townships near lake Wahnapitae. The more important outcrops of ore occur near Blue lake and south of it near the small Moose lake. On the shore of Blue lake the diamond drill has proved the existence of a body of ore, strongly magnetic and of some size. The outcrop near Moose lake shows a band of ore following the contact and varying in width from two to six feet of fairly good sulphides. In the test pits this ore appears rather lean, being mixed with some of the mother magma, but the proposition looks promising, having in view the improvement of transportation facilities. Further north, strong local attractions are found on the north end of Ella lake near the west side of WR 2, but no test pits have been opened to prove the existence of an ore body. The east side of Clear lake near the shore shows a few test pits with ore and a considerable extent of gossan.

"Leaving the Whistle property going westward the contact is found forty paces north of the northwest corner post of lot 7 in the fourth concession of Norman. The ground succeeding is low and drift-covered for nearly a mile, with no outcrops of the basic edge till near the line between lots 9 and 10, where the contact shows with a test pit and gossan 210 paces south of the northwest corner post of lot 9 in the fourth concession. To the west this outcrop is followed to low ground again with gravel deposits, but the norite outcrops south of the northwest corner post of lot 10 in the fourth concession at 410 paces. On following the uncut line half a mile to the west between lots 11 and 12 north from the post at the south boundary of the fourth concession a small test pit in a body of ore was encountered at 1940 paces. The Laurentian here contains good-sized bands of green hornblende schist like that which accompanies the Hutton magnetic ore deposits. The Laurentian was also found 1010 paces north of where the boundary of Wisner and Norman crosses the Vermilion river in concession four."

The acid edge of the eruptive was traced last summer southward through Norman and Capreol to the sand and gravel plains which hide the bed rock in Garson township; and the relationship of the eruptive to the overlying sediments was the same as has been described in other townships. A good exposure of

Digitized by Google

the contact is seen on the road north from Dawson toward Moose mountain where, as one advances, the tuffs take on the character of conglomerate, and then of boulder conglomerate with a felsitic ground-mass before the edge of the eruptive is reached. In general, the ridges of tuffs and conglomerate, as well as of the eruptive, run north and south at this eastern end of the range, evidently conforming here as everywhere else to the direction of the line of contact, showing a close relation between the dips and strikes of the overlying sediments and the line of outcrop of the basin-shaped eruptive sheet.

No ore deposits are known on the acid edge at this end of the nickel belt, but a so-called nickel mine was found not long ago at the east end of Onwatin lake in black slate. Two openings made here show only iron pyrites.

Acid Edge of South Range

The norite edge of the southern nickel range has attracted great attention because of its ore deposits, but very little work has yet been done in the way of tracing the acid edge. As far as time would permit characteristic sections across the southern range were examined for the sake of comparison with the northern range, the sections chosen being near Whitson (or Blezard) lake and between Murray mine and Azilda, both of which were examined years ago by Dr. T. L. Walker (5).

The section examined near Whitson lake followed the road toward the northeastern settlements, along which there are numerous outcrops of rock, instead of the shores of the lake itself where Dr. Walker had worked. The basic edge at Blezard mine is of the typical sort for the southern range, consisting of dark-gray norite with bluish quartz and some plates of biotite; unlike the paler gray rock common on the basic edge of the northern range, where bluish quartz and biotite are not conspicuous. A wide swamp intervenes between the outcrops near Blezard mine and the hills to the north, where rock once more appears; and the character of the rock is still that of norite, though coarser in texture and paler in color than at the mine. After a short interruption of pale flesh-colored, fine-grained rock, either a dike of granite or a mass of metamorphosed quartzite, a coarse flesh-colored to gray variety of the eruptive is again encountered, either a syenite or diorite in appearance. A sharp hill of reddish gneissoid rock rises just beyond this, possibly another band of later granite, though it is sheared into a distinct gneiss. Next comes a dark flesh-colored variety of the eruptive, suggesting syenite, but proving under the microscope to consist mainly of pegmatite with much quartz. Coming down to lower ground near the northwest end of Whitson lake a darker gray rock, sometimes gneissoid, represents the acid edge of the eruptive and stands in contact with the sediments.

At the edge there is a narrow band of conglomerate containing pebbles and boulders of quartzite, granite, and perhaps other rocks, with some green chlorite schist, partly as matrix and partly without pebbles. There has been a good deal of crushing along the margin of the eruptive, and the relationships are not always clear, but the strike is about 60 degrees with a dip of 35 degrees to 55 degrees to the southeast, as if the eruptive had overturned the edge of the sediments. Beyond the contact tuffs of the usual kind are found at various points along the road.

Except for the granite or gneiss interruptions in the eruptive and the narrowness of the band of conglomerate between it and the tuffs, the relationship is like that found in various places on the northern range.

As the eruptive with its varieties along the railway between Murray mine and Azilda has been described in some detail by Prof. Walker (6), little need be said of it here, except that it conforms to the types found near Blezard and is penetrated by irregular dikes and masses of flesh-colored granite.

The acid edge is found half a mile east of Azilda station, where a road turns north, and has the appearance of reddish syenite greatly broken and sheared, as exposed on a cliff to the east of the level farm land. Some lower points consist of gray gneissoid rock with much mica, probably the extreme edge of the eruptive, but passing wthout any marked break into what is probably rearranged quartzite or arkose, evidently sedimentary. The latter rock crops out at various points on the road to the north; and a less modified arkose stands out of the clay flat as a sharp hill nearly a mile northwest of Azilda. Beneath the arkose is chloritic slate or schist with some flattened boulders, striking N. 15 degrees to 30 degrees E. and dipping about 20 degrees toward the east.

At the northeast end of Whitewater lake the acid edge takes the form of a somewhat reddish-gray, distinctly gneissoid rock, but the adjoining sediments are hidden under swamp and clay. A

(5) Quar. Jour. Geol. Soc., Vol. LIII. (1897), pp. 47-56.

(6) Ibid, pp. 47-54.

Digitized by Google

promontory on the north side of the lake two miles west shows none of the eruptive, but must approach closely to the edge. Here schist conglomerate rises out of the water having a strike of about 40 degrees east of north and a dip of 35 degrees to 45 degrees to the southeast. It includes many boulders of arkose or quartzite and perhaps also granite in a matrix of chloritic or biotitic schist. Less than a quarter of a mile to the north is a hill of characteristic tuffs containing many angular pebbles of other rocks, and the point on the north shore of Whitewater lake may represent a basal conglomerate of the tuffs, like that so often found at the edge of the northern range. A curious feature of the schistose margin of the sediments at all three localities is the dip to the southeast. This may however, represent only the schistose structure, resulting from squeezing at right angles to this direction; and the real strike and dip may be quite different.

In general, it may be said that the acid edge of the eruptive is more broken by dikes of granite, etc., on the southern than on the northern edge, and the adjacent sediments have been more profoundly acted on, resulting in the production of schists. The regular boulder conglomerate found at the northern edge appears to be thinner and less constant along the southern edge.

Basin of the Eruptive

In connection with the study of the nickel-bearing eruptive numerous observations were made of the rocks within its boat-shaped synclinal basin; and the results may be brought together here. These rocks have attracted attention since the nickel region began to be studied geologically because of their unlikeness to the ordinary Huronian rocks of northern Ontario. Dr. Bell in his 1890 report (7) gives brief descriptions of the rocks; and Prof. Walker mentions them also in the paper previously referred to. Numerous references have been made to them in reports of the Bureau of Mines (8), but no detailed study has been made of them, so far as can be found in published accounts. Dr. Bell's map divides the rocks of the basin into "dark argillaceous and gritty sandstones with shaly bands, possibly Lower Cambrian," and "black silicious volcanic breccia with black slate in some parts"; and in his report he comments on the unchanged character of the upper sandstones, which he clearly considers much later in age than the Huronian rocks around.

Dr. Barlow however in 1902 (9) regards these rocks as belonging to the same system with the Huronian slates and quartzites.

Nature of the Sediments

Our study of the rocks occupying the basin shows that in most places along the northern range the next rock to the acid edge of the nickel-bearing eruptive is a coarse conglomerate of granite boulders up to several inches or a foot or two in diameter, cemented by finer grained granitic or gneissic looking material, perhaps a metamorphosed arkose. Next to this may come a thin band of white quartzite or arkose; then a gray quartzitic or cherty rock with many fragments of dark-gray or white chert and sometimes pebbles of quartzite and granite.

Tuffs

Beyond the different phases of conglomerate, which may have a width of 1,500 feet or less, comes the vitrophyre tuff which has attracted so much attention, and dark gray or black rock on fresh surfaces, but weathering brown or pale-gray or almost white. On fresh or not too much weathered surfaces the rock is seen to be largely a breccia of angular fragments of dark or pale-gray materials in a compact black basis. Thin sections show that the fragments consist often of chalcedony or of serpentine. Occasionally pebbles or large rounded blocks of chert, quartzite or granite are imbedded in the breccia, showing that at least some ordinary detrital materials joined the rain of volcanic ash and lapilli which is supposed to have fallen into the sea when the rock was formed. Undoubtedly, however, most of the constituents of this curious rock have come from explosive volcanic eruptions on a very large scale.

The boundary between the tuffs and the conglomerate beneath is not usually sharp, but the transition takes place more rapidly in some places than in others.

The width of the tuffs was not determined by us in many cases, but in two instances we found them at least a mile and a half wide, and were not sure even then that we had covered the full width. Although they were almost certainly deposited in water, marks of stratification were not observed with sufficient

(7) Geol. Sur. Can., 1890, Rep. F., p. 11 and pp. 22-24.

(8) Rep. 1903, p. 291, etc.

(9) Summary Rep. Geol. Sur. Can., 1902, pp. 255-6.

Digitized by Google

clearness to determine strike and dip, but the direction of the sharp ridges in which the rock now stands is always parallel to the edge of the nickel-bearing eruptive. As the dip is not known, the thickness cannot be reckoned with any certainty.

Slates

The hard variety of tuffs which forms sharp hills and precipices seems to pass gradually into a softer, slaty variety with a well-marked cleavage. In this the fragments are flattened, giving a spotty look to the cleavage surfaces, and none of the cherty or chalcedonic material is present. This again passes into ordinary black slate with a good cleavage across the planes of sedimentation as shown by a slight banding. As the slates are the softest of the sediments they have undergone more destruction than the other rocks, and so are often drift-covered when the tuffs and sandstones rise as ranges of hills. Specimens of the slate have been proved to contain 6.8 per cent. of carbon, and they should probably be considered as ordinary muddy sediments originally charged with organic matter. This rock is so poorly exposed that in many places one can only infer its presence under the sheet of drift along the rivers.

Sandstones

The sandstones or arkoses, sometimes spoken of as graywackes, form the uppermost rocks of the basin, and are widely exposed, since they are more resistant than the slate and stand up often as sharp ridges rising 50 or 100 feet above the plain. These rocks are rather dark-gray and vary in texture from very fine-grained material, almost slate, to coarse arkoses, in which there are rounded fragments of quartz and feldspar as large as a pea, or rarely small pebbles. In a general way, they are very uniform over the central tract of the syncline, but have at any given point considerable variety. Occasionally black bands of slate occur in the sandstone, bringing out distinctly the stratification, but more often the direction of the bedding is obscure, though the general course of the ridges may be supposed to represent it. Occasionally in the finer grained varieties there is a distinct cleavage, which must not be confused with stratification.

The points at which the sandstones can be most easily studied are Larchwood toward the northwest side of the syncline, and Chelmsford toward the southeast side, both stations on the Canadian Pacific railway.

At Larchwood the banks of Vermilion river and the hilly country to the north and west of the village give excellent outcrops. To the north there are several parallel ridges of the rock striking 45 degrees to 50 degrees, and having a dip of 20 to 30 degrees to the southeast. The ridges are steep toward the northwest and slope about as the rock dips. Quartz grains, a little mica, and small pebbles show on weathered surfaces; and finer grained parts, greenish-gray in color and banded lighter and darker, are sometimes greatly crumpled. A mile west of Larchwood along the railway, where the ridges trend 35 degrees, the dip as shown by slaty layers is only 10 degrees to the southeast, but a slaty cleavage has a strike of 55 degrees and a nearly vertical attitude. Some large angular fragments of fine slaty or compact texture are enclosed in the arkose, one mass having diameters of five by seven feet, but the slaty cleavage runs through both.

Large oval concretions of impure carbonate of lime are common in certain beds, weathering more rapidly than the surrounding rock and so forming slight depressions. In appearance on fresh surfaces the concretions do not seem to differ much from the rest. About a mile and a half west of Larchwood the sandstones are covered with stratified sand, and the next rock exposed, near Phelan about two and a half or three miles beyond, is vitrophyre tuff.

Going east from Larchwood, the rock is well exposed at the falls of the Vermilion near the railway bridge, where the river, running southwest, has cut a small canyon between ridges and then suddenly turns off to the southeast across the ridges. The strike is here 55 degrees or 60 degrees and some black slaty layers dip 45 degrees to the southeast. Two miles to the east the sandstone strikes 70 degrees, and dips 30 degrees to the northwest, while an indistinct cleavage is about vertical. Four miles east the bedding seems to be nearly horizontal, as shown by slaty layers, but rather high and sharp ridges rise above the clay plain about parallel to the imperfect slaty cleavage; which at Chelmsford, six miles to the east, has a strike of 60 degrees. Concretions are prominent features again at Chelmsford, and a stone quarry west of the village gives good exposures of the rock, but the stratification seems too uncertain and irregular to settle a general direction of dip.

Digitized by Google

About two miles northwest of Chelmsford a quite high and continuous ridge of sandstone rises above the flat clay land with a strike of 35 degrees or 40 degrees, but with a cleavage running 60 degrees. Here too there are some concretions and slaty layers, in places coarser and finer materia's showing contortion or swirling forms.

It may be said in a general way that the sandstones have the synclinal attitude, dipping southeast on the northwest side and northwest on the opposite side; but there is much irregularity in the arrangement, accompanied by a good deal of faulting and much squeezing and twisting of the slaty layers.

About four miles northwest of Chelmsford diabase penetrates the sandstone near its junction with the black slate, the only instance of the kind observed in these rocks, though large dikes of diabase occur in the slates and tuffs near the northeast end of the basin.

The data are not sufficient to estimate the thickness of the three main sediments of the syncline, the tuffs, slates and sandstones; but the total must represent several thousand feet, since the basin is ten miles wide between Whitewater lake and the inner edge of the eruptive sheet in Morgan township, and the dips run from 10 degrees to 45 degrees. If the average width of 8 miles is taken, and a dip of 30 degrees is assumed, the total thickness of the sediments will be over 10,000 feet, probably not at all an over-estimate. There may of course be more or less reduplication of strata by faulting, though evidence of faulting on a large scale has not been observed; but on the other hand the loss of thickness by erosion, which must have been very great in formations so old and so long exposed, may more than counterbalance it.

The River Systems

The relation of the rivers to the three main varieties of sedimentary rocks in the basin was noticed by Dr. Bell in the course of his survey (10), and deserves notice here. The Vermilion river, which is the most important, between Wisner and Norman townships, comes almost due south, with a nearly straight course between banks of slightly auriferous gravel, passing through a wide gap in the tuff ridges, and swinging southeast to Onwatin lake in the black slate. Upto this it has been a swift river with numerous rapids, but from Onwatin lake toward the southwest it changes its habit, flowing in a very meandering channel with gentle current between banks of clay and silt in the drift deposits overlying the slate among the northwestern edge of the sandstones. Near the northwest corner of Balfour township it is joined by another large stream, the Onaping, which after tumbling as violent falls and rapids over the tuffs turns northeast along the slates until it meets the Vermilion.

After the junction the Vermilion turns into the sandstones and passes through a series of rapids at Larchwood, then resumes its course southwest of Vermilion lake, which counterbalances Onwatin lake at the other end of the syncline, as noted by Dr. Bell, and flows out eastward once more along the band of slate; then doubles to the southwest, and finally escapes to the south across the tuffs and nickel-bearing eruptive near the boundary of Creighton and Fairbank townships. At its second sharp bend southwest it is joined by another considerable tributary, Whitson creek, coming from the northeast and following for miles the strike of the band of slate. The three most important streams of the district, when they escape from the tumult of their descent through the other rocks, wind gently in broad curves as soon as they reach the soft slates, and keep to the strike of the slate as long as possible.

As Dr Bell points out, there are many tributary streams pouring into the Vermilion and Onaping from the north, mostly with very rapid courses through rocky channels, but no tributaries of any magnitude join them in the flat lowlands of the interior of the syncline. The control of the watercourses by the ancient rocky structure of the country is very strikingly brought out in this region, as will be seen from the example just given.

(10) Geol. Sur. Can., 1890-91, p. 18F.

Digitized by Google

Petrographical and Stratigraphical Notes

Nickel-bearing Erupt ve

The nickel-bearing eruptive has already been studied at a few points in a somewhat detailed way, especially by Profesor Walker (11), and Dr. Barlow (12); but the rock is so important in its geological and also its economic relationships that a much more complete study is desirable. Professor Walker first recognized that the band of basic rock associated with the nickel ores of the region passed into a micropegmatitic rock and became much more acid on the edge opposite to the ore bodies, a section from the Murray mine to Rayside (now Azilda) being taken up in detail to bring this out, and another section from Blezard mine along the shores of Whitson (or Blezard) lake supplementing it. He also made the important fact clear that in the Windy lake region fifteen miles to the west of the Murray mine section, the arrangement is reversed, the basic edge being on the northwest side of the band, and the acid edge on the southeast. A series of analyses of rock specimens from the Blezard mine and Whitson lake brought out very clearly the chemical change in the eruptive on passing from the outer to the inner edge (13), the silica contents of the basic edge amounting to only 49.90 per cent., while two analyses from near the opposite edge showed 69.27 and 67.76 per cent. respectively.

In my last report on the Sudbury region the nickel-bearing eruptive was briefly described, Dr. Walker's views being confirmed, and the suggestion was made that the two bands of nickel-bearing eruptive joined at the ends, as a continuous belt, and that it probably formed an immense laccolithic sheet of synclinal form, with tuffs and ordinary sediments enclosed within it (14). The past summer's work has made this conclusion practically certain by connecting up the northern with the southern nickel range and actually following the eruptive belt from point to point, except where drift-covered, through the whole northern part of the area.

The edges of the boat-shaped eruptive sheet are everywhere in eruptive contact with the rocks above and below along the northern side, and probably also on the southern side except where later granites have come up between its basic edge and the rocks below.

Although the outcrop is continuous, its width varies greatly, being four miles or a little more along some parts of the southern range, as near the Creighton mine, but scarcely one mile in width at one point on the northern range near the northeast corner of Morgan township; and in general the southern side of the band averages wider than the northern. With the narrowing of the band as a rule the number and importance of the ore deposits along the basic edge diminishes, until, as in Morgan township, there may be miles of the edge without ore deposits or even a stain of gossan. The appearance of the rock in these narrowest parts is paler gray and less basic than at wider parts, so that in Dr. Bell's original map of the region they are not separated as bands of greenstone. Apparently, the differentiation of the magma was not carried so far where the thickness is less, or else the thickness is less because we are approaching the feather edge of the great sheet of rock, and the basic parts did not extend so far but might be found by sinking to a sufficient depth a mile or two in from the edge.

In Dr. Barlow's account of these rocks, which he groups under the convenient field term, greenstone, three varieties are distinguished, norite, diorite and amphibolite; the norite being the original form, and the other two representing a less and a more advanced stage of alteration. The norite is described as passing into micropegmatite and finally into a usually gneissoid rock, gray with paler phenocrysts, weathering flesh-colored, and consisting mainly of quartz and an acid plagioclase about which radiating pegmatite occurs, with some orthoclase and biotite or less often hornblende (15). His excellent account corresponds well with my own results for the southern range near the best known ore deposits; but the sections made in the northern range and in the southwest end of the southern range, near the bend connecting it with the northern range, show rocks and relationships differing in important ways from those described by Walker and Barlow.

A few of these sections will be taken up with more or less detail, beginning at the southwest corner of the area.

(11) Quar. Jour. Geol. Soc., Vol. lIII. (1897)

(12) Geol. Sur. Can., Summary Rep., 1902. pp. 256-260.

(13) Quar. Jour. Geol. Soc., lIII., p. 56.

(14) Bur. Mines, 1903, pp. 276-7.

(15) Geol. Sur. Can., Sum. Rep., 1902, pp. 259 and 60.

Digitized by Google



Nickel Eruptive, Windy lake.



Weathering of Nickel Eruptive; mouth of Moose Creek.

Digitized by Google

UNIV. OF MICH.

Digitized by Google

Strathcona nickel mine.

Big Levack nickel mine.

Digitized by Google

UNIV. OF MICH.

Digitized by Google



North Star nickel mine, October 1903.

Digitized by Google

UNIV. OF MICH.

Digitized by Google



No. 3 or new roast yard, Canadian Copper Company.

Digitized by Google

UNIV. OF MICH.

Digitized by Google

Sultana Mine—Fairbank Lake

The nickel-bearing eruptive is fairly well exposed for a width of about three miles and a half between Sultana mine and the north end of Fairbank lake in the townships of Drury and Fairbank, though drift deposits cover much of the section southwest of the lake. Near the Chicago mine, but a quarter of a mile to the north, the basic edge of the eruptive shows against rocks having the appearance of Huronian schists and eruptives. It is here a rather dark gray dioritic-looking rock of medium grain, quite different in appearance from the very dark, almost black, variety seen near Murray mine, not only as to color but in the lack of the blue quartz blebs, and the large scales of biotite so characteristic farther east.

A thin section might easily be taken for one of diorite, since it consists mainly of plagioclase and hornblende with smaller amounts of quartz and biotite and possibly some orthoclase. However, the hornblende is clearly secondary in most cases, and one mass of it encloses some hypersthene. The plagioclase tends to form elongated strips or broad plates slightly suggesting the ophitic structure, and the small amount of quartz is interstitial with a hint of pegmatitic intergrowth. The lighter gray color of the rock as compared with examples farther east is at least partly due to the absence of the minute brown particles darkening the plagioclase in the latter case.

A paler gray rock 600 paces south of Fairbank lake on the trail from the Chicago mine, about half a mile from the previous outcrop, differs little from the rock just described except in the presence of a considerable amount of micropegmatite around the well-shaped elongated crystals of plagioclase.

On the southwest bay of Fairbank lake a dark green schistose rock, taken at first for a hornblende schist included in the eruptive, is probably a sheared representative of the last rock, consisting now of quartz, orthoclase, plagioclase and green hornblende crushed and rolled out, some larger feldspars occurring as rounded grains enclosed in "mortar" of quartz and smaller particles of feldspar.

Two points on the west shore of Fairbank lake consist of somewhat schistose greenish-gray rock flecked with flesh-colored feldspars, containing, as seen under the microscope, large feldspar masses, mainly orthoclase, and an acid plagioclase, so far as their weathered condition permits a determination, with crushed quartz and feldspar between, and a large amount of a mineral like epidote, not in small scattered crystals, but as considerable areas made up of several individuals, crowded together. This mineral has in part a faint dichroism, pale-green and gray, and a small extinction angle, and should probably be referred to epidote, though it resembles the woehlerite determined by Professor Walker in the Onaping nickel-bearing eruptive.

At the north end of the northwest bay of Fairbank lake east of the portage from Vermilion lake, near the edge of the eruptive against the tuffs, the rock is once more dark gray-green, very slightly specked with a flesh-colored mineral. It is very fine-grained and sometimes slightly schistose. Thin sections show that it is less sheared and crushed than the rocks to the south, and contains in spite of its dark-green color a large amount of quartz and feldspar in the form of exceedingly fine micropegmatite, as usual radiating from plagioclase crystals. There is probably some orthoclase, and hornblende occurs, though chlorite is the chief dark-colored mineral, giving the tone to the rock. An analysis given later shows that it is rather basic granite or a grano-diorite.

The inner edge of the eruptive at Fairbank has the appearance of being less acid in character than in most places, perhaps because adjacent portions of the tuffs have been dissolved in them. Shearing or squeezing has been a very marked factor in the region, especially toward the middle of the eruptive band, and has given opportunities for weathering to an unusual degree, accompanied by the formation of chlorite, masking the real color. The analysis of this rock, made by Mr. Ardagh, shows 68.95 per cent. of silica, so that it is not so basic as its dark-green color would suggest.

No complete section has been examined at the extreme southwest end of the basin, though specimens were collected near the Sultana mine and in the township of Trill to the north near Ross lake. Where the northern and southern ranges converge there seems to have been a good deal of faulting so that the eruptive is confusedly mixed with metamorphosed sediments, such as arkose, the mixture a quarter of a mile north of the Sultana being breccia-like. The norite rising as a hill to the east of the Sultana camp is much like the weathered edge described near the Chicago mine; but a little north of the Sultana the rock is of a different type, consisting of masses of hornblende with a little biotite enclosing white areas of plagioclase made up of many small crys-

Digitized by Google

tals crowded together. These crystals are oval or short prismatic, and are sometimes untwinned, sometimes divided into halves, and sometimes of more complicated twinning; the extinction angles suggesting varieties from andesine to labradorite. The origin of this structure is not clear, but similar sections have been got from near Joe's lake in Wisner township and near Murray mine.

The acid edge varies in appearance. On Ross lake and another small lake to the north it is medium to coarse in grain and grayish flesh-colored, consisting chiefly of quartz, plagioclase and a little orthoclase, the quartz belonging mainly to the micropegmatitic outgrowths round sharp-edged plagioclases, but some forming clear separate blebs. A little hornblende and chlorite darken the color of the rock.

Specimens collected half a mile northeast of Ross lake, of a dark green-gray color with feldspar strips suggesting the ophitic structure, were at first taken for a dike or boss of a different rock; but thin sections prove to contain much micropegmatite so fine in texture as to be visible only with fairly high powers of the microscope. This may surround long slender, clear-cut plagioclase crystals or may form radiating masses with a rude black cross in polarized light, without any apparent nucleus.

Onaping-Windy Lake

The best section for the study of the northern side of the nickel-bearing eruptive is undoubtedly that along the Canadian Pacific railway between Phelan and Windy lake sidings, where numerous small rock cuttings expose the tuffs with their underlying conglomerate, the acid edge of the eruptive, its basic edge, and the Laurentian gneisses beyond. Taken at right angles to the strike of the belt of eruptive rock its width is nearly three miles. Rocks collected at different points on the section have been studied and described by Prof. Walker, (16), but it is worth while to refer to this section more in detail.

Going eastwards along the railway from Windy lake siding Laurentian is seen for a quarter of a mile, when drift and an esker ridge cover the rock for a distance. At the northwest end of Windy lake gray, dioritic-looking norite crops out, rather coarse and speckled in appearance, consisting, as seen under the microscope, mainly of plagioclase, hypersthene and augite, with a little quartz, biotite, and hornblende, many prisms of apatite and some magnetite. The plagioclase, which is clear and colorless and makes up about half of the rock, has extinction angles corresponding to andesine or labradorite, and is generally hypidiomorphic; while the hypersthene is idiomorphic. This mineral presents some anomalies, since some crystals showing the usual pleochroism, red, brown, pale brownish green and pale yellowish, have parallel extinction, while others extinguish at various angles up to 28 degrees. Diallage, brown and fibrous-looking, non-pleochroic, and with an extinction angle of about 45 degrees occurs in small quantities also; the small amount of hornblende present forms margins about the minerals just mentioned; and the brown biotite is present only in trifling quantities.

A specimen from a cutting a hundred yards east is coarser grained and not quite so fresh, but does not differ greatly in composition. An analysis of this rock given later, shows 56.89 per cent. of silica, considerably more than Professor Walker found in norite from Blezard mine on the southern range.

Fifty yards farther east coarse red syenitic-looking rock begins and lasts to Onaping station, showing in various cuttings. Thin sections prove however that the rock contains a large amount of quartz mostly pegmatitically intergrown with feldspar, but partly as fairly large clear spaces, so that it is too acid for syenite, and an analysis given later confirms this by showing 68.48 per cent. of silica. The feldspars are very badly weathered, but the well formed crystals making the starting point for micropegmatite seem to be all plagioclase, though the analysis proves that potash and soda are present in about equal amounts, (K_2O 3.36, Na_2O 3.72), so that the feldspar in the pegmatite must be chiefly orthoclase. The dark minerals include secondary looking hornblende and the mineral resembling epidote named by Professor Walker woehlerite. The last specimen collected to the west of Onaping station has extraordinarily slender prisms of feldspar, which strike the eye immediately on fresh surfaces.

To the east of the station the appearance of the rock changes and it becomes greenish gray and finer grained; though the microscope shows little difference except the presence of more hornblende. An analysis proves that this rock is less acid than the red variety west of Onaping, since it contains only 61.93 per cent. of silica.

At the margin of the eruptive against the basal conglomerate beneath the tuffs, it becomes finer grained, though still green and dioritic-looking; and thin sections show short, stout crystals and

(16) Q. J. Geol. Soc., Vol. lIII., pp. 36-59.

Digitized by Google

little micropegmatite, the quartz, which is present in considerable amount, being mostly granular.

Sections to the Northeast

Two miles north of Onaping at the outlet of Moose creek into Onaping river there is an interesting slope of gray rather coarse-grained nortie, rapidly weathering into boulder-like forms, the loose sandy and gravelly debris sometimes still supporting the round boulders of less decayed rock. Thin sections show the typical nortie of the nickel range, consisting of a small amount of quartz, partly pegmatitic, much labradorite, a little apparent orthoclase, and a large amount of pleochroic augite very like hypersthene, but seemingly monoclinic with various extinction angles. Secondary hornblende and a small amount of biotite and magnetite complete the dark minerals. The plagioclase is largely idiomorphic and is sometimes partly enclosed by the augite, which also tends to idiomorphy, so that the order of succession is plagioclase, augite, quartz and pegmatite, the plagioclase and augite overlapping.

A rock found at the basic edge of the nickel-bearing eruptive a little east of the Big Levack mine on the eastern side of Levack township is very similar, except that the pyroxenes are almost completely changed to dull-green fibrous hornblende, and that biotite is present in larger quantities.

A specimen from about a mile and a half southeast of the last locality near or the acid than the basic edge is coarse-grained and flesh-red in color, and consists as shown by the microscope mainly of micropegmatite and a little hornblende and biotite.

At the acid edge of the eruptive near the shore of the southwest bay of Moose lake the rock is fine-grained and flesh-colored with greenish patches. The freshest specimen is made up of plagioclase in well formed crystals (oligoclase to andesine) to the extent of one-half, the spaces being filled principally with quartz of a granular look and seldom showing pegmatitic structure. The dark minerals are chlorite filling interstices, and biotite, the latter in very small amounts. Close to this phase of the eruptive are rather coarse rocks also flesh-colored spotted with green, which in the field were collected as the altered edge of the basal conglomerate which underlies the tuffs. Thin sections however show very little difference in composition or character from the rock described above. One of the hand specimens contains a few black fragments of some other rock, and has a patch of coarse red feldspar mixed with quartz, which seems to have been deposited in a cavity of the rock. In the field the vague forms of pebbles and boulders resembling granite can be seen, and it is probable that the ground-mass of the conglomerate has been so long exposed to the heat and circulating solutions of the acid edge of the eruptive as to become completely recrystallized into quartz and feldspar.

In the eruptive itself near the acid edge and also in the metamorphosed conglomerate there are small vugs or enclosures surrounded with very red feldspar and enclosing hornblende and epidote. The space is sometimes completely filled and sometimes partly vacant.

Specimens taken from the basic and acid edges of the eruptive at about its narrowest point, in the northeast corner of Morgan township show little difference to the eye, though the one from the acid edge has a faint tinge of flesh-color which is lacking in the other. Thin sections show considerable differences however. One from the basic edge contains mainly feldspar with micropegmatite radiating from it, augite, hornblende and chlorite, the feldspar being largely plagioclase not far from andesine in optical characters, but with some untwinned crystals, probably of orthoclase, and one peculiar crystal, unstriated but containing irregular patches of plagioclase having low extinction angles from twin planes. Micropegmatite running into areas of unmixed quartz makes about a fourth of the section. The augite, partly very fresh, is nearly colorless and not appreciably pleochroic. The rock has not the usual character of the basic edge, being without hypersthene (or pleochroic pyroxene) or biotite among dark minerals, and containing a good deal more than the usual proportion of micropegmatite and orthoclase. One might almost hold that the true basic edge is absent at this narrow portion of the eruptive, and that the rock just described belongs rather to the intermediate facies between the basic and acid edges.

A thin section from the opposite or southeast side of the band consists mainly of very fine, often plumy, micropegmatite, sometimes arranged round broad crystals of andesine, sometimes about a narrow strip or about no apparent nucleus. This makes up at least two-thirds of the rock, while plagioclase and a crystal or two of orthoclase with hornblende and a small amount of the supposed woehlerite make up the rest.

Near Trout lake in Bowell township and Joe's lake in Wisner, sections across the eruptive are much like those al-

Digitized by Google

ready described and need not be taken up in detail.

Character of the Eruptive

We may sum up the general character of the nickel-bearing eruptive of the northern range by stating that the basic edge is paler in color and contains more silica than in the southern range, the difference being partly due to the absence of dusty-brown coloring in the plagioclases; but that it also consists essentially of plagioclase having the composition of labradorite with hypersthene or an augite very like hypersthene as to pleochroism, hornblende, usually secondary, and a little biotite. Among the pale minerals must be included small amounts of orthoclase and quartz, the latter seldom inclined to be micropegmatitic. This rather acid norite passes gradually into a reddish syenitic-looking rock, really a micropegmatitic granite or grano-diorite often containing a mineral resembling epidote possibly woehlerite, hornblende, and sometimes a little biotite, but seldom any of the pyroxenes. At the southeast edge of the eruptive the rock is usually greenish-gray in color and a little more basic, but otherwise like the central portions. The feldspars are apt to be lath-shaped. Occasionally the edge becomes quite basic and dark-green in color, still containing much micropegmatite but of a very minute and feathery kind; and this variety appears to occur where the acid edge comes in contact with tuffs, with little or no granite conglomerate between.

Where the eruptive band is very narrow there is less change in character in passing from the basic to the acid side, the most basic rock, norite, being largely wanting, as well as gossan or ore deposits.

Results of Rock Analyses

In order to check the results of microscopic work on the rocks forming the nickel-bearing eruptive, four analyses have been made by Mr. E. G. R. Ardagh, one of the chemists of the School of Science, and the results will now be compared with those of Professor Walker from the Whitson lake region on the southern range. Three of the rocks chosen for analysis come from outcrops along the Canadian Pacific railway near Onaping, where the exposures are good and the materials fairly fresh; the fourth is from the acid edge on the north shore of Fairbank lake, where the dark gray-green color led to doubts as to the real character of the rock. Specimen No. 1 is from near the basic edge west of Onaping, No. 2 from the middle of the eruptive, where the rock is flesh-colored, and No. 3 from the greenish-gray acid edge. For comparison Professor Walker's analyses of specimens from near Whitson lake are given in Nos. 5 to 9, No. 5 being from the basic edge and No. 9 from the acid edge, the others being distributed between the two edges in the order given:

—	No. 1.	No. 2.	No. 3.	No. 4.	No. 5.	No. 6.	No. 7.	No. 8.	No. 9.
SiO_2	56.89	68.48	61.93	68.95	49.90	51.52	64.85	69.27	67.76
Al_2O_3	19.39	12.70	13.03	12.74	16.32	19.77	11.44	12.56	14.00
Fe_2O_3	.38	2.41	.56	.46	.....	.47	2.94	2.89	.....
FeO	7.11	4.50	8.00	5.15	13.54	6.77	6.02	4.51	5.18
MgO	2.11	.74	1.76	1.57	6.22	6.49	1.60	0.91	1.00
CaO	8.11	1.41	4.02	1.72	6.58	8.16	3.49	1.44	4.28
Na_2O	3.31	3.72	3.18	3.80	1.82	2.66	3.92	3.12	5.22
K_2O	1.04	3.36	2.80	3.28	2.25	0.70	3.02	3.05	1.19
H_2O	1.35	1.13	1.95	1.50	.76	1.68	.78	.76	1.01
TiO_2	.43	.61	.84	.43	1.47	1.39	.....	.78	.46
P_2O_5	.11	.20	.32	.20	.17	.10	.24	.06	.19
MnO	.30	.05	.18	.13	trace	trace	trace	trace	trace
NiO	.....	.....	trace	trace	.....	.....	.....	.....	.....
S	.....	.....	.19	.....	.....	.....	.....	.....	.....
Total	100.53	99.31	98.76	99.93	99.03	99.71	98.30	99.35	100.29
Specific gravity	2.884	2.673	2.757	2.694	3.026	2.832	2.788	2.724	2.709

It will be seen from a comparison of Prof. Walker's analyses with Mr. Ardagh's that his examples from the basic edge are distinctly more basic than the specimen from Onaping, Nos. 5 and 6 having seven and five per cent. less silica respectively. However, the very large amount of iron oxide (13.54 per cent.) in No. 5 suggests an abnormal quantity of magnetite, so that the specimen may be less acid than the average. The difference in the amount of silica corresponds to the appearance of the two rocks, the one from Blezard mine (No. 5) being much darker in color than the example from Onaping (No. 1). The most acid specimen from

Digitized by Google

Onaping (No. 2) and also No. 4 from Fairbank lake correspond very well with Dr. Walker's No. 8; but No. 3, on the extreme edge at Onaping is distinctly more basic than his No. 9.

In the Onaping analysis the rock from the basic edge contains, as one would expect, much more lime, magnesia and alumina than the most acid phase, and much less potash and silica.

Working out the percentages of minerals represented by the analyses from Onaping and Fairbank lake by the tables of Cross, Iddings, Pirsson and Washington we have the following results:

Mineral.	No. 1.	No. 2.	No. 3.	No. 4.
Quartz	6.42	27.78	17.16	24.84
Orthoclase	6.12	20.02	16.68	19.46
Albite	31.96	31.44	27.25	31.96
Anorthite	32.80	6.12	12.51	7.51
Hypersthene	14.38	7.08	15.13	12.61
Diopside	5.33	.....	7.28	.....

In reality of course the orthoclase would contain some of the albite material and the rest of the albite with the anorthite would be combined as labradorite in No. 1, and as oligoclase in the others. As hypersthene does not occur in the more acid phases of the eruptive, but is replaced by hornblende, biotite, etc., probably some of the alumina, lime and potash with all the magnesia and much of the ferrous oxide really belong to these minerals.

In the new system of classification No. 1 is hessose; No. 2 toscanose; No. 3 is nameless, but comes in Sub-rang 2 of Rang 3 in austrare; while No. 4 is dacose close to adamellose. In reality the classification obscures the relations between No. 2 and No. 4, which, instead of being far apart, are near enough to have been chips from the same rock, so close do they come together in percentages of chemical constituents.

Effects of Eruptive

The basic edge of the eruptive seems to have had little metamorphic action on the adjoining underlying rock, usually Laurentian gneiss with bands of green schist, perhaps because these rocks were already completely crystalline and little pervious to solutions. Where offsets, like that in Foy, project into the Laurentian, there is much brecciation, and a confused mixture of rocks results cemented by fine-grained norite, but otherwise apparently not greatly changed by the presence of the eruptive.

At the acid edge the effect on the overlying rock was much more profound. In most cases this rock is a coarse conglomerate consisting of granite pebbles or boulders enclosed in a granitic or gneissoid ground-mass, so that the eruptive seems to merge into the sedimentary rock, which can only be distinguished from it by the presence of the boulders. Near the edge even these become indistinct. The apophyses of the eruptive are not dike-like but vague and irregular, and we must suppose very slow cooling with the circulation of water strongly charged with silica and silicates in solution. The metamorphosis of the conglomerate gradually diminishes, and at 1,000 or 1,500 feet the tuffs are encountered, somewhat hardened but otherwise little changed.

The acid edge of the eruptive is not nickel-bearing, though iron pyrites may occur in it; and in the adjoining sediments, especially if penetrated by gabbro or greenstone, small vein deposits containing zinc blende and galena occur.

Other Eruptive Rocks

In addition to the nickel-bearing eruptive a number of specimens of other eruptives were collected along the nickel range or within the sediments enclosed by it. Those which have been studied in thin sections are all of a basic character, and most of them occur as dikes, the most important being an olivine diabase found at various points in Capreol and Wisner, cutting the tuffs and slates. It differs little from diabase dikes described in last year's Report, and the same may be said of a mass of diabase found in sandstone about four miles north of Chelmsford.

A dark-green eruptive mass, which occurs associated with cherty gray rocks, containing a few quartzite pebbles at Prue's mine, WD 252, to the southwest of Trout lake, near the acid edge of the nickel-bearing eruptive, may have a bearing on the adjoining deposits of zinc and lead ore. Thin sections consist mainly of pyroxenes, hypersthene being in largest amount, though some crystals having the characteristic pleochroism, show oblique extinction. Part of the dirty, fibrous-looking pyroxene having extinction angles of 45 degrees or more, and little or no pleochroism, should be called diallage. The feldspar, which makes hardly more than a third of the section, is labradorite in rather short, stout prisms, less often laths, embedded in the pyroxene, and reversing the usual arrangement has clear centres with brown, almost opaque rims. There is a very little interstitial quartz. This norite is much more basic than the nickel-bearing norite two miles away to the

Digitized by Google

north, and differs from it greatly in habit, so that there is probably no connection between them.

Another dark green-gray, fine-grained rock was collected near a nickel deposit four or five miles north of Onaping, where it seems to have penetrated between the nickel-bearing norite and the Laurentian. This, however, has an entirely different character, consisting essentially of serpentine and magnetite, enclosing areas of still fresh olivine. A little augite and some crystals of brown biotite are scattered through the section also, but in too small amounts to be of importance in naming the rock, which must be called peridotite, largely changed to serpentine.

A somewhat similar rock collected from dikes in granite at Michipicoton falls near lake Superior may be mentioned here. It originally consisted of about equal amounts of olivine and biotite, the olivine now almost altogether changed to serpentine and a carbonate. Augite may also have been present in the beginning, but can now hardly be distinguished. The rock, which may be called picrite, or perhaps better, biotite-peridotite, may be compared with dike rocks from near Magpie river in the same region, and from Goetz lake, not far away, consisting of serpentine with some fresh olivine, biotite and augite (17).

Drillings in Blezard

Having found strong magnetic attraction on lot 8 in the second concession of Blezard township, Mr. J. V. Miller, in charge of explorations for Mr. Thos. A. Edison, decided to do some development work at the spot, which is about a mile and a half north of the Little Stobie mine on the basic edge of the southern nickel range. At the time of my visit a pit sunk about ten feet in the norite showed some ore, consisting of pyrrhotite, chalcopyrite and pyrite. The country rock is dark and basic-looking in spite of the distance in from the edge. Later a diamond drill hole was sunk 1,030 feet, and Mr. Miller has been good enough to provide me with cores at every fifty feet. In general the sections of core are much alike, except at 264 feet, where brownish schist with pyrite and many scales of mica, and also vein quartz, were encountered, and at 900 to 950 feet, where fine-grained flesh-colored granite, no doubt a dike, occurs.

Thin sections were made of drill cores from 50 feet, 550 feet, 850 feet and 1,000 feet. The four sections are all of quartz-norite with a little quartz, a large amount of plagioclase (andesine to labradorite) and a large amount of dark minerals. The quartz is partly interstitial and partly intergrown with feldspar as micropegmatite. In the section from 50 feet depth the feldspars are somewhat brownish, but on the whole very fresh, while all the pyroxene has been changed to rather fibrous hornblende. The section from 550 feet is fresher still, and contains much hypersthene (also pleochroic monoclinic pyroxene), a little diallage, hornblende and biotite. The sections from 850 and 1,000 feet are badly weathered, perhaps because somewhat crushed, and the lowest one is the worst in this respect.

It is evident that the word weathering as generally applied to these rocks is not to be taken in a literal sense as due to the action of surface conditions. Probably the different stages of so-called weathering shown in the cores are to be accounted for by the greater circulation of underground water in parts which have been sheared or crushed.

Micro-Norite Groups

A curious group of very fine-grained, almost compact rocks, dark greenish-gray on fresh surfaces, but weathering paler gray, with prominent bands of green, was briefly referred to in last year's Report (18), as having a doubtful position with reference to the nickel-bearing eruptive. When opportunity offered last summer these rocks were ex- specimens were collected. Their field re- amined in the field and characteristic lationships are still obscure, though it was found that the largest area occurs close along the basic edge of the nickel-bearing eruptive from Blezard mine to Murray mine. The rock is not continuous for this distance, but is greatly mingled with other rocks, such as hornblende porphyrite, amygdaloidal masses, and green schists. So far as could be determined these fine-grained norites or gabbros are older than the nickel norite which encloses fragments of them, in places almost forming a breccia. Besides the large area just mentioned similar rocks occur near Joe's lake on the northern range, and possibly also near Sultana mine at the southwest end of the range; but here there has been no attempt to determine their extent. The Murray mine area is extensive, covering probably some square miles, but the fine-grained norite is so intimately

(17) Bur. Mines, 1902, p. 179.

(18) Bur. Mines, 1903, pp. 294-5.

Digitized by Google

mixed with the other rocks mentioned that no attempt was made to separate it in mapping. So far as observed the micro-norites are not in themselves ore-bearing, though at the edge of the nickel eruptive they may be more or less penetrated by the sulphides.

The appearance of these rocks in thin sections is very different from that of the typical coarse-grained nickel-bearing norite, though the general composition of plagioclase running from labradorite to andesine, and hypersthene, with one or two other forms of pyroxene, is the same. The quartz, often pegmatitic, of the nickel-bearing norite seems almost wholly absent in the fine-grained variety, and biotite is much less common. The tendency to a plate-like shape of the feldspars too is not observed.

In the micro-norites the feldspars are usually in less amount than the dark minerals, and often form polygranular areas, made up of separate, often fairly well-formed, crystals of about equal diameters in different directions. The feldspar (usually labradorite) is very fresh as a rule, though the individual crystals are crowded together and sometimes suggest crushing. Some of the crystals seem unstriated, but crystals with twin halves are common, as well as sections with more complex twinning. In some weathered specimens there is a greenish rim between adjacent crystals.

The pyroxene, which is later in age than the feldspar, usually makes up more than half the rock as granules of nearly equal diameters, either scattered or assembled in small clusters. In some sections there are also larger crystals of pyroxene of a porphyritic kind. The general word pyroxene is used because there are undoubtedly monoclinic as well as rhombic varieties present. The color is usually pale gray with a faint pleochroism, pale reddish-brown, yellowish-brown and bluish-gray, though there are sections in which the pleochroism is almost entirely wanting. As a considerable number of the crystals show parallel or approximately parallel extinction, we may call them hypersthene, or enstatite where pleochroism is lacking; but many of the crystals in all thin sections examined have an undoubted extinction angle, ranging from a few degrees to forty-five, and hence cannot be called rhombic pyroxene, but should be named diallage when fibrous-looking, or augite in other cases. The two varieties of pyroxene are exactly alike in every respect except the extinction angle, and one cannot resist the impression of a continuous series connecting forms with no apparent angle of extinction with forms which must be rotated 45 degrees from the cleavage or prismatic edges to become extinct. In one or two sections there are a few crystals much larger than the rest enclosing feldspars poikilitically.

With the colorless minerals, quartz is sometimes sparsely found, and among the colored ones, a very little biotite, and in one case ragged, poikilitic hornblende of a brown color. Magnetite in small square crystals with no hint of leucoxene is always found, and may form as much as a sixth of the whole section, while sulphides are less common and more irregular in arrangement. Where dark-green ribs stand out on weathered surfaces thin sections show bands of green secondary hornblende along minute fissures permitting water to circulate.

The very fine-grained, uniform textured micro-norites seem to shade into porphyritic rocks in places, sometimes with black hornblende crystals alone, sometimes with white areas as well. In general composition the ground-mass is like the rock just described, while the large hornblende patches are seen to be more or less composite areas of a poikilitic kind, often associated with some quartz and plagioclase of larger dimensions than the surrounding feldspars. In some of the porphyritic specimens the pyroxene has largely changed to hornblende, and it may be that the hornblende and dioritic schists and the hornblende porphyrites mixed with the micro-norite are simply sheared and weathered forms of the rock.

It is less probable that the amygdaloid rocks found with the others have any connection with the norite, as no transitions toward them have been noticed; but the oval white areas which give the amygdaloidal effect consist mainly of short equi-dimensioned plagioclases very like those of the micro-norites though of a larger size. There are also some quartz grains with the plagioclase. The ground in which the seeming amygdules are enclosed consists to the extent of four-fifths of green, secondary looking hornblende with some magnetite, epidote and a few grains of plagioclase.

Digitized by Google

Hutton Township Iron Range

As a large number of iron locations had been taken up in Hutton township and the next (unnamed) township to the west (19), during the past two years, it seemed desirable to study these iron ranges more in detail than had been done previously by representatives of the Bureau of Mines; and some time was occupied in mapping the range and examining the associated rocks, part of the work being done by Mr. Culbert after I left the field. The Hutton iron deposits have been known for several years, but until 1902 the region had not been studied by geologists. During the past two summers, however, Professor Leith of Wisconisn university has had parties at work mapping the iron ranges for economic purposes in the interest of certain iron companies. In a brief account of the Hutton township deposits given by him in last year's Report, he compares them with those of the Vermilion iron district in Minnesota. (20), and discusses their probable origin.

At present the Hutton township range is best reached from Sudbury by a continuation of the wagon road leading to Dawson on Vermilion river. The road for some miles to the north of Dawson is excessively rough and hilly while crossing the tuffs, and the nickel-bearing eruptive; but afterwards follows gravel plains and morainic ridges with few outcrops of solid rock, what there is being coarse reddish granitoid gneiss of the Laurentian, until it ends at Osborn's camp, near the foot of Moose mountain, where there are several comfortable log buildings, one occupied by a caretaker. Further travel over the ranges must be done by trail and by canoe.

Canadian Pacific railway engineers last summer located a branch line to connect Moose mountain with Sudbury, finding, it is said, a very easy route without heavy grades or much rock cutting; but it may be supposed that the branch will not be built until there is a prospect of mining operations on a large scale. The projected road might prove of considerable value for some porperties on the northern nickel range as well as for the iron properties.

Moose Mountain

Owing to the widespread presence of iron ore field work in the Moose mountain region usually had to be done with the dial compass, and had always to be checked with the dial; so that on cloudy days, which were numerous last summer, work was possible only along survey lines or by running pickets from survey lines. Sections were traversed across Moose mountain at short intervals as far as ore was found, or the dip-needle or compass indicated magnetite beneath the drift or swamp, but the geology of the adjoining rocks was taken up only incidentally.

The largest outcrops of ore are on the main hill not far from the points where diamond drilling was done, so that this portion of the range is naturally taken up first. A large amount of stripping has been done exposing sections across the ore, usually of glacially polished surfaces often suggesting solid iron; but sometimes strikingly banded with gray or white layers of silica. Occasionally the banding is of magnetite and dark-green hornblende instead of silica, and the distinction is quickly made by hammering on the surface, silicious parts showing a white powder, the hornblende parts dark-gray or greenish-gray. In the purer parts the ore is highly magnetic, fragments being fairly strong natural magnets, and the soft steel of a hammer acquires a quite powerful induced magnetism, attracting broken fragments of the ore in a long string. These are of course dropped as the hammer is removed from the surface of the ore.

The banding of ore with hornblende or with silica is often greatly bent and contorted and no very constant direction of strike can be noted, though in a general way the strike of the banding tends to be parallel to the strike of the range as a whole, at the southern end running roughly northwest and southeast, but toward the north trending nearly north and south.

Intimately mixed with the ore in some places one finds irregular bands or masses of pale-green epidote, apparently filling cavities due to shearing or slight faulting.

On Moose mountain the ore is more or less mixed with other rocks such as greenstone and granite, and the former rock forms the walls of the iron formation on each side dipping under it on the brow of the hill towards camp. Besides the ore exposed on the hill there are points of strong local attraction with one or two outcrops of ore in the swampy ground to the southwest, apparently completely separated from the main body by greenstone or green schist. Still further to the south and west there is granite, generally considered Laurentian, but certainly later than the

(19) Since named Kitchener township.
(20) Bur. Mines, 1903, pp. 318-321.

Digitized by Google

Digitized by Google

banded ore, since small dikes of it penetrate the ore occasionally.

After a short valley where the range narrows up or is drift-covered, another hill rises toward the northwest continuing to the river (a branch of the Vermilion) at the Iron Dam. In this extension the ore is generally leaner and more silicious than on Moose mountain, though here also there are outcrops of magnetite banded with hornblende, apparently rich enough to be workable. The associated rock is largely green schist, though some parts appear massive, but the whole is greatly sheared and so far rearranged that the original character of the eruptive is hard to determine beyond the general fact that it was basic.

Near the Iron dam where the hill sinks toward the river a section shows green stone and green schist to the west, near a small lake expansion above the dam, followed by banded magnetite and silica, then green schist, once more banded silica, and then green schist and greenstone to the low ground near the river.

North of the Iron dam the band continues for half a mile in a direction nearly north and south but narrower and in general leaner, the adjoining rocks being usually green schist. The whole range is a little over a mile in length, but much the most important body of ore is exposed on Moose mountain, where it is stated that an area of 75 yards by 50 consists of good are which will run 58 to 60 per cent. in iron.

There are two patches of iron range rock to the south of the camp, largely hidden under drift deposits, but found with the dip-needle. Test pits disclose large blocks of the banded ore, and at some points ore is said to have been found in place, but it is doubtful if they will prove of importance.

Extension of the Range

About a mile and a half up the river from the Iron Dam a second iron range of some magnitude is found, beginning at about the middle of lot 11 in the fifth concession, and extending to the northwest corner of lot 12 in the same concession. A trail leads from an old camp ground generally called Black's camp on a point where the river suddenly turns northwest and runs the whole length of the range, which is parallel to the river, but a little to the northeast. The banded material can be followed with a few interruptions by drift, where the dip-needle indicates the presence of ore, for the whole distance, but in most places it is narrower than the southern range, and especially than the portion on Moose mountain.

Near Black's camp the range seems to have been faulted several times, causing slight interruptions in the continuity of the ore, and there are also minor faults of a few inches or feet. The strippings disclose ore very similar to that of Moose mountain but in narrower bands. The best is of magnetite banded with thin seams of green hornblende, and sometimes has a width of several feet; but much of the range, especially towards the northwest, is silicious and too low-grade to be of much value.

The adjoining rock toward the east is generally green schist having a strike parallel to the banded ore, but toward the west swampy ground along the river often hides the rock, though some outcrops of greenstone occur. The banded ore is not always continuous in width, but may form two bands separated by schist or greenstone. This iron range is cut off by the river, only a trace of it occurring on the south side of the bend.

A small outcrop of banded magnetite was found by us near the northeast corner of lot 10 in the fifth concession, having a width of at least 25 feet and striking a little north of west. Part of it is banded with hornblende, but most of it is silicious and very lean. A longer and apparently more important band runs for a third of a mile east and west at about the middle of lot 11 in the fourth concession.

Specimens of the ore from three points in the Hutton ranges, No. 1 from Moose mountain, No. 2 from the Iron Dam, and No. 3 from the northwest range, have been analyzed at the Provincial Assay Office, Belleville, with the following results:

Constituent.	No. 1.	No. 2.	No. 3.
Ferric oxide	58.30	52.55	43.16
Ferrous oxide	28.08	28.76	20.41
Silica	7.92	12.84	31.76
Alumina	1.22	1.49	.78
Lime	1.28	1.18	1.40
Magnesia	2.35	2.75	1.75
Sulphur	.056	.06	.06
Phosphorus	.011	.016	.094
Manganese	.20	.18	.22
Titanium	none	none	none
Total iron	62.64	59.12	46.08

The first two were of magnetite banded with hornblende, the third of magnetite banded with silica, evidently forming a very lean ore.

A number of locations have been taken up along the supposed continua-

Digitized by Google

tion of the northwestern range of Hutton in two unsurveyed townships to the west and northwest, since named Kitchener and Roberts, but as these were located when snow was on the ground it is doubtful if any ore was found, and there is no information as to the use of a dip-needle in locating them. Several of these claims have been only incompletely surveyed, the lines not having been cut out on some of the sides. As far as possible our work covered all the boundary lines up to the long lake crossing the line between Kitchener and Roberts, but no iron range rock was observed, though banded schist much like that accompanying the ore in Hutton township was found in several places.

To the northwest of the lake just mentioned bands of the iron range rock are found in Roberts and the next (unnamed) township to the west, but these will be reported on by Mr. Culbert, who examined them after I left the field.

Geology of the Region

While mapping the iron ranges and examining the locations to the northwest a considerable amount of information was gained concerning the other rocks of the region, which were found to be much more complex in arrangement than was expected. On the old maps of the region Hutton township along the west branch of the Vermilion river and the townships west of it are colored as Laurentian; but our work shows Huronian rocks, often broken by eruptive granite, it is true, over most of it, and a very irregular contact between the Huronian and Laurentian. In general all the green schists and eruptives as well as the undoubtedly sedimentary rocks are here classed as Huronian, and all the granites and gneiss without regard to age or relationships to the previous rocks are called Laurentian. A final classification of the rocks as to age and origin must be reserved for a much more detailed study of the region than we could bestow on it.

The large areas of stratified sand and gravel in the valleys and the widespread muskegs in many places hide the bed rock completely, even for whole square miles, and add to the difficulty of mapping.

To the south of Taylor's (or Osborn's), camp near the foot of Moose mountain wide gravel plains extend along the west branch of Vermilion river, hiding the rock almost completely except for a small outcrop of greenstone about a third of a mile southeast near the road; and it is two miles before rock shows again, this time coarse porphyritic granitoid gneiss which may be assigned to the Laurentian.

Eastwards of the Moose mountain iron range as far as Vermilion river the rock where exposed is all Huronian except a dike or two of granite near the river, but the Huronian shows considerable variety, green schist extending for half a mile east of the west branch of the Vermilion, followed by a little quartzite and then graywacke (or slate) conglomerate, the latter extending for more than half a mile. The conglomerate has a fine-grained gray or green ground-mass enclosing pebbles of granite and sometimes other rocks, often sparsely scattered but sometimes crowded. East of the corner post between lots 5 and 4 the conglomerate contains large boulders of granite for a short distance, and is then succeeded by coarse white or reddish quartzite to a small lake not far from Vermilion river, where dikes of granite occur. Beyond this toward the east, greenstone and gravel flats extend to the river, the latter taken up in part as placer locations some years ago.

To the north the graywacke conglomerate is found associated with white arkose on hills near the Vermilion, and with green schist on its shore; while to the northeast of the iron range near Black's camp greenstone and slaty rocks occur.

The locations partially surveyed in Kitchener and Roberts northwest of Hutton where not covered with gravel plains consist of Huronian rocks of various kinds bordering on granite or penetrated by dikes of that rock. West of the post of Niven's line between the fourth and fifth concessions green schist occurs, banded or uniform gray-green, and with a strike of from 130 degrees to 160 degrees; while granite shows just to the southwest.

To the north are found mainly banded green schists for some distance, resembling those which accompany the banded iron range rock, though the latter was not found; and still farther north near Speight's east and west line graywacke conglomerate containing granite and other pebbles is widespread with some quartzite at points. Some bosses or dikes of coarse red granite penetrate the green schists toward the southwest, probably coming from the area of granitoid gneiss in that direction.

Except for the small group of rugged hills at Moose mountain the region has only a gentle relief as compared with

Digitized by Google

the northern nickel range, and but for the drift sheet and the frequent muskegs would be easily mapped. Niven's north and south base line and Speight's east and west line are excellently cut out, and serve as good bases from which to run lines for survey purposes.

Relationships of the Ranges

In general character, the Hutton township iron ranges suggest those of various other parts of northern and western Ontario, the banding of silica and magnetite resembling the arrangement found in part of the iron-bearing rocks near Batchewana bay and of the Michipicoton region, and also part of those to the west of Fort William and near Dryden; but the entire absence of jasper is unusual, and the richness of much of the banded rock as iron ore is very unlike that of other regions, where the only workable deposits are entirely secondary and show no banding. In Hutton township all the ore is more or less banded, though in the best of it the intervening layers consist of hornblende and not of silica, and there are gradations between the bands of the two minerals. Professor Leith suggests that the banding represents some original structure, but that secondary enrichment has taken place without entirely destroying the structure. He thinks that the enclosing greenstones form a "pitching trough," as in the lake Superior iron regions, and in this way the concentration has been made possible. In this view he is probably correct, though the evidence as to a pitching trough at Moose mountain seems somewhat indefinite; and at the Iron dam just to the north and in the northern range near Black's camp, narrow bands of rich and heavy ore, banded with green hornblende, alternate with bands of lean ore banded with silica. If these also are formed in pitching troughs, it is not easy to see why the whole width should not have been enriched, instead of certain bands only.

The arrangement of the greenstone and green schist running parallel to the banded ore on each side certainly suggests that the iron range is nipped in as synclines, and the presence of intrusive patches and masses of greenstone or diorite in some places mixed with the ore may indicate a partitioning off of separate troughs, though no distinct dike has been observed to cut across the syncline, as in some of the western iron ranges.

If the large ore body on Moose mountain and the smaller but still probably important ones to the north are the result of local enrichment of the original banded material, whatever that was in the beginning, the process cannot have proceeded in the radical and complete way found at Helen mine or some of the Minnesota deposits, where all trace of the original structure has usually disappeared, and a somewhat porous and often concretionary mass of hematite or limonite presents fairly well defined borders against the lean banded rock alongside.

It is not impossible that the original deposit, however made, was richer than usual, rich enough to form an ore with little or no addition of iron from materials leached out of other portions of the range. The very compact nonporous character of the ore seems to leave little chance for percolation; though it is of course possible that an originally porous banded rock has had all its interstices plugged by the deposit of magnetite or hornblende.

A point of marked difference between the Hutton iron range and many others in Ontario is the very small quantities of pyrite or other sulphides associated with the ore. At the Helen mine there are great quantities of pyrites, and probably a considerable proportion of the ore has resulted from its oxidation; and at various other points banded magnetite and silica have parallel bands of sulphides. Siderite, which occurs in several of our iron ranges, appears to be absent also.

The age of the Hutton iron ranges is not easy to fix with certainty. The parallel green schists, the nearly vertical attitude of the range rock, and the fact that granite and granitoid rocks like the Laurentian have pushed up later, suggest a lower Huronian or Keewatin age for them; but not far off on either side of the ranges and associated with similar banded green schists are undoubted graywacke conglomerates, quartzites and arkoses that can hardly be other than upper Huronian, the equivalent of the so called "typical Huronian" north of lake Huron. So far no pebbles of iron range rock have been found in the conglomerates to determine the matter of age, and until some such decisive evidence is obtained the matter cannot be finally settled.

Similar but much leaner banded silica and magnetite occurs as small patches southeast of Clear lake in Wisner township, completely enclosed in granitoid gneisses always referred to as Laurentian; and these have been placed in the lower Huronian in a former report of the Bureau of Mines (21).

The band of Huronian containing the Hutton iron range is completely separ-

(21) Bur. Mines, 1901, p. 186.

Digitized by Google

ated from the nickel range to the south by about eight miles of Laurentian; but toward the east Dr. Bell's map connects it with the Huronian area around lake Wahnapitae, where a strip of somewhat jaspery iron range is found, with graywacke conglomerate, etc., of the Huronian. An examination of this stretch of intervening rock may some day solve the problem presented above, and help to determine the age of the nickel-bearing eruptive also.

Michipicoton Mining Division

Since the report on the Michipicoton Iron Region was published (22) much work has been done at the Helen mine, so that a clearer idea of the relationships of the ore body can be formed than at the time the field work was done.

Boyer lake, which filled a curious rock basin before mining operations began and overflowed into Sayers lake, was pumped almost dry last summer, and good opportunities were afforded for studying the basin and parts of the ore body which formerly were under water. The basin is of quite an extraordinary kind as seen from the bottom. Though only a quarter of a mile long its depth is 133 feet, and along its northern shore below the former water level, the rock walls are often vertical or even overhanging. On the south side the slope is more gentle but still reaches 30 degrees. This side has been strongly acted on by glacial ice, rounding and smoothing the rock surfaces and forming striae which run from south to 40 degrees east of south near the bottom of the basin at its southwest end.

Toward the east end the basin is walled with brown, red and yellow slopes of dried mud and yellow ochre, giving with the open cut of the mine beyond a lurid display of color.

The real basin is still deeper toward the east end beneath the ore body, which has been opened up by diamond drill to the depth of 275 feet, but whether the basin was ever actually open to this depth is uncertain. If it was, the ore has been deposited since, filling the eastern end of the basin and rising 95 feet above the old water level: but part of the ore may have been formed by slow replacement of the iron range rock originally filling this part of the basin.

Since the geology of the region about the mine was mapped, a dike of diabase about 30 feet wide, now greatly weathered, has been found by Professor Willmott to run northeast and southwest across the ore basin near the east end of Boyer lake. Most of the ore is to the southeast of the dike, which has suffered great destruction in the lake basin and no longer rises above the ore, but there is good ore to the west of the dike also, showing that on the whole its effect has not been great in determining the position of the ore body, which would probably have been formed in the basin if there had been no dike.

Mud occupied the floor of the basin to the depth of 40 to 60 feet against the ore, and a band of yellow ochre follows the dike across the pit. There is a large pocket of granular pyrite in the lake bottom to the west of the dike beyond a mass of good ore, and the two materials are said to meet sharply with no gradations. The thickness of pyrites shown by drilling is 123 feet, and it is intended to mine the pyrites for use at the sulphite pulp mill. It is said that there are about 120,000 tons of pyrites in the deposit.

There are now good opportunities to study the ore body in the large open pits and the lake bottom. A second level has been opened up at a depth of 168 feet below the old railway track, which was three feet above the original level of Boyer lake; and diamond drilling below that has disclosed 107 feet of ore of the same character. Including the hill of ore which rose nearly 100 feet above Boyer lake when mining began, there was a total thickness of 370 feet of ore in the thickest part, so far as known. The ore body proves to be 40 feet wider at the second level than in the pit, this widening taking place in 80 feet of sinking, and being due to the fact that the contact of ore and country rock on the south side dips somewhat southerly.

The ore to be seen in the open pit does not differ greatly from that produced in earlier stages of mining, consisting largely of limonite in thin, flat solid layers with porous concretionary layers between. The leaner parts toward the north of the ore body include breccia-like fragments of yellow to white granular silica having small cavities lined with minute quartz crystals,

(22) Bur. Mines, 1902, pp. 152-185.

Digitized by Google

showing that silica was dissolved and re-deposited after the shattering of the banded silica, which remains unchanged a little way to the north. In places it appears that the silica is being replaced by limonite which also fills cavities in the silica.

Large parts of the ore run above 60 per cent. of iron, but at the time of my visit mining operations were being managed so as to keep an average of 59 to 60 per cent. when dry, or about 55 per cent. wet. The amount mined per day at that time (July) was 1,400 tons, and it was stated that 800,000 or 900,000 tons had been mined in all. The mine seemed in a better condition to produce ore than when I had been familiar with it two years before, and no signs of exhaustion were visible. The ore was being shipped mainly to Hamilton and Cleveland, and it was said that its physical properties make it desirable for mixture with the Mesabi ores and hence secure it a market in the United States in spite of the duty.

A brief visit was made to the Wawa gold mining district, but as these mines will be reported on by the Inspector it will be unnecessary to speak of them in detail. At the Grace mine operations were progressing satisfactorily, and the monthly brick of $5,000 was just being sent out. As the fuel for the Grace mine requires the clearing of about 100 acres per month of the small timber of the region some other means of supplying power will ultimately be necessary. Fortunately, the splendid falls of the Michipicoton river, only a few miles away, will be available for power for the whole region if future developments make it necessary. The falls are over granite with some blebs of quartz, like certain granites near Magpie river; but narrow dikes of a dark eruptive penetrate it, and some masses of quartzite or arkose are enclosed in it.

In a general way the mines are situated in green schist or sheared greenstones not far from outcrops of granite or gneiss; and one mine, the Manxman, was simply quarrying a hillside of greenish gneissoid rock as ore.

The Iron Belt West of Hutton

By M. T. Culbert

The time at the disposal of Dr. Coleman being limited, he was unable to cover much of the ground along the iron-bearing belt west of Hutton township, and it fell to my lot to make an examination of as much territory as possible after his departure.

I left Sudbury, with one man and a few weeks' provisions, on 10th August 1903 and took to the canoe on Geneva lake, proceeding thence to Bannerman lake and along the Onaping creek to lower Onaping lake on which a long paddle brought us to the east end of the eastern arm. From this two short portages and Four-Mile lake lead to the Wahnapitae waters. This river is here expanded into a broad channel called Long lake, which lies between ridges of granite in a straight line for many miles, forming one of the most picturesque landscapes in the region. Leaving Long lake, two short portages and a pond intervene before Little Wahnapitae lake is reached, this lake being the head waters of the river Wahnapitae, which after making a big loop to the north turns south to lake Wahnapitae. Within this loop the Vermilion river and some of its tributaries take their rise, showing a peculiarity of contour on the great Laurentian plateau. Again, two portages and a pond lead from Little Wahnapitae lake to Roam lake where we pitched camp and commenced operations.

Geneva and Roam Lakes

The route from Geneva lake to Roam lake passes through country which is characterized by alternating hilly parts and gravel plains, the former predominating. No great elevations occur, the hills being mostly small and never exceeding a few hundred feet. Dr. Bell has mapped an area of the Huronian series in the vicinity of Geneva lake consisting of conglomerates, quartzites, slates and limestones. An interruption of granite occurs on the Onaping creek between this area and another area of the same series on the Lower Onaping lake. At the narrows of this lake a short distance south of the crossing of Speight's line a good outcrop of conglomerate occurs, showing pebbles of granite, greenstone, quartzite and jasper, the last named being scarce. Contacts with the granite are present near the dam at the head of the Onaping river and the granite appears to be later in age. The conglomerates are distinctly banded, showing the stratifica-

Digitized by Google

tion planes, and alternating with finer grained grits which show cross-bedding plainly. Above Speight's line granite again appears and continues along the route till Roam lake is reached. Dikes of greenstone are frequent, also altered diabase and diabase porphyrites which have a mottled appearance due to aggregates of the feldspar. In many places the granite passes into gneiss with sheared bands of schist running irregularly in curves and patches, following no definite direction.

Roam lake lies in the unsurveyed blolk or timber berth between Proudfoot's base line on the north and Speight's base line on the south, and between the six-mile and the twelve-mile posts of each. These posts number from the corners, northwest and southwest, of the township of Creelman which is north of Hutton township. Roam lake is a little over six miles in length running north and south, and having many bays and arms. It is crossed by Proudfoot's base line, and extends north of it a mile or so. Granite outcrops on this north extension of the lake, but near the base line green hornblende schists appear of considerable width, followed on the south by Upper Huronian sediments, including schistoze quartzite, conglomerates and slates. Further east limestones appear in the series and more silicious rocks approaching quartzite. The schistosity of the quartzite is due to scales of muscovite arranged along definite planes, and considerable chlorite is found in thin sections. The conglomerates have a dark silicious matrix, and show pebbles of granite, greenstone and quartzite, and small jasper grains are detectable under the microscope. This conglomerate is found on Speight's line east of Morton lake, and there has a strike northwest and southeast. Interbanded with it are reddish quartzites and silicious slates with good cleavage. The pebbles are almost absent in many places, apparently grading into the quartzitic phases, the whole series being conformable. This series of rocks has a schistose or slaty structure and the conglomerates greatly resemble the slate conglomerates of the north shore of lake Huron and are in all probability the same. Going east and west, on the base line from the northwest corner of Hutton, the outcrop is over two miles in length and the noted strikes vary from 290 degrees to 310 degrees, apparently dipping northeast. They seem to be more highly altered by metamorphism on Roam lake and westward where near the granite,which is of later origin. The eruption of the latter seems to have been accompanied by great dynamic activity, and faulting and folding has taken place on an immense scale, rendering detailed mapping of rocks very tedious and difficult.

The green hornblende schists which are so intimately associated with the iron deposits appear at both ends of Roam lake. A band crossing the north part of the lake runs southeastward to Morin lake and was not followed far to the west. The only iron so far discovered in this band is that on the Savage property on Morin lake. Another band crossing the southern part of the lake is narrow with few outcrops, but magnetic attractions determine the longest band of iron in the region stretching across the timber berth.

Crossing Speight's line about a quarter of a mile east of the eight-mile post, another band of schist runs southwest into the unsurveyed berth south of the base line. This was followed for a few miles, but no signs of magnetic deposits could be found with the exception of an olivine diabase dike giving slight attractions. If this band is continuous or connected with that one crossing Roam lake, the connection is covered with gravel deposits and does not outcrop. Towards the edges of these schist bands the granites are found apophysing into them in irregular stringers and dikes. Passing onward banded gneiss is found, the hornblende schist being sheared out into bands; and finally massive granite is reached, showing no basic inclusions whatever. The granite extends south to the nickel ranges with bands of schist and small scraps of iron range, samples of ore having been brought in by prospectors from various parts of the intervening country as far south as Foy township.

McCrindle Lake

Running from the northwest bay of McCrindle lake almost due west across Roam lake and two miles north of Speight's base line there is a band of iron range. It outcrops only in a few places, where it is very silicious and lean, but the parts of the band giving the strongest magnetic attractions are covered with gravel. The iron is flanked by green schist which in turn is flanked by granite, the total width of schist and iron on the outcrops being very narrow, only a few hundred yards. The drift-covered areas give strong magnetic attractions in places three hundred yards in width, and such local attractions of the needle give the only conception of what may be beneath.

Crossing Roam lake the needle dips in the canoe and after a short interrup-

Digitized by Google

tion near the west shore of the lake, where a band or dike of greenstone eruptive intervenes, the attraction is again found on the west shore. Passing towards Sandfly lake the iron range bends about ten or fifteen degrees to the south. As my provisions were limited I was unable to follow the band further in this direction, but iron properties have been taken up farther west as far as the longitude of the lower arm of the Onaping, north of Speight's nineteen-mile post.

Coming home along this route I noted the presence of green schists on the small lake, half a mile north of the base line, which drains into the Onaping river and is known on the map as the lower arm of the same.

Morin Lake

There are two small outcrops of iron near Morin lake which lies near the west boundary of the berth west of Creelman township. One of these on the shores of the lake on WR 121 runs for about a quarter of a mile, and at its widest outcrop is sixty paces in width. Much silica is present, alternating as usual with bands of magnetite, and the whole looking rather lean. The trend of the iron range is about twelve degrees north of west, the dip being almost vertical. The attractions cease to be strong within a short distance of Morin lake, being found first about one hundred yards inland and continuing till Lost End lake is reached, a small pond on the southwest of the lot. The iron ore outcrops for the greater part of its length, but presents no elevation above the surrounding green schists. Large masses of greenstone eruptives are found in the vicinity, and between this property and mining location WR 108, where another outcrop of iron is found, greenstone with some green schist occurs. The outcrop on W R 108 shows a short mass of banded iron ore and silica lying very flat and dipping to the northwest. The total thickness is from twelve to fifteen feet, but lying flat, as it does, it makes a better showing. On the line between this property and WD 359, adjoining to the west, the outcrop occurs 590 paces south from the northeast corner post of the latter property. It runs over the line only a short distance to the west, and from this point on the line it takes a direction northeast for 400 paces along a trail leading to the southeast bay of Morin lake. This showing is the least favorable of any examined as far as grade of material and area of outcrop are concerned.

A trip was made into Hutton to lot 2 in the fourth concession. Running east and west nearly across the lot extends a band of iron range with some good outcrops. This lies a short distance north of Yerkes lake and in the southern half of the lot. The iron ore, banded as usual with silica, much resembles the bands on lot 9 in the fourth and lot 11 in the fifth concession of the same township, and with the exception of the Moose mountain outcrops compares favorably with anything in the region. Green schists are associated, and granite is found a short distance south and to the west.

Iron Ranges in Rathbun

During the latter part of September I had occasion to visit lake Wahnapitae, and went in to see an outcrop of iron ore discovered by Henry Ranger on the boundary of the Indian reserve, and lot 24 in the sixth concession of Rathbun township. It occurs up the boundary from the lake about half a mile or more, rising in a hill from the plain to the south and about 300 yards from Post creek. This outcrop is very poor and lean, but presents some differences in association from the iron bands in Hutton and westward. The material itself is identical, being banded magnetite and silica in thin layers, but here the green hornblende schists are lacking, and in their place occur chlorite schists. On one side of the iron range occurs an eruptive much altered, but phenocrysts of plagioclase are still detectable under the microscope. The matrix is very fine-grained, showing minute lath-shaped feldspars which are probably original or may be due to later agencies causing a re-arrangement of the matrix. Mosaics of well-crystallized quartz occur in irregularly banded masses suggesting amygdules. Much secondary calcite is present, especially in small veinlets and associated with chlorite. This was probably originally an andesite, and presents an unusual occurrence among the rocks of the district. A hard, pinkish or flesh-red quartzite occurs near the iron range to the north, outcropping on lake Wahnapitae. A gravel plain lies on the reserve to the south covering the contact with the granite or Laurentian.

Other outcrops of iron range have been found between lake Wahnapitae and Hutton township, near the contact of the Huronian and the granite. Bad weather and lack of time prevented an examination of them.

Digitized by Google

Log jam, Onaping river.



Log chute, Onaping river.

Digitized by Google

UNIV. OF MICH.

Digitized by Google



Nickel ore deposit five miles north of Oi aping.



Richardson feldspar mine, Bedford, (nt.

Digitized by Google

UNIV. OF MICH.

Digitized by Google



Perched boulder near Nelson river.



Missanabie river at Hell or Long rapids.

Digitized by Google

UNIV. OF MICH.

Digitized by Google

Mineral Range Iron Mining Company. No. 1 or Childs mine.

Digitized by Google

UNIV. OF MICH.

Digitized by Google

19

The Iroquois Beach in Ontario

By A. P. Coleman

Wave action in the cutting of cliffs, the piling up of beach sands and gravels, and the formation of gravel spits or bars across the mouth of bays is so easily recognized that old shore lines, when so well marked as those of the Iroquois Beach, are certain to attract attention. It is not surprising then to find that the wide-spread terraces and beaches of ancient lake Iroquois have been noticed by farmers and land surveyors as well as geologists for many years. In Canada Thomas Roy, an early land surveyor, was the first to call attention to this splendid beach in a paper on the "Ancient State of the North American Continent," read by Sir Charles Lyell before the Geological Society of London in 1837 (1). Roy describes in this paper a series of "terraces or level ridges" to the north of Toronto, the first at 108 feet above lake Ontario, the second at 208 feet, and higher ones at various levels up to 762 feet above the lake or 1,008 above the sea. It is not quite certain which of his beaches was the Iroquois, but the one placed at 208 feet, described as two and a half miles north of the lake, probably represents it, though his measurement is 30 feet above the real level.

Lyell was so much interested in Roy's paper that he visited Toronto in 1842 and rode north with him to examine the supposed beaches; and he reports having seen in all eleven apparent beaches, the highest 680 feet above Ontario; but he was not certain that all were due to wave action, though he says that "with the exception of the parallel roads or shelves in Glen Roy and some neighboring glens of the western highlands of Scotland, I never saw so remarkable an example of banks, terraces and accumulations of stratified gravel, sand and clay maintaining over wide areas so perfect a horizontality as in the district north of Toronto." (2) It should be mentioned here that later geologists have not been able to find the numerous terraces described by Roy and Lyell, the only well marked one being the Iroquois beach.

Theories of Origin

Both Roy and Lyell had theories to account for the supposed beaches, Roy supposing a huge lake dammed to the east and south by ranges of mountains, slowly cut away by the water till the present level was reached; while Lyell prefers to think that the beaches were formed by the sea when the land stood lower than now.

In 1843 Hall recognized the beach in New York state, described the gravel ridges used as roads, and mentioned wood and shells as occurring in the beach gravels. In 1859 A. C. Ramsay referred briefly to the Iroquois terrace north of Toronto (3); and in the following year Charles Robb, a civil engineer of Hamilton, described a series of ridges of sand and gravel, seven in number, to be seen as one goes inland from lake Ontario, referring specially to the old Burlington beach, which he says rises 110 feet above the lake (4). In 1861 Prof. E. J. Chapman of Toronto University speaks of a great fresh-water lake as having formed this and other beaches as it gradually fell (5), and in the same year Sir Sandford Fleming gives an excellent account of the beach north of Toronto, illustrating his work with the map (6).

Hitherto all the writers had looked on the beaches as either formed in a

(1) Proc. Geol. Soc., London, Vol. II., No. 51, pp. 537-8.

(2) Lyell, Travels in North America, Vol. II., pp. 103-6.

(3) Quar. Jour. Geol. Soc., 1859, p. 203; and Can. Nat. Geol., Vol. IV., p. 328.

(4) Can. Jour., New Series, Vol. V., 1860, p. 509.

(5) Ibid, Vol. VI., 1861, p. 228.

(6) Ibid, pp. 247-253.

Digitized by Google

great lake enclosed by rock or drift materials toward the east, the outlet being afterwards cut away, or else as formed by the sea when the land stood lower; but in 1862 Newberry suggests the idea of an "ice-wall of the retreating glacier as forming the northern shore of the fresh water inland sea," (7) thus introducing a new element into the discussion.

In 1863 the summary of the Superficial Geology of Canada contains a description of the Burlington heights with bones of mammoth, wapiti and beaver found in the gravel during the excavation of the Desjardines canal(8), but there is no discussion of the origin of the beach.

In 1882 Dr. J. W. Spencer described Burlington heights and the plain rising 70 or 80 feet above Ontario in its rear, (9) and suggested that floating bay ice had much to do with the construction of the great gravel bar, but apparently had not followed the beach far enough to observe its northeast tilt. In 1889 he published "The Iroquois Beach; A Chapter in the Geological History of Lake Ontario" (10), introducing the name Iroquois, describing the beach, and discussing its origin. He gives a small sketch map of its outlines, drawing on G. K. Gilbert for the part south of lake Ontario, and presents diagrams illustrating the unequal tilting of the old water plain.

In 1890 Dr. Gilbert refers to the beach, giving a rough map to indicate its extent (11). Since then Spencer has more than once published brief accounts of the beach, his volume on "The Duration of Niagara Falls and the History of the Great Lakes" summing up his views on the whole subject (12). Gilbert and Spencer were the first to give a clear idea of the extent and character of the old shore, and its differential uplift toward the northeast; but they differed as to its cause, Dr. Gilbert accounting for it by an ice-dammed body of fresh water with an outlet through the Mohawk valley into the Hudson; while Dr. Spencer believed that it was formed at sea level by an extension of the gulf of St. Lawrence.

In 1899 the present writer mapped and described the portion of the beach crossing the county of York, giving an account of fresh water and other fossils found near Toronto and Hamilton in Iroquois gravels, and supporting the glacial lake theory (13).

Professor Fairchild in his report on the Pleistocene Geology of Western New York (14) gives the first large scale map of a considerable part of the Iroquois shore, reproducing, however, Dr. Spencer's rough sketch map of the shore to the north and east. Prof. Fairchild accepts the glacial lake theory and speculates on the tilting of the beach during Iroquois times, concluding that most of the warping is of post-Iroquois age.

My own work of mapping the beach in the Province of Ontario began in 1898 with the section near Toronto and was extended from time to time in each direction. The work was practically complete two years ago, but was not published, as it seemed desirable to trace the northeastern shore as far as possible. After several visits to the region between Campbellford and Havelock on the north side of Trent river, and also to the hills north of Madoc, which rise high enough to receive the beach, the conclusion was reached that it could not be traced farther, either because it had not been formed in that region or because the Laurentian hills with little drift upon them were not suited to record the event.

(7) Prof. Fairchild's Pres. Address, Geol. Sec. of Am. Assoc., Vol. XLVII., 1898, p. 33.
(8) Geol. Can., 1863, p. 914.
(9) Am. Jour, Sc., Vol. XXIV., pp. 410 and 415.
(10) Roy. Soc. Can., Trans., 1889, pp. 121-134.
(11) History of Niagara River, Com. Niag. Reservation, 6th An. Rep.; and Smithsonian Rep. for 1890 (pub. 1891).
(12) Pp. 44-57.
(13) Lake Iroquois and Its Predecessors at Toronto; Bul. Geol. Soc. Am., Vol. 10, pp. 165-176; also The Iroquois Beach, Trans. Can. Inst., 1898-9, pp. 29-44.
(14) 20th An. Rep. New York State Geologist, 1900, p. r. 105, etc.

Digitized by Google

Detailed Account of Iroquois Beach

Beginning at Niagara the beach may be traced with scarcely an interruption, except where river valleys have cut below its level and destroyed the terraces and gravel bars, westward to Hamilton, then northeast at varying distances from Lake Ontario to a point three miles northwest of Trenton; where it bends to the west once more forming a large bay with numerous islands. In this part the continuous shore line cannot be followed. The most easterly point is a small island near West Huntingdon on the Madoc railway; and the most northerly point is just north of the Trent river near Trent bridge. Though long stretches of the beach are occupied by various main roads easily followed by driving, it was found that much of the shore, especially toward the northeast end, could only be worked out on foot, owing to lack of roads and the wooded character of the country. For mapping purposes the old county maps were used, and were found on the whole quite satisfactory, though new roads and also railroads have frequently been made since the maps were published. The most inaccurate of these maps is unfortunately that of the county of Peterborough, where the final search for the northward extension of the beach was made.

The lack of a contoured map showing the elevations has been greatly felt, since at many points distant from railways or canals or from lake Ontario, the fixing of elevations can only be done by the aneroid, an unsafe method where there are not constant check readings.

The elevations of railway stations, sections of the Trent canal, etc., given in White's "Altitudes in Canada," have been used as fixed points, and from them hand level determinations have been made of numerous terraces and bars of the old shore. Where the distance is not too great and the slopes are suitable, work with the hand level is fairly accurate, certainly much more accurate than the average barometric determinations.

In the mapping, special attention was given to the main beach, but in most cases bays cut off more or less from the open lake by bars have been roughly mapped also. Usually the shores of bays are much less strongly marked than the main shore, owing to their portected position, which mitigated wave action.

The criteria for determining the beach, such as shore cliffs cut in hills of boulder clay, beaches of sand and gravel, or bars and spits of the same materials, are easily recognized; and often boulder-strewn fields a little below these levels give additional evidence of wave action. The characters of old beaches are admirably given by Dr. Gilbert (15) in U. S. Geological Survey Reports, and are well described also by Dr. Spencer (16) in his work on Niagara Falls and and the Great lakes.

The gorge of the Niagara below the escarpment has been cut largely since the Iroquois stage of water, and gives at Lewiston a fine exposure of the old gravel bar formed at its former mouth. The lower part of the river bank on both sides is formed of red Medina shale, covered on the American side by drift materials, especially thick cross-bedded gravels. From the level of the river to the terrace on which the lower part of Lewiston stands is about 57 feet, giving approximately the thickness of the solid rock; and above this, though a little inland, rise the coarse stratified gravels, often with a very steep dip to the south, to a height of 122 feet above the river, or 124 feet above Ontario, according to my hand level determination. The U. S. contoured map makes the level between 360 and 380 feet above the sea, or 114 to 134 feet above Ontario.

On the Queenston side the gravel bar is not in evidence, but the water line is clearly marked as a cut terrace at the foot of the escarpment just to the south of the main road leading to St. Davids. After a mile or two the rock cliff of the Niagara escarpment withdraws some miles to the south, round the bay-like valley of St. Davids, and the shore cliff, which is still followed by the road, rises but little above the Iroquois level, while a gently rolling plain runs southwards from its edge.

From St. Davids to Homer the same conditions are found, and all the way from Queenston the Iroquois terrace of flat rich land stretches with a very gentle slope northward toward lake Ontario.

At Homer gravel bars commence, the shore cliff having sunk to the old water level, and a shallow bay to the south is cut off in this way. The gravel ridge extends across Welland canal to St. Catharines, furnishing a good foundation for St. Paul and other main streets of the city, but is cut off abruptly by the river, whose channel was evidently

(15) Topographic Features of Lake Shores, U. S. Geol. Sur., 5th An. Rep., 1883-4, pp. 76-123.
(16) Duration of Niagara Falls, etc.

Digitized by Google

pushed to the westward by the growth of the bar.

The bar rises about 21 feet above the Grand Trunk station or 122 feet above Ontario. Beyond this the usual low shore cliff of clay extends once more to the westward and is followed by the main road for about three miles; but here the road descends and henceforth keeps to the foot of the cliff. At Fifteen-mile creek a ravine has been cut displaying beach gravels resting on unstratified clay; and a little to the east the low shore cliff is broken by Jordan river. Here the Niagara escarpment approaches the shore again for a mile or two.

From Jordan to Beamsville there is little change, except that the clay cliffs grow higher, the escarpment once more receding for a mile or two, and the soft Medina shale often forms part of the shore, usually however with almost stoneless till overlying it. West of Grimsby the bare or thickly wooded Niagara escarpment rises immediately above the Iroquois plain, and continues in this position to a point a mile or two from Stony creek, where there is a bay-like recession. West of Stony creek a valley interrupts the old shore for about a mile, and beyond it a gravel bar extends to the foot of the Niagara escarpment, at a bold promontory facing northeast; while from this to Hamilton the foot of the cliff forms the shore line.

Except for the approach or recession of the Niagara escarpment and an occasional gravel spit or bar near a stream crossing there is great uniformity in the shore line, which begins on the Niagara seven miles from lake Ontario and gradually comes nearer to the present shore, until near Grimsby the two are only a mile apart. Everywhere the gently sloping plain of fertile clay soil covered with orchards and vineyards extents almost unbroken to the northward, while somewhat hilly land of clay or red shale stretches to the south unless for a space the rock cliff of the Niagara formation forms the shore. This lakeward sloping plain is perhaps the most favored region in Canada as to climate, soil and beauty of scenery, and is mainly given up to fruit farming.

The Beach near Hamilton

One of the most interesting points on the whole Iroquois shore is found in Hamilton and its vicinity where the sharp turn to the northeast takes place, and several writers have mentioned or described the arrangement of gravel bars and bays in the modern and ancient lakes, Dr. Spencer having specially studied it (17).

A long bar cuts off the present Hamilton bay from lake Ontario, enclosing a triangular body of water five miles long and quite deep. At the west end of the bay a cliff of stratified sand and gravel rises 116 feet, called Burlington heights. After a width on top of only a few hundred feet where narrowest, it sinks as suddenly toward the west to a marsh at the same level as lake Ontario. This curious embankment was cut through many years ago to make an outlet for the Desjardins canal running westward to Dundas, but formerly the drainage of the Dundas valley escaped by a channel round the north end of the gravel bar. From this narrow ridge the bar runs southward through the cemetery and Dundurn park and the upper portion of the city of Hamilton to the foot of the "mountain" south of James street, forming a gentle curve with its hollow toward the east.

During the excavation of the canal it was found that blue clay underlies the stratified sand and gravel which are piled up to form the heights; but at present the lower part of the ridge is covered with talus. then stratified sand appears up to 57 feet, followed by fine and coarse gravels, often cross-bedded and mostly cemented to conglomerate.

South of the marsh and west of the gravel bar the land rises to a flat terrace 78 feet above the bay, and sections displayed by brickyards and sand pits, sometimes both on the same property, show gravel, sand and clay.

For instance, at Crawford's sand pit the succession is :

	Feet.	Above bay. Feet.
Clay making red brick..	6	78
Gravel	30	72
White sand	5	42
Hard pan	4	37
White sand, with mammoth tusks and bones		33
Level of bay		0

East of the bar and descending toward Hamilton bay one finds some cemented gravel, but more sand and especially brown silt.

Excavations made for the Hunter street tunnel in Hamilton cut through the gravel bar, and the section showed at that point 30 feet of coarse stratified gravel, often cross-bedded and sometimes containing boulders two feet in diameter, followed by two feet of brown

(17) Spencer, Am. Jour. Sc., Vol. XXIV., 1882, p. 415; also Trans. Roy. Soc. Can., 1889, pp. 129, etc.; Geol. Sur. Can., 1863, p. 914.

Digitized by Google

unstratified clay and eight feet of blue till enclosing a few stones. The brown clay is an old soil and contains quantities of partly decayed wood as well as mammoth remains (18). Bones of mammoth, wapiti and beaver were found in the Desjardins canal cutting about 70 feet above the lake, and since then many tusks and fragments of bones of mammoth have been found near King street west in sand pits at levels from 33 to 42 feet above the lake. Colonel Grant reports also "a shoulder blade of a large moose or deer," and horns of a buffalo, the latter from the Desjardins cut.

It is evident from the old soil more than 30 feet below the surface that dry land existed to at least that depth before the water rose sufficiently to permit the formation of the Burlington gravel bar. That the earliest water level was lower still is very probable from the finding of mammoth tusks and bones only 33 feet above the present lake, or 83 feet below the top of the bar. They were probably not washed to the spot by wave action, for long slender tusks, quite unworn, though now fragile from loss of organic matter, occur in the sand, no doubt deposited there by the death of the animal. The flats and bars beside the old Dundas bay were favorite haunts for these elephants, perhaps to get the breeze and escape the flies in summer.

While the bay must have been small and shallow in the earlier part of the Iroquois age it must have grown deeper and deeper, the dam-like gravel bar rising to correspond, until at the end the bay was over 100 feet deep and extended west to what is now Dundas, enclosing almost as large an area as the similarly shaped Hamilton bay. The materials for the bar were probably derived from the shore to the southwest along the foot of the Niagara escarpment, where accumulations of boulder clay still exist. Dr. Spencer calls attention to the fact that the pebbles of the bar are largely of Hudson river rock instead of Niagara limestone as might have been expected, so that they must have been ice-borne from the north or east.

Burlington Heights to Toronto

From Burlington heights to Toronto the Iroquois shore presents much the same features as from Queenston to Hamilton, a broad flat clayey surface sloping gently toward lake Ontario with a shore cliff of clay to the north varying in height but almost always distinguishable. From Burlington to Oakville the shore is nearly straight and runs parallel to that of Ontario, but about two miles inland. The streams flowing to the lake cut ravines into underlying Medina shale, thus destroying for a space the beach and its shore cliff, but the interruptions are unimportant. A little east of Waterdown station, however, a long gravel bar runs southwest toward Hamilton bay, thus partly overlapping the great Burlington bar, whose coarse conglomerates are so strikingly displayed on the Grand Trunk railway to Hamilton and Dundas.

About two miles after passing from Halton county to Peel the regular trend of the beach is broken by a deep bay before it crosses the Credit river, and Hudson river shale shows in the cliff which rises ten or twenty feet above the flat shore. Here a gorge has been cut through 20 feet of boulder clay and a somewhat greater thickness of shale, and above the clay are ten feet of beach materials, coarse gravel now cemented into a conglomerate.

The low shore cliff rises not far north of the Grand Trunk railway, and may easily be followed when passing by train from Burlington to the Credit bay. Beyond the Credit there is a gravel bar, and then low shores and the usual flat terrace to Cookstown, where a gravel bar occurs. From this village to Lambton Mills the main road between Hamilton and Toronto, called Dundas street, follows the old shore, partly above the low cliff of clay, partly on the terrace at its foot and partly on gravel bars across the openings of valleys.

At Lambton the Humber river cuts off the beach with its wide and deep valley and a bay extends three miles north to Weston. East of the Humber valley a great gravel bar extends for two miles to Davenport station on the Northern railway property, the Davenport ridge, though the shore cliff to the east is often called by that name.

The Davenport bar evidently crowded the Humber out of its old valley, now filled with stratified sand and clay, and forced it to cut a new valley, which is now walled with Hudson river shale for 30 or 40 feet at the bottom, and with boulder clay and later drift deposits above.

The Davenport ridge is greatly exploited for sand and gravel for building purposes in Toronto, and in a layer of clay beneath 20 or 25 feet of gravel horns and less often bones of caribou are found, sometimes in considerable quantities. A number of years ago

(18) The Iroquois Beach, A. P. Coleman, Trans. Can. Inst., 1898, v. 36.

Digitized by Google

Mr. Thompson reported finding a stone muller and arrowhead with bones and horns of deer while digging gravel at a depth of 20 feet from the surface, so that there is a strong probability that Indians dwelt on the shore of lake Iroquois.

To the north of Toronto the Iroquois terrace on which the city is built lies at the foot of a steep shore cliff of boulder clay and sand, and was once thickly strewn with great stones washed out of the clay. At Reservoir park a small gravel beach has furnished many fresh water shells of four or five species, including campeloma, pleurocera, sphaerium and unio, almost the only undoubted evidence as to the character of the water, though unios were reported from the shore in New York in early days.

The Don valley interrupts the beach for more than two miles, and a wide bay runs to the north with a broad series of gravel bars with lagoons between, very much like Toronto island of to-day, cutting it off from open water to the southeast. The town of York is situated near the west end of this bar, which is exposed in many sand and gravel pits, in one of which a mammoth's tooth was found a number of years ago. The York gravel bar has grown westwards like the Davenport bar and the present Toronto island. The source of the materials for the eastern bar, as well as for the modern island, is no doubt to be found, as suggested long ago by Sir Sandford Fleming, in the destruction by wave action of Scarboro' heights.

The sections afforded by the tributaries of the Don and Humber show a very large amount of sand and clay with some gravel also, filling in the old bays and extending to the eastward toward Scarboro' heights, the thickness sometimes reaching 100 feet, and exceeding 50 feet over a number of square miles. In one such deposit on a tributary of the Don, a quarter of a mile west of the main river, wells sunk to investigate the drift disclosed at a level 35 feet below the Iroquois terrace, sand and gravel partly cemented by lime to a depth of 38 feet, ending on what appeared to be a weathered surface of interglacial clay. A little above this the sand contained unios, sphaeriums and plueroceras. Though the evidence is not altogether conclusive, it points strongly toward a stage of water in the earlier Iroquois times 70 feet lower than when the final gravel bars were constructed, and confirms the evidence previously referred to near Hamilton.

Scarboro' to Colborne

At the eastern end of the York gravel bar the Iroquois shore approaches closely the shore cliff of lake Ontario, and 4 miles from York it ends abruptly against the highest part of Scarboro' heights, the present lake having cut back its shore far enough to destroy the old beach for half a mile. This is the only instance where the present lake encroaches on the boundaries of its predecessor, and this happens because a lofty morainic spur here runs southward from the Oak ridges. On each side of the gap at Scarboro' heights the Iroquois shore is deeply incised in the boulder clay with cliffs from 70 to 150 feet high. East of the heights the shore turns off to the northeast forming a bar south of Highland creek and being interrupted by the Rouge river two miles beyond, where another long bar occurs.

Continuing northeast beyond Pickering and Whitby the beach recedes 7 1-2 or 8 miles from lake Ontario, and then bends southwards again near Oshawa and Bowmanville. There is a large bay north of Newcastle and one of the boldest promontories on the whole shore projects to the south at Newtonville, where for a few miles the Kingston road follows the gravel bars and terrace of the old beach. Northwest of Port Hope there is another deep bay reaching 7 miles inland from lake Ontario with a drumlin island about 4 miles north of the town. Where the Midland railway crosses the beach near Quay's there are heavy gravel bars used for ballast, the level being 311 feet above Ontario.

From this point the beach follows the south side of the bold morainic ridge of central Ontario to Baltimore north of Cobourg, where a stream valley interrupts it for about two miles; and then draws a little nearer lake Ontario behind Grafton and Colborne.

For the whole distance from Hamilton the shore has been steadily rising, near Colborne reaching a height of 356 feet above Ontario, as determined by Dr. Spencer, but the beach is everywhere a unit. Though the gravel bars may be split up by lagoons, they all rise approximately to the same height, the differences between adjoining bars seldom exceeding five feet and never ten. These bars probably rose a few feet above the lake as they do now above lake Ontario, e.g., at Toronto island, so that the foot of the shore cliff in places where bars or beaches do not occur is somewhat lower, and the old

Digitized by Google

water level should be put perhaps five feet below the top of the bars.

Colborne to Trenton

Three miles to the northeast of Colborne near Silver lake the shore is found to have lost its unity, and there are bars at three levels, the highest 28 feet above the lowest. The gravel bars are massively developed on a promontory south of Silver lake, where they approach within a mile and a half of lake Ontario. Another interesting feature occurs here in the fact that Silver lake is really a small bay of lake Iroquois cut off by these heavy bars from the main body of water, so that its drainage is not towards lake Ontario two miles and a half away and 360 feet lower down, but by a stream flowing north and east to the Trent river. The valley of this stream must have been 30 feet below the highest level of lake Iroquois, implying a narrow strait running north from Colborne, making an island of the mass of high morainic hills between this and the river Trent, or perhaps a peninsula united to the mainland toward the west only by the gravel bar just referred to.

Beyond Silver lake the Iroquois terrace is strongly marked on the southeast flank of lofty morainic hills, where the wide expanse of open water allowed powerful wave action; and north of Brighton gravel bars once more occur at different levels, the difference being greater than at the last point. Three miles northeast of Trenton the large island ends in a bold promontory, rising in a very striking way above the flat Iroquois terrace with its gently sloping surface thickly covered with boulders.

Here the separation of the gravel beaches and terraces is still greater than at Brighton or Silver lake. As Dr. Spencer gives the level of the old shore as 436 feet above Ontario in one paper and 386 in another, and as this is a specially interesting point on the old shore, a line of levels was run from the Trent, practically at lake level, to the highest terrace, giving the following results:

	Above L. Ontario. feet.
Highest terrace, faint	450
Well-marked terrace	441
Rear of gravel beach	386
Slightly lower bar on road..	374
Rear of boulder pavement	339

The most prominent level is that at 386 feet, and it is that which Dr. Spencer has adopted in his later writings as the true water level. His earlier esimate, unless a misprint, may have been obtained from the terrace, which is put at 441 feet in the table above. The morainic hills behind rise at least a hundred feet higher and command a splendid view of the country in all directions except west. One of the highest hills some miles to the northeast appears to have a terrace cut upon it, and was later found to be an island.

If we start at the lowest beach, 374 feet above Ontario, we find the highest water level to be 76 feet above it; but if we take the two best marked features, at 386 and 441 feet, the difference in level is 55 feet.

Rounding the point of the hills the separated terraces may be followed southwestwards for about a mile and a half into a bay, and then north for a mile, after which the shore runs west, but is not very distinct, owing partly to the sandy, shifting nature of the soil, and no doubt also partly to the sheltered position, where wave action must have been feeble. It proved impossible to carry the line round to the old strait now occupied by the creek draining Silver Lake.

Islands to North and East

Owing to the faintness of its shore the great bay to the northwest of the Trenton promontory could not be mapped satisfactorily, and must be left until contoured maps make it possible to fit its position by the elevation. The bay probably goes as far west as Castleton and contains quite an archipelago of small and large islands, including twelve which have been wholly or partly mapped within the great bend of the River Trent. Some of these islands were low and show only the lower beaches, while others rise high enough to provide a respectable series of beaches, and some of the latter have been measured by hand level. There are also shoals, flat-topped drumlin hills with stones scattered thickly over them, which did not quite reach the surface of the bay, though sufficiently wave-washed to remove the clay from the bouldery till during the later stages of lake Iroquois.

A low-lying island with widespread gravel deposits lies about four miles north of the promontory, near Trenton. Another rises between this and Codrington, and a larger one between this and Warkworth. There are smaller islands west, northwest and north of the latter town, and a long island between it and Campbellford. The largest island of all extends for about seven miles northeast, and southwest a mile

Digitized by Google

or two north of Campbellford, and displays a fine set of beaches toward the northeast, where the hills fall away rapidly toward the Trent River at its southward bend, after the northeasterly course from Rice Lake.

At this point well-developed beaches were found at 432, 442 and 475 feet above lake Ontario, the highest 43 feet above the lowest, and Dr. Gilbert, here or a little southwest, found a beach ninety feet above the lowest. Except on the north no land high enough to receive the beaches can be seen for many miles.

There is a small island about two miles north of Frankfort, with four gravel beaches, the highest 47 feet above the lowest; and across the river an island six miles long runs off to the northeast as a central hill bordered by the Iroquois terrace. About halfway along this island on the northwest side is Oak Hill lake, a pretty sheet of water with no apparent outlet, really a bay of lake Iroquois, cut off from the main lake by a massive gravel bar, through which drainage now takes place as springs. People living near the lake report that it has a depth of 43 feet, as shown by soundings, and that the only fish in it before it was artificially stocked were minnows. A fine wall of small stones pushed up three or four feet by winter ice encloses most of the shore.

By hand level from the nearest point on Trent river, the elevation of Oak Hill lake above Ontario is made 435 feet. A boulder pavement begins at 398 feet, and gravel bars occur at 414, 430 and 466 feet, the last being the very well-defined bar enclosing the lake toward the northwest.

At the northeast end of the same island a small, marshy pond is enclosed in a similar way. To the north of this extensive boulder pavements and gravel beaches are found, and leveling from Madoc Junction makes their elevations 395 (small beach), 450, 460 and 475 feet, considerably higher than those near Oak Hill lake, three miles to the southwest, and not wholly accordant with them.

From this point a hill can be seen rising above Iroquois level, five or six miles to the northeast, the last place where the beach as been found. This island, which is 140 miles from Hamilton, in a direction 57 degrees east of north, rises as a prominent morainic ridge a little southeast of the railway between Madoc Junction and Madoc at mile 19, the nearest station being West Huntingdon. Gravel beaches occur at 440, 492 and 498 feet above Lake Ontario, the last being the highest level yet observed with certainty on the Iroquois beach in Canada.

All the hills referred to as rising above Lake Iroquois in the form of islands are morainic, most of them formed of boulder clay, but some partly kame-like with extensive rudely stratified masses of coarse and fine gravel, easily distinguished as a rule from the more uniform, well stratified and horizontal deposits of the old beaches.

North of Trent River

Splendidly formed gravel beaches, evidently made by powerful waves rising in a wide stretch of open water to the east and northeast, rise south of the river Trent a short distance from Campbellford; but the corresponding beaches to the north appear to be wanting. Careful search near Havelock has not disclosed any, though kame gravels somewhat suggestive of wave work are found just north and northeast of the village at levels of 454 to 500 feet; none of these, however, are horizontal enough for beaches. Search has also been made north of Blairton station on the C.P.R., with similarly doubtful results. In the former region flat sheets of limestone simulate water levels, but north of Blairton the hills are rounded knobs of Laurentian rock, on which waves could leave little impression, and the sparse drift materials are sand instead of boulder clay, providing poor materials for beach formation.

The same conditions prevail north of Madoc, near Eldorado and Malone, where the ground rises high enough to show the beach, flat limestones capping the higher hills in places, other hills being Laurentian or of the Hastings series. Here, however, there are some slopes of boulder clay, which should have retained the terraces and beaches if they had been formed; but no shore terraces or beach deposits were found, though they are so well marked on the island near West Huntingdon twelve miles to the south. Unless better success follows later attempts to find the Iroquois beach to the north of Havelock, Blairton and Madoc, we must conclude that in all probability it never existed there at all.

Southwest of Havelock, however, about a mile west of Trent bridge, a distinct gravel bar is found at 75 feet above the river, or 436 above Ontario, while at 455 feet there is a possible beach. About three miles southwest along the north bank of the river there are beaches at 424 and 436 feet, and still nearer Hastings a beach was found at 447 feet (aneroid). Just west of Hast-

Digitized by Google

ings a gravel deposit of imperfectly rounded stones suggesting river action is found 36 feet above the present river, and similar gravel beds occur farther down the river at about the same or a somewhat less height above it, but these probably have nothing to do with the Iroquois beach.

As the bay leading southwest from the beaches near Campbellford (at 432, 442 and 475 feet) narrows greatly, until at the outlet of the present Rice lake it is only about a mile wide with steep morainic hills on each side, one can no longer expect to find beach terraces or gravel bars of a well-defined character. If the tilt of the Iroquois shore is taken as three or four feet to the mile in this region the long narrow bay must have reached nearly to the southwestern end of the Rice lake basin, though no distinct old shores have been found along this narrow body of water. However, the elevation of the beach north of Port Hope, four miles from the southwest end of Rice lake, is only 311 feet, leaving a difference of 59 feet between them. As the lake is here very shallow and only 30 feet deep at any point, it is probable that the old bay stopped some distance short of Bewdley, the end of the present body of water.

From the map it will be seen that the southwest end of Rice lake is only a few miles from lake Ontario at Port Hope, so that there was a comparatively narrow isthmus in Iroquois days connecting the large morainic peninsula which projects towards Trenton with the mainland to the west. The range of great morainic hills here sinks almost to the level of Rice lake, and the people of Port Hope claim that the most satisfactory outlet for a canal from the chain of lakes connected with Trent river will be toward lake Ontario at this point instead of by the lower Trent to the bay of Quinte.

Lake Peterborough

It was thought at first that the old bay corresponding to Rice lake sent an arm up the valley of the Otonabee river to Peterborough, but an examination of the ground shows that the valley is so narrow and in places so steep-walled between drumlins and moraine ridges that the waters above must be looked on as a separate lake, connected with the bay just described by a short bit of river having but little fall.

Above the short stretch of river lake Peterborough expands to a width of two or three miles west of the Otonabee, and must have covered a wide flat of clay reaching beyond the Midland railway with rather indefinite shores where the moraine rises to the west. The lake narrows toward Peterborough and the deposits become sandy, and finally gravel terraces rise above the flat at the upper end where a great river, probably draining the upper lakes or lake of those days, entered it from the north. The plain of stratified sand is at the level of 388 feet, where the C. P. R. station stands, but ascends to 404 feet at the Grand Trunk station. The highest point in Peterborough, occupied by a park and court house, is a drumlin which formed an island at the upper end of the lake; and a little above this the present river banks show stratified coarse gravel representing the upper limit of delta deposits formed by the old river, one terrace rising to a height of 432 feet.

Below Peterborough the present Otonabee (which is really the Trent above Rice lake) has done very little cutting, its valley being hardly at all depressed below the clay plain mentioned above, but it has a rapid descent above the city. The new lift lock of the canal, which overcomes a rise of 65 feet, is placed in the high morainic hills to the east of the river, and the canal below is at the level of the old lake flat.

The Beach in New York

From the Niagara river at Lewiston the Iroquois beach has been traced by Dr. Gilbert and Prof. Fairchild (19) in a fairly direct course eastwards to Sodus on the south shore of lake Ontario. There a promontory somewhat like that near Trenton projects eastwards, with a great bay to the south, and islands and smaller bays diversify its shores as far as Rome, a long, narrow bay, like that of Rice lake, entering the basin of Cayuga lake. At Rome Dr. Gilbert discovered an old channel forming an outlet towards the Mohawk valley and the Hudson river; so that this great lake was drained far to the south of the present outlet of Ontario, its waters entering the sea at New York.

To the north of Rome the shore turns westward once more as far as Constantia, and then north to Adams Center, where it bends to the northeast toward Waterdown. Two miles south of this town the highest beach is about 454 feet, or a little more, above lake Ontario, the highest point recorded with certainty on the southeast side. Dr.

(19) See map by Prof. Fairchild in Pleistocene Geology of Western New York, 1900. His map has provided the materials for the portion of the old shore east of the Niagara given in the present paper.

Digitized by Google

Gilbert and Professor Fairchild do not carry the beach farther, but Dr. Spencer believes he has found fragments of it in the Adirondacks to the northeast, the last which he has measured being at Fine, 972 feet above the sea, or 726 feet above Ontario. However, as so skilled an observer as Dr. Gilbert, who examined the supposed beaches with Dr. Spencer, dissents from this view, and holds that they have been formed in local bodies of water, or in connection with glacial action, it is doubtful whether this extension of the shore should be accepted.

It is to be noted that the old shore north of the great bay from which the outlet opens is split up into several beaches, as it is on the north shore from Colborne towards West Huntingdon. Prof. Fairchild has made profiles of the different beaches in that region, and finds them irregular in regard to separation, though there seems a tendency for the separation to increase toward the north, the greatest amount recorded being 51 feet, near Waterdown (20).

The general characteristics of the shore in New York State are like those in Ontario, and do not require special mention; but it should be stated that the first recognition of the splitting up of the beaches north of the outlet, both in the United States and in Canada, is due to Dr. Gilbert, who connected this divergence with a tilting of the basin during Iroquois times.

Tilting of the Beach

The early work of Gilbert and Spencer on the two sides of the lake brought out the startling fact that the old shore is no longer horizontal, but is tilted up toward the northeast, the lowest level being at Hamilton, where the beach rises only 116 feet above lake Ontario; and the highest, as far as they know, at Trenton on the Canadian side at 386 feet, and Adams Center and Watertown, in New York, at 411 and 484, a difference of from 270 to 368 feet. The conclusion was reached that the rate of tilt is not uniform, but increases toward the northeast, or, more exactly, in a direction N. 28 degrees E., being estimated by Dr. Spencer at 1.6 feet per mile at the southwest end of the lake, and at 5 feet per mile in the region of Watertown.

In carrying out the present survey of the Iroquois beach a number of elevations have been determined, partly in new localities, partly redeterminations of points of importance which had been examined by Dr. Spencer or others; and some changes in the probable rate and direction of tilt result from these investigations. Special attention has been given to the height of gravel bars, since they may be supposed to give the most uniform results, rising of course a few feet above water level, but probably as in the case of lake Ontario at present, not reaching more than 5, or at most 10 feet above the average lake surface. Determinations of the foot of the shore cliff are less certain, owing to the slipping of loose materials when cut in drift deposits. In some cases the level as determined from the foot of a cliff is considerably below that measured on adjacent gravel bars, so that it has been decided to use only the summits of bars in working out the differential elevation. Unfortunately, there appear to be no statements in print as to whether gravel bars or shore cliffs were employed in fixing the levels in New York State.

Using the latest information and comparing the relative levels of points on each side of lake Ontario, isobases may be worked out showing the direction of the tilt of the old shore, the results giving N. 20 degrees E. as most probable. Accepting this as correct, it is convenient to divide up the shore into somewhat equal lengths along this line, using well determined levels for the purpose, and to work out the rate of elevation per mile in each.

The distance in a direction N. 20 degrees E. between Hamilton (116) and York (190), which stands on a well developed gravel bar a little northeast of Toronto, is 36 1-2 miles and the difference in elevation 74 feet, giving a rate of tilt of 2 feet per mile, differing considerably from Dr. Spencer's rate of 1.6 as determined from the height of Carlton station. It has been found however that the height given in his table for Carlton of 171 feet above Ontario, is about 7 feet below the summit of the gravel bar to the north of the station.

The next section chosen is from York to the gravel bar near Quay's, north of Port Hope, the rise being from 190 to 311 feet or 121 feet in 35 1-2 miles, averaging 3.4 feet per mile. Up to Port Hope the beach is practically a unit, the only variations being due to more powerful wave action in some places than in others, and not amounting at most to more than 5 or 10 feet.

From Port Hope to West Huntingdon, the last point to which the beach has been traced, the matter is much more complicated, since the old shore is split up into several beach levels, probably diverging, and the question arises which level should be taken for comparison, the lowest, the highest or some prominent intermediate beach.

(20) An. Rep. N. Y. State Geologist, 1900, p. r. 110.

Digitized by Google

The first carefully measured point where the divergence is distinctly marked is Trenton, where good beaches occur at 374 and 386 feet, and a well-marked terrace at 441, a faint one appearing about ten feet higher. As Trenton is 18 miles in the direction N. 20 degrees E. of Quay's, the tilt works out to 3.44 feet per mile for the lowest beach, 4.17 for the next, which is the best defined of all, and no less than 7.16 for the terrace at 441 feet.

If we compare with the beaches near Havelock, Madoc Junction and Campbellford we find more difficulty still, for the elevations at the three points, respectively 31, 32 and 33 miles in a direction N. 20 dgrees E. of Quay's, are not entirely in accord. The lowest beaches southwest of Havelock and north of Campbellford are at 436 and 432 feet, giving a tilt of 4 and 3.67 feet per mile. The highest beaches near Madoc Junction and Campbellford are at 475 feet, giving a rise of 5 feet per mile; but no corresponding beach has been found with certainty near Havelock. Dr. Gilbert however has found a difference of 90 feet between the lowest and highest beaches near Campbellford, which would greatly increase the rate per mile for the highest.

On the West Huntingdon island there are good beaches at 492 and 498 feet, but higher water levels could not be recorded here, since the island does not rise above the last gravel bar. As the distance northeast of Quay's is 37 miles, the differential elevation is 5 feet for the highest.

The Mohawk Valley Outlet

Dr. Gilbert showed long ago that lake Iroquois drained through the Mohawk valley toward the Hudson, and drew the inference that if the known tilting of the land was in progress during the existence of the lake its effects should be recorded in the beaches. The splitting up of the gravel bars just referred to as occurring northeast of Colborne he observed, and connected with this cause, and believed that Burlington heights and other points near Hamilton would be found to give evidence of lower water levels at the southwest end of the lake during its earlier than during its later stages. Between the extremes there must be of course a pivot where the water level remained constant (21). Professor Fairchild looked for evidence as to such a differential change of levels north of the outlet near Rome, and found the beaches greatly split up, as they are in eastern Ontario, but did not think that a regular spreading apart of the beaches could be proven (22), and concluded therefore that differential elevation during the lifetime of lake Iroquois was improbable.

The lack of regularity in the spreading of the beaches is apparent in Ontario also, though there is a marked increase in the divergence as one goes northeast. The first well-marked splitting up of the levels is at Silver lake, three miles northeast of Colborne, where there are three beach levels, the highest 28 feet above the lowest. Near Trenton, nine miles farther, the separation of the two main water levels is 55 feet, giving a rate of spread of 3 feet per mile. On the island north of Campbellford, 13 miles farther northeast, it is only 43 feet by my determinations, but 90 by Dr. Gilbert's. The latter difference between the highest and lowest beaches would give a divergence of 2.7 feet per mile between Trenton and the point just mentioned.

If the beaches spread 28 feet at Silver lake and 55 feet near Trenton, 9 miles away, in the direction N. 20 degrees E., they should converge and meet 9 miles southwest of Silver lake, about at Quay's gravel pit north of Port Hope. If a line is drawn at right angles to the direction N. 20 degrees E. from the outlet of lake Iroquois, near Rome, it passes a little south of Quay's, so that two modes of attacking the question agree pretty closely in their results, thus confirming each other.

If the divergence observed northeast of the hinge line from the Mohawk valley continues to the southwest, we should expect some evidence of lower water levels in that direction, though the divergence cannot be assumed to be so great as 3 feet per mile, since the rate of differential elevation per mile is less to the southeast. If we take the two as proportional we shall have a divergence between Port Hope and York of 2.45 feet per mile, which would put the lowest formed beach at York or Toronto at about 86 feet below the highest beach, which of course is the only one left exposed. If we carry out the same reasoning with reference to Hamilton, we find between Toronto and Hamilton an additional divergence of about 1.44 feet per mile, which amounts to 52 feet, or in all to about 139 feet. This would carry the original water level of lake Iroquois at its southwest end, below the present level of Hamilton bay, but the data obtained from the spreading of the

(21) 6th An. Rep. State Reservation at Niagara, 1888-9, p. 70; also History of Niagara River, Smithsonian Rep. 1890, p. 241.

(22) Pleistocene Geol. Western N.Y., 1900, p. r. 111.

Digitized by Google

beaches northeast of Port Hope are not sufficiently certain to make these results more than a rough approximation to the truth.

On the other hand, we have a considerable amount of direct evidence bearing on the question. At Toronto what are almost certainly Iroquois beach deposits, though half a mile south of the old shore, rest on an eroded surface of interglacial clay about 70 feet below the Iroquois beach level to the north. As the last ice advance intervened between the laying down of the interglacial clay and the opening up of the Iroquois basin, we must suppose that the upper sheet of boulder clay, which is quite thick at points both east and west, was removed during a time when the water stood 70 feet lower than at the last stage of the Iroquois lake.

At Hamilton an old soil with trees and bones of various animals was found in the Hunter street tunnel 30 feet below the top of the Iroquois gravel bar, so that the earlier water level must have been lower than that. To the west of this, as shown on a previous page, mammoth tusks and bones, evidently not waterworn, occur 33 feet above the level of Ontario, or 83 feet below the top of the Iroquois beach half a mile away. The bones and tusks occur together in a layer of sand, and similar remains are found a few feet higher up (42 feet above Ontario) in another sand pit a short distance away, so that we may suppose that the bones were not washed to their present resting place, but that the animals died where the bones are found. If this supposition is correct the water of lake Iroquois must at that time have been 80 feet lower then than at the latest stage.

The great thickness of the gravel bar at the Desjardins canal, and its extraordinarily narrow wall-like form suggest the same thing. When the canal was cut clay was found at about lake level; above this there are 57 feet of stratified sand, and then coarse gravel, largely cemented to conglomerate, to the top. The upper 60 feet of coarse gravel, scarcely at all interbedded with sand, could hardly have been piled up in deep water, but must have been built to the full height by successive additions as the water rose.

We have then evidence of two kinds showing that differential elevation took place during the existence of lake Iroquois: the splitting up of the beaches toward the northeast, and at the other end the presence of old soils and the remains of land animals buried from 30 to 80 feet beneath the latest gravel bars of the old lake. The evidence seems sufficient to settle the matter.

In working out the differential elevation of the beach as now found we must keep in mind that from Hamilton to Rome on the south of Ontario and to Port Hope on the north the level is that of the last stage of lake Iroquois and that its continuation toward the northeast is to be looked for in the lowest prominent beach of the series found beyond the hinge line. The higher beaches, beyond the line where they split up, represent continuations of buried beaches toward the southwest, the highest towards the northeast corresponding to the lowest toward the other end of the basin. The difference in present altitude of the extreme ends of the earliest beach of all cannot be less than 500 feet, and may be greater than that, while the difference of level between the ends of the latest formed beach (116 at Hamilton and 498 at West Huntingdon) is only 382 feet.

Conditions of Iroquois Time

The swinging of the old beaches about a fulcrum running 20 degrees north of west from the outlet near Rome, New York, gives clear proof that the body of water was completely enclosed and not an extension of the Gulf of St. Lawrence; for otherwise the divergence of the beaches would run from end to end of the old shore, growing less however toward the southwest. This confirms the evidence as to the character of the water afforded by the unios found in Iroquois gravels in New York, and the campelomas, etc., in deposits of that age in Toronto. The water was fresh, (23).

There is little doubt as to the character of the dam. It must have been the ice of the retreating glacier, which had withdrawn from the basin of lake Ontario, but still blocked the St. Lawrence valley to a height sufficient to turn the water southeastward into the Hudson. The highest part of the old shore, near West Huntingdon, is now 742 feet above the sea, but doubtless it then stood much lower, since the deformation recorded in the beach has taken place since then. Still it was high enough above sea level to allow of a current through the Mohawk valley to the Hudson.

The exact position of the ice dam is not easy to determine, partly no doubt because the barrier was slowly shifting toward the northeast. One would think that morainic deposits should record the stages of retreat, but so far no definite evidence of the kind has been found. Some points however seem fairly certain. There was wide open water surrounding the old islands near West

(23) Bull. Geol. Soc. Am., Vol. 10, p. 167.

Digitized by Google

Huntingdon and north of Campbellford, for the series of beaches at these points gives evidence of heavy wave action; and the latter point must have been exposed to open water for a long time, for there is a range of 43 feet between the highest and the lowest beach. It is curious however, to find only the lowest beach well marked a few miles away, to the north of Trent river, as if the region, which is drift-covered and well adapted to receive a beach, had been protected from wave action before that time by still unmelted ice.

The ice front appears to have covered the high hills north of Madoc and probably for a long time extended over Napanee and parts of New York State north of Watertown; and Dr. Gilbert's early map shows its position perhaps as well as any map that could be constructed now (24).

The climate was probably considerably colder than now but not quite Arctic, for even in the early days of lake Iroquois tamarac and spruce lived near its shore at Hamilton, and mammoths and caribou were very common, while wapiti, buffalo and beaver occasionally visited the shore, and man himself apparently fashioned stone tools at Toronto Junction. The crumpling of sand beds probably of Iroquois age in east Toronto may indicate the shove of icefloes or bergs, but the water was not too cold to be inhabited by a number of shell fish which still live in lake Ontario.

Duration and Age of Beach

The old shore of lake Iroquois is as mature as the present shore of Ontario, and it probably required as long a time to carve down its promontories and build its gravel bars and spits across the mouths of wide bays as the present lake has needed for operations of the same nature. Unfortunately, we have no very trustworthy chronometer for the work of either. That they required about equal amounts of time, and that both together have occupied a large part of the time since Niagara began to cut its gorge from Queenston heights to its present position seven miles to the south, is pretty certain; but opinions as to the age of Niagara vary from 5,000 or 7,000 years to 35,000, and a final settlement of the time limit has not been reached. I incline to the longer estimate, since 2,500 years seems far too short for the work of lake Ontario in cutting down Scarboro' heights and shifting the materials ten miles to the westwards to build up Toronto island.

The question may be approached from another side. How long did it require to deform the old beach to the extent of 500 feet since the lake began, or 320 feet since its beach was finished? If Dr. Gilbert's estimate of 42 feet per hundred miles per hundred years, as drawn from the shifting of water levels on the present lakes, is correct, the time since the Iroquois lake was drained off is not less than 67,000 years, and since its beginning not less than 100,000 years. The assumption that these processes of elevation and depressions go on uniformly is however decidedly improbable. It is more likely that such changes begin gently, attain a maximum, and then slowly decline; and the present rate of tilting probably represents the slowing down of the movement before it finally ceases, so that the change of level may have been much more rapid in earlier times.

However, the movement of elevation may not represent a simple wave. There may have been accelerations and retardations in the process, the latter corresponding to the better marked beaches to the northeast of the hinge line. Altogether this method of estimating the time gives only vague suggestions, and the other seems the more trustworthy. We may conclude then that the Iroquois lake lasted not more than 17,500 years, and probably less; and that the time since it was drained has been of something like the same duration.

Between the time of lake Iroquois and that of lake Ontario intervened the comparatively short period of retreat of the ice from the St. Lawrence valley, indicated probably by beaches rising to 135 feet above lake Ontario in the Bay of Quinte region; and a somewhat longer period when the gulf of St. Lawrence invaded the basin of lake Ontario, though the waters of the basin appear to have remained fresh from the large inflow of the Niagara and other rivers.

Economic Geology

The Iroquois beach in Ontario is of greater importance economically than at first would be imagined, since it affects in various ways the farmer, the railway engineer and the builder. It is not an accident that the old shore is the favorite locality for main roads and for farmers' houses and buildings, for the top of the shore cliff in clayey regions gives the driest

(24) 6th An. Rep. State Reservation at Niagara, 1888-9, p. 69.

Digitized by Google

locality in the farms it traverses, and the gravel spits and bars where the ground is low and muddy are even more important as giving good drainage and solid foundation for roads and farm premises. The gently sloping terrace below the shore cliff in most cases furnishes the richest clay land of the country, as below the "mountain" in the fruit-growing region south of Lake Ontario, and the farms "at the front" to the north of the lake; but toward the east these fields are apt to be marred by the stones washed out of the boulder clay cliffs by waves of the ancient lake. Even these boulders, however, are put to use for foundations, and where derived from limestone regions, for lime burning to supply local needs. The gravel bars across the mouths of old bays supply the favorite road-building material, especially in districts where clay is the prevailing soil, and the township roads are better where such gravel pits can be opened than elsewhere. The stone roads of the country are largely metalled with broken stone from the boulder pavements of the old beach.

The railroad engineer makes good use of the level terrace of the Iroquois shore, the Grand Trunk occupying the flat land near the foot of the old shore cliff for many miles south and north of the west end of Lake Ontario, while the Canadian Pacific does the same thing near Toronto. The wonderful gravel bar at Burlington Heights has furnished a high level causeway across the marshy flats between Hamilton and Dundas, which both railways and gravel roads have been glad to put to use. Even more important to the railways has been the convenient supply of ballast which the gravel bars afford in different parts of the Province. Such pits have been opened near Waterdown, York, Brooklin and Quay's, for example.

The importance of the old shore to towns and cities is well shown by the fact that many of them are planted on the well-drained gravel bars or the flat terrace of the old beach, St. Catharines, Hamilton and Toronto all occupying this position. The clay flats of old bays or lake slopes are used in many places for brick-making, the shallow water sand deposits are used in making mortar and cement and the shore gravels serve as road metal and for concrete. How serviceable these materials are may be seen from the immense excavations in the old gravel bars at Hamilton, and at Toronto Junction and York, where similar bars provide sand and gravel for use in the city. The red brick burned at Hamilton are made from the clay beds of Iroquois age to the west of the city in what was shoal water of Dundas Bay.

The old beaches of Iroquois levels to the northeast are too high up on the flanks of the great moraine (the Oak Ridges) to be of much use for railways and towns, but almost everywhere they are employed for local roadmaking and other purposes.

Lower Water Levels

When the great ice sheet withdrew from the northern flanks of the Adirondacks so far as to give a lower outlet eastwards than that through the Mohawk valley, the water fell successively to lower and lower levels, indicated, as shown by Dr. Gilbert and Professor Woodworth, by terraces and spillways where the drift has been scoured off to the solid rock by the rush of water between the ice front and the northern slope of the mountains. It is not likely that any of these halts were of long duration, but some of them seem to have been long enough to permit the cutting of terraces or the formation of beaches in the Bay of Quinte region. Later the ice withdrew so far to the northeast that the upper St. Lawrence and Ottawa valleys were free. There may have been a low level lake dammed by ice in the lower St. Lawrence, and emptying by the Champlain valley into the Hudson, as thought by Mr. Warren Upham, but no beaches have been certainly connected with it in Ontario.

Later still the St. Lawrence valley was wholly cleared of ice, and the sea entered it as an enlarged gulf of St. Lawrence, reaching past Montreal and expanding as a wide sea from the Ottawa above Pembroke to a point west of Ogdensburg in New York State.

The land stood so low at this time that sea level rose perhaps 100 feet above the surface of the present lake Ontario, and one would expect to find salt water beaches in the Ontario basin, but no marine shells have been found west of Brockville, so that we may suppose that the Niagara and other rivers sufficed to keep this great body of water fresh. The marine deposits of Ontario have been described previously (25). but part of the ground has since been covered more carefully and the results of the examination will be given here.

No distinct beaches lower than the Iroquois have yet been found in the western part of the Ontario basin, and

(25) Bur. Mines, 1901; Sea Beaches of Eastern Ontario. pp. 215-227.

Digitized by Google

the first clear evidence of water levels above the present lake are found near Port Granby, an old lake port between Newcastle and Port Hope.

Port Granby to Trenton

South of Newtonville, where a stream enters lake Ontario, a small terrace, probably wave-cut, shows at 28 feet above the lake or 274 feet above the sea, hills of boulder clay rising on each side, and the present shore cliff shows some stratified gravel overlying boulder clay. A mile or two east another terrace occurs at Port Granby, where a stream comes in. The present storm beach rises five feet above lake Ontario; the flat terrace at the postoffice is 28 or 29 feet above it and a stream terrace a little to the north rises about five feet higher or 280 feet above sea level.

Three and a half miles east of Port Granby where a bay-like depression parts the hills of boulder clay a gravel bar 18 feet above the lake runs a little north of west and south of east. evidently representing a still lower stage of water. From this point east to Port Hope no beach formation was found. In the town itself a clay flat 30 feet above the lake is possibly a terrace, and a higher flat at the foot of the drumlin on which Trinity School stands may be another, but both are too indefinite for certainty.

Similar beaches to those near Port Granby occur again east of Cobourg, a boulder pavement ending 23 feet above the lake at the foot of a low shore cliff. A little north an old island is largely covered with gravel bars, the highest 52 feet above Ontario or 298 feet above the sea. Still farther north and a quarter of a mile beyond the Grand Trunk railway, a clay flat ends abruptly in a well-marked shore cliff cut in bouldery clay hills, at about 330 feet above the sea (aneroid) and with few interruptions this shore can be followed to Grafton, where a little south of the village the height is 330 feet as found by hand level.

East of Grafton also gravel bars occur at lower levels,274 and 295 feet; and a mile west of Lake Port, near Colborne, there is a very well-defined gravel bar more than half a mile long with a front slightly convex toward lake Ontario, but a general east and west direction. This bar is 50 or 60 feet wide, and ascending from the present lake shore one finds a boulder pavement up to 23 feet, a lower bar up to 31 feet, and the highest rising to 50 feet.

Near the village of Colborne, but somewhat to the west the clay flat with shore cliff seems to run out, and gentle hills project southward as a vague promontory. To the east there are sand hills interfering with the tracing of the beach, but just east of Brighton, it once more becomes distinct with a high shore cliff against hills of boulder clay at a level of 334 feet above the sea, or 88 feet above Ontario. From this to Trenton the shore is well-defined.

Near Trenton

Near Trenton the beach levels suddenly become more numerous and better defined, probably because the body of water whose waves did the work was greatly widened toward the east. At the central Ontario railway station near the bay of Quinte a wide gravel bar runs northward at a level of 26 feet above the bay, which is the same as that of lake Ontario; and on the flanks of the great esker which forms so conspicuous a ridge to the northwest of the town, there is a pretty well-marked gravel terrace rising 78 feet above the bay. A sharply defined cut terrace at the southeast end of the esker stands 135 feet above the bay, and runs as a narrower shelf along each flank of the ridge, which rises to 190 feet at the highest point.

To the north of the Grand Trunk station at Trenton esker-like sand and gravel ridges rise as islands from the lowest flat, almost certainly a water level, and a gravel bar near a shore cliff at the Roman Catholic cemetery is 42 feet above the Trent river at the level of the bay.

Where the wide valley of the river Trent escapes from the morainic hills a series of terraces rises above it on the west side, the lowest 31 feet above the level of the bay, the second, which is also the best formed, at 55 feet, while a less defined terrace reaches 81 feet. The top of a stony ridge just above is flat, and may also represent a water level at 127 feet, but this is doubtful. The terrace at 55 feet (301 feet above the sea) is repeated at the same level by a broad gravel plain east of the river, and a cut bank south of the railway bridge shows a few feet of stratified gravel overlying shaly Trenton limestone.

It has been noted by former students of the region that the valley of Trent river is a misfit, being far too large for the present stream, and this has been explained by supposing that the waters of the upper lakes once discharged in this direction before the upward tilt of the region toward the

Digitized by Google

northeast forced them into their present circuitous course by lake Erie and Niagara Falls.

East of the Trent the old shore, which is fairly constant from Cobourg to Trenton, could not be traced farther, though hills of boulder clay rise high enough to receive it not far from the river. Nor has it been traced with certainty north of Belleville, though something like a boulder pavement at 377 feet above the bay is found about a mile north of the city. About ten miles to the north a gravel pit near the Belleville and Peterborough railway stands at 140 feet above the bay or 386 above the sea. The two elevations just given were determined by aneroid, the previous ones by hand level.

Prince Edward County

Crossing the narrow isthmus, now cut by the Murray canal, which transforms the Prince Edward peninsula into an island, low land follows, partly formed of gentle swells of till, partly of the greatly decayed surface of the shaly Trenton limestone; and it is not until Wellington is nearly reached that clear evidence of old wave action is found. Here a well formed bar more than a mile long runs parallel to the present shore, but at a height of 91 feet above it. It was apparently formed in the same way as the present long bar stretching across the mouth of a swampy bay to the east of the village, connecting it with the interesting series of sand dunes on the opposite shore. The "sand banks," which rise 50 or 60 feet above the lake, are a favorite and picturesque resort for parties from Wellington and Picton.

East of Wellington the tableland of Trenton limestone so characteristic of Prince Edward county rises, often as a steep escarpment with nearly level top, and at its southeast end, where it approaches the shore of lake Ontario at Waupoos and Top of the Rock, good beaches are found at several levels. At the former village, which lies between the cliff and the shore, a boulder pavement begins at 50 feet above the lake and slopes upward to 68 feet, beyond which is a gravel terrace with fairly well rounded stones at 78 feet, another gravel bar at 90 feet, and another good bar at 94 feet. There may be a fourth at 113 feet, but the evidence is rather faint. There is a lagoon between the second and third bars, and they are formed of pebbles as well-rounded as those of the present beach.

Near the Top of the Rock, two or three miles to the west, terraces or gravel bars occur at 39 feet, 49 feet, and 73 feet, the last with a low limestone cliff in the rear

On the bay of Quinte side of Prince Edward county much of the shore is formed of sheer limestone cliffs rising from 150 to 200 feet above the water; but near some of the bays terraces may be seen, as west of Cressy, where a well-defined sand terrace stands at 42 feet, with a doubtful water level at 57 and a good beach line and bar at 83 feet. The top of the cliff here rises 192 feet above the bay of Quinte.

At Glenora, where flour mills and foundries are run by water power from the Lake on the Mountain, terraces are seen to the west of the mills, which are at the foot of a vertical cliff, in a bay-like recession of the escarpment. The lowest, which is poorly marked, is at 16 feet, the second, also poorly defined, at 55 feet, and the highest, which is well cut at the foot of the cliff, is at 62 feet.

The Lake on the Mountain appears to be a rock basin, since its outlet is over the limestone of the cliff. Its surface is 176 feet above the bay of Quinte, and its depth is said to be 98 feet at the deepest point. It is about three miles long and three-quarters of a mile wide, with a drainage basin of about four square miles, the rocks rising 30 or 40 feet above it to the south. The stream flowing from it, as might be expected, is very small, but the great height of the fall, 175 feet, makes it of some importance, since the four small turbines of four to six inches diameter generate 200 horse power. It is said that 60 feet off shore at the mill the bay of Quinte is 100 feet deep, and not far out a depth of 150 feet is reached, so that the real height of the cliff is much greater than its apparent height. To the north an almost continuous cliff rises beyond the bay leading toward Picton and stretches most of the way to Deseronto.

Beach levels were looked for between Glenora and Picton, but only one was found, at 135 feet above the bay; a more careful search may disclose lower beaches however on the drift-covered hill-sides of the narrow valley.

Prince Edward is one of the most interesting counties in Ontario in some respects, formed as it is of two flat tablelands rising in steep precipices above the bay of Quinte on the north and lake Ontario on the south, with however a large area of quite low ground toward the west from Wellington to the Murray canal. A narrow valley separates the two blocks of high land, running between Picton and Wel-

Digitized by Google

lington, and at the higher water levels described above the two plateaus were islands. In spite of the tableland character of much of the county it nowhere rises to a greater height apparently than 220 or 240 feet above the adjoining waters, and during the time of lake Iroquois it was deeply submerged.

Belleville to Gananoque

On the north shore of the bay of Quinte there has been no success in the search for beaches, though a number of promising localities were examined. Near Napanee hills rise to 407 feet above sea level, or 261 feet above the bay, with boulder clay in many places of fair thickness, but nowhere was a beach discovered. There are stratified clays covering stratified sand and rising 21 feet above Napanee river, which is at the level of the bay below the town, but no higher terraces are to be found. East of the river above its fall at the town there are flats that somewhat suggest water levels, but these are almost certainly caused by horizontal beds of the limestone exposed in a quarry near by. As there would be a a wide sweep for waves from the south against this hill, one would expect to find beaches there.

The next point examined for old beaches was Kingston and its environs; but near Bath, while passing by steamer, one observes what may be a terrace with shore cliff east of the village. The hill near the fort east of Kingston rises nearly 130 feet above the lake, with some boulder clay, but shows no evidence of the lower beaches. However, the amount of drift is small, the rock consisting of Laurentian granite capped with limestone and coming near the surface in most places. The hills three or four miles north of Kingston rise still higher, but were not explored.

Still to the east the region near Gananoque was carefully searched for beaches, almost every hill rising high enough to take the upper beaches having been visited, but without result, though there should have been a wide stretch of water to the south. It should be noted, however, that most of the hills consist of rock without much drift. Near Marble rock, a few miles up Gananoque river, there are slopes of stony till resting on hills of quartzite and granite, which might be expected to record wave action if there had been upper water levels of any duration, but nothing of the kind was seen.

In the lower ground there is a broad, nearly flat plain of clay, forming good farming land to the east of the Thousand Island station on the Grand Trunk, much suggesting a water level; but occasionally a gently rounded surface of Laurentian shows through it, and more often flat-lying standstone crops out, so that apparently the level surface of the plain is largely due to this and not to pleistocene water action. Lower down there is some stratified sand toward the west end of Gananoque rising as a cliff 46 feet above the St. Lawrence, which is still practically at the level of lake Ontario. Sand hills a few miles west of Gananoque have the appearance of kame deposits of glacial and not wave formation.

East of Gananoque

The region east of Gananoque as far as Brockville and north to Athens and Delta was traversed in numerous places with results no more conclusive than before. The only probable water level is a continuation of the clay plain near Gananoque past Lansdowne and Mallorytown; but here also the level surface is probably due to flat beds of sandstone or limestone, which occasionally crop out as a low escarpment. The higher hills are usually of rock, though sometimes morainic.

Exploration near Smith's Falls and Perth was equally unsuccessful, though kame-like deposits exist at the former place.

As marine shells occur at Brockville, the region surrounding the town was more carefully explored, but without finding any well-marked raised beaches. The shells, which seem to be small macomas, are found in the stratified clay worked for brickmaking just north of the Grand Trunk railway. The clay rises to 285 feet above the sea, or about 40 feet above the St. Lawrence, and seems to have been deposited in a narrow bay running up the valley of the creek, with a promontory of boulder clay hills, on which the higher part of the town stands, rising 100 feet higher and projecting eastwards.

Similar stratified clay, in which, however, no fossils have yet been found, is exposed by the creek at Lyn 3 or 4 miles west of Brockville. The drumlin hills north and west of the town were not found to be terraced, and the higher hills near Lyn and north of that place showed no signs of lake or marine action, though there are structural plains caused by flat limestone or sandstone capping the irregularly rounded summits of the Laurentian. There is stratified sand on the shore of the St. Lawrence at a cemetery west of Brockville, but no shells were found there, and the sand rises only 20 feet or so above the water, with no suggestion of a terrace.

Digitized by Google

East and northeast of Brockville marine deposits with numerous shells have been found at many points, as noted in a former paper, and it was thought well to re-examine the points nearest to Brockville. Near Maitland a gravel ridge or bar south of the Grand Trunk railway, containing fragments of marine shells (macoma), was leveled once more and found to rise 331 feet above the sea, instead of 350, as determined formerly by aneroid. The shell pockets in the Gladstone gravel pit a few miles farther east, not for from Prescott, were examined again, and their level determined as 320 feet above the sea, confirming the aneroid work done in former years.

Old Beaches in New York

As the search for raised beaches on the north shore of the St. Lawrence met with so little success, some attention was paid to the south shore also, and with better results. The Canadian islands east of Kingston scarcely rise high enough to record any but the very lowest beaches, and on Howe island, the only one studied, little of interest was found. Well stratified clay rises as a low cliff near the east end, but without any distinct beach level, and the thin boulder clay on higher parts showed no sign of water action. A few isolated hills of Archaean rocks rise through the Trenton limestone forming most of the surface, one reaching 126 feet above lake Ontario, but too bare of drift materials to preserve much record of wave action.

On Grindstone Island, south of Gananoque, and just south of the international boundary, rolling hills of till give better opportunities for wave action, and here well-formed gravel beaches occur at 125 and 140 feet above the river. Morainic hills west of Clayton scarcely rise high enough for the highest of these beaches, but stratified gracel occurrs on top at about 132 feet above the St. Lawrence. At lower levels there are stratified clays with sand beneath rising 41 feet above the river, and similar materials are found in cuttings made by a creek to the south of the town, with a clay plain at 63 feet. Near Lafargeville, six or seven miles to the southeast, morainic hills show good gravel bars and beaches facing northwest at 204 and 209 feet, and less certainly at 262 feet above the St. Lawrence.

Near Ogdensburg, opposite Prescott, flat delta deposits, mainly of sand, rising 36 feet above the river, contain numerous marine shells, chiefly large macomas, though saxicava and cylichna were found also. At Norwood, N. Y., 24 miles east of Ogdensburg, marine shells are found in stratified gravel 115 feet above the St. Lawrence, or about 360 feet above the sea. A well-formed gravel beach occurs on a morainic hill northeast of the town at a slightly higher level.

I am under great obligation to Dr. Merrill, Director of the Geological Survey of New York, and to Professor Woodworth of Harvard University, for providing the opportunity to visit these old beaches and others in the Lake Champlain region, farther to the east.

As the scourways north of the Adirondacks, where the waters rushed past the edge of the ice during its slow retreat, determined the levels of the lake behind, it is evident that they must have controlled the series of beaches lower than the Iroquois level and above sea level, but Professor Woodworth's report must be awaited for detailed connections between them. He is of opinion that the higher beaches were formed at successive stages of the freshwater lake, and the lower ones formed by the sea, and this must be accepted as highly probable. It is, however, not easy to determine just which level should be looked upon as representing the highest marine beach.

Thousand Island Straits

In confirmation of this view we have the negative evidence from the north side of the St. Lawrence, where no well-defined beaches of any description occur, so far as observed, between the Bay of Quinte and Brockville. Is not this accounted for by supposing the region to have been occupied by ice while the beaches in New York were being formed? If this explanation is accepted it may be connected with the similar lack of beaches belonging to the higher Iroquois series to the north and east of West Huntingdon. It is even possible that the ice still held the hills north of Lyn and Gananoque after the salt water had reached the present Thousand Island region, though it is evident that there was open water surrounding Grindstone island. If the limit of marine shells represents also the highest level of the sea when the Thousand Island straits were first opened by the withdrawal of the ice, the water stood 86 feet above the present river at Maitland and 115 feet above it at Norwood, N. Y., 33 miles away in a direction a little north of east. The difference seems rather large however, to be due to differential elevation toward the northeast. At Gananoque 35 miles to the southwest the ele-

Digitized by Google

vation would be less than at Maitland, perhaps not more than 50 or 60 feet above the St. Lawrence, and may be represented by the stratified clay forming plains near Clayton.

If this assumption is correct the strait at Gananoque and Clayton was less than twice as wide as the St. Lawrence is now, and allowing for clay eroded from the river channel since the marine period, not more than 20 or 30 feet deeper than the present channel. At Lyn near Brockville the strait was still narrower, but its shore on the New York side is not exactly known.

It may be considered doubtful however if the upper limit of sea shells really represents the highest sea level in the straits, although the shell beds referred to are of coarse materials, gravel or sand, which could not have been formed in deep water. If the gravel beaches on Grindstone island, in which no shells have been found, are of marine formation, the water level must have been 140 feet above the St. Lawrence, and allowing for erosion of clay by the present river, the depth of water must have been at least 100 feet greater than now. How wide the straits were at the time is uncertain, since ice probably occupied the north shore as far west as Gananoque and perhaps as far as Napanee, but the straits can hardly have been less than 7 or 8 miles wide.

As the ice abandoned the region of the Ottawa and St. Lawrence valleys and the low land between, the sea followed up its edge, its first level being undoubtedly above that of lake Ontario at its northwestern end, but probably considerably below its level at the southwestern end, owing to the difference in altitude of the land to the northeast at the time. Though the water of the Ontario basin stood at sea level it was apparently kept fresh by the rivers which flowed into it, especially Niagara.

As the land to the northeast rose the sea withdrew until the Ontario basin was cut off from the gulf of Eastern Ontario, and the St. Lawrence river began to flow at the Thousand Islands. As suggested by Dr. Spencer, the valley was floored at first with boulder clay and later stratified materials, but these were gradually removed to form the present channel, which is mainly rocky but of an accidental character, the river practically having done no cutting into its present bed of Archaean and Cambro-Silurian rock.

The lowest beaches and terraces in the Bay of Quinte region may have been formed before the drift materials of the Thousand islands were swept off by the river.

As soon as lake Ontario was cut off from the sea, the continued differential elevation toward the northeast caused the backing up of its waters at the opposite end, so that now there are 60 or 70 feet of water in the Niagara river near its mouth and about the same depth in Hamilton bay within the Burlington barrier beach.

Summary

The succession of events in the retreat of the last ice sheet (Wisconsin sheet) may be summed up as follows, paying special attention to water levels in the Ontario and St. Lawrence valleys:

1. Retreat of the ice front to the Oak ridges moraine set free the basin of lake Ontario and drained off lake Warren; but the St. Lawrence valley from Havelock to Watertown in New York was still blocked with ice, so that the overflow from lake Algonquin, occupying the basins of the three upper lakes, was impounded as lake Iroquois, which had an outlet past Rome, N.Y., into the Hudson. The northeastern part of the continent stood lower than at present, so that the water level at the southwest end of lake Iroquois was perhaps below the present level of Ontario, while the northeast end near the ice front is now more than 500 feet higher. The Rome outlet was above sea level, however.

2. Differential elevation in a direction N. 20 degrees E. took place during the existence of lake Iroquois until at its close the water level was 116 feet above the present lake Ontario at the southwest end, but had sunk to 440 feet at the northeast end; a line drawn from Rome to Quay's, north of Port Hope, being the fulcrum about which the swinging took place.

3. The ice dam in the St. Lawrence valley so far melted that water could escape past its front against the northern flank of the Adirondacks, and the level of lake Iroquois rapidly sank. The Rome outlet was abandoned, and the drainage took place northeast at successively lower levels past the Adirondacks, first through lake Champlain to the Hudson, afterwards to the gulf of St. Lawrence.

4. The partial or total disappearance of the ice dam left the St. Lawrence channel, 330 feet or more lower than at present and at the level of the sea, but the influx of fresh water from the upper lakes and the narrowness of the

Digitized by Google

strait near Brockville and Gananoque kept the water fresh, so that marine animals went no farther west than Brockville.

5. Continued rising toward the northeast at length raised the St. Lawrence channel at the Thousand islands above sea level, and the present river began to flow, lake Ontario being cut off from the gulf of St. Lawrence, but with its basin at such a tilt that the water at the southwest end was probably 70 feet lower than at present; while at its outlet it was probably at least 20 or 30 feet higher than now, because of the clay deposits not yet excavated from its bed.

6. The St. Lawrence cut down its channel through the soft drift materials to bed rock in most places, lowering lake Ontario to its present level at the outlet. Gradually the elevation toward the northeast backed up the water at the southwest end of the lake, and this process is still progressing, causing dead water at the mouths of all the rivers entering that end of the lake.

Digitized by Google

INDEX

Page

Aberdeen, iron in 76
Abies balsamea 125
Abitibi, Agricultural Capabilities of, By Tennyson D. Jarvis.....121-134
Birds of..... 126
Fish of 127
Flies of 127
Injurious insects of 128
Soils of 130
Timber of 125
Weather observations in 129
Wild animals of 127
Abitibi Region, Report on, by George F. Kay.....104-121
Climate of 116
Drainage systems of 115
Drift-covered area of 115
Glaciation in 115
Petrography of 116
Physical features of 105
Resources of 115
Topography of 115
Abitibi river.....130, 145, 147
Lignite on the 138
Accipter atricapelus 126
Acer dasycarpum 126
Acer pennsylvanicum..... 176
Acer spicata 126
Acid edge of nickel-bearing eruptive 213
Acid edge of south nickel range..204, 205
Acrophyllum oneidaense, Bill 181
Actinolite in Hastings county..... 11, 92
Actinolite near Actinolite 11
Statistics of 2
Treatment of 11
Uses of 11
Actinolite and asbestos 92
Actinostroma moosensis 188, 184
Stellulatum..... 183
Tyrelli 184
Acton, lime kilns at 14
Addington county.....11, 91
Lead in 11
Muscovite in 91
Admont, manufacture of peat board and paper at 35
Agaskagou lake..... 137, 148
A L 278 and 200 gold locations.....71-72
A L 282 or Sunbeam gold mine....5, 71
Alabastine 21
Alabastine Company 21
Albany river..... 145
Albite 118
Alder 126
Alder blight 129
Allan, Mr. J. G., graphite producer.. 12
Alsophila pometaria..... 129
Allanhurst graphite mine 12
Alnus incana 126, 176
Alnus viridis 126, 176
Alsophila pometaria..... 129
Aluminium, An ore of..... 19
Aluminium from corundum, experiments in production of 19
Alveolites squamosus, Bill 181
Alveolites vallorum, Meek, indet.... 181
Amabel township 24
Amelanchier canadensis.. .....126, 176
American goshawk..... 126
American herring gull 126
American saw-fly 128
American tent caterpillar 128
Ampelis cedrorum..... 126
Amphigenia elongata, Vanuxem 186
Analysis, methods of..... 130
Analyses of iron ore..... 218
Analysis of lime at Milton 15
Anas obscura 126

Page

Anglo-Canadian Gold Estates, Limited, accident at..... 89
Animikie formation 101
Annabergite 98
Anthozoa 161
Apatite 116
Aphis sp. 129
Aphrophora sp. 129
Argenteuil Mining Co, operations of. 74
Arsenic..... 98
In Hastings County 16
On T. & N. O. Ry line 1
Production of 18
Statistics..... 2, 4
Arsenolite 98
Asbestos in Elzevir township..... 99
Asbestos and actinolite 92
Ash-colored blister beetle..... 129
Ashley, mica at..... 91
Aspen leaf roller 129
Aspen poplar 125, 176
Assay Office, Provincial, Report on by A. G. Burrows.....50-51
Analyses, table of..... 51
Assays, table of..... 51
Laboratory determinations.. ....50, 51
Laboratory methods 51
Work for Bureau of Mines..... 50
Work for private parties 50
Athyris spiriferoides, Eaton 186
Atlas gold mine 98
Atrypa reticularis, Linn.. 188
Augite 117
Avicula textilis..... 188

Baden-Powell gold mine 65
Balm of Gilead 125
Balm of Gilead leaf gall..... 129
Balsam..... 125, 176
Banded purple, The 129
Banksian or jack pine.....125, 176
Bannockburn, iron pyrites mines near 22
Bantiste lake..... 112
Basic edge of nickel-bearing eruptive 213
Basilarchia arthemis 129
Basin of nickel-bearing eruptive ... 206
Battle, John, Estate of 18
Bauxite, an ore of aluminium..... 19
Beach, Iroquois, in New York..... 233
Beachville, lime kilns at..... 14
Bear 127, 178
Beaver 127
Beaverton, peat factory at 29
Benzine, statistics of..... 3
Benzine and naphtha, production of 24
Bedford township 21, 92
Feldspar in 21
Mica in 92
Bell, J. Mackintosh, report of on Economic Resources of Moose River Basin... 135-179
Bellerophon pelops..... 187
Belleville Portland Cement Co. 17
Belmont gold mine 98
Accidents at 40
Belted kingfisher 126
Bethea lake..... 110
Betula papyrifera..... 125
Big Levack nickel mine 198
Big Master gold mine 58, 68
Accidents at 39
Biotite 140
Birch aphis 129
Birch case-bearer... 128
Bird lake..... 112
Black ash 126, 176
Black Bay Mining Co. 78

Digitized by Google

Page

Black bear.... 127
Black blister beetle.... 129
Black Cat Mining Co. 61
Black Donald graphite mine 12, 92
Black duck 126
Black flies 127, 128
Black river 109, 114, 124, 125, 126, 130, 131
Black spruce 125, 176
Black Sturgeon lake, iron range at. 9
Blackburn lake..... 112
Black's camp, iron at.....218, 220
Blast furnaces .. ..,.... 10
Blezard nickel mine 204
Blezard township, drillings in..... 214
Bob's lake mica mine..... 12
Boerth gold mine..... 93
Bonasa umbellus 126
Bounty on iron ore 11
Bounty on pig iron 11
Bowell township, nickel in..... 200
Bow Park farm, gas and petroleum wells at 25, 26
Bowman township 109
Boyer lake..... 221
Brachiopoda 185
Brant county, petroleum in..... 25
Brant lake, iron ore at..... 9
Brantford, natural gas at..... .22, 25
Brantford, petroleum in..... 25
Breakneck falls.... .... 136, 177
Breitung Iron Co. 75
Breitung iron mine..... 75
Brick 15
Prices of at Casselman 15
At Fort William..... 15
At Sandwich..... 15
At Toronto... 15
At Waterloo..... 15
Production of 15
Uses of 15
Brick, common, statistics of..... 2, 13
Brick, paving, statistics of... 2
Uses of 15
Brick, pressed, at Beamsville 15
At Brampton 15
At Milton 15
At Toronto 15
Statistics of 2, 13
Briquettes, peat, plant for making.. 27
Brockville, peat factory at..... 29
Bronzed grackle 126
Brooke township, petroleum in 24
Brougham township, graphite in 12
Bruce copper mine 81
Brunner, peat factory at 29
Condition of 32
Buffalo gold mine 65
Building material 13
Production of, 1890 to 1903 13
Statistics of, 1890 to 1903 13
Building stone, statistics of 2, 13
Bulldog tabanus 128
Burley gold mine 60
Burlington heights.... 228
Burns mica mine 91
Buttercup oil beetle... 129
Byturus unicolor.... 128

Cabbage butterfly 129
Calcium carbide, manufacturers of .. 18
Production of 18, 19
Statistics of 2, 4, 19
Uses of 18
Caledonia springs, peat bog at..... 29
Calymene platys..... 190
Camarotoechia tethys, Bill..... 186
Cameron lake..... 198
Cameron island gold mine..... 62
Cameron Island Mining and Development Co. 62
Camp Bay Mining Co., Limited....62, 63
Canada Corundum Co, ...88, 90
Works of 19, 89
Canada grouse 126
Canada jay 126
Canadian Copper Company 6
Operations of..... .....82, 86
Smelter of 83
Works of 59

Page

Canadian Copper Co.'s mines, accidents at 38, 39
Canadian Goldfields Limited..... 18
Canadian Oil Refining Co. 28
Canadian Portland Cement Co. 17
Canadian Salt Co. 22
Candles and paraffin wax, production of 24
Cannington, peat bog at 35
Canoe lake..... 112
Capreol township, nickel in 202
Carbide of calcium (see calcium carbide)
Carbonates, iron 150, 152
Caribou..... 178
Carlow township, corundum in..19, 89, 90
Carman township 124, 181, 182
Carpodacus purpureus 126
Carr township 109
Carter, W. E. H., Report of on Mines Of Western Ontario.....58-87
On peat fuel..... 26-35
Carter and Kittermaster, salt producers 22
Cascaden township, nickel in 196
Catbird 126
Cecidomyia strobiloides 129
Cedar 176
Cedar waxwing 126
Cement, Portland 16
Plants 17
Production of, 1891 to 1903 18
Statistics of 3, 16
Uses of 14
Cement, natural rock, statistics of.3, 18
Cement, plants, natural rock 18
Cephalopoda..... 188
Ceryle alcyon 126
Charcoal pig iron 10
Chermes abietis..... 128
Cherry lake..... 110
Chicago nickel mine 194
Chickadee 126
Chionaspis sp. 129
Chipmunk 127
Chipping sparrow 126
Chloanthite 98
Chokecherry 176
Chonetes antiopia, Bill 186
Cf. lineata 186
Cf. lineata, Hall 186
Chordeiles virginianus 126
Chysops.... 128
Cimbex americana..... 128
Cladopora cryptodens. Bill.... 181
Clark J. M., prospecting for iron.... 42
Clathrodictyon laxum 183
Problematicum 184
Clay, deposits of 13
Products of 15, 16
Cliff swallow 126
Clisiocampa americana.... 128
Clouded sulphur 129
Coal, price of in Sweden 34
At Wallaceburg, prospecting for.. 43
In Dufferin county, prospecting for 43
Coastal plain, peat bogs of 174
Cobalt on T. & N. O. Ry. line ..1, 59, 96
Cobalt ores elsewhere 108
Cobalt-Nickel Arsenides and Silver, Report on by Willet G Miller 96-104
Cockshutt Plough Works, Brantford, natural gas and petroleum at 25
Cody T., accident to 40
Cody township 124, 181
Coe iron mine 94, 95
Coke pig iron 10
Colaptes auratus..... 126
Coleman A. P., Report of on Northern Nickel Range..... 192-222
Report of on the Iroquois Beach in Ontario..... 225-244
Coleolus tenuicinctum..... 188
Tenuistriatus 188
Coleophora sp. 128
Collonema bellatula 186
Colonial Portland Cement Co. 17
Combined gold mine 62
Combined Gold Mine Co. 62
Congking river..... 145

Digitized by Google

Page

Conlon Bros., iron prospect of..... 43
Conocardium cuneus.. 188
Consolidated copper mine 93
Consolidated Mines Co. of Lake Superior, Limited 72
Contopus virens... 126
Cook gold mine 93
Copper, in Morin township..... 79
In Salter township 79
On north shore of lake Huron..... 58
Statistics of 2, 6, 7
Copper Cliff mine 84, 85
Accident at..... ... . 38, 39
Copper mines 7, 77, 93
Bruce 81
Copper Queen 80
Consolidated 94
E. S. 106 78
Hermina..... 79
McA. 217 78
Massey Station..... 78
Pattison prospect 78
Ranson 81
Rising Sun 79
Rock Lake 81
Superior 82
Taylor 82
Tip-top 77, 78
Wilcox 94
Copper pyrites 94, 95
Copper Queen Mining Co 80
Corundum 10-21
In Carlow township..... ....19, 89, 90
In Raglan township 19, 21, 89
Production of 19, 21
Statistics of 3, 4, 21
Corundum Refiners, Limited 21, 89
Corvus americanus.... 126
Corylus americana..... 176
Corythuca arcuata 128
Craig gold mine ...(..... 93
Craig, B. A. C., on aluminium as an ore of corundum 19
Crataegus coccinea..... 176
Cree Indians 179
Creighton nickel mine.....6, 83, 85
Accident at 39
Creighton, Walter, accident to..... 39
Crepidophyllum archaici, Bill 181
Crow 126
Crown Point gold mine 61
Crown Point Mining Co., Limited.. 61
Crown Reef vein 59
Crushed stone, statistics of 2
Culbert, M. T., Report of on the Iron Belt West of Hutton 222-224
Culvert pipe, cement 15
Cut worms 129
Cypricardinia..... 188
Cyathophyllum halli, M. E. and H... 181
Cyclotrypa borealis 185
Cyclotrypa communis 185
Cyathophyllum exiguum, Bill 181
Cyclotrypa collina.. 185
Corniferous series of rock formations 154
Petroleum in 25
Coronation Gold Mining Co., Limited. 60

Dalmanites anchiops 190
Stemmatus 190
Dance township 124, 130, 132, 133
Darcy, W., accident to..... 40
Davenport bar 229
Davis lake..... 111
Deer flies..... 128
Delbert lake..... .....105, 122, 130
Deloro gold mine 18, 93
Demonstrating plant, A peat fuel.... ....29, 30, 31
Denbigh township, graphite in 12
Dendragapus canadensis.... 126
Dendroica aestiva 126
Denmark, peat fuel industry in 33
Desjardins canal 236
Deseronto blast furnace 10
Devonian Fauna of Kwataboahegan River, Report on by William Arthur Parks 180-191
Devonian rock formations 13, 138, 159

Page

Diamond drills 42-45
Prospecting with 42-45
Purchasers of 42
Regulations for use of 42
Summary of operations with 45
Dicerca divaricata..... 125
Diorites 119
Diphyphyllum arundinaceum, Bill... 181
Simcoense, Bill 181
Dobson, Alex., peat factory of 27
Dobson peat dryer 29
Dobson peat press 30
Dolerites ... .116, 117
Dominion Peat Products, Limited .. 27
Works of 30
Donnelly mica mine 12
Dorion Mining Syndicate 11
Dorion township, lead in 59, 87
Zinc in 59, 87
Doryphora decemlineata.... 129
Dowling township, nickel in 196
Downy woodpecker 126
Drain tile, statistics of 2, 15
Uses of 15
Driftwood river.... .....109, 124, 126
Drilling for lignite at Elis' bend 166
Drillings in Blezard township 214
Drury township, nickel in 195
Dryobates pubescens..... 126
Villosus..... 126
Dufferin county, prospecting for coal in 43
Dundonald township 108, 124, 131
Duty on pig iron 10
Dyscrasite.... 98

Eagle lake area, gold in.....64, 66
Economic geology of Iroquois beach 237
Edison, T. A., mining operations of 214
Eldorado gold mine 64
Elizabeth gold mine, accident at 39
Elora, lime kilns at 14
Elzevir township, asbestos in..... 92
Enterprise or Lead Hills mine..... 87
Epicauta cinera 129
Pennsylvanica..... 129
Ermine 127
E S 106 copper mine..... 78
Essex county, natural gas in 22
Euomphalus sp..... 187
Decewi.... 186
Laxus 186
Eurymus philodice..... 129
Extra-Provincial mining companies.. 38

Fairbank lake..... ... .194.. 209, 210
Fairchild, Prof., theory of as to Lake Iroquois 226
Fall canker worm 129
Favosites basaltica, Gold.... 181
Gibsoni, sp. nov. 181, 182
Hemispherica, M. E. and H. 181
Turbinata, Bill..... 181
Winchelli, Rom. 181
Feigle gold mine 93
Feldspar 21, 117, 140
Along the K. & P. Ry. 21, 90
Exports of 21
In Bedford township 21
In Frontenac county 90
Production of 21
Statistics of 3, 4, 21
Feldspar mines 90
Jenkins 90
Richardson 90
Worth..... 90
Ferari, Basil, accident to 39
Fergus, lime kilns at 14
Fertilizer, peat meal as a 35
Fisher 127
Flicker 126
Flint Lake mine.... 63
Flying Post, iron range near..... 9
Foley township, prospecting for iron in 44
Fossil remains in Iroquois beach.... 228
Fralick, Mr. E. L., mining operations of 92
Frances iron mine 9
Fraxinus sambucifolia 126, 176

Digitized by Google

Page

Frederick House river...108, 123, 125, 145
Freeman mica mine 12
French river.... ... .137, 145, 147
Gypsum on 158
Frikovitch, Toni, accident to 39
Frontenac county, feldspar in 90
Lead in 11, 94
Mica in 12, 91
Frontenac lead mine.. .....11, 94
Fuel oil, statistics of 3
Fuel oils and tar, production of.. 24
Galeoscoptes carolinensis 126
Galt, lime kilns at 14
Galena 11, 100
Gananoque, talc deposits near 13
Garter snake 127
Gas oil, statistics of 3
Gas and fuel oils and tar, production of 24
Gasteropoda 186
Gemmell, L. J., mining operations of 12
General Electric Co. 12
Operations of 91, 92
Geneva lake..... 222
Geology of the northern nickel range 219
German township 108, 125, 131
Gertrude nickel mine 87
Giant gold mine 67
Gillespie nickel mine 196
Glacial rocks of Moose basin..... 143
Gladstone gold mine 93
Gold, in Eagle lake area.. .. .. 64, 66
In Van Horne township 66
Statistics of..... ....2, 3, 5
Gold mines 59, 72, 93
A L 278 and 200.....71, 72
A L 282 or Sunbeam..... 71
Atlas 93
Baden-Powell 65
Belmont 93
Big Master 68
Boerth 93
Buffalo 65
Burley 60
Cameron Island..... 62
Combined 62
Cook 93
Craig 93
Crown Point 61
Crown Reef 59
Deloro 93
Eldorado 64
Giant 67
Gladstone 67
Gold Reefs 62
Gold Rock..... 66
Gold Standard 67
Golden Eagle 64
Golden Horn 64
Grace (Michipicoton) 47, 222
Grace (Eagle lake)..... 64
Great Northwest 62
Ideal 66
Indian Joe 62
King Edward 69
Lost..... 66
Little Master 68
Mikado 60
National 69
Nino 64
Olympia 61
Redeemer..... 66
Reliance 66
S 100.. 66
St. Anthony Reef 70
Shakespeare 70
Sovereign 93
Star of the East 93
Sultana 59
Twentieth Century 67
Viking 65
Virginia 64
Walsh 72
Gold mines, productive, in 1903.... 4
Atlas..... .... 4, 93
Belmont..... .... 4, 93
Big Master..... ... ... 4, 68
Grace..... .... 4, 222
Twentieth Century.... .,.....4, 67

Page

Gold mining, causes of lack of success in..... 14
Gold Reefs gold mine 62
Gold Rock gold mine 66
Gold Rock Mining and Milling Co. .. 66
Gold Standard gold mine 67
Gold Standard Mining Co. 68
Golden Eagle gold mine 64
Golden Horn gold mine 61
Gompnoceras oeta..... 190
Goniophora 188
Goodwin, W. L., Report of on Summer Mining Schools. 52-57
Gosage mica mine 91
Gosfield township, natural gas in ... 26
Grace gold mine (Michipicoton)....47, 222
Grace gold mine (Eagle lake)..... 64
Grace Mining Co., Limited 64
Grand Rapids, iron ore at 9
Graphite 92-93
In Brougham township 12
In Denbigh township 12
In Lanark county.... 12
Production of 92
Statistics of 3
Treatment of 12
Graphite mines 92-93
Allanhurst 12
Black Donald 12, 92
McConnell 12, 92, 93
Grave lake..... 110
Great Northwest gold mine 62
Great Northwest Mining Co. 62
Green alder 176
Grey and Bruce Cement Co. 17
Grey, Young and Sparling Co., salt producers 22
Griendtveen Moss Litter Co, works of 34
Ground Hog river..... 145
Iron range on 9
Grypidula galeata, Dalman..... 186
Guelph limestone, petroleum in 25
Gunflint lake, iron formation at..... 8
Gypsum 21, 150, 156, 157, 158
Deposits of, near Paris 21
On Moose river..... 137
Production of 21
Statistics of 3, 4
Uses of 21

Hadena sp. 129
Haileybury cobalt-nickel deposits . .. 101
Hairy woodpecker 126
Hamilton blast furnace 10
Hamilton and Toronto Sewer Pipe Co. 15
Hanlan mica mine 12, 91
Hanover Portland Cement Co. 17
Hares 127
Harricanaw river, gypsum on..... 158
Harrison talc mine..... 92
Harrowing peat for air-dying..... 31
Hastings county, actinolite in 11, 92
Arsenic in 18
Corundum in 19, 88
Gold in 93
Lead in 11
Hawthorn 176
Hazel 176
Helenaveen, peat works at..... 34
Helen iron mine 7, 9, 46, 58, 220
Accidents at 39
Iron pyrites at 22
Henderson, C., talc producer 13
Hercoceras auriculum.... 190
Hermina copper mine 79
Hermina Mining Co. 79
Hespeler, lime kilns at 14
Higbee, E.. mining operations of.... 66
Hodgins, James A., accident to 38
Hollandia lead mine 11, 94
Holopea 187
Hornblende..... 116
House sparrow 126
Hoyle township 105, 123, 134
Hunter's Island, iron formation on.. 8
Huronian formation 76, 87, 101, 138, 219, 220, 222, 223
Latent wealth of 2
Hutton township, iron in....8, 58, 216, 220

Digitized by Google

Page

Hutton township iron range.....216-221
Analyses of ore from 218
Extension of the range 218
Geology of the region 219
Moose mountain 216
Relationships of the ranges 220
Hydraulic power sites of Moose basin 145
Ideal gold mine 66
Ideal Mining Co. 66
Illuminating oil, production of 24
Statistics of 3
Imperial Cement Co. 17
Imperial Oil Co. 26
Wells sunk to Trenton by 24
Imperial Peat Co. 28
Indian Joe gold mine 62
Inez nickel mine 194
International Asbestos Co. 92
Interstate Consolidated Mineral Co..4, 68
Iron around Jackfish bay..... 74
At Steep Rock lake, prospecting for 42-48
In Aberdeen 76
In Foley township, prospecting for 44
In Hutton township.. .. ..216, 218, 220
In Kitchener township..... 219
In Moose mountain region... ..216, 220
In Roberts township..... 219
Near Little Current, prospecting for 48
On the Mattagami river.... 152
On the Opazatika river.. 136
Iron and steel production, 1896 to 1903.... 10
Iron belt west of Hutton, The, Report on by M. T. Culbert 222-224
Iron dam..... .. ..218, 220
Iron industry, importance of 7
Iron lake, iron range at..... 9
Iron mines 73, 94
AL 383..... 74
Breitung or Loon lake.. 75
Frances 9
Helen 7, 9, 22, 39, 46, 58, 220
Radnor 94
Williams 74
Iron ore..... .... 8, 58
Analyses of..... 218
Deposits of U. S..... 7
In Hutton township 58
In Michipicoton..... 9
In vicinity of Loon lake..... .. 58
On the T & N. O. Ry... 58
Production of..... 7
Statistics of..... 2
Iron ores, inferior..... 9
Iron, pig, statistics of..... ... 2
Iron pyrites..... ... .22, 95, 156, 157
Deposits of near Bannockburn..22, 95
At Helen mine..... 22
At Jarman mine 95
Production of..... 22
Statistics of..... .... 3, 4, 22
Iron ranges, on Hunter's island 9
In Hutton township..... ..... 9, 216
In Rathbun township..... 224
Near lake Nipigon..... 9
Near Round lake..... 9
Of United States..... 8
On lake Temagami... ... . 9, 58
Iroquois Beach in Ontario, The; Report on by A. P. Coleman ..225-244
Belleville to Gananoque..... 241
Burlington Heights to Toronto..... 229
Colborne to Trenton..... 231
Conditions of Iroquois time..... 236
Detailed account of..... 227-244
Duration and age of..... 237
East of Gananoque..... 241
Economic geology of..... 237
Extent of..... 227
Fossil remains in..... 228
In New York..... .... 233, 234
Islands to north and east..... 231
Lake Peterborough..... 233
Lower water levels..... 238
Mohawk Valley outlet.. 235
Near Hamilton..... 228
Near Trenton..... 239
North of Trent river..... 232

Page

Old beaches in New York 242
Port Granby to Trenton..... 239
Prince Edward county..... 240
Scarboro' to Colborne..... 230
Summary..... 243
Theories of origin of..... 225
Thousand Islands straits.. 242
Tilting of the beach..... 234

Jack Lake Gold Mining Co..... 70
Jack or Banksian pine..... 126
Jackfish bay, iron around..... 74
Jackson, Geo., mining operations of.. 13
James, Joseph, mining operations of. 12, 92
Jarman pyrites mine..... 95
Jarvis, Tennyson D., on Agricultural Capabilities of Abitibi... ... 121-134
Jarvis lake..... ... . 105, 122
Jenkins, Charles, feldspar producer .. 21
Jenkins feldspar mine 90
Johnson, Albert, accident to..... 39, 40
Jokinen John, accident to 39
Josephine iron mine.. ..... 9, 47
Juneberry or shad-bush..... 128
Juniper..... 176
Juniperus communis 176

Kallio, Jacob, accident to.. 39
Kaolin..... 150
Kapuskasing river..... 145
Katherine lead mine 11
Kay, George F., Report of on Abitibi Region.. 104-121
Kelso, lime kilns at..... 14
Kenoja (or Kenozha) lake 112
Kent Bros., mining operations of.... 12
Properties of 92
Keppel township 211
Kesagami lake.... ....144, 148
Cliffs of peat around..... 148, 150
Peat bogs of..... 174
King Edward gold mine 69
Kingston Feldspar & Mining Co. 21
Kingston and Pembroke Ry, feldspar on..... .... 21, 90
Kitchener township, iron in.. 219
Kitchi-gammi gold mine..... 47
Ko-ko-ko lake, iron range at.. 9
Kwataboahegan river.. ... . 137, 147

Lace bugs..... 128
Lacey mica mine..... ... . 12, 91
Lakefield Portland Cement Co..... 17
Lake Huron, copper ore on north shore of... 58
Lake Nipigon, iron ranges near 9
Lake Peterborough..... 233
Lake Superior Power Company..... 6
Operations of.... 82, 83, 84, 87, 195, 197
Lake Temagami, iron ranges on..... 9
Lambton, petroleum in..... 23
Lamellibranchiata 188
Lanark county, graphite in.. 92
Lime in..... 15
Mica in..... .... 12, 91
Lanius borealis..... 126
Larch or tamarac..... 126
Larch saw fly..... 128
Larix americana 126
Larus argentatus smithsonianus 126
Lost gold mine..... 66
Laurentian formation.. .... 138, 219, 220
Lead, pig, statistics of.... 2
Lead Hills or Enterprise mine..... 87
Lead mines..... .... 11, 87
In Dorion township 59, 87
In Loughborough township 11, 94
Hollandia..... 94
Katherine... 11
Lead Hills or McTavish.. 87
Victoria.... 11
Lead smelter, at Hollandia mine ... 11
At Kingston..... 11
Leeches..... 127
Leith, Prof. C. K., work of..... 216
Leptostrophia, cf. magnifica, Hall... 183
Levack nickel ore deposits 197
Lignite..... ..... 150, 159, 161, 162, 164, 166, 168, 169, 170, 172, 174
As fuel.... .... 28, 29

Digitized by Google

Page

Lignite, continued.
At Blacksmith rapid. 169, 170, 172, 174
Of Moose river, analysis of.....174, 175
On the Abitibi river 168, 169
On the Kwataboahegan river....168, 169
On the Missanabie river..... 136
On the Soweska river..... 136
Other deposits of..... 174
Lime, analysis of Milton..... 15
Consumption of..... 14
Deposits of..... 13
In Renfrew... 15
In Lanark..... 15
Methods of producing.... 14
Statistics of..... ... . 3, 13
Lime kilns..... 14
Limestone..... 13
Quarries of..... 14
Uses of..... 14
Limonite on Mattagami river.. 152
Little Abitibi river..... 145
Little Master gold mine..... 88
Little Rock Consolidated Mining & Development Co..... 71
Little Stobie nickel mine... 214
Locusts..... 129
Longford Mills, limestone at..... 14
Longford Quarry Co..... 14
Long Portage district..... 123
Loon..... 126
Loon lake (A. C. & H. B. R.), iron ore at..... .... 59, 75
Loon Lake (C. P. R.), iron ore at.. 8, 73
Loon Lake Iron Co., operations of... 75
Loon Lake iron mine (A. C. & H. B. R.) Accident at 40
Loughborough tp., lead in..... 11
Mica in..... 91
Mica mines in 92
Low-grade iron ores..... 9
Larix americana..... 176
Loxonema robusta, Hall..... 186
Subattenuta 186
Lubricating oil, production of..... 24
Statistics of..... 3
Lyell, on origin of Iroquois beach... 225
Lyman, A., accident to.. 40
Lynx..... 127
Lyriopecten dardanus..... 188

McA 217 copper mine 78
McClatchey mica mine..... 12
McConnell graphite mines.... .... 12, 92
McConnell, Rinaldo, mine owner.... 12
McCrindle lake..... 223
McTavish township, lead in 87
Zinc in..... 87
Madoc, talc at..... .... 13, 92
Madoc Mining Co..... 22
Manitou gold area..... 69
Manxman gold mine. 47
Maple borer..... 129
Mariposa gold mine..... .....46, 47
Marshall, Peter, accident to... 39
Marten..... .... 127, 178
Massey Station copper mine.... 58, 78
Matheson tp..... .... 125, 134
Mattagami river..... .... 105, 145, 147
Iron ore on... .... 9, 152
Mattawishquaia river 145
Matte, nickel-copper, output of..... 6
Mealten, Fred., accident to..... 39
Medina formation, petroleum in..... 25
Megambonia 188
Megascops asio..... 126
Meloe angusticollis 129
Methods of mica mining..... 12
Meristella nasuta, Conrad 186
Mersea tp., natural gas in.... 26
Merula migratoria 126
Mesabi formation in Ontario..... 8
Methuen tp., muscovite in..... 91
Mica..... 116
Exports of..... 12-13
Production of.... 12
Statistics of.... 3
Uses of..... .... 90, 91
Varieties of 12, 90

Page

Mica in Bedford township 92
In district of Nipissing..... 12
In district of Parry Sound..... 12
In Frontenac Co 12., 91
In Lanark county..... 12, 91
In Loughborough tp..... 91
In North Burgess tp..... 91
Mica, "amber" or phlogophite.. 12
Mica, white or muscovite... 12
Mica industry, condition of..... 90
Mica mines..... 90-92
Bob's Lake..... .... 12, 92
Donnelly..... 12
Freeman..... 12
Hanlan 12, 91
Lacey..... ....*.... 12, 91
McClatchey..... 12
Stoness..... 92
Mica mining, methods of 12
Mica trimming works at Perth..... 92
At Sydenham..... 92
Micanite..... 12
Michipicoton, iron ore in..... 9
Michipicoton iron range... 9
Michipocoton island, minerals on.... 102
Michipicoton mining division..... 221
Michipicoton Mining Division, Report on by D. G. Boyd, Inspector.. 46-47
Micro-norite rocks in nickel field.... 214
Midland blast furnace..... 10
Mikado gold mine..... ... . 58, 60
Miller, Willet G., Report of on Mines of Eastern Ontario..... 88-95
On Cobalt-Nickel Arsenides and Silver.... 96-103
Milne peat press..... .. 32
Milne peat gatherer, the..... 32
Milton, lime kilns at..... 14
Milton lime, analysis of..... 15
Mineral production, 1899 to 1903..... 4
Mineral production, 1903... 2
Mineral production, 1893 and 1903 compared..... 3
Mineral Range Iron Mining Co..... 94
Miners' licenses..... 48
Mines Contract and Investigation Co..... 61
Mines of Eastern Ontario, Report on by Willet G. Miller, Inspector. 88-95
Actinolite and asbestos..... 92
Condition of..... 88
Copper mines..... 93
Coe..... 94
Consolidated..... 93
Wilcox..... 94
Corundum mines..... 88
In Hastings Co..... 88
In Renfrew Co..... 89
Feldspar mines..... 90
Jenkins..... 90
Richardson..... 90
Gold mines..... 93
Atlas..... 93
Belmont... 93
Boerth..... 93
Cook..... 93
Craig..... 93
Deloro..... 93
Sovereign..... 93
Star of the East.. 93
Graphite mines..... 92
Black Donald..... 92
McConnell..... 92
Iron mines..... 94
Radnor..... 94
Iron pyrites mines... 95
Jarman..... 95
Lead mines... 94
Frontenac..... 94
Hollandia..... 94
Mica mines..... 91
Bob's Lake 92
Hanlan... 91
Lacey..... 91
Loughborough 92
Stoness..... 92
Zinc mines..... 94
Richardson..... 94
Mineral industries, miscellaneous... 95

Digitized by Google

Page

Mines of Western Ontario, Report on by W. E. H. Carter, Inspector . 56-87
Condition of.... 58
Copper mines.... 77-82
Bruce.... 81
Copper Queen.... 80
E S 106.... 78
Hermina.... 79
McA 217.... 78
Massey Station.... 78
Pattison prospect.... 78
Ranson.... 81
Rising Sun.... 79
Rock Lake.... 81
Superior.... 82
Taylor.... 82
Tip-top.... 77
Gold mines.... 59-72
A L 278 and 200.... 71
A L 282 or Sunbeam.... 71
Baden-Powell.... 65
Big Master.... 68
Buffalo.... 65
Burley.... 60
Cameron Island.... 62
Combined.... 62
Crown Point.... 61
Crown Reef.... 59
Eldorado.... 64
Flint Lake.... 68
Giant.... 67
Gold Reefs.... 62
Gold Rock.... 66
Gold Standard.... 67
Golden Eagle.... 64
Golden Horn.... 64
Grace.... 64
Great Northwest.... 62
Ideal.... 66
Indian Joe.... 62
King Edward.... 69
Lost.... 66
Little Master.... 68
Mikado.... 60
National.... 69
Nino.... 64
Olympia.... 61
Redeemer.... 66
Reliance.... 66
St. Anthony Reef.... 70
Shakespeare.... 70
S 500.... 66
Sultana.... 59
Twentieth Century.... 67
Viking.... 65
Virginia.... 64
Walsh.... 72
Iron mines.... 73-77
A L 388.... 74
Breitung.... 75
Loon Lake.... 75
Williams.... 74
Nickel-copper mines.... 82-87
Copper Cliff.... 84, 85
Creighton.... 83, 85
Gertrude.... 87
No. 2.... 85
No. 3.... 85
North Star.... 86
Victoria.... 82, 86
Silver mines.... 72
West End.... 72
Mining, American investments in.... 36
Mining accidents.... 38-40
Laws regarding.... 38
Table of.... 41
Mining companies.... 36-38
Extra-Provincial.... 38
Incorporated in 1903.... 37
Licensed.... 38
Methods of "wild-cat".... 36
Mining lands, disposed of.... 36
Leased.... 36
Sold.... 36
Mink.... 127, 178
Missanabie river.... 145, 147
Lignite on.... 136
Modimorpha.... 188

Page

Mokaki lake.... 144
Molybdenite, statistics of.... 2
In township of Sheffield.... 11
Mond Nickel Company.... 6
Operations of.... 86
Smelting works of.... 58, 86
Monohammus confusor.... 128
Montreal river.... 112
Moose.... 127, 178
Moose Factory.... 178, 179
Moose lake.... 109, 124
Moose lake region.... 198
Moose Mountain iron range.... 8, 216, 220
Moose river.... 145, 147
Gypsum deposits on.... 137
Moose River Basin, Economic Resources of; Report on by James Mackintosh Bell.... 135-179
Aboriginal inhabitants of.... 178, 179
Clays, analyses of.... 160
Climate of.... 174, 175
Coastal Plain of.... 140
Economic geology.... 150
Forest trees of.... 176
Gypsum, analyses of.... 159
Deposits of.... 156, 157, 158, 159
Hydraulic power sites of.... 145
Iron carbonate.... 150, 152
Analysis of.... 152
Kaolinic clay.... 160
Lakes of.... 144, 145
Lignite, deposits of.... 161, 162, 164, 166, 168, 169, 170, 172, 174
Physiography of.... 144
River habits and effects.... 146, 147
River systems of.... 145
Shales and clays.... 159, 160
Soil of.... 175, 176
Stratigraphy of.... 138
Territory explored.... 135
Wild animals of.... 177
Morgan township, nickel in.... 190
Morin lake.... 224
Morin tp., copper in.... 79
Morrison, James, accident to.... 39
Morton lake.... 223
Mosquitoes.... 127
Mountain alder.... 126
Mountain ash.... 126, 176
Mountain maple.... 126, 176
Mulmer tp., prospecting for coal in.... 43
Murchisonia desiderata.... 187
Murdock, James, accident to.... 39
Murphy tp.... 133
Muscovite, deposits of.... 12, 91
In Addington county.... 91
In Methuen township.... 91
Muscovite or white mica.... 12, 91
Muskrats.... 127
Mytilarca.... 188

National gold mine.... 69
National Gold Mining Co.... 69
National Portland Cement Co.... 17
Naphtha and benzine, statistics of. 3, 24
Nasi, Gustave, accident to.... 39
Natural gas.... 22-23
At Brantford.... 22, 25
In Essex county.... 22
In Gosfield township.... 26
In Mersea township.... 26
In Welland county.... 22
Order-in-Council, prohibiting export of.... 22
Production of.... 22
Statistics of.... 3, 4
Wells.... 23, 25
Natural rock cement (see also Cement).... 17
Manufacturers of.... 18
Production of.... 18
Uses of.... 18
Nematus erichsonii.... 128
New Caledonia, production of nickel in.... 6
New cement plants.... 17
Neslin lake.... 136, 145

Digitized by Google

Page
Nettogami lake... 137
Newington, peat factory at..... 29, 30
Newberry, on origin of Iroquois beach 226
Niccolite..... .... 98, 103
Nickel, statistics of 2, 6
Nickel district, Sudbury 59
Nickel, in Bowell township..... 200
In Capreol township.... ....202, 203, 204
In Cascaden township..... 196
In Drury township.... 195
In Morgan township.... ..... 199, 200
In Norman township.. .... 202, 203, 204
In Wisner township..... 202
On T. & N. O. Ry. line 1
Nickel ores, table of analyses of..... 199
Nickel deposits on northern range 194-208
Big Levack..... 198
Chicago..... 194
Gillespie..... 196
Inez..... 194
Ross..... .... 200, 201
Stobie, No. 3..... 198
Sultana..... ....195, 209, 210
Trillabelle..... 196
Whistle 203
WD 14..... 203
WD 16.... 202
WD 35..... 200
WD 150..... 201
WD 252..... .. ..201, 213
WR 5..... 200
Nickel Cliff mine, prospecting by diamond drill at..... 44
Nickel-copper mines..... 82-87
Copper Cliff..... 84
Creighton..... 83-86
Gertrude..... 87
No. 2..... 85
No. 3.. 85
North Star..... 86
Victoria..... .... 82, 86
Nickel-copper mines, condition of.... 82
Nickel-Copper Co. 79
Nickel-copper mining..... 5
Night Hawk..... 126
Night Hawk lake..... 106, 122, 125, 133
Night Hawk river.. .... 107, 124
Nino gold mine..... 64
Nipissing district, mica in..... 12
No. 2 nickel-copper mine.... 85
No. 3 nickel-copper mine..... 85
Norman township, nickel in.. 202, 203, 204
North Burgess tp., mica in..... 91, 92
North shore lake Superior, iron sands on..... 73
North Shore Reduction Co..... 73
North Star nickel-copper mine..... ... 86
Northern Light Mines Co..... 5, 64
Northern Nickel Range, The; Report on by A. P. Coleman.....192-222
Analysis of ores..... 199
Bowell township..... 200
Drillings in Blezard township..... 214
Eruptive, acid edge of.... 204
Basic edge of..... 204
Basin of..... 205
Character of..... 212
Effects of..... 213
Rocks, other..... 213
South edge of..... 201
Extension of range.. 218
Geology of range..... 220
Levack ore deposits..... 197
Micro-norite rocks..... 214
Moose lake region..... 198
Morgan township..... 199
Nature of sediments..... 205
Norman and Capreol townships..... 202
Relationship of ranges..... 220
Results of rock analyses..... ... 212
River systems..... 207
Ross nickel mine..... 200
Sandstones..... 206
Slates... 206
Southwest corner..... 194
Strathcona nickel mine 198
Stratigraphical relationships..... 193
Sultana nickel mine..... ..... 195, 209
Topography of..... 192

Page
Trillabelle nickel mine.... 196
Tuffs..... 205
Windy lake region..... 196
Wisner township..... 202
Northern shrike..... 126
Norway or red pine..... 126
Norway, peat bogs of.... ... . 33, 34
Peat fuel industry in..... 33
Norwegian Marsh Association, Report of engineer of 33

Oil, see Petroleum.
Ojibway Indians..... 179
Olden zinc mine..... 11
Olden township, lead in..... 11
Zinc in..... 94
Olivine 116, 140
Olympia gold mine..... 61
Onaping river..... 207
Onaping—Windy lake..... 210
Ontario Colorado Mining Co..... 94
Ontario Corundum Co.....19, 89, 90
Ontario Graphite Co..... 12
Ontario Lead & Zinc Co..... 87
Ontario Mining & Smelting Co..... 11
Ontario Paving Brick Co... 15
Ontario People's Salt & Soda Co..... 22
Ontario Portland Cement Co..... 17
Ontario Sewer Pipe Co..... 15
Ontario Smelting Works.....6, 84
Onwatin lake.... 207
Opazatika lake..... 144
Opazatika river..... ... ...135, 136, 145
Iron deposit on..... 136
Open-hearth steel, output of..... 10
Open-tube peat press..... 27
Optic lake..... 112
Ore of aluminium, corundum as an.. 19
Orford Nickel Refining Co, works of.. 59
Orthoceras algomense..... 189
Extremum..... 189
Luxum..... 189
Pelops 189
Procerus.. 189
Pulcher 189
Thoas..... 189
Osborn's camp 219
Osmunda regalis..... 177
Ottawa Carbide Co..... 18
Otter..... ... . 127, 178
Owen Sound Portland Cement Co.... 17

Pale brown byturus..... 128
Paper and peat board..... 33
Paper birch..... 125
Papilio turnus..... 120
Paraffin wax, statistics of.... ... 3, 24
Parks, William Arthur, Report of on Devonian Fauna of Kwataboahegan river..... 180-191
Parry Sound District, mica in..... 12
Parus atricapillus..... 126
Pashoskoota river..... 145
Passer domesticus 126
Pattison, Martin, copper mine of.... 78
Pattison copper prospect.. 78
Paving brick, statistics of..... 15
Uses of..... 15
Peat, products of... 34
On lake Kesagami 148
Properties of 31
Peat Board Company, Limited..... 35
Peat board and paper..... 35
Peat bogs..... 33
At Caledonia Springs..... 29
At Cannington..... 35
At Rondeau..... 31
Of Moose river basin... 174
In Norway..... .....33, 34
Requisite properties of..... 34
Peat coking plants 29
Peat dryer, the Dobson..... 29
Simpson..... 30
Peat factories in Ontario..... 28
Peat fuel..... .... 26, 35
Production of... .... 3, 4, 27
Statistics of..... 3
Works for producing..... 30

Digitized by Google

Page
Peat Fuel, W. E. H. Carter on.... 26-35
Condition of the industry..... 27
Demonstrating plant..... 29, 30, 31
In Norway..... 33, 34
Price in Sweden..... 34
Swedish tests of..... 34
Peat fuel industry, methods in use at Beaverton 30
At Welland..... 30, 31
In Europe..... 33
Peat gatherers..... 31, 32
Peat Industries, Limited 30
Peat-making in Ontario..... 29
Peat meal as a fertilizer..... 35
Manufacture of..... 34, 35
Uses of..... 34, 35
Works 31, 32 34
Peel township 24
Pelkonen, William, accident to..... 40
Pennsylvania Feldspar Co..... 21
Perch..... 127
Perisoreus canadensis..... 126
Perth, mica trimming works at..... 92
Petrochelidon lunifrons 126
Petroleum..... 23-26
Condition of the industry..... 23
Prices of..... 23
Production of..... 23
Products, table of, 1902 and 1903... 24
Refineries of..... 23
Statistics of..... 3, 4, 23, 24
In Brant county..... 25
In Corniferous formation..... 25
In Lambton county..... 23
In Raleigh township..... 26
In Romney tp. 25
Petroleum crude, and products of, imports of..... 23
Petroleum and petroleum products, statistics of..... 24
Phacops cristata..... 190
Phillipsastrea gigas, Owen 181
Phillipsastrea verneuli, M. E. & H. 181
Phlogopite, or "amber" mica..... 12
Deposits of..... 91
Phoebe..... 126
Phosphorus in iron ore..... 9
Picea alba..... 125, 176
Balsamea..... 176
Nigra 125, 176
Pickerel..... 127
Picton, peat fuel factory at..... 28-30
Pieris rapae 129
Pig iron..... 10
Statistics of..... 2, 10
Pig lead..... 11
Pike..... 127
Pike river..... 114
Pilkington tp., boring for oil in..... 24
Pine borer..... 128
Pine-cone willow gall..... 129
Pinus banksiana..... 126, 176
Pinus resinosa..... 126, 176
Pinus strobus..... 126, 176
Platyostoma lineata 187
Pleistocene series..... 142
Pleurotomaria adjutor 187
Camera 187
Delicatula 187
Poocaetes gramineus..... 126
Poplar Rapids river..... 145
Populus balsamifera candicans 125
Tremuloides..... 125, 176
Porcupine lake..... 106, 130
Porcupine river..... 106, 122, 123, 134
Port Arthur district, zinc in..... 11
Portland cement (see also Cement)..16-17
Duty on..... 17
Manufacturers of..... 17
Production of, 1891 to 1903..... 18
Table of imports of..... 16
Table of prices..... 16
Uses of..... 16
Post-glacial rocks in Moose basin.. 143
Pottery, production of..... 16
Statistics of..... 3, 15
Potato beetles..... 129
Prebencore, P., accident to..... 39
Pressed brick..... 15

Page
Prices of brick..... 15
Production of minerals, 1903.. 2
Prospecting for minerals..... 2
Proteus..... 191
Prue's nickel mine..... 213
Prunus pennsylvanica..... 126, 176
Prunus virginiana..... 176
Purple finch..... 126
Pyrites, copper..... 94
Pyrites, iron, statistics of..... 3
Pyroxene..... 140
Pyrus americana 126, 176
Quarries, limestone..... 13
Quarrying, methods of..... 14
Queenston Quarry Co..... 14
Quiscalus quiscula aeneus 126
Radnor iron mine..... 7, 9, 94
Raglan township, corundum in.... 19, 89
Raleigh township, petroleum in..... 26
Ranson copper mine..... 81
Ransford, R. & J., salt producers.... 22
Rathbun township, iron ranges in.... 224
Raven Lake Portland Cement Co.... 17
Red cherry..... 176
Red deer..... 126, 178
Red or Norway pine..... 126, 176
Red squirrels..... 127
Redeemer gold mine..... 66
Redstone river..... 105, 124, 132
Reid, H., accident to..... 40
Reliance gold mine..... 66
Reliance Gold Mining and Milling Company..... 66, 67
Renfrew county, corundum in..... 88
Lime in..... 15
Review, statistical for 1903..... 1
Rice lake..... 233
Richardson & Sons, J., zinc producers 11
Mica producers..... 92
Richardson feldspar mine..... 90
Richardson zinc mine..... 94
Rising Sun copper mine..... 79
Ross nickel mine..... 201
Roy, Thos., on terraces north of Toronto..... 225
Roam lake..... 223
Roberts township, iron in.. 219
Robin..... 126
Rock Lake copper mine.....59, 81
Rockwood, lime kilns at..... 14
Romney township, petroleum in..... 25
Rondeau, peat bog at..... 31
Peat factory at..... 29
Round lake, iron range near..... 9
Ruffled grouse..... 126
Rusty blackbird..... 126
Russia, peat fuel industry in..... 33
Sabawe Lake Gold Mining Co..... 72
St. Anthony Reef mine..... 5, 70
St. David's, limestone at..... 14
St. Jean, Napoleon, accident to..... 39
St. Mary's, lime kilns at..... 14
Salix..... 126, 176
Salt..... 21
Producers of..... 22
Production of..... 22
Statistics of..... 3, 4, 22
Salter township, copper in 79
Sand flies..... 128
Sandfly lake..... 224
Sandstones..... 13, 206
Sarnia Salt Co..... 22
Savage iron mine..... 223
Sayer's lake..... 221
Sayornis phoebe 126
Scaphopoda..... 188
Schists..... 120, 140
Schizoneura tessellata..... 129
Schwendiman, F. W., cement manufacturer..... 18
Scolecophagus carolinus 126
Screech owl..... 126
Scurfy back louse..... 129
Separation lake..... 110
Service berry..... 176
Sewer pipe..... 3, 15
Shad-bush or juneberry..... 126
Shakespeare, find of gold in..... 5

Digitized by Google

Page

Shakespeare Gold Mining Co., Limited..... 70, 71
Shales..... 13, 229
Shakespeare gold mine..... 70, 71
Sheffield township, lead in..... 11
Silver..... 98
On T. & N. O. Ry. line..... 197
Statistics of..... 2, 5
Silver mines..... 72
Silver Islet..... 101
West End..... 72
Wright..... 101
Simpson peat dryer..... 30
Simulium molestum..... 127
Slate..... 102, 206
Slate-breccia..... 102
Smaltite..... 98
Smelting works, at Hollandia lead mine..... 11, 94
Canadian Copper Company's..... 88
Ontario Smelting Works..... 84
Snider tp., nickel-copper ore in..... 96
Soft maple..... 126
Sovereign gold mine..... 93
Sovereign Gold Mining & Development Corporation, Limited..... 93
Soweska river, lignite on the..... 136
S 100 gold mine..... 66
Spencer, Dr. J. W., on Iroquois beach..... 226
Sphagnum moss..... 148, 150
Uses of..... 35
Spirifer, arenosus, Conrad..... 186
Divaricatus, Hall..... 186
Duodenaris, Hall..... 186
Euryteines, Owen..... 186
Fimbriatus, Hall..... 186
Murchisoni, Castelnau..... 186
Varicosus, Hall..... 186
Spittle bugs..... 129
Spizella socialis..... 128
Spruce-gall louse..... 128
Star of the East gold mine..... 93
Statistical Review for 1908..... 1
Statistics of mineral output, 1908..... 2
Steel, statistics of..... 2, 10
Steep Rock lake, prospecting for iron at..... 42, 43
Steinhoff and Gordon, boring for coal by..... 44
Stobie No. 8 nickel mine..... 198
Stone building..... 13
Statistics of..... 2, 13
Uses of..... 13
Varieties of..... 13
Stoness mica mine..... 92
Strathcona nickel mine..... 197
Streptelasma prolificum, Bill..... 181
Stromatopora, expansa..... 184
Solidula..... 184
Tubulifera..... 184
Stromatoporella, selwyni..... 184
Tuberculata..... 183
Stromatoporoidea..... 182
Strophonella ampla, Hall..... 186
Strophoedonta concava, Hall..... 186
Strophoedonta, demissa, Conrad..... 186
Inequistriata, Conrad..... 186
Pattersoni, Hall..... 186
Perplana, Conrad..... 186
Strophostylus unicus..... 187
Sudbury nickel district..... 6, 59
Sulphur, in iron ore..... 9
Sultana gold mine..... 58, 59, 60
Sultana Gold Mine, Limited..... 59, 60
Sultana nickel mine..... 195, 209, 210
Summer Mining Schools, Report on by W. L. Goodwin..... 52-57
Big Master mine..... 55
Black Donald mine..... 53-54
Copper Cliff mine..... 54-55
Cordova mine..... 54
General remarks on..... 57
Grace mine..... 57
Helen mine..... 57
Huronian mine..... 56
Massey mine..... 55
Olden mine..... 54

Page

Season's itinerary..... 52-53
Superior mine..... 57
Tip-Top mine..... 55, 56
Twentieth Century mine..... 55
Summit Lake Mining Co..... 68
Sunbeam or AL 282 gold mine..... 71
Sunny lake..... 111
Sun Portland Cement Co..... 17
Sunrise gold mine..... 46, 47
Superior copper mine..... 43, 58, 82
Prospecting by diamond drill at..... 43
Swamp elm..... 176
Syringostroma aurora..... 182, 183
Densum..... 183, 184
Syringopora hisingeri, Bill..... 181
Sydenham, mica trimming works at..... 92
Syenites in Abitibi region..... 117
Syringopora nobilis, Bill..... 181
Perelagans, Bill..... 181
Syringostroma Restigouchense..... 182

Tabanus affinis..... 128
Table of analyses of nickel ores..... 199
Talc..... 92
At Madoc..... 13, 92
Near Gananoque..... 13
Production of..... 13
Statistics of..... 3
Uses of..... 13
Tamarac..... 126, 176
Tar, statistics of..... 3
Tar and gas and fuel oils, production of..... 24
Taylor's camp, Moose mountain..... 219
Taylor copper mine..... 82
Taylor Copper Mining Company..... 81
Temagami Forest reserve, regulations re prospecting in..... 2
Temiskaming & Northern Ontario Ry 1
Cobalt-Nickel arsenides, deposits on line of..... 59, 96
Iron ore on..... 58
Withdrawal of lands on..... 2
Terra cotta and pressed brick, statistics of..... 2, 13
Tennyson lake..... 122
Tent lake..... 112
Tettix sp..... 129
Thomas township..... 124, 132, 133
Thompson, Peter, accident to..... 40
Thuya accidentalis..... 126, 176
Tile, drain, statistics of..... 2
Tip-Top copper mine..... 59, 77, 78
Tisdale township..... 121, 133
Titanium in iron ore..... 9
Toads..... 127
Toronto Lime Company..... 18
Toronto Peat Fuel Co..... 28
Works of..... 32
Trenton formation, petroleum in..... 24
Trillabelle nickel mine..... 196
Trilobita..... 190-191
Trousdale, J. W., mica producer..... 12
Tuffs..... 205
Turdus fuscescens..... 126
Turtle lake..... 112
Twentieth Century gold mine..... 67
Twentieth Century Gold Mining Company..... 4, 67

Ulmus americana..... 126, 176
United Gas and Oil Co..... 22
Oil wells of..... 26
Urinator imber..... 126
Usher, Isaac, cement manufacturer. 18

Van Horne township, gold in..... 66
Vermilion lake, iron range at..... 9
Vermilion river..... 207
Verrault, J., accident to..... 39
Vesper sparrow..... 126
Victoria nicel-copper mine..... 82, 86
Accident at..... 39
Smelter at..... 58, 82
Victoria lead mine..... 11
Viking gold mine..... 65
Viking Mining Co..... 65
Virginia gold mine..... 64
Volcanic tuff..... 120

Digitized by Google

	Page
Wabiskagami lake	136
Wabiskagami river	136, 145
Wahnapitae lake	224
Wallaceburg, prospecting for coal at	43
Walsh gold mine	72
Wall plaster	21
Wataybeeg lake	111, 145
Wataybeeg river	113
WD 14	202
WD 16	202
WD 35	200
WD 150	201
WD 252	201, 213
WD 359	224
Welland, peat factory at	29, 30
Welland county, natural gas in	22
West End silver mine	72
Whistle nickel mine	203
White alder	176
White birch	176
White cedar	126
White Clay river	114
White elm	126
Whitefish	127
White peat briquetting machine	28
White pine	126, 176
White spruce	125, 176
White-throated sparrow	126
Whitewater peat press	28
Whitney township	106, 123, 131
Wilcox copper mine	94
"Wild-cat" mining companies	36, 37
Wild red cherry	126
Williams' iron mine	74
Williams' Iron Mines, Limited	74
Willow, sp	126
Willson Carbide Works Co	18
Wilson's thrush	126
Wisner township, nickel in	202
Wolf	127
Wood pewee	126
Worth feldspar mine	90
WR 5	200
WR 108	224
WR 121	224
Wright silver mine	101
Yellow swallow tail	129
Yellow warbler	126
Yeomans, E., accident to	40
Yerkes lake	224
Zadi lake	136, 145
Zaphrentis gigantea, Lesueur	181
Ziegler peat coking process	29
Zinc ore, statistics of	2
In Dorion township	87
In McTavish township	87
In Olden township	11, 94
In Port Arthur district	11
Zinc mines, Olden	11, 94
Zinc and lead mines	11, 94
Zonotrichia albicollis	126

Digitized by Google

Digitized by Google

Digitized by Google

Digitized by Google

Digitized by Google

Digitized by Google

BOUND

JAN 26 1925

UNIV. OF MICH.
LIBRARY

UNIVERSITY OF MICHIGAN
3 9015 06860 0306

To renew the charge, [illegible] to the d
T[illegible]C [illegible] K

Digitized by Google

Digitized by Google